

WEST VALLEY DEMONSTRATION PROJECT SITE ENVIRONMENTAL REPORT CALENDAR YEAR 2000



Prepared by: West Valley Nuclear Services and URS Group, Inc.
Prepared for: U.S. Department of Energy
Ohio Field Office OH/WVDP

Under: Contract DE AC24-81NE-44139

August 2001
10282 Rock Springs Road
West Valley, New York 14171-9799



Department of Energy
Ohio Field Office
West Valley Demonstration Project
10282 Rock Springs Road
West Valley, NY 14171-9799

To The Reader:

This report, prepared by the U.S. Department of Energy (DOE) West Valley Demonstration Project (OH/WVDP), summarizes the environmental protection program at the West Valley Demonstration Project (WVDP) for calendar year 2000. Consistent with prior years, this report is being made available to the public as soon as possible and well in advance of DOE's required release date of October 1, 2001.

Monitoring and surveillance of the WVDP facilities are conducted in order to protect public health and safety and the environment. The quality assurance protocols applied to the environmental monitoring program by the DOE ensure the validity and accuracy of the monitoring data. Also included in this report are groundwater and ambient air data from the New York State Energy Research and Development Authority's (NYSERDA) New York State-licensed Disposal Area (SDA).

Air, surface water, groundwater, soil, and biological samples are collected and analyzed for radiological and nonradiological constituents in order to evaluate the potential effects of activities at the WVDP. Calculated doses to the hypothetical maximally exposed off-site individual from air- and waterborne radiological releases in 2000 were less than one percent of the DOE limit. Radionuclide concentrations in biological samples were at levels near or statistically identical to background concentrations.

Results of nonradiological (chemical) tests of surface water and soil samples showed no effects on the off-site environment. Nonradiological liquid effluent releases are controlled and permitted through the New York State Pollutant Discharge Elimination System (SPDES). Releases in 2000 were below regulatory limits with no exceptions. Monitoring of treated water effluents and facility ventilation system emissions verified that the dose received by off-site residents continues to be minimal.

The Project's commitment to safety and environmental responsibility was recognized in 2000 when it was awarded the DOE Voluntary Protection Program Star and accepted by the U.S. Environmental Protection Agency as a National Environmental Performance Track charter member.

If you have any questions or comments about the information in this report, please contact the West Valley Nuclear Services Company (WVNS) Communication Department at (716) 942-4555 or complete and submit the enclosed survey.

Sincerely,

A handwritten signature in cursive script, reading "Alice C. Williams".

Alice C. Williams, Director
West Valley Demonstration Project



SUMMARY OF CHANGES TO THE 2000 WVDP SITE ENVIRONMENTAL REPORT FROM THE 1999 SITE ENVIRONMENTAL REPORT

This report, prepared by the U.S. Department of Energy (DOE) West Valley Demonstration Project office, summarizes the environmental protection program at the West Valley Demonstration Project (WVDP) for calendar year (CY) 2000. Monitoring and surveillance of the facilities used by the DOE for the WVDP are conducted in order to protect public health and safety and the environment. The quality assurance protocols applied to the environmental monitoring program by the DOE ensure the validity and accuracy of the monitoring data. Also included in this report are groundwater and ambient air data from the New York State Energy Research and Development Authority's (NYSERDA) New York State-licensed Disposal Area (SDA).

Changes in content for the 2000 WVDP annual Site Environmental Report are summarized below. The overall organization of the report is the same as that of the 1999 Site Environmental Report.

REVISIONS AND ADDITIONS

- The Executive Summary lists the seven major focus areas leading to completion of Project cleanup and briefly describes implementation of the environmental monitoring program for CY 2000.
- The Environmental Compliance Summary has been updated to reflect the CY 2000 regulatory compliance status. New tables summarizing NESHAP compliance, SPDES compliance, release of property containing residual radioactive material, and reportable chemicals were added. All tables relating to compliance issues were moved to a separate section at the end of the chapter. In addition, the table listing WVDP environmental permits (formerly Table K-3 in Appendix K of the 1999 Site Environmental Report) was moved to this new section of the Environmental Compliance Summary.
- Data and text have been updated throughout the report to reflect results from the CY 2000 environmental monitoring program. Tables, graphs, maps, and references also were updated.
- Chapter 1 summarizes CY 2000 activities at the WVDP. Graphs summarizing performance measures were updated to include results from CY 2000. The graph depicting curies transferred to the vitrification facility (Fig. 1-7) now covers the duration of the entire vitrification project, 1996 through 2000, rather than just the individual subject year.
- Chapter 2 includes a discussion of 2000 radiological results from samples taken from air emissions and water effluents as compared with DOE concentration guides (as applicable). Results from air, water, and soil samples taken from other on-site, near-site, and community locations are compared with results from background locations in order to evaluate effects of site activities. The current status of nonradiological monitoring on-site is also discussed. The section addressing special monitoring during the year (both radiological and nonradiological) was moved to the end of the chapter, and the discussions of special monitoring for iodine-129 emissions in stack air and mercury in waters from the low-level waste treatment facility were updated. One graph summarizing estimated iodine-129 emissions in air since vitrification began was added to this chapter.

- Chapter 3 was updated to summarize and discuss results of the 2000 groundwater monitoring program, including continued monitoring, characterization, and mitigation of the strontium-90 plume on the north plateau. Figures were updated to reflect monitoring results in CY 2000. One new figure (Fig. 3-14) was added to depict monitoring results for tributyl phosphate at selected locations in the sand and gravel unit.
- Chapter 4 provides an assessment of dose to the general public resulting from exposure to radiation and radionuclides released by the Project to the surrounding environment in CY 2000. An estimate of dose attributable to radon-220 was added to Table 4-2 and a new sidebar containing a discussion of radon-220, including a graph of estimated releases from the WVDP since 1995, was added on p. 4-9. One new table (Table 4-3) summarizing radiological doses and releases was added in response to DOE guidance for site environmental reports requesting a standardized format for reporting dose and release data collected from all DOE sites. As in previous years, the WVDP was found to be in compliance with all applicable effluent radiological guidelines and standards.
- Chapter 5 was updated to include changes regarding the WVDP quality assurance program in CY 2000 and to summarize the results of assessments of the environmental monitoring program. NPDES crosscheck results, not available in CY 1999, became available again in CY 2000 and are listed in Appendix J, Table J-3.
- Maps in Appendix A were updated to include graphic scales in both standard and metric units. Sampling locations were updated to reflect CY 2000 environmental monitoring and groundwater monitoring programs.
- Changes in the environmental monitoring program are summarized at the beginning of Appendix B.
- Appendices C, D, E, F, and H — the data tables summarizing results from samples of water, sediment, soil, air, groundwater, and biological matrices, and data from direct radiation monitoring — were updated with CY 2000 results. A convention for bolding high and low data within the data tables was initiated in this year's report. A key describing the criteria for bolding has been included at the beginning of each of the abovementioned appendices.
- There were no errata or corrigenda from the 1999 Site Environmental Report.

SPECIAL ISSUES

The WVDP was awarded the DOE Voluntary Protection Program STAR designation in early 2000.

The WVDP was accepted into the EPA's National Environmental Performance Track in CY 2000 and was awarded charter member status as part of the first group of applicants.

For the third consecutive year no SPDES exceptions were noted at the WVDP.

No unplanned radiological releases to the off-site environment occurred in 2000.

West Valley Demonstration Project
Site Environmental Report
for
Calendar Year 2000

Prepared for the U.S. Department of Energy

Ohio Field Office

West Valley Demonstration Project Office

under contract DE-AC24-81NE44139

August 2001

West Valley Nuclear Services Co.

10282 Rock Springs Road

West Valley, New York 14171-9799

Preface

Environmental monitoring at the West Valley Demonstration Project (WVDP) is conducted by the West Valley Nuclear Services Company (WVNS), under contract to the U.S. Department of Energy (DOE). The data collected provide an historical record of radionuclide and radiation levels and chemical and meteorological data from natural and manmade sources in the survey area. The data also document the chemical and radiological quality of the groundwater on and around the WVDP and in the air and water discharged by the WVDP.

It is the policy of the WVDP to conduct all activities, including design, construction, testing, start-up, commissioning, operation, maintenance, and decontamination and decommissioning, in a manner that is appropriate to the nature, scale, and environmental effects of these activities. The WVDP is committed to full compliance with applicable federal and New York State legislation and regulations for the protection of the environment, to continual improvement, to the prevention and/or minimization of pollution, and to public outreach, including stakeholder involvement.

This report represents a single, comprehensive source of off-site and on-site environmental monitoring data collected during 2000 by environmental monitoring personnel. The environmental monitoring program and results are discussed in the body of this report. The monitoring data are presented in the appendices. Appendix A contains maps of on-site and off-site sampling locations. Appendix B is a summary of the site environmental monitoring schedule. Appendices C through J contain summaries of data obtained during 2000 and are intended for those readers interested in more detail than is provided in the main body of the report. Appendix K lists laws and regulations pertaining to the WVDP. Appendix L provides groundwater monitoring data from the New York State-licensed Disposal Area (SDA).

Requests for additional copies of the 2000 Site Environmental Report and questions regarding the report should be referred to the WVDP Communications Department, 10282 Rock Springs Road, West Valley, New York 14171 (telephone: 716-942-4555). Site environmental reports also are available electronically at <http://www.wvnsc.com> under the Media Research link.

Table of Contents

EXECUTIVE SUMMARY	EXE-1
-------------------------	-------

The West Valley Demonstration Project was established to demonstrate that technologies could be developed to safely clean up and solidify radioactive waste.

INTRODUCTION	INT-1
--------------------	-------

An environmental surveillance and monitoring program was developed and implemented to ensure that operations at the Project would not adversely affect public health and safety or the environment.

ENVIRONMENTAL COMPLIANCE SUMMARY: CALENDAR YEAR 2000	ECS-1
--	-------

Project activities are governed by federal and state regulations, Department of Energy Orders, Presidential Executive Orders, and regulatory compliance agreements.

CHAPTER 1. ENVIRONMENTAL PROGRAM INFORMATION

The radionuclides monitored at the Project are those that have the potential to contribute a dose above background or that are most abundant in air and water effluents discharged from the site.

Introduction	1-1
Radiation and Radioactivity	1-1
Measurement of Radioactivity	1-3
Measurement of Dose	1-3
Environmental Monitoring Program Overview	1-4
Data Reporting	1-5
Changes in the 2000 Monitoring Program	1-6
Vitrification Overview	1-6
2000 Activities at the WVDP	1-8
Vitrification	1-8
Environmental Management of Aqueous Radioactive Waste	1-8
Environmental Management of Airborne Radioactive Emissions	1-9
Environmental Management of Radiological Exposure	1-9
Unplanned Radiological Releases	1-10
NRC-licensed Disposal Area (NDA) Interceptor Trench and Pretreatment System	1-11
Waste Minimization Program	1-11
Waste Management	1-11
Pollution Prevention Awareness Program	1-12
National Environmental Policy Act Activities	1-12

Table of Contents

Chapter 1 (continued)

Self-assessments	1-14
Occupational Safety and Environmental Training	1-14
Voluntary Protection Program STAR Status	1-14
Environmental Management System Implementation	1-15
Integrated Safety Management System Implementation	1-15
Performance Measures	1-16
Radiation Doses to the Maximally Exposed Off-site Individual	1-16
SPDES Permit Limit Exceptions	1-16
Waste Minimization and Pollution Prevention	1-17
Spills and Releases	1-18
Vitrification	1-19

CHAPTER 2. ENVIRONMENTAL MONITORING

The West Valley Demonstration Project's environmental monitoring program includes monitoring and sampling of liquid and air effluents both on- and off-site. Deer, fish, milk, hay, and various fruits and vegetables also are sampled.

Routine Monitoring Program	2-1
Sampling Program Overview	2-2
Radiological Monitoring: Surface Water	2-3
Low-level Waste Treatment Facility Sampling Location	2-3
Northeast Swamp and North Swamp Sampling Locations	2-4
Other Surface Water Sampling Locations	2-4
NDA and SDA Sampling Locations	2-7
Standing Pond Water Sampling Location	2-9
Off-site Surface Water Sampling Locations	2-9
Drinking Water Sampling Locations	2-11
Radiological Monitoring: Sediments:	2-12
Radiological Monitoring: Air	2-14
On-site Ventilation Systems	2-15
Perimeter and Remote Air Sampling	2-18
Fallout Pot Sampling	2-19
Off-site Surface Soil Sampling	2-21
Radiological Monitoring: Food Chain	2-21
Direct Environmental Radiation Monitoring	2-23

Table of Contents

Chapter 2 (continued)

Meteorological Monitoring	2-25
Nonradiological Monitoring: Surface Water	2-26
Nonradiological Monitoring: Drinking Water	2-27
Nonradiological Monitoring: Air	2-27
Special Monitoring	2-28

CHAPTER 3. GROUNDWATER MONITORING

Groundwater is routinely sampled for radiological and chemical parameters both inside the Project site security fence and outside the site to determine and document any effect of site activities on groundwater quality.

Groundwater Monitoring Program Overview	3-1
Geologic History of the West Valley Site	3-1
Surface Water Hydrology of the West Valley Site	3-2
Hydrogeology of the West Valley Site	3-2
Routine Groundwater Monitoring Program	3-5
Monitoring Well Network	3-5
Groundwater Monitoring Program Highlights 1982 to 2000	3-8
Annual Analytical Trigger Level Review	3-8
Results of Routine Groundwater Monitoring	3-9
Long-term Trends of Gross Beta and Tritium at Selected Groundwater Monitoring Locations	3-11
North Plateau Seeps	3-13
North Plateau Well Points	3-13
Results of Radioisotopic Sampling	3-14
Results of Monitoring at the NDA	3-14
Volatile and Semivolatile Organic Compounds Sampling	3-15
Special Groundwater Monitoring	3-16
Gross Beta Plume on the North Plateau	3-16
Permeable Treatment Wall	3-16
Northeast Swamp Drainage Monitoring	3-17
North Plateau Groundwater Quality Early Warning Sampling	3-17
Investigation of Chromium and Nickel in the Sand and Gravel Unit and Evaluation of Corrosion in Groundwater Monitoring Wells	3-18

Table of Contents

CHAPTER 4. RADIOLOGICAL DOSE ASSESSMENT

Because of the difficulty of directly measuring any dose contributed by the Project to the off-site environment and the public, computer models are used to calculate dose estimates. Estimates are based on concentrations of radionuclides measured in air and water collected from on-site effluent points and meteorological data gathered during the sampling year.

Introduction	4-1
Exposure Pathways	4-2
Land Use Survey	4-2
Radioactive Vitrification Operations	4-3
Dose Assessment Methodology	4-3
Measurement of Radionuclide Concentrations in Liquid and Air Releases	4-5
Measurement of Radionuclide Concentrations in Food	4-5
Comparison of Near-site and Background Environmental Media Concentrations	4-7
Predicted Dose from Airborne Emissions	4-7
Predicted Dose from Waterborne Releases	4-10
Calculated Dose from Local Foodstuff Tests	4-11
Predicted Dose from All Pathways	4-12
Risk Assessment	4-13
Summary	4-14

CHAPTER 5. QUALITY ASSURANCE

The West Valley Demonstration Project's quality assurance program helps to ensure that sample collection and analyses are consistent, precise, and accurate.

Organizational Responsibilities	5-1
Program Design	5-1
Procedures	5-2
Quality Control in the Field	5-2
Quality Control in the Laboratory	5-3
Personnel Training	5-5
Record Keeping	5-6
Chain-of-Custody Procedures	5-6
Audits and Appraisals	5-6
Self-Assessments	5-6
Lessons Learned Program	5-7
Data Management and Data Validation	5-7

Table of Contents

Chapter 5 (continued)

Data Assessment and Reporting	5-7
Summary	5-8

APPENDIX A	<i>Maps</i>
APPENDIX B	<i>2000 Environmental Monitoring Program</i>
APPENDIX C	<i>Summary of Water, Sediment, and Soil Monitoring Data</i>
APPENDIX D	<i>Summary of Air Monitoring Data</i>
APPENDIX E	<i>Summary of Groundwater Monitoring Data</i>
APPENDIX F	<i>Summary of Biological Data</i>
APPENDIX G	<i>Summary of Nonradiological Monitoring Data</i>
APPENDIX H	<i>Summary of Direct Radiation Monitoring Data</i>
APPENDIX I	<i>Summary of Meteorological Data</i>
APPENDIX J	<i>Summary of Quality Assurance Crosscheck Analyses</i>
APPENDIX K	<i>Environmental Regulations, Standards, and Orders</i>
APPENDIX L	<i>Summary of NYSDERDA Groundwater Monitoring Data</i>

REFERENCES and BIBLIOGRAPHY

GLOSSARY

ACRONYMS and ABBREVIATIONS

UNITS OF MEASURE

SCIENTIFIC NOTATION and CONVERSION CHART

DISTRIBUTION

ACKNOWLEDGMENTS

Table of Contents

Summary List of Maps

Location of the Western New York Nuclear Service Center	INT-4
North Plateau Gross Beta Plume Area: Fourth-Quarter 2000 Results	3-12
Project Base Map	A-3
On-site Surface Water and Soil/Sediment Sampling Locations	A-4
Off-site Surface Water and Soil/Sediment Sampling Locations	A-5
On-site Air Monitoring and Sampling Points	A-6
Off-site Air and Fallout Sampling Points	A-7
Active WVDP Groundwater Monitoring Points	A-8
North Plateau On-site Groundwater Monitoring Network	A-9
South Plateau On-site Groundwater Monitoring Network	A-10
Near-site Drinking Water and Biological Sampling Points	A-11
Location of On-site Thermoluminescent Dosimeters (TLDs)	A-12
Location of Off-site Thermoluminescent Dosimeters (TLDs)	A-13
Environmental Sample Points more than 5 Kilometers from the WVDP Site	A-14

Figures

1. Location of the Western New York Nuclear Service Center	INT-4
1-1. Annual Average Quarterly Exposure at the CPC-WSA (DNTLD24)	1-10
1-2. Annual Average Quarterly Exposure at the Drum Cell (DNTLD36)	1-10
1-3. Annual Effective Dose Equivalent to the Maximally Exposed Off-site Individual	1-16
1-4. Yearly SPDES Permit Exceptions	1-17
1-5. Percentage of Waste Reduction Exceeding Goals	1-18
1-6. Number of Immediately Reportable Spills or Releases	1-19
1-7. Number of Curies Transferred to the Vitrification Facility 1996 through 2000	1-19
2-1. Fourteen-year Trends of Gross Alpha, Gross Beta, and Tritium Concentrations at Sampling Location WNSP006	2-6
2-2. Fourteen-year Trends of Gross Alpha, Gross Beta, and Tritium Concentrations at Sampling Location WNNDADR	2-8

Table of Contents

List of Figures (continued)

2-3. Fourteen-year Trends of Gross Alpha, Gross Beta, and Tritium Concentrations at Sampling Location WFFELBR	2-12
2-4. Fifteen-year Trends of Cesium-137 in Stream Sediments at Two Locations Upstream and Three Locations Downstream of the WVDP	2-13
2-5. Comparison of Cesium-137 with Naturally Occurring Potassium-40 Concentrations in 2000 at Downstream Sampling Location SFTCED	2-14
2-6. Fourteen-year Trends of Gross Alpha and Gross Beta Activity at the Main Stack Sampling Location (ANSTACK)	2-15
2-7. Fourteen-year Trends of Gross Alpha and Gross Beta Concentrations at the Rock Springs Road Sampling Location (AFRSPRD)	2-19
2-8. Seventeen-year Trend of Environmental Radiation Levels at Perimeter TLDs	2-25
2-9. Estimated I-129 Releases from the WVDP	2-28
3-1. Geologic Cross Section through the North Plateau	3-3
3-2. Geologic Cross Section through the South Plateau	3-3
3-3. North Plateau Gross Beta Plume Area: Fourth-Quarter 2000 Results	3-12
3-4. Annualized Average Strontium-90 Concentrations at WNSWAMP	3-17
3-5. Ten-year Trends of Averaged Gross Beta Concentrations at Selected Locations in the Sand and Gravel Unit	3-19
3-6. Fifteen-year Trends of Averaged Gross Beta Concentrations at Selected Locations in the Sand and Gravel Unit	3-19
3-7. Fifteen-year Trends of Averaged Gross Beta Concentrations at Selected Locations in the Sand and Gravel Unit	3-20

Table of Contents

List of Figures (continued)

3-8. Ten-year Trends of Averaged Tritium Concentrations at Selected Locations in the Sand and Gravel Unit _____	3-20
3-9. Ten-year Trends of Averaged Tritium Concentrations at Selected Locations in the Sand and Gravel Unit _____	3-21
3-10. Fifteen-year Trends of Averaged Tritium Concentrations at Selected Locations in the Sand and Gravel Unit _____	3-21
3-11. Ten-year Trends of 1,1-DCA at Selected Locations in the Sand and Gravel Unit _____	3-22
3-12. Ten-year Trends of Dichlorodifluoromethane at Selected Locations in the Sand and Gravel Unit _____	3-22
3-13. Ten-year Trends of 1,2-DCE-t and 1,1,1-TCA at Well 8612 in the Sand and Gravel Unit _____	3-23
3-14. Trends of Tributyl Phosphate at Selected Locations in the Sand and Gravel Unit _____	3-23
4-1. Comparison of Annual Background Radiation Dose to the Dose from 2000 WVDP Effluents _____	4-2
4-2. Effective Dose Equivalent from Liquid and Airborne Effluents to a Maximally Exposed Individual Residing Near the WVDP _____	4-13
4-3. Collective Effective Dose Equivalent from Liquid and Airborne Effluents to the Population Residing within 80 Kilometers of the WVDP _____	4-14
A-1. Project Base Map _____	A-3
A-2. On-site Surface Water and Soil/Sediment Sampling Locations _____	A-4
A-3. Off-site Surface Water and Soil/Sediment Sampling Locations _____	A-5
A-4. On-site Air Monitoring and Sampling Points _____	A-6

Table of Contents

List of Figures (continued)

A-5. Off-site Air and Fallout Sampling Points _____	A-7
A-6. Active WVDP Groundwater Monitoring Points _____	A-8
A-7. North Plateau On-site Groundwater Monitoring Network _____	A-9
A-8. South Plateau On-site Groundwater Monitoring Network _____	A-10
A-9. Near-site Drinking Water and Biological Sampling Points _____	A-11
A-10. Location of On-site Thermoluminescent Dosimeters (TLDs) _____	A-12
A-11. Location of Off-site Thermoluminescent Dosimeters (TLDs) _____	A-13
A-12. Environmental Sample Points more than 5 Kilometers from the WVDP Site _____	A-14
A-13. Projected 2000 Census Population by Sector within 80 Kilometers of the Site _____	A-15
E-1. pH - Sand and Gravel Unit _____	E-23
E-2. Conductivity - Sand and Gravel Unit _____	E-23
E-3. Gross Alpha - Sand and Gravel Unit _____	E-24
E-4. Gross Beta - Sand and Gravel Unit _____	E-24
E-4a. Gross Beta (magnified scale of Fig.E-4) - Sand and Gravel Unit _____	E-25
E-4b. Gross Beta (magnified scale of Fig.E-4a) - Sand and Gravel Unit _____	E-25
E-5. Tritium - Sand and Gravel Unit _____	E-26
E-6. pH - Till-Sand Unit _____	E-26
E-7. Conductivity - Till-Sand Unit _____	E-26
E-8. Gross Alpha - Till-Sand Unit _____	E-27
E-9. Gross Beta - Till-Sand Unit _____	E-27
E-10. Tritium - Till-sand Unit _____	E-27
E-11. pH- Weathered Lavery Till Unit _____	E-27
E-12. Conductivity - Weathered Lavery Till Unit _____	E-28
E-13. Gross Alpha - Weathered Lavery Till Unit _____	E-28
E-14. Gross Beta - Weathered Lavery Till Unit _____	E-28
E-14a. Gross Beta (magnified scale of Fig. E-14) - Weathered Lavery Till Unit _____	E-28
E-15. Tritium - Weathered Lavery Till Unit _____	E-29
E-15a. Tritium (magnified scale of Fig. E-15) - Weathered Lavery Till Unit _____	E-29
E-16. pH - Unweathered Lavery Till Unit _____	E-29
E-17. Conductivity - Unweathered Lavery Till Unit _____	E-29
E-18. Gross Alpha - Unweathered Lavery Till Unit _____	E-30
E-19. Gross Beta - Unweathered Lavery Till Unit _____	E-30
E-20. Tritium - Unweathered Lavery Till Unit _____	E-30

Table of Contents

List of Figures (continued)

E-21. pH- Kent Recessional Sequence	E-30
E-22. Conductivity - Kent Recessional Sequence	E-31
E-23. Gross Alpha - Kent Recessional Sequence	E-31
E-24. Gross Beta - Kent Recessional Sequence	E-31
E-25. Tritium - Kent Recessional Sequence	E-31
H-1. 2000 Average Yearly Gamma Exposure Rates around the West Valley Demonstration Project Site	H-6
H-2. 2000 Average Yearly Gamma Exposure Rates on the West Valley Demonstration Project Site	H-6
I-1. Wind Frequency Rose: 10-meter at the Regional Monitoring Station	I-3
I-2. Wind Frequency Rose: 10-meter at the Primary Monitoring Station	I-4
I-3. Wind Frequency Rose: 60-meter at the Primary Monitoring Station	I-5
I-4. Calendar Year 2000 Weekly Precipitation	I-6
I-5. Calendar Year 2000 Cumulative Precipitation	I-6

Table of Contents

Tables

Compliance Tables:

West Valley Demonstration Project 2000 Air Quality Noncompliance Episodes	ECS-20
West Valley Demonstration Project 2000 NPDES/SPDES Permit Limit Noncompliance Episodes	ECS-20
Release of Property Containing Residual Radioactive Material	ECS-20
EPCRA Compliance in 2000	ECS-21
Reportable Chemicals Above Threshold Planning Quantities Stored at the WVDP in 2000	ECS-21
West Valley Demonstration Project Environmental Permits	ECS-22
2-1. 2000 Gross Alpha Concentrations at Surface Water Sampling Locations	2-5
2-2. 2000 Gross Beta Concentrations at Surface Water Sampling Locations	2-5
2-3. Gross Alpha Concentrations at Off-site, Perimeter, and On-site Ambient Air Sampling Locations	2-20
2-4. Gross Beta Concentrations at Off-site, Perimeter, and On-site Ambient Air Sampling Locations	2-20
3-1. 2000 Groundwater Sampling and Analysis Agenda	3-6
4-1. Potential Local Off-site Exposure Pathways Under Existing WVDP Conditions	4-3
4-2. Summary of Annual Effective Dose Equivalents to an Individual and Population from WVDP Releases in 2000	4-6
4-3. WVDP Radiological Dose and Release Summary	4-15

Table of Contents

List of Tables (continued)

C-1.	Total Radioactivity of Liquid Effluents Released from Lagoon 3 (WNSP001) in 2000 _____	C-3
C-2.	Comparison of 2000 Lagoon 3 (WNSP001) Liquid Effluent Radioactivity Concentrations with Department of Energy Guidelines _____	C-4
C-3.	Radioactivity Concentrations and pH in Surface Water: Facility Yard Drainage (WNSP005) _____	C-5
C-4.	Radioactivity Concentrations in Surface Water: Downstream of the WVDP at Frank's Creek (WNSP006) _____	C-6
C-5.	Radioactivity Concentrations in Surface Water: Sewage Treatment Facility (WNSP007) _____	C-7
C-6.	Radioactivity Concentrations in Surface Water: French Drain (WNSP008) _____	C-7
C-7.	Radioactivity Concentrations and pH in Surface Water: Northeast Swamp (WNSWAMP) _____	C-8
C-8.	Radioactivity Concentrations in Surface Water: North Swamp (WNSW74A) _____	C-9
C-9.	Radioactivity Concentrations and pH in Surface Water: Frank's Creek East of the SDA (WNFRC67) _____	C-10
C-10.	Radioactivity Concentrations and pH in Surface Water: Erdman Brook (WNERB53) _____	C-10
C-11.	Radioactivity Concentrations and pH in Surface Water: Cooling Tower Basin (WNCoolW) _____	C-11
C-12.	Radioactivity Concentrations and pH in Surface Water: SDA Drainage (WNSDADR) _____	C-11
C-13.	Radioactivity Concentrations and pH in Surface Water: Waste Tank Farm Underdrain (WN8D1DR) _____	C-12

Table of Contents

List of Tables (continued)

C-14. Radioactivity Concentrations in Surface Water: Drum Cell Drainage (WNDCELD) _____	C-12
C-15. Radioactivity Concentrations, pH, and Conductivity: Environmental Laboratory Potable Water (WNDNKEL) _____	C-13
C-16. Radioactivity Concentrations, pH, and Conductivity: Maintenance Shop Potable Water (WNDNKMS) _____	C-13
C-17. Radioactivity Concentrations, pH, and Conductivity: Main Plant Potable Water (WNDNKMP) _____	C-14
C-18. Radioactivity Concentrations and Water Quality Parameters: Utility Room Potable Water (WNDNKUR) _____	C-15
C-19. Radioactivity Concentrations and Water Quality Parameters: Storage and Disposal Area Drainage (WNNDADR) _____	C-16
C-20. Radioactivity Concentrations, NPOC, and TOX in Groundwater at the NDA Interceptor Trench (WNNDATR) _____	C-17
C-21. Radioactivity Concentrations and Water Quality Parameters in Surface Water at the Standing Water (WNSTAW-series) Sampling Locations _____	C-18
C-22. Radioactivity Concentrations, pH, and Conductivity in Surface Water Upstream of the WVDP in Buttermilk Creek at Fox Valley (WFBCBKG) _____	C-19
C-23. Radioactivity Concentrations, pH, and Conductivity in Surface Water Downstream of the WVDP in Buttermilk Creek at Thomas Corners Bridge (WFBCTCB) _____	C-20
C-24. Radioactivity Concentrations and pH in Surface Water Downstream of the WVDP in Cattaraugus Creek at Felton Bridge (WFFELBR) _____	C-20
C-25. Radioactivity Concentrations in Surface Water Upstream of the WVDP in Cattaraugus Creek at Bigelow Bridge (WFBIGBR) _____	C-21
C-26. Radioactivity Concentrations, pH, and Conductivity in Potable Well Water around the WVDP _____	C-21

Table of Contents

List of Tables (continued)

C-27. Surface Water Quality at Locations WFBCBKG, WNSP006, WNSWAMP, and WNSW74A _____	C-22
C-28. Radioactivity Concentrations and Metals Concentrations in On-site Soils/Sediments _____	C-23
C-29. Radioactivity Concentrations in Surface Soil Collected at Air Sampling Stations around the WVDP _____	C-24
C-30. Radioactivity Concentrations in Stream Sediments around the WVDP _____	C-25
D-1. Airborne Radioactive Effluent Totals Released from the Main Ventilation Stack (ANSTACK) _____	D-3
D-2. Comparison of 2000 Main Stack Exhaust Radioactivity Concentrations with Department of Energy Guidelines _____	D-4
D-3. Airborne Radioactive Effluent Totals from the Vitrification System (HVAC) Ventilation Stack (ANVITSK) _____	D-5
D-4. Airborne Radioactive Effluent Totals from the Seismic Sampler (ANSEISK) for the Vitrification System (HVAC) Ventilation Stack _____	D-6
D-5. Airborne Radioactive Effluent Totals from the 01-14 Building Ventilation Exhaust (ANCSSTK) _____	D-7
D-6. Airborne Radioactive Effluent Totals from the Contact Size-reduction Facility Ventilation Stack (ANCSRFK) _____	D-8
D-7. Airborne Radioactive Effluent Totals from the Supernatant Treatment System Ventilation Stack (ANSTSTK) _____	D-9
D-8. Airborne Radioactive Effluent Totals from the Container Sorting and Packaging Facility Ventilation Stack (ANCSPFK) _____	D-10

Table of Contents

List of Tables (continued)

D-9. Airborne Radioactive Effluent Totals from the Former Low-level Waste Treatment Facility Hot Side Ventilation (ANLLWTVH) _____	D-11
D-10. Airborne Radioactive Effluent Totals from the New Low-level Waste Treatment Facility Ventilation (ANLLW2V) _____	D-11
D-11. Airborne Radioactive Effluent Totals from the Laundry Change Room (ANLAUNV) _____	D-12
D-12. Radioactivity Concentrations in Airborne Particulates at the Lag Storage Area Air Sampler (ANLAGAM) _____	D-13
D-13. Radioactivity Concentrations in Airborne Particulates at the NDA Air Sampler (ANNDAAAM) _____	D-14
D-14. Airborne Radioactivity Concentrations at the SDA Trench 9 Air Sampler (ANSDAT9) _____	D-15
D-15. Airborne Radioactive Effluent Totals from Outdoor Ventilation Enclosures/Portable Ventilation Units _____	D-16
D-16. Airborne Radioactivity Concentrations at the Rock Springs Road Air Sampler (AFRSPRD) _____	D-17
D-17. Radioactivity Concentrations in Airborne Particulates at the Dutch Hill Air Sampler (AFBOEHN) _____	D-18
D-18. Radioactivity Concentrations in Airborne Particulates at the Fox Valley Air Sampler (AFFXVRD) _____	D-18
D-19. Radioactivity Concentrations in Airborne Particulates at the Bulk Storage Warehouse Air Sampler (AFBLKST) _____	D-19
D-20. Radioactivity Concentrations in Airborne Particulates at the Route 240 Air Sampler (AFRT240) _____	D-19
D-21. Radioactivity Concentrations in Airborne Particulates at the Thomas Corners Road Air Sampler (AFTCORD) _____	D-20

Table of Contents

List of Tables (continued)

D-22. Radioactivity Concentrations in Airborne Particulates at the West Valley Air Sampler (AFWEVAL) _____	D-20
D-23. Radioactivity Concentrations in Airborne Particulates at the Springville Air Sampler (AFSPRVL) _____	D-21
D-24. Airborne Radioactivity Concentrations at the Great Valley Background Air Sampler (AFGRVAL) _____	D-22
D-25. Radioactivity Concentrations in Airborne Particulates at the Nashville Background Air Sampler (AFNASHV) _____	D-23
D-26. Radioactivity and pH in Fallout: Dutch Hill (AFDHFOP) _____	D-24
D-27. Radioactivity and pH in Fallout: Rain Gauge (ANRGFOP) _____	D-24
D-28. Radioactivity and pH in Fallout: Route 240 (AF24FOP) _____	D-25
D-29. Radioactivity and pH in Fallout: Thomas Corners Road (AFTCFOP) _____	D-25
D-30. Radioactivity and pH in Fallout: Fox Valley Road (AFFXFOP) _____	D-26
E-1. Groundwater Monitoring Network: Super Solid Waste Management Units _____	E-3
E-2. Contamination Indicator and Radiological Indicator Results: Sand and Gravel Unit _____	E-7
E-3. Contamination Indicator and Radiological Indicator Results: Lavery Till-sand Unit _____	E-11
E-4. Contamination Indicator and Radiological Indicator Results: Weathered Lavery Till Unit _____	E-12
E-5. Contamination Indicator and Radiological Indicator Results: Unweathered Lavery Till Unit _____	E-13

Table of Contents

List of Tables (continued)

E-6. Contamination Indicator and Radiological Indicator Results: Kent Recessional Sequence _____	E-14
E-7. Contamination Indicator and Radiological Indicator Results: North Plateau Seep Monitoring Locations _____	E-14
E-8. Contamination Indicator and Radiological Indicator Results: North Plateau Well Points _____	E-15
E-9. Detections of Volatile Organic Compounds at Selected Groundwater Monitoring Locations _____	E-15
E-10. Tributyl Phosphate Sampling Results at Selected Groundwater Monitoring Locations _____	E-16
E-11. Metals Sampling Results _____	E-16
E-12. Sampling Parameters at Early Warning Monitoring Wells _____	E-17
E-13. Alpha-, Beta-, and Gamma-emitting Radioisotopic Results for Selected Groundwater Monitoring Locations _____	E-18
E-14. Practical Quantitation Limits _____	E-20
F-1. Radioactivity Concentrations in Milk _____	F-3
F-2. Radioactivity Concentrations in Meat _____	F-4
F-3. Radioactivity Concentrations in Food Crops _____	F-5
F-4. Radioactivity Concentrations in Fish Flesh from Cattaraugus Creek _____	F-6
G-1. West Valley Demonstration Project State Pollutant Discharge Elimination System (SPDES) Sampling Program _____	G-3
G-2. SPDES Results for Outfall 001 (WNSP001): Water Quality _____	G-5
G-3. SPDES Results for Outfall 001 (WNSP001): Metals _____	G-7
G-4. SPDES Results for Outfall 001 (WNSP001): Organics _____	G-9
G-5. SPDES Results for Outfall 007: Water Quality and Iron _____	G-11
G-6. SPDES Results for Outfall 008 (WNSP008): Water Quality _____	G-12

Table of Contents

List of Tables (continued)

G-7. SPDES Results for Sums of Outfalls 001, 007, 008, and 116: Water Quality _____	G-13
G-8. Annual/Semiannual SPDES Results for Outfall 001: Water Quality, Metals, and Organics _____	G-14
G-9. Annual SPDES Results for Outfall 007: Water Quality _____	G-15
G-10. Annual SPDES Results for Outfall 008: Water Quality _____	G-15
H-1. Summary of 2000 Quarterly Averages of Off-site TLD Measurements _____	H-3
H-2. Summary of 2000 Quarterly Averages of On-site TLD Measurements _____	H-4
H-3. 3rd-Quarter 2000 TLD Results and Instantaneous Dose Readings with a High-pressure Ion Chamber (HPIC) at Each Monitoring Location _____	H-5
I-1. Site Precipitation Collection Data _____	I-7
I-2. Annual Temperature Summary at the 10-Meter Primary Meteorological Tower _____	I-8
I-3. Annual Barometric Pressure Summary _____	I-8
J-1. Comparison of Radiological Results with Known Results of Crosscheck Samples from the DOE Environmental Measurements Laboratory Quality Assessment Program 52 _____	J-3
J-2. Comparison of Radiological Results with Known Results of Crosscheck Samples from the DOE Environmental Measurements Laboratory Quality Assessment Program 53 _____	J-5
J-3. Comparison of Results from Crosscheck Samples Analyzed for Water Quality Parameters as Part of the EPA's 2000 Discharge Monitoring Report - Quality Assurance Study 20 for the National Pollutant Discharge Elimination System _____	J-7
K-1. Department of Energy Radiation Protection Standards and Derived Concentration Guides _____	K-3
K-2. Environmental Regulations, Orders, and Standards _____	K-4
L-1. Contamination Indicator Results at SDA Monitoring Wells _____	L-3
L-2. Radiological Indicator Results at SDA Monitoring Wells _____	L-4
L-3. Radioisotopic Results at SDA Monitoring Wells _____	L-6

EXECUTIVE SUMMARY

Project Description

The West Valley Demonstration Project (WVDP), the site of a U.S. Department of Energy (DOE) environmental cleanup activity operated by West Valley Nuclear Services Co. (WVNS), is in the process of stabilizing liquid high-level radioactive waste that remained at the site after commercial nuclear fuel reprocessing had been discontinued. The Project is located in Western New York State, about 30 miles south of Buffalo, within the New York State-owned Western New York Nuclear Service Center (WNYNSC).

The WVDP is currently focusing on seven major projects that will lead to completion of the cleanup work:

- shipping spent nuclear fuel to Idaho
- shipping low-level waste off-site for disposal
- constructing a facility where large high-activity components can be safely packaged for disposal
- packaging and removing expended materials from the vitrification facility

- removing the remaining waste in the high-level waste tanks and closing the tanks
- monitoring the environment and managing contaminated areas within the Project facility premises
- cleaning up and closing high-level waste-solidification facilities no longer in use.

Compliance

Management at the WVDP continued to provide strong support for environmental compliance in 2000. DOE Orders and applicable state and federal statutes and regulations are integrated into the Project's compliance program. Highlights of the 2000 compliance program were as follows:

- All State Pollutant Discharge Elimination System (SPDES) permit limits were met in 2000.

A reader opinion survey has been inserted in this report. If it is missing, please contact the Communications Department at (716) 942-4555. Additional Project information is available on the internet at <http://www.wvnsc.com>

- No notices of violation or inspection findings from any environmental regulatory agencies were received by the WVDP in 2000.
- Inspections of hazardous waste activities by the New York State Department of Environmental Conservation (NYSDEC) verified Project compliance with the applicable regulations.
- The Project continued to monitor specific waste management areas at the site in order to comply with the Resource Conservation and Recovery Act (RCRA) §3008(h) Administrative Order on Consent.
- The Project also met the requirements of the Emergency Planning and Community Right-to-Know Act (EPCRA) by collecting information about hazardous materials used at the Project and making this information available to the local community.
- The SPDES permit currently identifies four permitted liquid outfalls at the Project. A SPDES permit application was submitted to NYSDEC in 2000 to cover process changes and storm water runoff. A permit modification is not expected until 2002.
- In June 2000 the WVDP received final approval of a State Facility Air Permit from NYSDEC, one of the first such permits in this region.
- In accordance with the Site Treatment Plan developed under the Federal Facility Compliance Act, all calendar year 2000 milestones for the characterization, treatment, and disposition of mixed waste at the WVDP were completed.
- Among other pollution-prevention accomplishments, waste minimization goals for 2000 were met or exceeded in all but one of the waste

categories set in the one-year goals statement. Although low-level radioactive waste generation missed the established goal of 85%, it still was reduced by 73%.

- There were no unplanned off-site releases of radiological material in 2000.

Environmental Monitoring Program

Throughout the first three years of vitrification, specific and sustained attention was given to environmental monitoring and assessment of effluents from changing site operations. Project environmental scientists continued in 2000 to sample and measure effluent air and water, groundwater, surface streams, soil, sediment, vegetation, meat, milk, and game animals, and to record environmental radiation measurements. More than 10,000 samples were collected in order to assess the effect of site activities on public health, safety, and the environment.

The Project's environmental monitoring network is evaluated and updated to ensure that all the locations and sample types that would be sensitive to process-related changes are monitored. Samples are tested for radioactivity and/or non-radioactive substances using approved laboratory procedures. Both the laboratory test results and direct measurement data are reviewed at several stages for quality and for comparison with similar data.

The environmental data are entered in a controlled database and are automatically compared with upper and lower acceptance values. Data points falling outside these values are brought to the attention of WVDP scientists for further investigation. WVDP scientists assess all data points and evaluate trends at each location.

Surface Water Monitoring. The largest single source of radioactivity released to surface waters from the Project is the discharge from the low-level waste treatment facility through the lagoon 3 release outfall. The treated effluent water flows into Erdman Brook, which joins Frank's Creek just before exiting the Project's fenced area. Six treated batches totaling approximately 11.5 million gallons were released periodically over the course of thirty-seven days in 2000. In 1999, 7.7 million gallons were released. The difference can be attributed to a lag in batch releases of water from facility cleanup processes along with more precipitation in 2000 than in 1999.

The combined average concentration of all radionuclides in liquid releases from lagoon 3 in 2000 was approximately 34% of the DOE derived concentration guide (DCG), which is used to evaluate liquid process discharges. (See Chapter 1, p.1-5, for an explanation of DCGs.) The average radioactivity concentrations from 1996 through 2000 were 35%, 22%, 23%, 32%, and 34% of the DCG, respectively. The major dose contributors to the total combined liquid effluent in 2000 were cesium-137, strontium-90, and uranium-232. Higher concentrations of uranium-232 and strontium-90 in facility effluents may be a factor contributing to the increase between 1999 and 2000.

Surface water is routinely sampled on the Project premises by four automatic samplers: Timed composite samples are collected at Frank's Creek where it exits the Project, at two other on-site points where water flows off-site, and at a surface drainage point near the former radioactive waste disposal areas. Samples also are collected periodically at nine other points of drainage from facility areas. The data from these samples are used to determine the type,

amount, and probable origin of both radiological and nonradiological contaminants.

As in 1999, the most notable source of gross beta and strontium-90 radioactivity in surface water in 2000 was from groundwater migrating through the subsurface of the north plateau and emerging as seepage to join the surface water drainage from the north plateau into Frank's Creek. (See location WNSWAMP on Fig.A-2 in Appendix A [p.A-4].) This drainage point has been carefully monitored since the contaminated seep was identified in 1993. A groundwater recovery and treatment system currently is being used to reduce the migration of strontium-90 to surface water on the north plateau. The strontium-90 concentration at WNSWAMP, which originates from pre-Project operations, dropped about 20% in 2000 from the concentration in 1999. The decrease in the strontium-90 concentrations in 2000 at this northeast swamp drainage is thought to be linked to a combination of groundwater dilution, dispersion, and more precipitation in 2000 than in 1999.

The WVDP is evaluating a pilot-scale permeable treatment wall installed in 1999 in order to treat contaminated groundwater on the north plateau. A subsurface trench filled with ion-exchange media, installed in the eastern lobe of the plume, removes contaminants from the groundwater as it flows through the trench. (See Chapter 3, p.3-16, for additional discussion of this technology.)

Nonradiological contaminants, measured at three outfalls and calculated at one monitoring point, were below the New York SPDES permit limits.

Soil and Stream Sediments. Surface soil is collected annually near the ten air sampler locations in order to track long-term deposition. Sediments from off-site creeks are collected annually from three downstream and two upstream locations. Soil from three on-site drainage areas is also sampled annually in order to track waterborne movement of contaminants.

Surface soil samples in 2000 showed little change from previous years. Except for one area that historically has shown average cesium-137 concentrations higher than background values, the concentrations of radionuclides normally present in soil from both worldwide fallout and from Project air emissions are no different at near-site locations than at background locations.

Because of pre-Project releases from nuclear fuel reprocessing activities, the concentrations of cesium-137 in downstream creek sediments have been historically higher than concentrations in the upstream sediments. However, in 1998 and 1999 sediment samples at one downstream location showed a marked decrease in cesium-137, compared with historical values, after an unusually high June 1998 flood. The calendar year 2000 samples rebounded to a level of cesium-137 that is consistent with historical values. The fifteen-year graph (Fig. 2-4 [p.2-13]) indicates no upward trends at either upstream or downstream points.

Groundwater Monitoring. Groundwater samples were collected as scheduled from sixty-five on-site locations in 2000. Computerized screening of calendar year 2000 data speeded identification and evaluation of changes. Monitoring activities in 2000 included gathering more detailed information about the north plateau strontium-90 contamination. The calendar year 2000 groundwater program confirmed that

strontium-90 is still the major contributor to elevated gross beta contamination in the plume on the north plateau. The concentrations of other isotopes were below the DCG levels usually applied to surface water.

In addition to collecting samples from wells, groundwater was routinely collected from seeps on the bank above Frank's Creek along the northeastern edge of the north plateau. Results of radiological analyses indicate that gross beta activity from the north plateau plume has not migrated to these seepage areas.

Site groundwater also is tested for a number of nonradiological contaminants: In 2000 there were no statistically remarkable changes in the levels measured.

As in previous years, calendar year 2000 sample results from near-site residential water-supply wells were within the historical range of values measured at the background well.

Air Monitoring. WVDP airborne radiological emissions in 2000 included emissions from six routinely operated permitted exhaust points and four exhausts excluded from permitting because of their low emission potential. As anticipated, radioactive releases from the Project in 2000 were far below the most restrictive limits that ensure public health and safety. Operating the vitrification process at a reduced capacity resulted in radiological air releases that were less than those noted in calendar year 1999.

The dose from air emissions in calendar year 2000 was about 0.08% of the EPA radionuclide emissions standard of 10 millirem (mrem) per year effective dose equivalent to the maximally exposed off-site individual. In 1999 the dose from these emissions was about 0.11%.

Although several fission products contribute to the radioactivity, the most significant continued to be airborne iodine-129, a long-lived radionuclide that exists in gaseous form at the high temperatures of the vitrification process and that is not fully removed during treatment of the air effluent. The calendar year 2000 levels of gaseous iodine-129 emissions were lower than 1999 levels. Approximately 99% of the 2000 calculated airborne dose to the public is attributable to iodine-129 emissions from vitrification-related processes.

Six air samplers on the perimeter of the WNYNSC and four in more distant locations continuously collect samples of air at the average human breathing height. The samples are tested for radioactivity carried by airborne particles. Samples also are collected for analysis for tritium and iodine-129 at two of the ten locations, the Rock Springs Road sampler near the site and the Great Valley background sampler.

Gross radioactivity (airborne particulate) in air samples from around the perimeter was within the historical range of radioactivity measured at remote background locations or nearby communities. Gross radioactivity at the nearest perimeter sampler remained the same in 2000 as in 1999. Concentrations in samples from three on-site ambient air samplers located near waste storage facilities operated during 2000 also were far below any applicable limits.

Nitrogen oxides, nonradiological byproducts of the vitrification process, are monitored as part of the emission-control process. The WVDP continues to monitor nitrogen oxides and sulfur dioxide emissions as a condition of the New York State Facility Air permit. The monitoring demonstrates that emissions are well below the 99-ton cap for each. No opacity or permit limits were exceeded in 2000.

Vegetation, Meat, and Milk. Test results from near-site samples of beans, apples, corn, hay, beef, and milk were consistent with results noted in previous years. When near-site samples were compared with background samples, no site-related effects were noted.

Game Animals. Fifty fish specimens from Cattaraugus Creek were collected in 2000 for testing. Ten of these were from below the Springville dam, including species that migrate up from Lake Erie. Two semiannual sample sets of ten fish each were collected downstream of Buttermilk Creek, which receives Project liquid effluents, and two sets were collected upstream. These samples represent sportfishing species and bottom-feeding indicator species. Testing for gamma-emitting isotopes (see *gamma isotopic* in the Glossary) and strontium-90 showed a slight statistical difference in median concentrations of strontium-90 between upstream (background) fish and downstream fish collected above the dam. No statistical differences in other isotopes were noted in the fish samples.

Three samples of venison from near-site (WNYNSC) whitetail deer were tested for gamma-emitting isotopes and strontium-90. Control deer samples from locations more than thirty miles away from the site also were collected in 2000. Low levels of radioactivity from cesium-137, strontium-90, and naturally occurring potassium-40 were detectable in both control and near-site deer samples. Although results vary from year to year, data from the last ten years show no statistical differences between radionuclide concentrations in near-site and control venison samples.

In 2000, the seventh year of public access to portions of the WNYNSC for deer hunting, seventy-five deer were taken by hunters during

the hunting season. Although testing of the deer for radioactivity is made available by the WVDP, no hunters chose to have their venison tested.

Program Quality

The WVDP environmental monitoring program is designed to produce high-quality, reliable results. To maintain this standard, each scientist must give continuous attention to the details of sample handling, following approved collection and analysis procedures and data review. Formal self-assessments were performed, and the environmental laboratory also continued the practice of analyzing radiological crosscheck samples sent from a national laboratory. Of 120 radiological crosscheck analyses performed at both the on-site Project laboratory and off-site commercial service laboratories, 115 (96%) were within the control limits. The samples tested on-site at the Project environmental laboratory (twenty-five samples) were all within acceptable limits. Off-site laboratories address data deficiencies under approved quality assurance programs.

Test results from the crosscheck program, self-assessments, and comparisons of co-located sample measurements taken by independent agencies such as the New York State Department of Health (NYSDOH) and NYSDEC indicate that high quality standards are being met.

The WVNS Environmental Affairs and Quality Assurance departments also periodically conducted and documented reviews of program activities in 2000.

In addition, a November 2000 DOE Ohio Field Office surveillance of the WVDP environmental monitoring program showed that the WVDP was in compliance with applicable requirements.

Notable 2000 Events

In 1999 the WVDP was recommended for STAR status, the highest safety award given within the DOE. This award, received in early 2000, was granted in recognition of superior health and safety performance by contractor management and employees.

The WVDP also was recognized as a top environmental leader in 2000 and was accepted into the EPA's National Environmental Performance Track. The WVDP was awarded Charter Member status as one of the first facilities awarded membership. This award has been given to only four other DOE sites.

The WVDP is one of only two DOE sites to hold both the EPA's highest award for environmental sustainability and the DOE's STAR award.

Dose Assessment

There were no events affecting public health and safety or the environment associated with Project operations in 2000. The small amounts of radioactive materials that were released were assessed and doses were calculated using approved computer modeling codes. These evaluations also included calculations of doses received from the consumption of game animals and locally grown food. Airborne doses were calculated using CAP88-PC, an EPA-approved computer code. The result was a maximum dose to an off-site individual of 0.0081 millirem (mrem). The limit is 10 mrem. Doses from the liquid pathway to the maximally exposed person were estimated to be 0.030 mrem from Project effluents (excluding north plateau drainage). The north plateau drainage contribution to the total liquid dose was estimated to

be an additional 0.024 mrem. The predicted dose from all pathways was less than 0.07 mrem, or 0.07% of the 100-mrem DOE limit.

Conclusion

The West Valley Demonstration Project conducts extensive monitoring of on-site facilities and the surrounding environment. This program fulfills federal and state requirements to assess the effect of Project activities on public health and safety and the environment. In addition to demonstrating compliance with environmental regulations and directives, evaluation of data collected in 2000 continued to indicate that Project activities pose no threat to public health or safety or the environment.

INTRODUCTION

Purpose of this Report

This annual environmental monitoring report is published to inform Project stakeholders (see *stakeholder* in the Glossary) about environmental conditions at the WVDP. The report summarizes the environmental monitoring data gathered during the year in order to characterize the performance of the WVDP's environmental management, confirm compliance with standards and regulations, and highlight significant programs.

Information in this Report

Individual chapters in this report provide information on compliance with regulations, general information about the monitoring program and significant activities in 2000, summaries of the results of radiological and nonradiological monitoring, calculations of radiation doses to the population within 80 kilometers (50 mi) of the site, and information about practices that ensure the quality of environmental monitoring data. Graphs and tables illustrate important trends and concepts. The bulk of the supporting data is found in the appendices following the text. Page numbers refer the reader to the appendices, figures, and graphs cited in the text.

Appendix A contains maps showing on-site and off-site sampling locations.

Appendix B summarizes the calendar year 2000 environmental monitoring program at the on-site (i.e., on the WNYNSC) and off-site locations. Samples are designated by a coded abbreviation indicating sample type and location. (A complete listing of the codes is found in the index to Appendix B [pp.B-v through B-vii].) Appendix B lists the kinds of samples taken, the frequency of collection, the parameters analyzed, the location of the sampling points, monitoring and reporting requirements, and a brief rationale for the monitoring activities conducted at each location.

Appendices C through I summarize radiometric, chemical analytical, and physical data from air, surface water, groundwater, fallout in precipitation, sediment, soils, biological samples (meat, milk, food crops, and fish), and direct radiation measurements and meteorological monitoring.

Appendix J provides data from the comparison of results of analyses of identically prepared samples (crosscheck samples) by both the

WVDP and independent laboratories. Radiological concentrations and chemical water quality parameters in crosscheck samples of air, water, soil, and vegetation are reported here.

Appendix K provides a list of radiation protection standards set by the Department of Energy (DOE) that are most relevant to the operation of the WVDP. It also lists federal and state laws and regulations that affect the WVDP.

Appendix L contains groundwater monitoring data for the New York State-licensed disposal area (SDA), provided by the New York State Energy Research and Development Authority (NYSERDA).

Acronyms, often used in technical documents to speed up the reading process, are listed in a separate section at the back of this report. Although using acronyms can be a practical way of referring to agencies or systems with unwieldy names, having to look up rarely used acronyms can defeat the purpose of using them. Accordingly, full names of agencies and systems have been used in this report where it will help the reader. However, acronyms that the reader is apt to recognize (e.g., DOE, EPA, NRC, NYSERDA) or that are used often in this report (e.g., WVDP, WNYNSC) are spelled out only at the beginning of sections. Other information that may be helpful is found in the Glossary, References, Scientific Notation, Conversion Chart, and Units sections at the back of this report.

History of the West Valley Demonstration Project

In the early 1950s interest in promoting peaceful uses of atomic energy led to the passage of an amendment to the Atomic Energy Act that allowed the Atomic Energy Commission to en-

courage commercialization of nuclear fuel reprocessing as a way of developing a civilian nuclear industry. The Atomic Energy Commission made its technology available to private industry and invited proposals for the design, construction, and operation of reprocessing plants.

In 1961 the New York State Office of Atomic Development acquired 1,332 hectares (3,345 acres) near West Valley, New York and established the Western New York Nuclear Service Center (WNYNSC). Davison Chemical Co., together with the New York State Atomic Research and Development Authority, which later became NYSERDA, constructed and began operating a nuclear fuel reprocessing plant under a co-license issued by the Atomic Energy Commission (later the Nuclear Regulatory Commission [NRC]).

Nuclear Fuel Services, Inc. (NFS) was formed by Davison Chemical Co. to operate the plant as a commercial facility. NFS leased the property at the WNYNSC and in 1966 began operations to recycle fuel from both commercial and federally owned reactors.

In 1972, while the plant was closed for modifications and expansion, new and more rigorous safety regulations were imposed. Most of the changes concerned the disposal of high-level radioactive liquid waste and the prevention of earthquake damage to the facilities. NFS decided that compliance with the new regulations was not economically feasible and in 1976 notified NYSERDA that it would not continue in the fuel-reprocessing business.

Numerous studies followed the closing, leading eventually in 1980 to the passage of Public Law 96-368, the West Valley Demonstration Project Act, which authorized the DOE to dem-

onstrate a method for solidifying the 2.3 million liters (600,000 gal) of liquid high-level waste that remained at the West Valley site. Congress anticipated that the technologies developed at West Valley would be used at other facilities in the United States.

Under the original agreement between NFS and New York State, the state was ultimately responsible for both the radioactive wastes and the facility. The WVDP Act specifically provides that the facilities and the high-level radioactive waste on-site shall be made available (by the state of New York) to the DOE without the transfer of title for as long as required to complete the Project. The facility's NRC license was amended in 1981 to allow the DOE cleanup to proceed at the Project under a Memorandum of Understanding. Although the lead agency for the WVDP is the DOE, under the Memorandum of Understanding the DOE and the NRC each have specific responsibilities related to the WVDP.

West Valley Nuclear Services Co. (WVNS), a subsidiary of Westinghouse Government Services Group, was chosen by the DOE to be the management and operating contractor for the West Valley Demonstration Project. Site operations began at the WVDP in March 1982.

The high-level waste, contained in underground storage tanks, had separated into two layers, a liquid supernatant and a settled sludge layer. Various subsystems were constructed that permitted the successful startup in May 1988 of the integrated radwaste treatment system (IRTS). The system removed most of the radioactivity from the liquid supernatant, allowing the major portion of the liquid to be treated as low-level waste. Treatment of the supernatant liquid from the high-level waste tanks through the IRTS was completed in 1990.

The next step in the process, washing the sludge with water to remove soluble constituents, began in late 1991 and was completed in 1994. (See *Vitrification Overview* [p.1-6] in Chapter 1 for a more detailed description.) In 1995, the contents of the high-level waste tanks were combined and the subsequent mixture washed a final time. Vitrification of the high-level waste residues began in July 1996. In June 1998 the WVDP successfully completed the first phase of the vitrification campaign. Currently the WVDP is conducting the second phase of vitrification, which involves removing and solidifying the high-level residuals (heels) remaining in the tanks, and is planning for future decommissioning of vitrification and support facilities.

Description of the West Valley Demonstration Project

The purpose of the WVDP is to solidify the high-level radioactive waste left at the site from the original nuclear fuel reprocessing activities, develop suitable containers for holding and transporting the solidified waste, arrange transportation of the solidified waste to a federal repository, dispose of any Project low-level and transuranic waste resulting from the solidification of high-level waste, and decontaminate and decommission the Project facilities.

At this stage in the Project, the high-level waste has been solidified in glass in 254 stainless steel canisters and stored in a shielded cell. In order to continue the Project mission, seven major projects are under way that will lead to completion of the cleanup work:

Spent fuel shipping. The original operator at the site, Nuclear Fuel Services, Inc. (NFS), had accepted 750 spent fuel assemblies for reprocessing before discontinuing operations in 1975. These spent fuel assemblies were stored in the




Figure 1. Location of the Western New York Nuclear Service Center.

on-site fuel pool. During an early 1980 shipping campaign, 625 of the spent fuel assemblies were returned to the utilities that owned them. The remaining 125 assemblies, which continued to be stored at the WVDP, will be transported to the Idaho National Engineering and Environmental Laboratory (INEEL) for interim storage in 2001. Removal of the spent fuel will enable the WVDP's fuel pool to be drained and decontaminated.

Waste management. Part of the DOE's cleanup mission at the West Valley site is the disposal of low-level radioactive waste that is generated through WVDP operations. Stored wastes resulting from cleanup activities are being shipped off-site for disposal. The WVDP has refurbished the 1.8-mile railroad spur that enters the Project premises and is now shipping low-level waste directly from the site.

Vitrification expended materials processing. As materials used in vitrification are expended they are inventoried, identified, sorted, classified, cleaned, size-reduced (as needed), packaged, and removed from the facility. The vitrification facility itself will be decontaminated and decommissioned when high-level waste processing is complete.

High-level waste tank closure. Liquid high-level waste processing is expected to be completed in 2003. The underground waste tanks will be closed following decisions on long-term site management.

Remote-handled waste. A remote-handled waste facility is under construction on-site. It will be used to prepare higher activity wastes for shipment and disposal.

Environmental monitoring. Site-wide environmental monitoring and management will con-

tinue to ensure the safety of the public and the environment.

Facility closure projects. To complete the West Valley Demonstration Project Act, the facilities used to solidify the high-level waste will be decontaminated and decommissioned in preparation for implementing long-term management decisions.

General Environmental Setting

The geography, socioeconomics, climate, ecology, and geology of the region are principal factors in assessing possible effects of site activities on the surrounding population and environment and are an integral consideration in the design and structure of the environmental monitoring program.

Location of the West Valley Demonstration Project. The WVDP is located in northern Cattaraugus County about 50 kilometers (30 mi) south of Buffalo, New York (Fig.1 [facing page]). The WVDP facilities occupy a security-fenced area of about 80 hectares (200 acres) within the WNYNSC. This fenced area is referred to as either the Project premises or the restricted area.

The WVDP is situated on New York State's Allegheny plateau at an average elevation of 400 meters (1,300 ft). The communities of West Valley, Riceville, Ashford Hollow, and the village of Springville are located within approximately 8 kilometers (5 mi) of the Project. Several roads and a railway pass through the WNYNSC, but the public does not have access to the WNYNSC. Hunting, fishing, and human habitation on the WNYNSC generally are prohibited. A NYSERDA-sponsored program to control the deer population, initiated in 1994,

continued in 2000. Limited access to the WNYNSC was given to local hunters, and community response continued to be favorable.

Socioeconomics. The WNYNSC lies within the town of Ashford in Cattaraugus County. The nearby population, approximately 9,200 residents within 10 kilometers (6.2 mi) of the Project, relies primarily on an agricultural economy. No major industries are located within this area.

The land immediately adjacent to the WNYNSC is used principally for agriculture and arboriculture. Cattaraugus Creek is used locally for swimming, canoeing, and fishing. Although some water to irrigate nearby golf course greens and tree farms is taken from Cattaraugus Creek, no public water supply is drawn from the creek downstream of the WNYNSC before the creek flows into Lake Erie south of Buffalo, New York. Water from Lake Erie is used as a public drinking-water supply.

Climate. Although there are recorded extremes of 37°C (98.6°F) and -42°C (-43.6°F) in Western New York, the climate is moderate, with an average annual temperature of 7.2°C (45.0°F). Rainfall is relatively high, averaging about 104 centimeters (41 in) per year. Precipitation in 2000 was slightly below average, totaling about 97 centimeters (38 in). Precipitation is evenly distributed throughout the year and is markedly influenced by Lake Erie to the west and, to a lesser extent, by Lake Ontario to the north. Regional winds are generally from the west and south at about 4 m/sec (9 mph).

Biology. The WNYNSC lies within the northern deciduous forest biome, and the diversity of its vegetation is typical of the region. Equally divided between forest and open land, the site provides a habitat especially attractive to white-

tailed deer and various indigenous birds, reptiles, and small mammals. No species on the federal endangered-species list are known to be present on the WNYNSC.



Indigenous Small Mammal at the WVDP

Geology and Groundwater Hydrology. The WVDP site is located on the west shoulder of a steep-sided glacially scoured bedrock valley that is filled with a sequence of glacial sediments. (See Figs. 3-1 and 3-2 [p.3-3] in Chapter 3, Groundwater Monitoring.) The WVDP site is bordered by two stream valleys (Frank's Creek and Quarry Creek) and divided by a third stream valley (Erdman Brook) into two portions, the north and south plateaus. (See Figs.A-6 through A-8 [pp.A-8 through A-10] in Appendix A.)

The uppermost layer of glacial sediments on the south plateau consists of a silty clay till, the Lavery till. The Lavery till does not transmit significant quantities of water except where it is exposed at the ground surface, where weathering has fractured the near-surface sediments. Groundwater flow in the weathered till has both a vertically downward component and a hori-

zontal component to the northeast. Groundwater flow in the unweathered portion of the till, beneath the exposed weathered till, is predominantly downward.

On the north plateau a permeable alluvial sand and gravel layer overlies the less permeable glacial sequence of sediments (i.e., the Lavery till, the Kent recessional sequence, and the Kent till). Groundwater flow in the sand and gravel unit of the north plateau is predominantly horizontal, towards the northeast, discharging to seeps and streams along the plateau's edge and via evapotranspiration.

Within the Lavery till on the north plateau is a silty, sandy unit of limited extent, the Lavery till-sand. Gradients indicate that groundwater flows east-southeast. Surface discharge points have not been observed.

The Kent recessional sequence that underlies the Lavery till beneath both north and south plateaus is composed of silt and silty sand with localized pockets of gravel. Groundwater flow in the Kent recessional sequence is also toward the northeast with discharge to Butter-milk Creek.

Environmental Monitoring Program

The WVDP's environmental monitoring program began in February 1982. The primary program goal is to detect changes in the environment resulting from Project or pre-Project activities and to assess the effect of any such changes on the human population and the environment surrounding the site.

The monitoring network and sample collection schedule have been structured to accommodate specific biological and physical characteristics

of the area. Among the several factors considered in designing the environmental monitoring program were the kinds of wastes and other byproducts resulting from the processing of high-level waste; possible routes that radiological and nonradiological contaminants could follow into the environment; geologic, hydrologic, and meteorologic site conditions; quality assurance standards for monitoring and sampling procedures and analyses; and the limits and standards set by federal and state governments and agencies. As new processes and systems become part of the Project, appropriate additional monitoring is provided. As processes are completed, unnecessary monitoring may be eliminated from the program.

Monitoring and Sampling. The environmental monitoring program consists of on-site effluent monitoring and on- and off-site environmental surveillance in which samples are measured for both radiological and nonradiological constituents. (See the Glossary [pp.3 and 4] for more detailed definitions of *effluent monitoring* and *environmental surveillance*.) Monitoring and surveillance include both the continuous recording of data and the collecting of soil, sediment, water, air, and other samples at specific times.

Monitoring and sampling of environmental media provide two ways of assessing the effects of Project or pre-Project activities. Monitoring generally is a continuous process of measurement that allows rapid detection of any changes in the levels of constituents that could affect the environment. Sampling is the collection of media at specific times; sampling is slower than direct monitoring in indicating changes in constituent levels because the samples must be analyzed in a laboratory to obtain data. However, sample analysis allows much smaller quantities of radioactivity or chemical concentrations to be detected.

Permits and Regulations. Data gathering, analysis, and reporting to meet stringent federal and state requirements and standards are an integral part of the monitoring program. The current program meets the requirements of DOE Orders 5400.1 (General Environmental Protection Program), 5400.5 (Radiation Protection of the Public and Environment), and 231.1 (Environment, Safety, and Health Reporting), and DOE Regulatory Guide DOE/EH-0173T (Environmental Regulatory Guide for Radiological Effluent Monitoring and Environmental Surveillance).

The WVDP holds a State Pollutant Discharge Elimination System (SPDES) permit as required by the New York State Department of Environmental Conservation (NYSDEC), which regulates liquid effluent discharges containing nonradiological pollutants. The SPDES permit identifies the outfalls where liquid effluents are released to surface water drainage systems and specifies the sampling and analytical requirements for each outfall. It also specifies that concentrations of radionuclides at these outfalls must meet the requirements of DOE Orders 5400.1 and 5400.5.

Radiological air emissions must comply with the National Emission Standards for Hazardous Air Pollutants (NESHAP) regulations. Depending upon the potential to emit radionuclides, some radiological emission points must be permitted by the Environmental Protection Agency (EPA).

In addition, the site operates under state-issued air discharge permits for nonradiological plant emissions. The WVDP received final approval of a State Facility Air Permit from NYSDEC on June 1, 2000.

For more information about air and SPDES permits see the Environmental Compliance

Summary: Calendar Year 2000 (pp.ECS-7 and ECS-9). Environmental permits are listed at the back of the Environmental Compliance Summary (pp.ECS-22 through ECS-23).

Exposure Pathways Monitored at the West Valley Demonstration Project

The major near-term pathways for potential movement of contaminants away from the site are by surface water drainage and airborne transport. For this reason the environmental monitoring program emphasizes the collection of air and surface water samples.

Samples are collected on-site from locations such as plant ventilation stacks, various water effluent points, and surface water drainage locations. Analyses of samples of air, water, soils, and biota from the environment surrounding the site would detect radioactivity that might reach the public from site releases. Extensive groundwater monitoring addresses the subsurface pathway.

Water and Sediment Pathways. Process waters are treated through filtration and ion-exchange in a liquid-treatment facility, the LLW2. The treated water is sent to a series of on-site holding lagoons for testing before being discharged through a single outfall. (The locations of the lagoons are noted on Fig.A-2 [p.A-4] in Appendix A.) Samples of this process water and the effluent at two other discharge points are collected in accordance with permit requirements.

The samples are analyzed for radiological parameters, including gross alpha and gross beta, tritium, strontium-90, and gamma-emitting radionuclides, and for nonradiological parameters, including pH. Additional analyses of composite samples determine metals content,

solids, biochemical oxygen demand, nitrates, nitrites, ammonia, sulfate, organic chemicals, and specific radionuclides.

In general, surface water samples are collected regularly and analyzed, at a minimum, for gross alpha and gross beta radioactivity, tritium, and pH. Selected samples are analyzed for conductivity, chlorides, metals, volatile organic compounds, and other parameters. Potable water on the site is analyzed monthly for radioactivity and annually for chemical constituents. Residential drinking water wells located near the site are sampled annually and analyzed for gross alpha and gross beta radioactivity, tritium, gamma-emitting radionuclides, pH, and conductivity.

Off-site surface waters, primarily from Cattaraugus Creek and Buttermilk Creek, are sampled upstream of the Project for background radioactivity and downstream to measure possible Project contributions. Sediments deposited downstream of the facility and at upstream background locations are collected annually and analyzed for gross alpha, gross beta, and specific radionuclides. (See Appendix C [pp.C-3 through C-25] for water and sediment data summaries.)

Groundwater Pathways. Groundwater discharge at the WVDP site occurs as springs or seeps along stream channels, direct discharge to streams, evapotranspiration, vertical groundwater migration to underlying strata, and discharge to artificial draining systems and lagoons. All of these discharges vary with the seasons. Discharge from springs and seeps is highest during the spring. Evapotranspiration is at a maximum during the summer. Groundwater discharge is, in general, lowest during the winter because the ground surface is frozen, which minimizes recharge.

Routine monitoring of groundwater includes sampling for contamination and radiological

indicator parameters (pH and conductivity, and gross alpha, gross beta, and tritium) and for specific analytes of interest such as volatile organic compounds, semivolatile organic compounds, metals, and radionuclides at selected monitoring locations. (See Table E-1 [pp. E-3 through E-6] in Appendix E.)

Air Pathways. Permitted effluent air emissions are continuously monitored for alpha and beta activity. Alarms indicate any unusual rise in radioactivity. Air particulate sampling filters, which are retrieved and analyzed weekly for gross radioactivity, are also composited quarterly and analyzed for strontium-90 and specific gamma- and alpha-emitting radionuclides. Iodine-129 and tritium also are measured in effluent ventilation air at some locations. At two of the effluent locations silica gel-filled columns are used to collect water vapor that is then distilled from the desiccant and analyzed for tritium. The distillates are analyzed weekly. Six permanent samplers at effluent locations contain activated charcoal adsorbent that is analyzed for iodine-129; the charcoal is collected weekly and composited for quarterly analysis.

Off-site sampling locations include those considered most representative of background conditions and those most likely to be downwind of airborne releases. Among the criteria used to position off-site air samplers are prevailing wind direction, land usage, and the location of population centers.

Off-site air is continuously sampled at ten locations. Background samplers are located far from the site in Great Valley and Nashville, New York. Nearby-community samplers are in Springville and West Valley, New York. (See Fig.A-12 [p.A-14] in Appendix A for these four off-site air sampling locations.) Six samplers are located on the perimeter of the WNYNSC. (See Fig.A-5 [p.A-7] in Appendix A.) Samples from these

locations are analyzed for parameters similar to the effluent air samples. (See Appendix D [pp.D-3 through D-26] for air monitoring data summaries.)

Atmospheric Fallout. An important contributor to environmental radioactivity is atmospheric fallout. Sources of fallout include earlier atmospheric testing of atomic explosives and residual radioactivity from accidents such as that which occurred at Chernobyl in the Ukraine.

Four site perimeter locations and one on-site location currently are sampled for fallout using pot-type samplers that are collected every month. Long-term fallout is assessed by analyzing soil collected annually at each of the six perimeter and four off-site air samplers. Three additional on-site soil samples are taken annually. (See Appendix D [pp.D-24 through D-26] for fallout data summaries and Appendix C [pp.C-23 and C-24] for soil data summaries.)

Food Pathways. A potentially significant pathway for radioactivity to reach humans is through consuming produce, meat, and milk from domesticated farm animals raised near the WVDP and game animals and fish that live in the vicinity of the WVDP. Animal and fish samples from potentially affected areas are gathered and analyzed for radionuclide content in order to reveal any long-term trends. Fish are collected along Cattaraugus Creek at several locations downstream of the WVDP. Venison is sampled from deer ranging within the WNYNSC. Control samples of both fish and venison are collected from background areas outside WVDP influence. Beef, milk, hay, and produce samples also are collected at nearby farms and at selected locations well away from WVDP influence. (See Appendix F [pp.F-3 through F-8] for biological data summaries.)

Direct Radiation Measurement. Direct penetrating radiation is measured using thermoluminescent dosimeters (TLDs) located on- and off-site. Measurement points within the site are placed near selected waste management units and around the inner security fence. Other locations are around the site perimeter and access road and at background locations remote from the WVDP. Forty-three measurement points were used in 2000. The TLDs are retrieved quarterly and are processed by an off-site service to obtain the integrated gamma exposure. (See Appendix H [pp. H-3 through H-6] for a summary of the direct radiation data.)

Meteorological Monitoring

Meteorological data are continuously gathered and recorded at meteorological towers on-site and a nearby regional location south of the WNYNSC. Wind speed and direction, barometric pressure, temperature, dewpoint, and rainfall are measured on-site. Wind speed and direction are measured at the regional tower. These data are valuable for modeling both airborne dispersion and long-term hydrologic trends. In the event of an emergency, immediate access to the most recent meteorological data is indispensable for predicting the path and concentration of any materials that become airborne. (See Appendix I [pp. I-3 through I-8] for meteorological data summaries.)

Quality Assurance and Control

The work performed by and through the on-site Environmental Laboratory is regularly reviewed by several agencies for accuracy and compliance with applicable regulations. Assessments of the laboratory routinely focus

on proper record keeping and reporting, timely calibration of equipment, training of personnel, adherence to accepted procedures, and general laboratory safety.

The Environmental Laboratory also participates in quality assurance crosscheck programs administered by federal agencies. (See Appendix J [pp. J-3 through J-7] for a summary of cross-check performance.) The performance of outside laboratories contracted to analyze WVDP samples also is regularly assessed.

Environmental monitoring management continues to strengthen the formal self-assessment program, developing and implementing new strategies and procedures for ensuring high quality data. Experienced senior scientists and specialists in varying disciplines follow an annual schedule of self-assessments, produce formal reports with recommended corrective actions, and track the actions as they are completed.

into the EPA's National Environmental Performance Track. The WVDP was awarded Charter Member status as part of the first group of applicants.

To qualify for the award the WVDP had to demonstrate that it voluntarily has adopted and implemented an environmental management system, has attained previous specific environmental achievements, has made a commitment to achieve four future goals, and has a sustained record of environmental compliance.

The WVDP is one of only two DOE sites to hold both the EPA's highest award for environmental achievement and the DOE's STAR award for excellence in safety and health.

Safety Management System

During 1998 WVNS developed a safety management system for the WVDP, which was subsequently validated by the DOE Ohio Field Office. The safety management system integrates all safety programs, including environmental protection, to ensure that Project work can be safely and efficiently performed. As a continuation of this effort, the WVDP applied for the DOE Voluntary Protection Program STAR designation, reserved for companies that have demonstrated sustained excellence in their safety and health program. STAR status for the WVDP was announced in early 2000.

The WVDP also was recognized as a top environmental leader in 2000 and was accepted

ENVIRONMENTAL COMPLIANCE SUMMARY

CALENDAR YEAR 2000

Compliance Program

The West Valley Demonstration Project (WVDP) is currently focusing on several goals that will lead to eventual site closure. Processing of the high-level liquid waste into durable, solid glass is almost complete, and the WVDP is now working on removing and vitrifying residual radioactivity remaining in the high-level waste tanks. In addition, the WVDP is shipping low-level waste, constructing a remote-handled waste facility, actively managing on-site groundwater contamination, preparing for the shipment of spent nuclear fuel, and cleaning up facilities not presently used in anticipation of eventual closure.

The activities in progress at the WVDP are regulated by various federal and state laws that protect the public, workers, and the environment.

The U.S. Department of Energy (DOE), the federal agency that oversees the WVDP, established its policy concerning environmental protection in DOE Order 5400.1, General Environmental Protection Program. This Or-

der lists the regulations, laws, and required reports that are applicable to DOE-operated facilities. DOE Order 5400.1 and DOE Order 231.1, Environment, Safety, and Health Reporting, require the preparation of this annual site environmental report, which is intended to summarize environmental data gathered during the calendar year, describe significant environmental programs, and document WVDP compliance with environmental regulations.

The major federal environmental laws and regulations that apply to the West Valley Demonstration Project are the Resource Conservation and Recovery Act, the Clean Air Act, the Emergency Planning and Community Right-to-Know Act, the Clean Water Act, the Safe Drinking Water Act, the Toxic Substances Control Act, and the National Environmental Policy Act. These laws are administered primarily by the U.S. Environmental Protection Agency (EPA) and the New York State Department of Environmental Conservation (NYSDEC) through state programs and regulatory requirements such as permitting, reporting, inspecting, and self-auditing.

In addition, because the emission of radiological and nonradiological materials from an active facility cannot be completely prevented, the EPA, NYSDEC, and the DOE have established standards for such emissions that are intended to protect human health and the environment. The WVDP applies to NYSDEC and the EPA for permits that allow the site to release limited amounts of radiological and non-radiological constituents through controlled and monitored discharges into water and air in concentrations that have been determined to be safe for humans and the environment. In general, the permits describe the discharge points, specify management and reporting requirements, list the limits on those pollutants likely to be present, and define the sampling and analysis schedule.

A summary of permits may be found on pp. ECS-22 through ECS-23.

Environmental inspections and audits are conducted routinely by the EPA, NYSDEC, the New York State Department of Health (NYSDOH), and the Cattaraugus County Health Department. On-site and off-site radiological monitoring in 2000 confirmed that site activities were conducted well within state and federal regulatory requirements. On-site non-radiological effluent monitoring confirmed that site effluents remained within permitted limits.

Management at the WVDP continued to provide strong support for environmental compliance in 2000.

The WVDP has implemented an integrated safety management system (ISMS) to control work processes at all levels. Through the ISMS, DOE Orders and applicable state and federal environmental statutes and regulations are integrated into work activities, demonstrating a

commitment to protecting WVDP employees, the public, and the environment while working toward the WVDP goals.

Compliance Status

The following environmental compliance summary describes the federal and state laws and regulations that are applicable to the WVDP and the relevant environmental compliance activities that occurred at the WVDP during calendar year 2000.

Resource Conservation and Recovery Act (RCRA). The Resource Conservation and Recovery Act was enacted to ensure that hazardous wastes are managed in a manner that protects human health and the environment. RCRA and its implementing regulations govern the generation, treatment, storage, and disposal of hazardous waste. RCRA regulations mandate that generators take responsibility for ensuring the proper treatment, storage, and disposal of their wastes. The EPA is the federal agency responsible for issuing guidelines and regulations for the proper management of solid and hazardous waste (including mixed waste).

In New York, the EPA has delegated the authority to enforce these regulations to NYSDEC. In addition, the U.S. Department of Transportation (DOT) is responsible for issuing guidelines and regulations for the labeling, packaging, and spill-reporting provisions for hazardous and mixed wastes while in transit.

A Part A Permit Application (for interim status) is required for a facility that treats or stores large quantities of hazardous waste for more than 90 days or disposes of hazardous waste at that facility. The facility must apply for a permit from the EPA (or authorized state). The Part A Permit Application defines the treatment

processes to be used, the design capacities, the location of hazardous waste storage units, the design and operating criteria for disposal units, and the hazardous wastes to be managed.

In 1984 the DOE notified the EPA of hazardous waste activities at the WVDP and identified the WVDP as a generator of hazardous waste. In June 1990 the WVDP filed a RCRA Part A Hazardous Waste Permit Application with NYSDEC for storage and treatment of hazardous wastes and has been operating under interim status since then.

The WVDP updates its RCRA Part A Permit Application as changes to the site's interim-status waste-management operations occur. The permit application was updated in October 1995; a further update was developed in 2000 and submitted to NYSDEC in early 2001.

Hazardous Waste Management Program.

Hazardous wastes at the WVDP are managed in accordance with 6 NYCRR (New York Official Compilation of Codes, Rules, and Regulations) Parts 370-374 and 376. In order to dispose of hazardous wastes generated from on-site activities, the WVDP uses New York State-permitted transporters (pursuant to 6 NYCRR Part 364) to ship RCRA-regulated wastes to permitted or authorized treatment, storage, or disposal facilities (TSDFs). Using these services, the WVDP shipped approximately 1.79 metric tons (1.97 tons) of nonradioactive hazardous waste to off-site TSDFs in 2000.

Off-site hazardous waste shipments and their receipt at designated treatment, storage, or disposal facilities are documented by signed manifests that accompany the shipment. If the signed manifest is not returned to the WVDP within the regulatory limit of forty-five days from shipment, an exception report must be

filed and receipt of the waste confirmed with the TSDF. No exception reports for WVDP waste shipments were required to be filed in 2000. One exception report was filed in February 2001 for a shipment in 2000.

Hazardous waste activities must be reported to NYSDEC every year through the submittal of the facility's annual Hazardous Waste Report. This report summarizes the hazardous waste activities for the previous year, specifies the quantities of waste generated, treated, and/or disposed, and identifies the TSDFs used. The annual Hazardous Waste Report for calendar year 2000 was submitted to NYSDEC by March 1, 2001.

In addition, a hazardous waste reduction plan must be filed every two years and updated annually. This plan documents efforts to minimize the generation of hazardous waste and was first submitted to NYSDEC in 1990. The most recent Annual Status Report for the Hazardous Waste Reduction Program was updated in June 2000. The next update is due in July 2001.

An annual inspection to assess compliance with hazardous waste regulations was conducted by NYSDEC on March 31, 2000, and April 17, 2000. No deficiencies were noted.

Nonhazardous, Regulated Waste Management Program.

The WVDP shipped approximately 50 metric tons (55 tons) of nonradioactive, non-hazardous material off-site to solid waste management facilities in 2000. Of this amount, 3.1 metric tons (3.4 tons) were recycled or reclaimed. Some of the recycled materials were lead-acid batteries, nonhazardous oils such as motor oil, hydraulic oil, and compressor oil, and spent lamps, which were recycled at off-site authorized reclamation and recycling facilities. Lead-acid batteries and spent lamps are

managed as universal wastes. (See Glossary.) The WVDP also shipped approximately 1,810 metric tons (1,990 tons) of digested sludge and untreated wastewater from the site sanitary and industrial wastewater treatment facility to the Buffalo Sewer Authority for treatment.

Mixed Waste Management Program. Mixed waste contains both a radioactive component, regulated under the Atomic Energy Act, and a hazardous component, regulated under RCRA. Both the EPA and NYSDEC oversee mixed waste management at the WVDP.

In March 1993 the DOE entered into a Federal and State Facility Compliance Agreement (FSFCA) with the EPA, NYSDEC, the New York State Energy Research and Development Authority (NYSERDA), and West Valley Nuclear Services Company (WVNS), the primary contractor for the DOE at the WVDP. The FSFCA addressed requirements for managing the hazardous component of the mixed waste, storage requirements for mixed waste, and characterization of historical wastes in storage at the WVDP. Characterization of historical wastes was completed and the FSFCA terminated on March 22, 1999.

The Federal Facility Compliance Act (FFC Act) of 1992, an amendment to RCRA, required DOE facilities to prepare plans for treating their mixed waste inventories and to update these plans annually to account for development of treatment technologies, capacities, and changes in mixed waste inventories. Each plan was approved by the respective state agency or the EPA after consultation with other affected states and after consideration of public comments.

The WVDP's plan comprises two volumes: The Background Volume provides information on each mixed waste stream and information on the preferred treatment method for the waste.

The Plan Volume contains proposed schedules for treating the mixed waste to meet the land disposal restriction (LDR) requirements of RCRA.

The DOE and NYSDEC entered into a consent order on September 3, 1996 that requires the completion of the milestones identified in the Plan Volume. The WVDP began implementing its site treatment plan immediately and updates it annually to bring waste stream, inventory, and treatment information current to September 30, the end of the DOE fiscal year. An update of fiscal year 2000 activities was completed and submitted to NYSDEC in October 2000. All Plan Volume milestones for 2000 were met.

Shipments of mixed waste to off-site facilities for treatment and their receipt at the designated TSDF are documented via manifests. In 2000 the WVDP shipped approximately 5.62 metric tons (6.20 tons) of mixed waste to an off-site facility.

RCRA §3008(h) Administrative Order on Consent. The DOE and NYSERDA entered into a RCRA §3008(h) Administrative Order on Consent with NYSDEC and the EPA in March 1992. The Consent Order required NYSERDA and the DOE's West Valley Demonstration Project Office (OH/WVDP) to conduct RCRA-facility investigations (RFIs) at solid waste management units (SWMUs) in order to determine if there had been a release or if there is a potential for release of RCRA-regulated hazardous constituents from SWMUs. The final RFI reports were submitted in 1997, completing the investigative activities associated with the Consent Order. As a result of the RFIs, no corrective actions were required. Groundwater monitoring as specified in the RFI reports continued during 2000. The WVDP also continued to monitor SWMUs and to comply with the re-

quirements of the RCRA §3008(h) Administrative Order on Consent. (Monitoring results are detailed in Chapter 3.)

Waste Minimization and Pollution Prevention.

The WVDP continued a long-term program to minimize the generation of low-level radioactive waste, mixed waste, hazardous waste, industrial waste, and sanitary waste and to promote affirmative procurement as directed by Executive Order 13101 (Greening the Government Through Waste Prevention, Recycling, and Federal Acquisition) and Executive Order 13148 (Greening the Government Through Leadership in Environmental Management), which promote the Affirmative Procurement Program and RCRA §6002. The Affirmative Procurement Program specifies responsibilities and direction for federal agencies in acquiring recycled and environmentally preferable products and services designated by the EPA in 40 CFR Part 247. WVNS reports its challenges and successes associated with the purchase and use of these materials and services to the DOE each year.

On-site waste streams are separated into either waste from sources directly associated with the vitrification process or into other nonvitrification sources.

The WVDP set the following cumulative non-vitrification waste-reduction goals for 2000: an 85% reduction in the generation of low-level radioactive waste, a 70% reduction in the generation of mixed waste, a 40% reduction in the generation of nonvitrification hazardous waste, a 53% reduction in the generation of nonvitrification industrial waste, and a 65% reduction in the generation of sanitary waste, compared to an annualized 1993 total of waste generated. The waste-reduction goals for wastes associated with vitrification operations were a 95% reduction in vitrification hazardous wastes and

an 18% reduction in vitrification industrial waste, compared to an annualized 1996 total of waste generated.

All but one of these goals were met or exceeded during calendar year 2000. Low-level radioactive waste generation was reduced by 73%, missing the established goal of 85%. Mixed waste generation was reduced by 86%, nonvitrification hazardous waste by 40%, vitrification hazardous waste by more than 99%, nonvitrification industrial waste by 78%, vitrification industrial waste by 94%, and sanitary wastes by 83%. (See Chapter 1, pp.1-17 through 1-18, for more detailed information concerning waste minimization.)

Underground Storage Tanks Program. RCRA regulations also cover the use and management of underground storage tanks and establish minimum design requirements in order to protect groundwater resources from releases. The regulations, specified in 40 CFR Part 280, require underground storage tanks to be equipped with overfill protection, spill prevention, corrosion protection, and leak detection systems. New tanks must comply with regulations at the time of installation.

New York State also regulates underground storage tanks through two programs, petroleum bulk storage (6 NYCRR, Parts 612 — 614) and chemical bulk storage (6 NYCRR, Parts 595 — 599). The state registration and minimum design requirements are similar to those of the federal program except that petroleum tank fill ports must be color-coded using American Petroleum Institute standards to indicate the product being stored.

A 550-gallon double-walled steel underground storage tank, upgraded in 1998 to bring it into compliance with the most recent EPA requirements (40 CFR Part 280.21), is used to store

diesel fuel for the supernatant treatment system ventilation blower system. This tank is equipped with aboveground piping, an upgraded interstitial leak detection system, and a high-level warning device. This is the only underground petroleum-storage tank currently in use at the WVDP.

A former underground petroleum-storage tank, closed in place before the New York State underground storage tank program closure requirements were implemented in 1985, was removed in 1997. Testing of soils from the tank excavation had shown evidence of earlier petroleum leakage, and on March 19, 1999 the DOE and NYSDEC executed a Stipulation Agreement Pursuant to Section 17-0303 of the Environmental Conservation Law and Section 176 of the Navigation Law for mitigation of the petroleum contamination.

A bioventing system, installed in August 1999 to remediate localized petroleum-contaminated soils, stimulates natural in situ biodegradation of petroleum hydrocarbons in the soil by providing an abundant oxygen supply to existing soil microorganisms within the contaminated soil zone.

This system is scheduled to operate for two years and was operated continuously in 2000, except during any necessary maintenance. It is checked daily by site operations personnel, and the combined effluent airflow from the extraction wells is monitored weekly for total volatile organic compounds (VOCs) using a photoionization detector.

The system was assessed in August 2000. Results of this assessment indicated that the system is meeting its intended purpose of providing an oxygen supply to stimulate biodegradation

of contaminants present in the subsurface soils. A report was transmitted to NYSDEC in September 2000.

There are no underground bulk chemical storage tanks at the WVDP.

New York State-regulated Aboveground Storage Tanks. The state of New York regulates aboveground petroleum bulk storage under 6 NYCRR Parts 612, 613, and 614, and aboveground hazardous bulk chemical storage under 6 NYCRR Part 595 et seq. These regulations require secondary containment, external gauges to measure the current reserves, monthly visual inspections of petroleum tanks, and documented daily, annual, and five-year inspections of chemical tanks. Documentation relating to these periodic inspections is maintained by the WVDP and is available for regulatory agencies to review. Petroleum tank fill ports also must be color-coded and chemical tanks must be labeled to indicate the product stored.

WVDP registration at the end of 2000 included nine aboveground petroleum tanks and eleven aboveground chemical storage tanks. Three of the petroleum tanks contain No. 2 fuel oil, one contains unleaded gasoline, and the remainder contain diesel fuel. The Quality Assurance department inspects the aboveground petroleum tanks every month.

Nine of the chemical storage tanks are used as needed to contain nitric acid or nitric acid mixtures. Sodium hydroxide and anhydrous ammonia are stored in the remaining two tanks. All of the tanks are equipped with gauges and secondary containment systems except the anhydrous ammonia tank, which does not require secondary containment. (Any release of the contents of the anhydrous ammonia tank would be in gas-

eous form; thus, secondary containment is unnecessary.) The WVDP is in compliance with requirements to upgrade chemical bulk storage tanks that went into effect in December 1999.

Medical Waste Tracking. Medical waste poses a potential for humans to be exposed to infectious diseases and pathogens from contact with human bodily fluids. Medical evaluations, inoculations, and laboratory work at the on-site nurse's office regularly generate potentially infectious medical wastes that must be tracked in accordance with NYSDEC requirements (6 NYCRR Part 364.9).

The WVDP has retained the services of a permitted waste hauler and disposal firm to manage these medical wastes. Medical wastes are sterilized with an autoclave by the disposal firm to remove the associated hazard and then disposed. Fifteen kilograms (34 lbs) of medical waste consisting of dressings, protective clothing such as rubber gloves, and needles, syringes, and other sharps were generated and disposed in 2000.

Clean Air Act (CAA). The Clean Air Act, including Titles I through VI, establishes a framework for the EPA to regulate air emissions from both stationary and mobile sources. These amendments mandate that each state establish a program to permit the operation of sources of air pollution. In 1996 NYSDEC amended 6 NYCRR Parts 200, 201, 231, and 621 to implement the requirements of the new EPA Clean Air Act Title V permitting processes.

In New York State, either the EPA or NYSDEC issues permits for stationary sources that emit regulated pollutants, including hazardous air pollutants. Sources requiring permits are those that emit regulated pollutants from a particular

source (e.g., a stack, duct, vent, or other similar opening) if the pollutants are in quantities above a predetermined threshold. WVDP radiological emissions are regulated by the EPA. All other air pollutants are regulated by NYSDEC.

Air emissions of radionuclides from point sources at the WVDP are regulated by the EPA under the National Emission Standards for Hazardous Air Pollutants (NESHAP) regulations, 40 CFR Part 61, Subpart H, National Emission Standards for Emission of Radionuclides Other Than Radon From Department of Energy Facilities. The WVDP currently has permits for six radionuclide sources, including the slurry-fed ceramic melter and the vitrification heating, ventilation, and air conditioning (HVAC) system. Other less significant sources of radionuclide emissions, such as those from the on-site laundry, do not require permits.

Non-point radiological sources of air emissions such as lagoons also do not require permits. Emissions from all these sources are quantified for reporting to the EPA. The WVDP reports the radionuclide emissions from its non-permitted and permitted sources to the EPA annually in accordance with NESHAP regulations. Calculations to demonstrate compliance with NESHAP radioactive dose limits showed calendar year 2000 doses to be less than 0.1% of the 10 millirem standard. (See Table 4-2 [p.4-6].)

Nonradiological point sources of air emissions are regulated by NYSDEC. Major-source facilities are required by 6 NYCRR Part 201 to file a Title V Permit Application, unless operating limits are established, to ensure that the facility does not emit pollutants above the threshold limits. The WVDP demonstrated that emissions of nitrogen oxides (NO_x) and sulfur

dioxide (SO₂) were each below the threshold limit of 100 tons per year. Thus, the WVDP is not required to file a Title V permit.

The WVDP opted to file a State Facility Permit Application for the site. A State Facility Permit modification to incorporate sitewide air emission sources was submitted in December 1997 and approved June 1, 2000. Annual NO_x and SO₂ emissions under the updated permit are capped at 99 tons each. A compliance assessment in June 2000 verified that all conditions of this permit were being met.

The permit describes the conditions of the NO_x and SO₂ capping plan and the operational conditions for the boilers, melter, cold chemical facility, and the vitrification HVAC system. In July 1999 NYSDEC granted the WVDP a waiver of quarterly submissions of NO_x and SO₂ emission totals. The WVDP is required to submit only an annual certification, in January, that contains NO_x and SO₂ emission totals. The 2000 certification reported 7.44 tons of NO_x and 0.77 tons of SO₂, which were well below the 99-ton cap for each category.

The WVDP also conducts cylinder gas audits every quarter but is no longer required to conduct relative accuracy test audits of the melter off-gas NO_x analyzers.

The air permits that were in effect at the WVDP in 2000 are included on the West Valley Demonstration Project Environmental Permits table (pp. ECS-22 through 23). There were no air permit or regulatory exceedances in 2000. (See also the West Valley Demonstration Project 2000 Air Quality Noncompliance Episodes table on p. ECS-20.)

Emergency Planning and Community Right-to-Know Act (EPCRA). The Emergency Planning and Community Right-to-Know Act was

enacted as Title III of the Superfund Amendments and Reauthorization Act (SARA). EPCRA was designed to create a working partnership between industry, business, state and local governments, public health and emergency response representatives, and interested citizens. EPCRA is intended to address concerns about the effects of chemicals used, stored, and released in local communities.

Executive Order 12856, Federal Compliance with Right-to-Know Laws and Pollution Prevention Requirements, requires all federal agencies to comply with the following EPCRA provisions: planning notification (Sections 302—303), extremely hazardous substance (EHS) release notification (Section 304), material safety data sheet (MSDS)/chemical inventory (Sections 311—312), and toxic release inventory (TRI) reporting (Section 313). The WVDP continued to comply with these provisions in 2000. (See also the EPCRA Compliance Chart on p. ECS-21.)

- WVDP representatives participated in semi-annual meetings of the Cattaraugus County Local Emergency Planning Committee (EPCRA Sections 302—303). WVDP representatives also attended meetings held by the Cattaraugus and Erie County Emergency Management Services concerning WVDP and other local emergency planning activities. Area hospitals and the West Valley Volunteer Hose Company continued to participate in on-site training drills and in information exchanges concerning hazardous-substance management at the WVDP.

- Compliance with all EPCRA reporting requirements was maintained and all required reports were submitted within the required time frame. There were no releases of extremely hazardous substances (EHS) at the WVDP that triggered the release notification requirements of Section 304 of EPCRA.

- Under EPCRA Section 311 requirements, the WVDP reviews information about reportable chemicals every quarter. If a hazardous chemical, which was not previously reported, is present on-site in an amount exceeding the threshold planning quantity, an MSDS and an updated hazardous chemical list are submitted to the state and local emergency response groups. This supplemental reporting ensures that the public and the emergency responders have current information about hazardous chemicals at the WVDP. No new chemicals were added to the hazardous chemicals list in 2000 and no additional EPCRA Section 311 notifications were required.

- Under EPCRA Section 312 regulations, the WVDP submits annual reports to state and local emergency response organizations and fire departments that specify the quantity, location, and hazards associated with chemicals stored on-site. Seventeen reportable chemicals above threshold planning quantities were stored at the WVDP in 2000. (A list of reportable chemicals is provided on p. ECS-21.)

- Under EPCRA Section 313 the WVDP provides information about releases to all environmental media of EPA-listed Toxic Release Inventory (TRI) chemicals that are used at or above specified regulatory thresholds at the WVDP. TRI reports are filed for the preceding year. In 1999 the WVDP used one TRI chemical above the regulatory threshold amount of 10,000 lbs: nitric acid. Thus, the TRI report for this chemical was filed with the EPA in 2000.

Clean Water Act (CWA). Section 404 of the CWA regulates the development of areas in and adjacent to the waters of the United States. Supreme Court interpretations of Section 404 have resulted in the inclusion of certain non-isolated wetlands in the regulatory definition of waters of the United States. Section 404 regulates the

disposal of solids, in the form of dredged or fill material, into these areas by granting the U.S. Army Corps of Engineers the authority to designate disposal areas and issue permits for these activities. Executive Order 11990, Protection of Wetlands, directs federal agencies to “avoid to the extent possible the long and short term adverse impacts associated with the destruction or modification of wetlands and to avoid direct or indirect support of new construction in wetlands wherever there is a practical alternative.” (Article 24 of the New York State Environmental Conservation Law also contains requirements for the protection of freshwater wetlands.)

In addition, Section 401 of the CWA requires applicants for a federal license or permit pursuant to Section 404 to obtain certification from the state that the proposed discharge complies with effluent and water quality-related limitations, guidelines, and national standards of performance identified under sections 301, 302, 303, 306, 307, and 511(c) of the CWA. The EPA has delegated administration of this program to New York State.

Wetlands. Jurisdictional wetlands are defined in Clean Water Act Section 404 as those satisfying specific technical criteria related to vegetation, soils, and hydrologic conditions. The WVDP notifies the U.S. Army Corps of Engineers and NYSDEC of proposed actions that could affect wetland units not specifically exempted from regulation or notification.

A wetlands assessment in August 1998 identified and delineated jurisdictional wetlands regulated under the Clean Water Act, Section 404, and/or those wetlands that may be regulated by the state of New York under Article 24 of the Environmental Conservation Law. The 375-acre (152-hectare) assessment area covered a portion of the Western New York Nuclear Service

Center (WNYNSC), including the entire 200-acre (89-hectare) WVDP and adjacent parcels north, south, and east of the WVDP premises. The assessment also supported the requirements of Executive Order 11990, Protection of Wetlands, and updated a 1993 investigation. Fifty-nine jurisdictional wetlands ranging in size from 0.01 acres to 8.6 acres, a total of approximately 39 acres (16 hectares) of wetland, were identified. This wetland delineation was submitted to the U.S. Army Corps of Engineers for verification of the wetland boundaries. Verification was obtained in November 1999.

Additional jurisdictional wetlands in a 150-ft corridor along both sides of the railroad spur from the southern fenced boundary of the Project premises to the intersection with Fox Valley Road were assessed in August and September 1999. Twenty-three separate wetland units ranging in size from 0.01 acres to 4.7 acres, a total of approximately 12 acres (5 hectares), were identified.

In December 1999 a Joint Application for Permit was submitted to NYSDEC and the U.S. Army Corps of Engineers for activities in Buttermilk Creek and in or near the wetlands associated with the railroad spur. These activities included repairs to the culvert that carries the railroad over Buttermilk Creek and improvements to portions of the railyard storm water drainage system. In April 2000 an Individual Dredge and Fill Permit was obtained from the Army Corps of Engineers and a Water Quality Certification and Freshwater Wetlands permit was obtained from NYSDEC for these activities.

An additional wetland unit at the foot of the Lake No. 1 dam was delineated in August 2000 to verify permitting requirements for improvements to the dam. NYSDEC and the Corps of Engineers reviewed the wetland mapping and


the associated information and subsequently determined that these improvements were not within their permitting jurisdiction. The improvements were initiated in October 2000. The purpose of the railroad spur and dam improvements was to facilitate off-site shipment of spent nuclear fuel, which began during the first half of 2001.

Storm Water Discharge Permit. Section 402 of the Clean Water Act of 1972 generally regulates disposal of liquids and, as amended, authorizes the EPA to regulate discharges of pollutants to surface water through a National Pollutant Discharge Elimination System (NPDES) permit program. The EPA has delegated this authority to the state of New York, which issues State Pollutant Discharge Elimination System (SPDES) permits for discharges to surface water.

Surface water runoff from precipitation can become contaminated with pollutants from industrial process facilities, material storage and handling areas, access roads, or vehicle parking areas. To protect the environment, aquatic resources, and public health, Section 402(p) of the Clean Water Act requires that a storm water discharge permit application containing facility-specific information be submitted to the permitting authority. NYSDEC, the permitting authority in New York State, uses this information to ascertain the potential for pollution from storm water collection and discharge systems and to determine appropriate permitting requirements.

In April 1996 the WVDP obtained storm water characterization data through sampling and analysis and submitted an application for a modification of the SPDES permit to address overall site storm water discharges. The permit application is currently with NYSDEC awaiting final approval.

**WVDP SPDES Permit Limit Exceptions
1982-2000**



Number of samples collected in 2000: 1,106. Number of analyses: 2,180.
Compliance with the SPDES permit limit was 100%.

A permit application covering changes addressing storm water and process water discharges associated with the construction and operation of the new remote-handled waste facility and with the operation of the site's refurbished railroad spur was submitted to NYSDEC in September 2000. The permit modification is not expected until 2002.

SPDES-permitted Outfalls. Point-source liquid effluent discharges to surface waters of New York State are permitted through the New York SPDES program. The WVDP has four SPDES-permitted compliance points for discharges to Erdman Brook and Frank's Creek.

- Outfall 001 (WNSP001) discharges treated wastewater from the low-level waste treatment facility and the north plateau groundwater recovery system. (See North Plateau Groundwater Recovery System [p.ECS-12] and Chapter 3, Groundwater Monitoring, Special Groundwater Monitoring [p. 3-16].) The treated wastewater is held in lagoon 3, sampled and analyzed, and periodically released after notifying

NYSDEC. In 2000 the treated wastewater from the low-level waste treatment facility was discharged at WNSP001 in six batches totaling 43.7 million liters (11.5 million gal) for the year. The annual average concentration of radioactivity at the point of release was approximately 34% of the DOE derived concentration guides (DCGs). None of the individual releases exceeded the DCGs. (See *derived concentration guide* in the Glossary and in Chapter 1 [p.1-5].)

- Outfall 007 (WNSP007) discharges the effluent from the site sanitary and industrial wastewater treatment facility, which treats sewage and various nonradioactive wastewaters from physical plant systems (e.g., water plant production residuals and boiler blowdown). The average daily flow at WNSP007 in 2000 was 55,800 liters (14,700 gal).
- Outfall 008 (WNSP008) discharges groundwater and surface water runoff directed from the northeast side of the site's low-level waste treatment facility (LLWTF) lagoon system through a french drain. The average daily flow at WNSP008 in 2000 was 7,110 liters (1,880 gal).
- Monitoring point 116, located in Frank's Creek, represents the confluence of discharge from outfalls 001, 007, and 008; base stream flow; wet weather flows (e.g., surface water runoff); groundwater seepage; and augmentation water (untreated water from the site reservoirs). This is not a physical outfall but a location where the combination of source-flow inputs is used to calculate values for determining compliance with SPDES permit limits dur-

ing discharge of lagoon 3. Before discharge of lagoon 3, sample data for total dissolved solids (TDS) and flow measurements from upstream sources are used to calculate the amount of augmentation water and flow needed to maintain compliance with SPDES-permitted TDS limits.

As shown on the chart on p. ECS-11, the annual number of exceptions to the discharge concentration limits specified in the site's SPDES permit have been substantially reduced, especially when compared to the peak of thirty-five exceptions noted in 1986. In 2000, for the third consecutive year, no exceptions were reported. (See also p.ECS-20.)

In March 2000 NYSDEC conducted its annual facility inspection. At the request of the inspector, the SPDES outfalls, the sanitary and industrial wastewater treatment facility, and the LLWTF were observed. No violations were noted during the inspection.

SPDES permit modifications. In 1999 increasing concentrations of total mercury were observed in process water collected in the low-level waste treatment facility. The source of the mercury was determined to be process water from the liquid waste treatment system evaporator. (The evaporator is used to reduce the volumes of liquid waste generated during processing of high-level radioactive waste.) Negotiations with NYSDEC regarding additional SPDES permit monitoring requirements and limits were initiated in 1999. It is expected that a final SPDES permit that addresses mercury will be issued in 2001.

In March 1996 a SPDES permit application was submitted to NYSDEC to increase the average flow of effluent from the north plateau groundwater recovery system from approximately 9.8

million liters (2.6 million gal) a year to approximately 39.7 million liters (10.5 million gal) a year. (See North Plateau Groundwater Recovery System below.) NYSDEC issued the draft SPDES permit in June 1997 for public comment. A final permit is expected to be issued to the WVDP in 2001.

North Plateau Groundwater Recovery System.

In November 1995 the WVDP installed a groundwater recovery system to mitigate the movement of strontium-90 contamination in the groundwater northeast of the process building. Three recovery wells, installed near the leading edge of the groundwater plume, collect contaminated groundwater from the underlying sand and gravel unit. The groundwater is then treated in the new low-level waste treatment facility (LLW2) using ion-exchange to remove strontium-90. After the groundwater is processed, it is discharged to lagoon 4 or 5, near the LLW2. Approximately 83 million liters (22 million gal) of groundwater have been processed through the system since its inception, including about 16 million liters (4.2 million gal) in 2000.

In 1998 the Project began evaluating in-place permeable treatment wall (PTW) technology for treating contaminated groundwater. PTW technology is a passive treatment method, i.e., neither pumps nor a separate water treatment system are used. Rather, contaminants are removed from the groundwater as it flows through a subsurface trench filled with treatment media. Laboratory benchscale tests were initiated in December 1998 to examine this technology for removal of strontium-90 in WVDP groundwater, and a pilot-scale treatment wall was installed in 1999. Since its installation, chemical and water-level data have been collected and continue to be evaluated. Analytical data collected from within the wall indicate that stron-

tium-90 is removed from groundwater entering the wall. Groundwater elevation data suggest that some groundwater is bypassing the PTW. A detailed evaluation of groundwater conditions in and around the pilot PTW began in February 2001.

Petroleum- and Chemical-Product Spill Reporting. The WVDP has a Spill Notification and Reporting Policy to ensure that all spills (see Glossary) are properly managed, documented, and remediated in accordance with applicable regulations. This policy identifies the departmental responsibilities for spill management and the proper spill-control procedures. The policy stresses the responsibility of each employee to notify the main plant operations shift supervisor upon discovery of a spill. This first-line reporting requirement helps to ensure that spills are properly evaluated and managed.

Under a 1996 agreement with NYSDEC regarding petroleum spill-reporting protocol, the WVDP is not required to report spills of petroleum products of 5 gallons or less onto an impervious surface that are cleaned up within two hours of discovery. Petroleum-product spills of 5 gallons or less onto the ground are entered in a monthly petroleum spill log, which is submitted to NYSDEC by the fifteenth day of the following month. Spills of any amount that travel to waters of the state must be reported within two hours to the NYSDEC spill hotline and also are entered in the monthly log. Spills of petroleum products that enter navigable waters of New York State are reported to the National Response Center within two hours of discovery. There were no spills to navigable waters at the WVDP in 2000.

The WVDP also reports spills or releases of hazardous substances in accordance with the reporting requirements of RCRA, the Compre-

hensive Environmental Response, Compensation, and Liability Act (CERCLA) if a reportable quantity has been exceeded, and the CAA, EPCRA, the CWA, and the Toxic Substances Control Act (TSCA). No chemical spills or releases exceeded reportable quantities and, thus, no reporting during calendar year 2000 was required.

In the event of a spill or release all spills are cleaned up in a timely manner in accordance with the WVDP Spill Notification and Reporting Policy, thereby minimizing any effects on the environment. Debris generated during cleanup is characterized and dispositioned appropriately.

Safe Drinking Water Act (SDWA). The Safe Drinking Water Act requires that each federal agency having jurisdiction over a federally owned or maintained public water system must comply with all federal, state, and local requirements regarding safe drinking water. Compliance with regulations promulgated under the SDWA in the state of New York is overseen by the New York State Department of Health (NYSDOH) through county health departments.

The WVDP obtains its drinking water from surface water reservoirs on the WNYNSC and is considered a non-transient, noncommunity public water supplier. The WVDP's drinking water treatment facility purifies the water by clarification, filtration, and chlorination before it is distributed on-site.

As an operator of a drinking water supply system, the WVDP routinely collects and analyzes drinking water samples to monitor water quality. The results of these analyses are reported to the Cattaraugus County Health Department, which also independently analyzes a sample of WVDP drinking water every month to deter-

mine bacterial and residual chlorine content. Analysis of the microbiological samples collected in 2000 produced satisfactory results and the free chlorine residual measurements taken throughout the distribution system were positive on all occasions, indicating proper disinfection.

The WVDP regularly tests the site's drinking water for lead and copper in accordance with EPA and NYSDOH regulations. NYSDOH regulations allow a facility to reduce sampling from once a year to once every three years if three consecutive annual sampling campaigns produce results below the action level. Because sampling for lead and copper in 1997, 1998, and 1999 indicated that all results were below the action levels for these metals, the next scheduled sampling for lead and copper will be in 2002.

The Cattaraugus County Health Department conducted its annual inspection of the WVDP water supply system on November 8, 2000. No findings or notices of violation were issued.

Toxic Substances Control Act (TSCA). The Toxic Substances Control Act of 1976 regulates the manufacture, processing, distribution, and use of chemicals, including asbestos-containing materials (ACM) and polychlorinated biphenyls (PCBs).

Asbestos-containing materials. The WVDP Asbestos Management Plan update (West Valley Nuclear Services Co. October 26, 1999) includes results of a review of the asbestos-management program completed by the WVDP Waste Operations department in January 1999.

In 2000 the WVDP continued to maintain compliance with all TSCA requirements pertaining to asbestos by managing asbestos-containing material (ACM) at the site in accordance with

the Asbestos Management Plan. The plan was prepared to ensure compliance with TSCA requirements and includes requirements for limiting worker exposure to ACM and for asbestos-abatement projects, maintenance activities, and periodic surveillance inspections (at least once every three years). The plan also identifies the inventory and status of on-site ACM.

Activities in 2000 included the repair or abatement of damaged/friable ACM, removal of ACM insulation from abandoned lines, removal of nonfriable asbestos duct insulation from the fuel receiving and storage (FRS) ventilation building, and the maintenance of signs and labels to warn workers of asbestos-containing material. All activities associated with ACM are completed by personnel who are certified by the New York State Department of Labor (NYSDOL). WVNS maintains an asbestos-handling license issued by NYSDOL.

PCBs. Because PCBs are regulated as a hazardous waste in New York State, the WVDP continued in 2000 to manage radioactively contaminated PCB waste as mixed waste and non-radioactive PCB waste as hazardous waste. Details concerning PCB-contaminated radioactive waste management, including a description of the waste and proposed treatment technologies and schedules, can be found in section 3.1.5 of the Site Treatment Plan, Fiscal Year 2000 Update (West Valley Nuclear Services Co. October 25, 2000).

To comply with TSCA, all operations associated with PCBs comply with the PCB and PCB-Contaminated Material Management Plan (West Valley Nuclear Services Co., Inc. December 28, 1998). The WVDP also maintains an annual document log that details PCB use and appropriate storage on-site and any changes in storage or disposal status. The WVDP com-

plies with the regulations for the disposal of PCBs, which conditionally allow radioactive and nonradioactive PCB wastes to be stored for more than one year (40 CFR Parts 750 and 761).

National Environmental Policy Act (NEPA).

The National Environmental Policy Act of 1969, as amended, establishes a national policy to ensure that protection of the environment is included in federal planning and decision making (Title I). Its goals are to prevent or eliminate potential damage to the environment that could arise from federal legislative actions or proposed federal projects.

Nationwide Management of Waste. In May 1997 DOE Headquarters issued the Final Waste Management Programmatic Environmental Impact Statement (EIS) to evaluate nationwide management and siting alternatives for the treatment, storage, and disposal of five types of radioactive and hazardous waste. The alternatives address waste generated, stored, or buried over the next twenty years at fifty-four sites in the DOE complex.

The Final Waste Management Programmatic EIS was issued with the intent of developing and issuing separate records of decision for each type of waste analyzed. In 1998 the DOE issued records of decision for transuranic and non-wastewater hazardous waste. In 1999 the DOE issued the record of decision for high-level radioactive waste. This decision specifies that the WVDP high-level vitrified waste will remain in storage on-site until it is accepted for disposal at a geologic repository.

On December 10, 1999 the DOE issued its preferred alternative for the management of low-level radioactive waste and mixed low-level waste. Hanford and the Nevada Test Site were identified as the preferred regional disposal

sites for these waste types (64 Federal Register 69241). The Federal Register notes that the term “regional” does not impose geographic restrictions on which DOE sites could ship low-level and mixed low-level waste to these disposal sites.

Completion of the WVDP and Closure of the WNYNSC. The DOE and NYSERDA continued efforts in 2000 to develop a preferred alternative for completion of the WVDP and closure or long-term management of the WNYNSC. Late in the summer of 2000 the DOE announced a new approach to reaching its goal for completion of the WVDP: the environmental impact statement decision-making would be separated into two phases by re-scoping the Draft Environmental Impact Statement for Completion of the West Valley Demonstration Project and Closure or Long-term Management of Facilities at the Western New York Nuclear Service Center (DOE-EIS-0226-D).

Re-scoping would allow for two separate environmental impact statements: a WVDP decontamination and waste management EIS and a West Valley site decommissioning and/or long-term stewardship EIS. In this way, actions ready for decision-making could be separated from actions such as site closure or long-term management that would benefit from additional evaluation.

Under this revised EIS strategy, OH/WVDP will focus in the near-term on decontamination and waste management. Waste will be shipped off-site for disposal, and the main process building, the vitrification facility, and the high-level waste tank farm will be decontaminated and placed in a safe condition until they can be decommissioned. Site closure and long-term stewardship issues will become the subject of a new EIS.

Migratory Bird Treaty Act. The WVDP monitors Project activities to ensure continued compliance with the requirements of both the Migratory Bird Treaty Act and the Endangered Species Act. A New York State Fish and Wildlife License allows the WVDP to remove nests of migratory birds as needed to avoid the potential spread of radioactive contamination or to otherwise protect the health and safety of Project employees and visitors. The WVDP's license (DWP00-001) was received from NYSDEC on January 23, 2001 and is effective from January 1, 2001 through December 31, 2001.

Every two years the WVDP updates its information about the potential for federally listed or proposed endangered or threatened species to be in the vicinity of Project activities. This was originally done via correspondence with the U.S. Fish and Wildlife Service in June 1999. Their reply on June 21, 1999, reconfirmed that "except for occasional transient individuals" no plant or animal species protected under the Endangered Species Act were known to exist at the WVDP. An update of the information on the Endangered Species Act list will be requested from the U.S. Fish and Wildlife Service in the spring of 2001.

Current Achievements and Program Highlights

The WVDP's successful high-level waste vitrification program is one of only two such programs operating in the nation.

Phase II Vitrification. Phase II of vitrification, processing the high-level waste residuals (heels) in storage tank 8D-2, continued in 2000. Nine glass canisters were filled during this phase of operation, bringing the total number processed since operations began in 1996 to 254 canisters.

Considerable progress has been made in the development and deployment of radiological instrumentation for remote surveying of the interior surfaces of the high-level waste tanks. This includes installing beta/gamma probes, gamma detectors, and neutron detectors. The instruments are installed through the tank riser openings and remain within the tank for a predetermined period of time. They are then removed for analysis so that the radionuclide content remaining in the tank can be assessed and compared against future characterization goals.

Integrated Safety Management System (ISMS). In August 2000 a self-assessment was conducted to confirm that the WVDP's integrated environmental, safety, and health management system continued to function as verified in the DOE's annual review in February 2000. The WVDP continues to demonstrate its commitment to an all-inclusive approach to safety through its safety programs and through ongoing efforts to strengthen its integrated safety management program by worker involvement in the safety program.

STAR Status. The DOE Voluntary Protection Program (VPP) is based on a program developed by the Occupational Safety and Health Administration (OSHA). The DOE adopted the VPP to recognize superior health and safety performance by contractor management and employees. On May 5, 2000 the WVDP received VPP STAR Status, the highest safety award given within OSHA or the DOE.

U.S. EPA National Environmental Achievement Track. The WVDP was recognized as a top environmental leader in 2000 and was accepted into the EPA's National Environmental Achievement Track. The WVDP was awarded Charter Member status as part of the first group of applicants.

To qualify for the award the WVDP had to demonstrate that it voluntarily has adopted and implemented an environmental management system (EMS), has attained previous specific environmental achievements, has made a commitment to achieve four future goals, has a public outreach program, and has a sustained record of environmental compliance.

Acceptance into the Achievement Track allows the WVDP to use the Achievement Track logo, the EPA's recognition of accomplishments under the Achievement Track program. The WVDP also will be listed on the EPA's National Environmental Performance Track website and other EPA internet sites and will be mentioned in promotional materials related to the program. In December 2000 the EPA held a special award ceremony in Washington, D.C. for all facilities accepted into the program. Representatives from the site's DOE office and WVNS attended the ceremony.

Environmental Management System (EMS).

WVNS's environmental management system comprises procedures that provide the basic policy and direction for accomplishing work through proactive management, environmental stewardship, and the integration of appropriate technologies across all Project functions. Environmental management is integrated with other safety management and work planning processes at the WVDP through the integrated environmental, health, and safety management program (ISMS).

The WVNS EMS satisfies the requirements of both the Code of Environmental Management Principles (CEMP) for federal agencies and ISO (International Organization for Standardization) 14001, Environmental Management Systems: Specifications for Guidance and Use, which are the two major frameworks for envi-

ronmental management systems. The CEMP was developed by the EPA in response to Executive Order 12856, Federal Compliance with Right-to-Know Laws and Pollution Prevention Requirements. It embodies the principles and underlying performance objectives that are the basis for responsible environmental management. ISO 14001 is an EMS comparable to the CEMP.

Closed Landfill Maintenance. Closure of the on-site nonradioactive construction and demolition debris landfill (CDDL) was completed in August 1986. The landfill area was closed in accordance with NYSDEC requirements for this type of landfill, following a closure plan (Standish 1985) approved by NYSDEC. To meet routine post-closure requirements, the CDDL cover was inspected twice in 2000 and found to be in generally good condition. The grass cover on the clay and soil cap is routinely maintained and cut, and drainage is maintained to ensure that no obvious ponding or soil erosion occurs.

Release of Materials Containing Residual Radioactivity. The release of property containing residual radioactivity from DOE facilities is carefully controlled by DOE guidelines and procedures. In two special memoranda issued in January and July of 2000, the Secretary of Energy placed a moratorium on the release of contaminated materials and on the unrestricted release, for recycling, of metal from radiological areas within DOE facilities. The moratorium will be in place until directives clarifying the release criteria have been developed and implemented. Any transfer that places property (real property, structures, equipment, or scrap metal) containing radioactivity into public use is classified as a type of environmental release. In keeping with DOE initiatives to expand environmental information provided to the public, certain details of transfers of property

containing residual radioactivity are to be included in annual site environmental reports. The information provided should include, among other things, the type of material and the amount of residual radioactivity, the basis for releasing the property for public use (including release limits and when the property was released), the end use and cost savings associated with release of the property, and potential doses to individuals and the potential collective dose to the public associated with each release. The WVDP did not release any property classified per DOE Order 5400.5 as material containing residual radioactive material in 2000. (See also the Release of Property Containing Residual Radioactive Material table on p. ECS-20.)

Flood Protection: Water-Supply Dam Repairs.

In 1998 an inspection by NYSDEC of the site's two water-supply reservoir dams and the emergency spillway showed that an area around dam #1 had slumped and, although structurally sound, repairs were needed. Plans and permit applications for the repairs and improvements were filed with NYSDEC and the Corps of Engineers in October 2000. NYSDEC concurred with the plans and the Corps determined that no permit was required. Work began in the fall of 2000 and was completed in spring 2001.

Completion of the WVDP and Closure of the WNYNSC. Although negotiations conducted between the DOE and NYSERDA through January 2001 did not reach agreement on long-term cleanup responsibilities, both parties remain committed to accomplishing important Project-related goals. These include shipping the 125 spent fuel assemblies to Idaho; completing high-level waste vitrification; working with the NRC on decontamination and decommissioning criteria; and completing environmental impact statement analyses to support decisions on facility decontamination, waste management, and

site decommissioning and/or long-term stewardship. (See also p.ECS-15.) Other important Project goals include safely managing low-level waste, constructing the remote-handled waste facility, and managing contaminated groundwater on the north plateau.

Project Assessment Activities in 2000

As the primary contractor for the DOE at the WVDP, WVNS maintains a comprehensive review program for proposed and ongoing operations. Assessments are conducted through formal surveillances and informal programs. Formal surveillances monitor compliance with regulations, directives, and DOE Orders.

The informal program is used to identify issues or potential problems that can be corrected on the spot. The local DOE Project office also independently reviews various aspects of the environmental and waste management programs, and in 2000 overall results of the reviews reflected continuing, well-managed environmental programs at the WVDP.

Significant external environmental overview activities in 2000 included inspections by NYSDEC for compliance with RCRA and SPDES and an annual compliance inspection of the WVDP potable water supply system by the Cattaraugus County Health Department. These inspections did not identify any environmental program findings and further demonstrated the WVDP's commitment to protection of the environment.

Compliance Tables

DOE Headquarters uses environmental compliance summary information from sites across the DOE complex to compile national environmental summary reports. The tables on the following pages were prepared to assist in this compilation.

West Valley Demonstration Project 2000 Air Quality Noncompliance Episodes

Permit Type	Facility	Parameter	Date(s) Exceeded	Description / Solutions
<i>EPANESHAP</i>	<i>All</i>	<i>All</i>	<i>None</i>	<i>None</i>
<i>NYSDEC Air</i>	<i>All</i>	<i>All</i>	<i>None</i>	<i>None</i>

There were no episodes of noncompliance in 2000.

West Valley Demonstration Project 2000 NPDES/SPDES Permit Limit Noncompliance Episodes

Permit Type	Outfall	Parameter	Date(s) Exceeded	Description / Solutions
<i>SPDES</i>	<i>All</i>	<i>All</i>	<i>None</i>	<i>None</i>

There were no episodes of noncompliance in 2000.

Release of Property Containing Residual Radioactive Material

Approved Limit	Rationale	Date of Approval	Type of Material Released	Basis for Release	End Use	Volume of Material Released	Total Activity	Maximum Individual Dose	Collective Dose
<i>NA</i>	<i>NA</i>	<i>NA</i>	<i>None</i>	<i>NA</i>	<i>NA</i>	<i>0</i>	<i>0</i>	<i>0</i>	<i>0</i>

No property containing residual radioactivity was released in 2000.

EPCRA Compliance in 2000

EPCRA 302-303:

Planning Notification	[] Yes	[] No	[] Not Req.
-----------------------	---------	--------	--------------

EPCRA 304:

EHS Release Notification	[] Yes	[] No	[] Not Req.
--------------------------	---------	--------	--------------

EPCRA 311-312:

MSDS/Chemical Inventory	[] Yes	[] No	[] Not Req.
-------------------------	---------	--------	--------------

EPCRA 313:

TRI Reporting	[] Yes	[] No	[] Not Req.
---------------	---------	--------	--------------

***Reportable Chemicals Above Threshold Planning Quantities
Stored at the WVDP in 2000***

Anhydrous ammonia	Diesel fuel #2
Ferric hydroxide slurry	Gasoline
Hydrogen peroxide solution (35%)	Ion-exchange media
Liquid nitrogen	Lithium hydroxide
Lubricating oils	Nitric acid
Portland cement	Potassium hydroxide
Silicon dioxide	Sodium hydroxide
Sodium tetraborate decahydrate	Sulfuric acid
Zinc bromide solution	

West Valley Demonstration Project Environmental Permits

<i>Permit Name and Number</i>	<i>Agency/Permit Type</i>	<i>Description</i>	<i>2000 Changes</i>	<i>Status</i>
West Valley Demonstration Project Part A Permit Application	NYSDEC	Provides interim status under RCRA for treatment and storage of hazardous waste	None	No expiration date.
Article 19 State Facility Air Permit 90422-00005/00091	NYSDEC	Sitewide permit includes: <ul style="list-style-type: none"> • 2 boilers • cold chemical solids transfer system • cold chemical vessel vent system • cold chemical vessel dust collection hood • vitrification facility heating, ventilation, and air conditioning (HVAC) system • vitrification off-gas treatment system (melter) 	Modification to incorporate all site sources approved 6/01/00.	Effective 6/01/00. No expiration date.
Slurry-fed ceramic melter (modification to WVDP-687-01) process building ventilation	EPA/NESHAP	Slurry-fed ceramic melter radionuclide emissions — main plant stack modified 2/18/97	None	Permit approved 2/18/97. No expiration date. Request to modify submitted to the EPA 8/99.
Vitrification facility HVAC system	EPA/NESHAP	Vitrification facility HVAC system for radionuclide emissions	None	Permit approved 2/18/97. No expiration date.
01-14 building ventilation system (WVDP-187-01)	EPA/NESHAP	Liquid waste treatment system ventilation of radionuclide emissions in the 01-14 building	None	Issued 10/5/87. Modified 5/25/89. No expiration date.

West Valley Demonstration Project Environmental Permits (concluded)

<i>Permit Name and Number</i>	<i>Agency/Permit Type</i>	<i>Description</i>	<i>2000 Changes</i>	<i>Status</i>
Contact size-reduction facility (WVDP-287-01)	EPA/NESHAP	Contact size-reduction and decontamination facility radionuclide emissions	None	Issued 10/5/87. No expiration date.
Supernatant treatment system/Permanent ventilation system (WVDP-387-01)	EPA/NESHAP	Supernatant treatment system ventilation for radionuclide emissions	None	Revised 1/1/97. No expiration date.
Outdoor ventilated enclosures (WVDP-587-01)	EPA/NESHAP	Ten portable ventilation units for removal of radionuclides	None	Issued 12/22/87. No expiration date.
State Pollutant Discharge Elimination System (NY-0000973)	NYSDEC/Water	Covers discharges to surface waters from various on-site sources	Renewed effective 2/1/99. Expires 2/1/04. No other changes.	NYSDEC has prepared a draft permit modification for stormwater discharges and for a groundwater recovery system discharge increase. Permit terms for NYSDERDA and DOE responsibilities related to storm water discharges are being negotiated with NYSDEC.
Buffalo Pollutant Discharge Elimination System (00-04-TR096)	Buffalo Sewer Authority/Sanitary sewage and sewage sludge disposal	Permit issued to hauler of waste from the wastewater treatment facility	Renewed 6/30/00.	Hauler must renew permit by 6/30/01.
Fill Discharge Permit (94-973-29(4))	U.S.Army Corps of Engineers/Water	Buttermilk Creek culvert repairs and railroad spur improvements	Not applicable	Issued 4/27/00. Expires 4/27/05.
Freshwater Wetlands Permit and Water Quality Certification (9-0422-00005/00093)	NYSDEC/Water	Buttermilk Creek culvert repairs and railroad spur improvements	Not applicable	Issued 3/31/00. Expires 4/1/05.
Chemical bulk storage (9-000158)	NYSDEC/Chemical bulk storage tank	Registration of bulk storage tanks used for listed hazardous chemicals	None	Permit expires 7/5/01. Will renew before expiration.
Petroleum bulk storage (9-008885)	NYSDEC/Petroleum bulk storage tank registration	Registration of bulk storage tanks used for petroleum	None	Registration expires 9/2/01. Will renew before expiration.
Bird depredation license (DWP99-01)	New York State Division of Fish and Wildlife	State license for the removal of inactive nests of migratory birds	Renewed 1/1/01	CY2000 NYS license expired 12/31/00. Received new NYS license for 2001.

ENVIRONMENTAL PROGRAM INFORMATION

Introduction

The high-level radioactive waste (HLW) presently stored at the Western New York Nuclear Service Center (WNYNSC) on the West Valley Demonstration Project (WVDP) premises is the byproduct of the reprocessing of spent nuclear fuel during the late 1960s and early 1970s, when the WNYNSC was leased by Nuclear Fuel Services, Inc. (NFS) for a commercial nuclear fuel reprocessing facility.

Inasmuch as the WNYNSC is no longer an active nuclear fuel reprocessing facility, the environmental monitoring program focuses on measuring radioactivity and chemicals associated with the residual effects of NFS operations and the Project's high-level waste treatment and low-level waste management operations. The following information about the operations at the WVDP and about radiation and radioactivity will be useful in understanding the activities of the Project and the terms used in reporting the results of environmental testing measurements.

Radiation and Radioactivity. Radioactivity is a process in which unstable atomic nuclei spontaneously disintegrate or "decay" into atomic nuclei of another isotope or element. (See *isotope*, p.5, in the Glossary.) The nuclei decay until only a stable, nonradioactive isotope remains. Depending on the isotope, this process can take anywhere from less than a second to hundreds of thousands of years.

As atomic nuclei decay, radiation is released in three main forms: alpha particles, beta particles, and gamma rays. By emitting energy or particles, the nucleus moves toward a less energetic, more stable state.

Alpha Particles. An alpha particle, released by decay, is a fragment of a much larger nucleus. It consists of two protons and two neutrons (similar to the nucleus of a helium atom) and is positively charged. Compared to beta particles, alpha particles are relatively large and heavy and do not travel very far when ejected by a decaying nucleus. Alpha radiation, therefore, is easily stopped by a thin layer of material such

Ionizing Radiation

Radiation can be damaging if, in colliding with other matter, the alpha or beta particles or gamma rays knock electrons loose from the absorber atoms. This process is called ionization, and the radiation that produces it is referred to as ionizing radiation because it changes an electrically neutral atom, in which the positively charged protons and the negatively charged electrons balance each other, into a charged atom called an ion. An ion can be either positively or negatively charged. Various kinds of ionizing radiation produce different degrees of damage.

Potential Effects of Radiation

The biological effects of radiation can be either somatic or genetic. Somatic effects are restricted to the person who has been exposed to radiation. For example, sufficiently high exposure to radiation can cause clouding of the lens of the eye or loss of white blood cells.

Radiation also can cause chromosomes to break or rearrange themselves or to join incorrectly with other chromosomes. These changes may produce genetic effects and may show up in future generations. Radiation-produced genetic defects and mutations in the offspring of an exposed parent, while not positively identified in humans, have been observed in some animal studies.

The effect of radiation depends on the amount absorbed within a given exposure time. The only observable effect of an instantaneous whole-body dose of 50 rem (0.5 Sv) might be a temporary reduction in white blood cell count. An instantaneous dose of 100-200 rem (1-2 Sv) might cause additional temporary effects such as vomiting but usually would have no long-lasting side effects. Assessing biological damage from low-level radiation is difficult because other factors can cause the same symptoms as radiation exposure. Moreover, the body apparently is able to repair damage caused by low-level radiation.

The effect most often associated with exposure to relatively high levels of radiation appears to be an increased risk of cancer. However, scientists have not been able to demonstrate with certainty that exposure to low-level radiation causes an increase in injurious biological effects, nor have they been able to determine if there is a level of radiation exposure below which there are no biological effects.

Background Radiation

Background radiation is always present, and everyone is constantly exposed to low levels of such radiation from both naturally occurring and manmade sources. In the United States the average total annual exposure to this low-level background radiation is estimated to be about 360 millirem (mrem) or 3.6 millisieverts (mSv). Most of this radiation, approximately 295 mrem (2.95 mSv), comes from natural sources. The rest comes from medical procedures, consumer products, and other manmade sources. (See Figure 4-1 [p.4-2] in Chapter 4, Radiological Dose Assessment.)

Background radiation includes cosmic rays, the decay of natural elements such as potassium, uranium, thorium, and radon, and radiation from sources such as chemical fertilizers, smoke detectors, and televisions. Actual doses vary depending on such factors as geographic location, building ventilation, and personal health and habits.

as paper or skin. However, if radioactive material is ingested or inhaled, the alpha particles released inside the body can damage soft internal tissues because all of their energy is absorbed by tissue cells in the immediate vicinity of the decay. An example of an alpha-emitting radionuclide is the uranium isotope with an atomic weight of 232 (uranium-232). Uranium-232 is in the high-level waste mixture at the WVDP as a result of a thorium-based nuclear fuel reprocessing campaign conducted by NFS and has been previously detected in liquid waste streams.

Beta Particles. A beta particle is an electron that results from the breakdown of a neutron in a radioactive nucleus. Beta particles are small compared with alpha particles, travel at a higher speed (close to the speed of light), and can be stopped by a material such as wood or aluminum less than an inch thick. If beta particles are released inside the body they do much less damage than an equal number of alpha particles. Because they are smaller and faster and have less of a charge, beta particles deposit energy in tissue cells over a larger volume than alpha particles. Strontium-90, a fission product (see Glossary, p.4), is an example of a beta-emitting radionuclide. Strontium-90 is found in the stabilized supernatant.

Gamma Rays. Gamma rays are high-energy “packets” of electromagnetic radiation, called photons, that are emitted from the nucleus. They are similar to x-rays but generally have a shorter wavelength and therefore are more energetic than x-rays. If the alpha or beta particle released by the decaying nucleus does not carry off all the energy generated by the nuclear disintegration, the excess energy may be emitted as gamma rays. If the released energy is high, a very penetrating gamma ray is produced that can be effectively reduced only by shielding

consisting of several inches of a heavy element, such as lead, or of water or concrete several feet thick. Although large amounts of gamma radiation are dangerous, gamma rays are also used in many lifesaving medical procedures. An example of a gamma-emitting radionuclide is barium-137m, a short-lived daughter product of cesium-137. Both barium-137m and cesium-137 are major constituents of the WVDP high-level radioactive waste.

Measurement of Radioactivity. The rate at which radiation is emitted from a disintegrating nucleus can be described by the number of decay events or nuclear transformations that occur in a radioactive material over a fixed period of time. This process of emitting energy, or radioactivity, is measured in curies (Ci) or becquerels (Bq).

The curie is based on the decay rate of the radionuclide radium-226 (Ra-226). One gram of radium-226 decays at the rate of 37 billion nuclear disintegrations per second ($3.7\text{E}+10$ d/s), so one curie equals 37 billion nuclear disintegrations per second. One becquerel equals one decay, or disintegration, per second. (See the Scientific Notation section at the back of this report for information on exponentiation, i.e., the use of “E” to mean the power of 10.)

Very small amounts of radioactivity are sometimes measured in picocuries. A picocurie is one-trillionth ($1\text{E}-12$) of a curie, equal to $3.7\text{E}-02$ disintegrations per second, or 2.22 disintegrations per minute.

Measurement of Dose. The amount of energy absorbed by the receiving material is measured in rads (radiation absorbed dose). A rad is 100 ergs of radiation energy absorbed per gram of material. (An erg is the approximate amount of energy necessary to lift a mosquito one-six-

teenth of an inch.) “Dose” is a means of expressing the amount of energy absorbed, taking into account the effects of different kinds of radiation.

Alpha, beta, and gamma radiation affect the body to different degrees. Each type of radiation is given a quality factor that indicates the extent of human cell damage it can cause compared with equal amounts of other ionizing radiation energy. Alpha particles cause twenty times as much damage to internal tissues as x-rays, so alpha radiation has a quality factor of 20 compared to gamma rays, x-rays, or beta particles, which have a quality factor of 1.

The unit of dose measurement to humans is the rem (roentgen-equivalent-man). Rems are equal to the number of rads multiplied by the quality factor for each type of radiation. Dose can also be expressed in sieverts. One sievert equals 100 rem.

Environmental Monitoring Program Overview

Exposure of human beings to radioactivity would be primarily through air, water, and food. At the WVDP all three pathways are monitored, but air and surface water pathways are the two primary means by which radioactive material can move off-site.

The geology of the site (types of soil and bedrock), the hydrology (location and flow of surface water and groundwater), and meteorological characteristics of the site (wind speed, patterns, and direction) are all considered in evaluating potential exposure through the major pathways.

The on-site and off-site monitoring program at the WVDP includes measuring the concentra-

tion of alpha and beta radioactivity, conventionally referred to as “gross alpha” and “gross beta,” in air and water effluents. Measuring the total alpha and beta radioactivity from key locations, which can be done within a matter of hours, produces a comprehensive picture of on-site and off-site levels of radioactivity from all sources. In a facility such as the WVDP, frequent updating and tracking of the overall levels of radioactivity in effluents is an important tool in maintaining acceptable operations.

More detailed measurements are also made for specific radionuclides. Strontium-90 and cesium-137 are measured because they have been previously detected in WVDP waste materials. Radiation from other important radionuclides such as tritium or iodine-129 is not sufficiently energetic to be detected by gross measurement techniques, so these must be analyzed separately using methods with greater sensitivity. Heavy elements such as uranium, plutonium, and americium require special analysis to be measured because they exist in such small concentrations in the WVDP environs.

The radionuclides monitored at the Project are those that might produce relatively higher doses or that are most abundant in air and water effluents. Because manmade sources of radiation at the Project have been decaying for more than thirty years, the monitoring program does not routinely include short-lived radionuclides, i.e., isotopes with a half-life of less than two years, which would have less than 1/1,000 of the original radioactivity remaining. (See Appendix B [pp. B-1 through B-44] for the schedule of samples and radionuclides measured and Appendix K, Table K-1 [p.K-3] for related Department of Energy [DOE] protection standards, i.e., derived concentration guides [DCGs] and half-lives of radionuclides measured in WVDP samples.)

Derived Concentration Guides

A derived concentration guide (DCG) is defined by the DOE as the concentration of a radionuclide in air or water that, under conditions of continuous exposure by one exposure mode (i.e., ingestion of water, submersion in air, or inhalation) for one year, would result in an effective dose equivalent of 100 mrem (1 mSv) to a “reference man.” These concentrations — DCGs — are used as reference screening levels to enable site personnel to review effluent and environmental data and to decide if further investigation is needed. (See Table K-1, Appendix K, p.K-3 for a list of DCGs.)

DOE Orders require that the hypothetical dose to the public from facility effluents be estimated using specific computer codes. (See Dose Assessment Methodology [p.4-3] in Chapter 4, Radiological Dose Assessment.) Doses estimated for WVDP activities are calculated using actual site data and are not related directly to summed DCG values.

Dose estimates are based on the product of radionuclide quantities released and the dose equivalent effects for that radionuclide. For liquid effluent screening purposes, the percentages of the DCGs for all radionuclides present are added. If the total is less than 100%, then the effluent released complies with the DOE guideline. Although no drinking water is drawn from either effluent streams on-site or from downstream Cattaraugus Creek, DCGs are also compared with radionuclide concentrations from these sources.

The DOE provides DCGs for airborne radionuclides in locations where persons could breathe air containing contaminants. However, in a regulatory sense, DCGs do not apply at the point of release. The more stringent U.S. Environmental Protection Agency (EPA) National Emission Standards for Hazardous Air Pollutants (NESHAP) apply to Project airborne effluents at the point of release. Although DCGs are not directly applicable to radionuclides in air at the point of release, at a distance from a human breathing zone DCGs may be used as a basis for evaluating concentrations from air emission points. For a consistent guide to relative concentrations both air and water sampling results are compared with DCGs throughout this report.

Data Reporting. Because the decay of radioactive atoms is a random process, there is an inherent uncertainty associated with all measurements of environmental radioactivity. This can be demonstrated by repeatedly measuring the number of atoms that decay in a radioactive sample over some fixed period of time. The result of such an experiment would be a range of values for which the average value would provide the best indication of how many radioactive atoms were present in the sample.

However, in actual practice an environmental sample usually is measured for radioactivity

just once, not many times. The inherent uncertainty of the measurement, then, stems from the fact that it cannot be known whether the result that was obtained from one measurement is higher or lower than the “true” value, i.e., the average value that would be obtained if many measurements had been taken.

The term *confidence interval* is used to describe the range of measurement values above and below the test result within which the “true” value is expected to lie. This interval is derived mathematically. The width of the interval is based primarily on a predetermined confidence

level, i.e., the probability that the confidence interval actually encompasses the “true” value. The WVDP environmental monitoring program uses a 95% confidence level for all radioactivity measurements and calculates confidence intervals accordingly.

The confidence interval around a measured value is indicated by the plus-or-minus (\pm) value following the result, e.g., $5.30 \pm 3.6\text{E-}09$ $\mu\text{Ci/mL}$, with the exponent of 10^{-9} expressed as “E-09.” Expressed in decimal form, the number $5.30 \pm 3.6\text{E-}09$ would be $0.00000000530 \pm 0.0000000036$ $\mu\text{Ci/mL}$. A sample measurement expressed this way is correctly interpreted to mean “there is a 95% probability that the concentration of radioactivity in this sample is between $1.7\text{E-}09$ $\mu\text{Ci/mL}$ and $8.9\text{E-}09$ $\mu\text{Ci/mL}$.” If the confidence interval for the measured value includes zero (e.g., $5.30 \pm 6.5\text{E-}09$ $\mu\text{Ci/mL}$), the value is considered to be below the detection limit. The values listed in tables of radioactivity measurements in the appendices include the confidence interval regardless of the detection limit value.

In general, the detection limit is the minimum amount of constituent or material of interest detected by an instrument or method that can be distinguished from background and instrument noise. Thus, the detection limit is the lowest value at which a sample result shows a statistically positive difference from a sample in which no constituent is present. (Maximum and minimum values in data sets showing positive results have been set in boldface type in the data appendices at the back of this report; the key to this convention is described at the beginning of each appropriate appendix.)

Nonradiological data conventionally are presented without an associated uncertainty and

are expressed by the detection limit prefaced by a “less-than” symbol ($<$) if that analyte was not measurable. (See also Data Assessment and Reporting [p.5-7] in Chapter 5, Quality Assurance.)

Changes in the 2000 Environmental Monitoring Program. Changes in the 2000 environmental monitoring program enhanced the environmental sampling and surveillance network in order to support current activities and to prepare for future activities.

- Analyses for beryllium, nickel, thallium, and cyanide in the annual drinking water sample collected in the utility room (WNDNKUR) were added to the program. The annual sample to be analyzed for nitrate was collected by the Cattaraugus County Health Department, which will continue to collect and analyze this sample for nitrate.

- Groundwater seepage monitoring locations SP02, SP05, SP18, and SP23 were found to be redundant locations or repeatedly dry and therefore were deleted from the groundwater program beginning with the first-quarter 2000 monitoring event.

See Appendix B for a summary of the program changes (p.B-iv) and the sample points and parameters measured in 2000 (pp. B-1 through B-44).

Vitrification Overview

High-level radioactive waste from NFS operations was originally stored in two of four underground tanks (tanks 8D-2 and 8D-4). The waste in 8D-2, the larger of the active tanks, had settled into two layers: a liquid — the supernatant — and a precipitate layer on the tank

bottom — the sludge. To solidify the high-level waste, WVDP engineers designed and developed a process of pretreatment and vitrification.

Pretreatment Accomplishments. The supernatant (in tank 8D-2) was composed mostly of sodium and potassium salts dissolved in water. Radioactive cesium in solution accounted for more than 99% of the total radioactivity in the supernatant. During pretreatment, sodium salts and sulfates were separated from the radioactive constituents in both the liquid portion of the high-level waste and the sludge layer in the bottom of the tank.

Pretreatment of the supernatant began in 1988. The integrated radwaste treatment system (IRTS) reduced the volume of the high-level waste needing vitrification by producing low-level waste stabilized in cement: The supernatant was passed through zeolite-filled ion exchange columns in the supernatant treatment system (STS) to remove more than 99.9% of the radioactive cesium. The resulting liquid was then concentrated by evaporation in the liquid waste treatment system (LWTS). This low-level radioactive concentrate was blended with cement in the cement solidification system (CSS) and placed in 269-liter (71-gal) steel drums. The cement-stabilized waste form has been accepted by the U.S. Nuclear Regulatory Commission (NRC).

In the last step the steel drums were stored in an on-site aboveground vault, the drum cell. (See Fig.A-1, p. A-3.) Processing of the supernatant was completed in 1990, with more than 10,000 drums of cemented waste produced.

The sludge that remained was composed mostly of iron hydroxide. Strontium-90 accounted for most of the radioactivity in the sludge. Pre-

treatment of the sludge layer in high-level waste tank 8D-2 began in 1991. Five specially designed 50-foot-long pumps were installed in the tank to mix the sludge layer with water in order to produce a uniform sludge blend and to dissolve the sodium salts and sulfates that would interfere with vitrification. After mixing and allowing the sludge to settle, processing of the wash water through the integrated radwaste treatment system began. Processing removed radioactive constituents for later solidification into glass, and the wash water containing salt was then stabilized in cement.

Sludge washing was completed in 1994 after approximately 765,000 gallons of wash water had been processed. About 8,000 drums of cement-stabilized wash water were produced. In January 1995, high-level waste liquid stored in tank 8D-4 was transferred to tank 8D-2. (Tank 8D-4 contained THOREX high-level radioactive waste, which had been produced by a single reprocessing campaign of a special fuel containing thorium that had been conducted from November 1968 to January 1969 by the previous facility operators.) The resulting mixture was washed and the wash water was processed. The IRTS processing of the combined wash waters was completed in May 1995.

In all, through the supernatant treatment process and the sludge wash process, more than 1.7 million gallons of liquid had been processed by the end of 1995, producing a total of 19,877 drums of cemented low-level waste.

As one of the final steps, the ion-exchange material (zeolite) used in the integrated radwaste treatment system to remove radioactivity was blended with the washed sludge before being transferred to the vitrification facility for blending with the glass-formers. In 1995 and

early 1996 final waste transfers to high-level waste tank 8D-2 were completed in preparation for vitrification.

Preparation for Vitrification. Nonradioactive testing of a full-scale vitrification system was conducted from 1984 to 1989. In 1990 all vitrification test equipment was removed to allow installation of shield walls for fully remote radioactive operations. The walls and shielded tunnel connecting the vitrification facility to the former reprocessing plant were completed in 1991. The slurry-fed ceramic melter was fully assembled, bricked, and installed in 1993, and the cold chemical building was completed, as was the sludge mobilization system that transfers high-level waste to the melter. This system was fully tested in 1994. Several additional major systems components also were installed in 1994: the canister turntable, which positions the stainless steel canisters as they are filled with molten glass; the submerged bed scrubber, which cleans gases produced by the vitrification process; and the transfer cart, which moves filled canisters to the storage area.

Nonradiological testing ("cold" operations) of the vitrification facility began in 1995, and the first canister of nonradiological glass was produced. The WVDP declared its readiness to proceed with the necessary equipment tie-ins of the ventilation and utility systems to the vitrification facility building and tie-ins of the transfer lines to and from the high-level waste tank farm and the vitrification facility. In this closed-loop system, the transfer lines connect to multiple common lines so that material can be moved among all the points in the system.

High-level waste vitrification began in 1996. Phase I, which saw the majority of the high-level liquid waste vitrified, was completed in mid-1998. Phase II, removing and vitrifying

residual radioactivity, continued throughout 2000. (See Vitrification below.)

2000 Activities at the WVDP

The WVDP's environmental management system is an important factor in the environmental monitoring program and the accomplishment of its mission. Significant components, initiatives, and pertinent information about the work accomplished at the WVDP in 2000 are summarized below.

Vitrification. Solidification of the high-level waste in glass continued in 2000. The high-level waste mixture of washed sludge and spent zeolite from the ion-exchange process is combined in batches with glass-forming chemicals and then fed to a ceramic melter. The waste mixture is heated to approximately 2,000°F and poured into stainless steel canisters. Approximately 300 stainless steel canisters eventually will be needed to hold all of the vitrified waste. Each canister, 10 feet long by 2 feet in diameter, is filled with a uniform, high-level waste glass that will be suitable for eventual shipment to a federal repository. During Phase I (June 1996 to June 1998) 210 canisters were filled.

In 2000 more than 0.3 million curies of radioactivity were transferred to the vitrification facility and nine high-level waste canisters were produced. Since the beginning of vitrification in 1996 through calendar year 2000, 254 high-level waste canisters have been filled and more than 11 million cesium/strontium curies have been transferred to the vitrification facility and vitrified.

Environmental Management of Aqueous Radioactive Waste. Water containing radioactive material from site process operations is collected and treated in the low-level waste treat-

ment facility LLW2. (Water from the sanitary system, which does not contain added radioactive material, is managed in a separate system.)

The treated process water is held, sampled, and analyzed before it is released through a New York State Pollutant Discharge Elimination System (SPDES)-permitted outfall. In 2000, 43.7 million liters (11.5 million gal) of water were treated in the low-level waste treatment facility (LLWTF) system (i.e., the LLW2 and associated lagoons) and discharged through outfall 001, the lagoon 3 weir. The discharge waters contained an estimated 19.1 millicuries of gross alpha plus gross beta radioactivity. Comparable releases during the previous fifteen years averaged about 37 millicuries per year. The 2000 release was about 52% of this average. (See Radiological Monitoring: Surface Water, Low-level Waste Treatment Facility Sampling Location [p.2-3] in Chapter 2.)

Approximately 0.14 curies of tritium were released in WVDP liquid effluents in 2000 — 10% of the fifteen-year average of 1.38 curies.

Environmental Management of Airborne Radioactive Emissions. Ventilated air from the various points in the IRTS process (high-level waste sludge treatment, main plant and liquid waste treatment system, and the cement solidification system) and from other waste management activities is sampled continuously during operation for both particulate matter and for gaseous radioactivity. In addition to monitors that alarm if particulate matter radioactivity increases above pre-set levels, the sample media are analyzed in the laboratory for the specific radionuclides that are present in the radioactive materials being handled.



Air used to ventilate the facilities where radioactive material cleanup processes are operated

is passed through filtration devices before being emitted to the atmosphere. These filtration devices are generally more effective for particulate matter than for gaseous radioactivity. For this reason, facility air emissions tend to contain a greater amount of gaseous radioactivity (e.g., tritium and iodine-129) than radioactivity associated with particulate matter (e.g., strontium-90 and cesium-137). However, gaseous radionuclide emissions still remain so far below the most restrictive regulatory limit for public safety that additional treatment technologies beyond that already provided by, for example, the vitrification off-gas treatment system, are not necessary.

Gaseous radioactivity emissions from the main plant in 2000 included approximately 5.00 millicuries of tritium (as hydrogen tritium oxide [HTO]) and 1.26 millicuries of iodine-129. (See Chapter 2, p.2-28, for a discussion of iodine-129 emissions from the main plant stack.) As expected, these 2000 values are quite low when compared to 1997, a year in which the vitrification system was in operation for the entire year at a relatively high rate of production and tritium and iodine-129 emissions were 140 millicuries and 7.43 millicuries respectively.

Particulate matter radioactivity emissions from the main plant in 2000 included approximately 0.06 millicuries of beta-emitting radioactivity and 0.001 millicuries of alpha-emitting radioactivity. In 1997, beta-emitting and alpha-emitting radioactivity emissions were 0.4 millicuries and 0.001 millicuries respectively.

Environmental Management of Radiological Exposure. Radiological exposures measured at on-site monitoring locations DNTLD24, located near the chemical process cell waste storage area (CPC-WSA), and DNTLD36, located near the drum cell, have shown steady decreases



for several years. (See Fig.A-10 [p.A-12] for the locations of these two monitoring points.) Exposure data for these two monitoring locations are shown in Figures 1-1 and 1-2 (*above*).

The beginning of the long-term steady decrease in exposure at DNTLD24 correlates well with the cessation of placement of waste containers in the CPC-WSA in 1987 and with the decay of the mix of isotopes in the stored waste. The decreases noted at DNTLD36 can be attrib-

uted to the cessation of the placement of waste drums in the drum cell as well as the decay of the mix of isotopes in the stored waste over time and to the revised stacking plan initiated in 1990, which changed the arrangement of waste and shield drums in the drum cell.

Unplanned Radiological Releases. There were no unplanned air or liquid radiological releases on-site or to the off-site environment from the Project in 2000.

NRC-licensed Disposal Area (NDA) Interceptor Trench and Pretreatment System.

Radioactively contaminated n-dodecane in combination with tributyl phosphate (TBP) was discovered at the northern boundary of the NDA in 1983, shortly after the DOE assumed control of the WVDP site. Extensive sampling and monitoring through 1989 revealed the possibility that the n-dodecane/TBP could migrate. To contain migration of this subsurface organic contaminant, an interceptor trench and liquid pretreatment system (LPS) were built.

The trench was designed to intercept and collect subsurface water, which could be carrying n-dodecane/TBP, in order to prevent the material from entering the surface water drainage ditch leading into Erdman Brook. The LPS was installed to decant the n-dodecane/TBP from the water and to remove iodine-129 from the collected water before its transfer to the low-level waste treatment facility. The separated n-dodecane/TBP would be stored for subsequent treatment and disposal.

As in previous years, no water containing n-dodecane/TBP was encountered in the trench and no water or n-dodecane/TBP was treated by the LPS in 2000. Approximately 580,000 liters (154,000 gals) of water were collected from the interceptor trench and transferred to lagoon 2 during the year. Results of surface and groundwater monitoring in the vicinity of the trench are discussed in Chapter 2 under NDA and SDA Sampling Locations, p.2-7, and in Chapter 3 under Results of Monitoring at the NDA, p.3-14.

Waste Minimization Program. The WVDP formalized a waste minimization program in 1991 to reduce the generation of low-level waste, mixed waste, and hazardous waste. This program is a comprehensive and continual effort to prevent or minimize pollution, with the over-

all goal of reducing health and safety risks, protecting the environment, and complying with all federal and state regulations. (See also the Environmental Compliance Summary: Calendar Year 2000, Waste Minimization and Pollution Prevention [p.ECS-5].)

Waste Management. The WVDP continued reducing and eliminating waste generated by site activities. Reductions in the generation of low-level radioactive waste, mixed waste, hazardous waste, industrial wastes, and sanitary waste such as paper, plastic, wood, and scrap metal were targeted. Specific waste minimization achievements included the following:

- 44 tons of excess vitrification chemicals were sent back to the manufacturer for re-certification
- approximately 30,000 lbs of structural steel used in a decommissioning activity were released for reuse in future projects
- an Aqua-Flo magnetic water conditioner was installed, eliminating the need to remove scale by flushing with an acidic solution and reducing the generation of hazardous waste from this flushing process by 33%
- 117 tons of scrap carbon and stainless steel were collected and sold to a metal recycling vendor
- acid digestion of high-level waste samples was streamlined to reduce the volume of waste acid and the number of waste containers produced during analysis
- an electrostatic cloth replaced sweeping compound in the main plant laboratories, eliminating approximately 800 lbs per year of used sweeping compound disposed as radioactive waste

- 263 tons of concrete were sent off-site to landfills or for recycling
- oil filters were drained and crushed to allow disposal as industrial waste, and used oil was recycled
- a white containment tent was “free released” for on-site use after confirmatory radiological surveys.

Pollution Prevention Awareness Program.

The WVDP’s pollution prevention (P2) awareness program is a significant part of the Project’s waste minimization program. The goal of the program is to make all employees aware of the importance of pollution prevention both at work and at home.

A crucial component of the P2 awareness program at the WVDP is the Pollution Prevention Coordinators group. This group communicates, shares, and publicizes prevention, reduction, reuse, and recycling information to all departments at the WVDP. The P2 coordinators identify and facilitate the implementation of effective source-reduction, reuse, recycling, and procurement of recycled products.

National Environmental Policy Act Activities.

Under the National Environmental Policy Act (NEPA), the Department of Energy is required to consider the overall environmental effects of its proposed actions or federal projects. The President’s Council on Environmental Quality established a screening system of analyses and documentation that requires each proposed action to be categorized according to the extent of its potential environmental effect. The levels of documentation include categorical exclusions (CXs), environmental assessments (EAs), and environmental impact statements (EISs).

Categorical exclusions evaluate and document actions that will not have a significant effect on the environment. Environmental assessments evaluate the extent to which the proposed action will affect the environment. If a proposed action has the potential for significant effects, an environmental impact statement is prepared that describes proposed alternatives to an action and explains the effects.

Facility maintenance and minor projects that support high-level waste vitrification are documented and submitted for approval as categorical exclusions, although environmental assessments occasionally are necessary for larger-scale activities.

Citizen Task Force

In addition to the public comment process required by the National Environmental Policy Act, NYSERDA, with participation from the DOE, formed a Citizen Task Force in January 1997. The mission of the Task Force is to assist in the development of a preferred alternative for the completion of the West Valley Demonstration Project and the cleanup, closure, or long-term management of the facilities at the Western New York Nuclear Service Center. The Task Force process has helped illuminate the various interests and concerns of the community, increased the two-way flow of information between the site managers and the community, and provided an effective way for the Task Force members to establish a mutually agreed upon set of recommendations for the site managers to consider in their decision-making process.

In December 1988 the DOE published a Notice of Intent to prepare an environmental impact statement for the completion of the WVDP and closure of the facilities at the WNYNSC.

The draft environmental impact statement, which describes the potential environmental effects associated with Project completion and various site closure alternatives, was completed in 1996 and released for a six-month public review and comment period. Having met throughout 1997 and 1998 to review alternatives presented in the draft environmental impact statement, the Citizen Task Force (see description on facing page) issued the West Valley Citizen Task Force Final Report (July 29, 1998). This report provided recommendations and advice on the development of a preferred alternative. The Citizen Task Force continues to meet and discuss issues related to Project completion and site closure decision-making.

Because the Nuclear Regulatory Commission (NRC) is authorized by the West Valley Demonstration Project Act to prescribe decommissioning criteria for the WVDP, the NRC staff proposed such criteria for the Project to the NRC Commissioners in 1998 (Decommissioning Criteria for West Valley, October 30, 1998 [SECY 98-251]). The DOE, the New York State Research and Development Authority (NYSERDA), the New York State Department of Environmental Conservation (NYSDEC), and the Citizen Task Force attended a public meeting on January 12, 1999 to provide input to the NRC on their issues and concerns. As a result of this meeting, the NRC issued a Staff Requirements Memorandum (SRM) on January 26, 1999 requesting additional information on the proposed decommissioning criteria. In response, the NRC staff provided SECY 99-057, Supplement to SECY 98-251, on February 23, 1999. On June 3, 1999 the NRC sub-

sequently issued an SRM based on the contents of both SECY 98-251 and SECY 99-057 and the written and oral comments from interested parties. This SRM approved applying the NRC's License Termination Rule (LTR) as the decommissioning criteria to be applied to the WVDP and the West Valley site.

On December 3, 1999, the NRC published its draft policy statement in the Federal Register (Vol.64, No.232, pp. 67952-67954) and a public meeting was held on January 5, 2000 at the Ashford Office Complex to solicit public comment on the draft policy statement. The NRC continued work on the draft policy statement during 2000. (This is available electronically at <http://www.nrc.gov/NRC/ADAMS/index.html>. In addition, copies of SECY 98-251, SECY 99-057, transcripts of the public meetings, the 1999 SRM, and the NRC's vote sheets on SECY 98-251 and SECY 99-057 can be obtained electronically at <http://www.nrc.gov/NRC/COMMISSION/activities.html>.)

The DOE and NYSERDA continued their effort during 2000 to develop a preferred alternative for completion of the WVDP and closure or long-term management of the WNYNSC. In late summer of 2000 the DOE announced a new approach to reaching this goal: The decision-making process would be separated into two phases by revising the scope of the 1996 draft environmental impact statement. Re-scoping will allow two separate environmental impact statements — a WVDP decontamination and waste management environmental impact statement and a West Valley site decommissioning or long-term stewardship environmental impact statement. (See the Environmental Compliance Summary: Calendar Year 2000, p.ECS-15 for more information.)

Self-assessments. Self-assessments continued to be conducted in 2000 to review the management and effectiveness of the WVDP environmental protection and monitoring programs. Results of these self-assessments are evaluated and corrective actions are tracked through to completion. Overall results of these self-assessments found that the WVDP continued to implement and in some cases improve the quality of the environmental protection and monitoring program. (See the Environmental Compliance Summary: Calendar Year 2000 [p.ECS-18] and Chapter 5, Quality Assurance [p.5-6].)

Occupational Safety and Environmental Training. The safety of personnel who are involved in industrial operations under DOE cognizance is protected by standards mandated by DOE Order 5480.4, Environmental Protection, Safety, and Health Protection Standards, which directs compliance with specific Occupational Safety and Health Act (OSHA) requirements. This act governs diverse occupational hazards ranging from electrical safety and protection from fire to the handling of hazardous materials. The purpose of OSHA is to maintain a safe and healthy working environment for employees.

Hazardous Waste Operations and Emergency Response regulations require that employees at treatment, storage, and disposal facilities, who may be exposed to health and safety hazards during hazardous waste operations, receive training appropriate to their job function and responsibilities. The WVDP environmental, health, and safety training matrix identifies the specific training requirements for such employees.

The WVDP provides the standard twenty-four-hour hazardous waste operations and emergency response training. (Emergency response train-

ing includes spill response measures and controlling contamination of groundwater.) Training programs also contain information on waste minimization, pollution prevention, and the WVDP environmental management program. Besides this standard training, employees working in radiological areas receive additional training on subjects such as understanding radiation and radiation warning signs, dosimetry, and respiratory protection. In addition, qualification standards for specific job functions at the site are required and maintained. These programs have evolved into a comprehensive curriculum of knowledge and skills necessary to maintain the health and safety of employees and ensure the continued compliance of the WVDP.

The WVDP maintains a hazardous materials response team that is trained to respond to spills of hazardous materials. This team maintains its proficiency through classroom instruction and scheduled training drills.

Medical emergencies on-site are handled by the WVDP Emergency Medical Response Team. This team consists of on-site professional medical staff, volunteer New York State-certified emergency medical technicians, and main plant operators who are certified as New York State First Responders.

Any person working at the WVDP who has a personal photo badge receives general employee training covering health and safety, emergency response, and environmental compliance issues. All visitors to the WVDP receive a site-specific briefing on safety and emergency procedures before being admitted to the site.

Voluntary Protection Program STAR Status. On May 5, 2000 the WVDP received Voluntary Protection Program (VPP) STAR status, the highest safety award given within OSHA or

the DOE. This prestigious award was granted in recognition of the WVDP's excellent worker safety and health programs. (See also the Environmental Compliance Summary: Calendar Year 2000 [p.ECS-16].)

Environmental Management System (EMS) Implementation. The WVNS environmental management system provides the basic policy and direction for work at the WVDP through procedures that support proactive management, environmental stewardship, and the integration of appropriate technologies throughout all aspects of the work at the WVDP.

The Project's environmental management system satisfies the requirements of the Code of Environmental Management Principles (CEMP) for federal agencies and ISO 14001, Environmental Management Systems: Specification for Guidance and Use, which is being implemented worldwide. The CEMP was developed by the EPA in response to Executive Order 12856, Federal Compliance with Right-to-Know Laws and Pollution Prevention Requirements, in order to serve as the basis for responsible environmental management. Following the principles and performance objectives of the CEMP helps to ensure that a federal facility's environmental performance is proactive, flexible, cost-effective, and sustainable. The WVDP was awarded charter membership in the EPA's National Performance Track program for implementation of this EMS.

Integrated Safety Management System (ISMS) Implementation. A plan to integrate environmental, safety, and health (ES&H) management programs at the WVDP was developed and initiated at the WVDP during 1998. During development of the ISMS, the enhanced work planning program (EWP) was identified as an integral part of the ISMS and a site-wide



The National Environmental Performance Track is designed to recognize and encourage top environmental performers — those who go beyond compliance with regulatory requirements to attain levels of environmental performance and management that benefit people, communities, and the environment.

The logo identifies those facilities that qualify for Achievement Track membership. Achievement Track facilities can participate in a peer exchange network to share experience, benchmark each other's performance, share information on successful practices and strategies, and receive recognition for their work at state and local levels.

work review group was established to review work plans, identify ES&H concerns, and specify practices that ensure that work is performed safely.

Implementation of an ISMS at the WVDP, including the EWP, was verified by the DOE Ohio Field Office in November 1998. The annual ISMS review by the DOE occurred in February 2000. This review verified that the ISMS continues to be effectively implemented at the WVDP. In August 2000 a self-assessment by WVNS confirmed that evaluation. No issues concerning the ISMS or the EMS were identified.

Performance Measures


Performance measures can be used to evaluate effectiveness, efficiency, quality, timeliness, productivity, safety, or other areas that reflect achievements related to organization or process goals and can be used as a tool to identify the need to institute changes.

The performance measures applicable to operations conducted at the WVDP, discussed here, reflect process performance related to wastewater treatment in the low-level waste treatment facility, the identification of spills and releases, the reduction in the generation of wastes, the potential radiological dose received by the maximally exposed off-site individual, and the transfer of high-level waste to the vitrification system.

Radiation Doses to the Maximally Exposed Off-site Individual. One of the most important pieces of information derived from environmental monitoring program data is the potential ra-

diological dose to an off-site individual from on-site activities. As an overall assessment of Project activities and the effectiveness of the as-low-as-reasonably achievable (ALARA) concept, the effective radiological dose to the maximally exposed off-site individual is an indicator of well-managed radiological operations. The effective dose equivalents for air effluent emissions, liquid effluent discharges, and other liquid releases (such as swamp drainage) from 1993 through 2000 are graphed in Figure 1-3 (*below*). Note that the sum of these values is well below the DOE standard of 100 mrem per year. These consistently low results indicate that radiological activities at the site are well-controlled. (See also Table 4-2 [p.4-6] in Chapter 4, Radiological Dose Assessment.)

SPDES Permit Limit Exceptions. Effective operation of the site wastewater treatment facilities is indicated by compliance with the applicable discharge permit limitations. Approximately sixty parameters are monitored regularly as part of the SPDES permit require-






Figure 1-4. Yearly SPDES Permit Exceptions

ments. The analytical results are reported to NYSDEC via Discharge Monitoring Reports, required under the SPDES program.

Although the goal of the low-level waste treatment facility (LLWTF) and wastewater treatment facility (WWTF) operations is to maintain effluent water quality consistently within the permit requirements, occasionally SPDES permit limit exceptions do occur. All SPDES permit limit exceptions are evaluated to determine their cause and to identify corrective measures. A Water Task Team composed of WVDP personnel with expertise in wastewater engineering, treatment plant operations and process monitoring, and NPDES/SPDES permitting and compliance was formed in 1995 to address the causes of these exceptions.

Since 1995 virtually all of the recorded exceptions had been for parameters such as nitrite, pH, and five-day biochemical oxygen demand (BOD₅), which regulate or are greatly influenced by natural (microbiological) treatment processes occurring at the site's industrial and sanitary WWTF and the LLWTF. The Water Task Team's efforts produced significant results: for the third consecutive year there were no

permit limit exceptions. (See Fig. 1-4 [this page].)

Although exceptions are not always related to operating deficiencies, corrective actions may include improved operation or treatment techniques. In 1997 the WVDP notified NYSDEC of the presence of mercury in the influent wastewater to the LLWTF and of its likely presence at outfall 001 at concentrations below the detectable level of 0.2 µg/L. In 1998 and 1999 an

increase in the mercury concentration was observed in process wastewater from the liquid waste treatment system (LWTS) evaporator, water that is eventually treated at the low-level waste treatment facility. The LWTS evaporator processes residual radioactive wastewater from the high-level radioactive waste processing and supernatant treatment operations.

During the first half of 2000 an engineering report and plans and specifications for a mercury pretreatment system designed to remove mercury from the LWTS process water were prepared. NYSDEC approval of the engineering report and plans and specifications was obtained by September 2000. The system was subsequently installed and the treatment media loaded into the treatment vessels. Processing of LWTS wastewater through this system began in January 2001.

Waste Minimization and Pollution Prevention. The WVDP continued its program of reducing and eliminating the amount of waste generated from site activities. Emphasis on good business practices, source-reduction, and recycling continued to reduce the generation of low-level radioactive waste, mixed waste, hazardous waste, industrial wastes, and sanitary

wastes such as paper, glass, plastic, wood, and scrap metal. (See p.1-11 for a list of specific waste minimization achievements.)

To demonstrate the effectiveness of the waste minimization program, a graph of the percentage of waste reduction achieved above the annual goal for each category is presented in Figure 1-5 (*below*) for calendar years 1994 through 2000. (See also the Environmental Compliance Summary: Calendar Year 2000, p. ECS-5.)


A number of waste streams have been tracked over this period. Note that the low-level radioactive waste figures from 1994 through 1995 include the volume of drummed waste produced in the cement solidification system. The hazardous waste quantity for 1994 also includes about 1,900 kilograms (4,200 lbs) of waste produced in preparing for vitrification. Hazardous waste and industrial waste volumes have been tracked separately for vitrification-related and nonvitrification-related waste streams since vitrification began in 1996. To maintain historical comparability, the percentages in Fig-


ure 1-5 include only the nonvitrification portions of these two waste streams.

Spills and Releases. Chemical spills greater than the applicable reportable quantity must be reported immediately to NYSDEC and the National Response Center and other agencies as required. There were no reportable chemical spills during 2000.

Petroleum spills greater than 5 gallons or of any amount that travel to waters of the state must be reported immediately to the NYSDEC spill hotline and entered in the monthly log. There were no reportable petroleum spills in 2000. Figure 1-6 (*facing page*) is a bar graph of immediately reportable spills from 1994 to 2000.

Prevention is the best means of protection against oil, chemical, and hazardous substance spills or releases. WVDP employees are trained in applicable standard operating procedures for equipment that they use, and best management practices have been developed that identify potential spill sources and measures that will re-






duce the potential for releases to occur. Spill training, notification, and reporting policies have also been developed to emphasize the responsibility of each employee to report spills immediately upon discovery. This first-line reporting helps to ensure that spills will be properly documented and mitigated in accordance with applicable regulations.

Vitrification. To safely solidify the high-level radioactive waste in borosilicate glass, the high-level waste sludge is transferred in batches from the tank where it currently is stored to the vit-

rification facility. After transfer, the waste is solidified into a durable glass for safe storage and future transport to a federal repository. It is estimated that 11 million to 12 million curies of strontium and cesium radioactivity in the high-level waste eventually will be vitrified. (Radioactive cesium and strontium isotopes account for 98% of the long-lived radioactivity.) To quantify the progress made toward completing the vitrification goal, Figure 1-7 (*below*) shows the number of curies transferred to the vitrification facility from 1996 through 2000.

On June 10, 1998, the WVDP marked completion of the Project's production phase (Phase I) of high-level waste processing. This milestone included safely filling 210 canisters with solidified waste glass. More than 11.3 million curies were immobilized through vitrification and 254 canisters were filled by the end of 2000.



ENVIRONMENTAL MONITORING

Routine Monitoring Program

Routine activities at the West Valley Demonstration Project (WVDP) can lead to the release of radioactive or hazardous substances that could affect the environment. Possible pathways for the movement of radionuclides or hazardous substances from the WVDP to the public include milk and food consumed by humans; forage consumed by animals; sediments, soils, groundwater, and surface water; and effluent air and liquids released by the WVDP.

The food pathway is monitored by collecting samples of beef, hay, milk, and produce at near-site and remote locations, samples of fish upstream and downstream of the site, and venison samples from near-site deer and deer taken from background locations. Stream sediments are sampled upstream and downstream of the WVDP, and both on-site groundwater and off-site drinking water are routinely sampled. Direct radiation is monitored on-site, at the perimeter of the site, in communities near the site, and at background locations.

The primary focus of the monitoring program, however, is on surface water and air pathways, as these are the principal means of transport of radionuclides from the WVDP.

Liquid and air effluents are monitored on-site by collecting samples at locations where radioactivity or other regulated substances are released or might be released. Release points include water effluent outfalls and plant ventilation stacks.

Surface water samples are collected within the Project site from ponds, swamps, seeps, and drainage channels that flow through the Western New York Nuclear Service Center (WNYNSC) and thence off-site into Cattaraugus Creek.

Both surface water and air samples are collected at site perimeter locations where the highest off-site concentrations of transported radionuclides might be expected. Samples are also collected at remote locations to provide background concentration data for comparison with data from on-site and near-site samples.

Sampling Program Overview

The complete environmental monitoring schedule is delineated in Appendix B. This schedule provides information on monitoring and reporting requirements and the types and extent of sampling and monitoring at each location. An explanation of the codes that identify the sample medium and the specific sampling or monitoring location is also found in Appendix B (p.B-iii). For example, a sample location code such as AFGRVAL indicates an air sample (A), off-site (F), at the Great Valley (GRVAL) sampling station. These codes are used throughout this report for ease of reference and to be consistent with the data reported in the appendices.

Surface Water Sampling Locations. Automatic samplers collect surface water at points along drainage channels within the WNYNSC that are most likely to show any radioactivity released from the site. These automatic samplers collect a 50-milliliter (mL) aliquot (about one-quarter of a cup of water) every half-hour. The aliquots are pumped into a large container for compositing samples from which the samples are then collected.

The samplers operate on-site at four locations: WNSP006, the point in Frank's Creek where Project drainage leaves the security-fenced area; WNNDADR, the drainage point downstream of the Nuclear Regulatory Commission (NRC)-licensed disposal area (NDA); WNSWAMP, the northeast swamp drainage; and WNSW74A, the north swamp drainage.

Off-site, automatic samplers collect surface waters from Buttermilk Creek at a background station upstream of the site (WFBCBKG), from Buttermilk Creek downstream of the site at Thomas Corners Road bridge (WFBCTCB), the last monitoring point before Buttermilk Creek



Collecting a Sample at a Stream Sampling Location

leaves the WNYNSC, and from Cattaraugus Creek at Felton Bridge (WFFELBR). Grab samples are collected at several other surface water locations both on-site and off-site, including a background location on Cattaraugus Creek at Bigelow Bridge (WFBIGBR).

Figure A-2 (p.A-4 in Appendix A) shows the locations of the on-site surface water monitoring points. Figure A-3 (p.A-5) shows the locations of the off-site surface water monitoring points.

Air Sampling Locations. Air samplers are located on-site, at the perimeter of the site, and at points remote from the WVDP. Figure A-4 (p.A-6) shows the locations of the on-site air effluent monitors and samplers and the on-site ambient air samplers; Figure A-5 (p.A-7)

and Figure A-12 (p.A-14) show the locations of the perimeter and remote air samplers.

Radiological Monitoring: Surface Water

The WVDP site is drained by several small streams. (See Surface Water Hydrology of the West Valley Site in Chapter 3, p.3-2, and Figs.A-2 [p.A-4] and A-3 [p.A-5].) Frank's Creek flows along and receives drainage from the south plateau. As Frank's Creek flows northward, it is joined by a tributary, Erdman Brook, which receives effluent from the low-level waste treatment facility. On the north plateau, beyond the Project fence line, the north and northeast swamp areas and Quarry Creek drain into Frank's Creek.

Frank's Creek continues past the WVDP perimeter and flows across the WNYNSC, where it enters Buttermilk Creek. Radionuclide concentrations in Buttermilk Creek are monitored upstream and downstream of the WVDP. Further downstream, Buttermilk Creek leaves the WNYNSC and enters Cattaraugus Creek, which is also monitored for radionuclide concentrations both upstream and downstream of the point where the creek receives effluents from the WVDP.

Two liquid effluents, from the low-level waste treatment facility and from the northeast and north swamp drainage, are primary contributors to site dose estimates. (See Chapter 4, Radiological Dose Assessment, Table 4-2 [p.4-6] for an estimate of the dose attributable to these waterborne effluents.)

Low-level Waste Treatment Facility Sampling Location. The discharge from the low-level waste treatment facility (LLW2) through the lagoon 3 weir (WNSP001 on Fig.A-2 [p.A-4])

into Erdman Brook, a tributary of Frank's Creek, is the largest single source of radioactivity released to surface waters from the Project. There were six batch releases totaling about 43.7 million liters (11.5 million gal) in 2000. Composite samples were collected near the beginning and end of each discharge and one effluent grab sample was collected during each day of discharge. Samples were analyzed for gross alpha and gross beta radioactivity, for gamma-emitting radionuclides, and for specific radionuclides as noted in Appendix B, p.B-7.

The total amounts of radioactivity from specific radionuclides in the lagoon 3 effluent are listed in Appendix C, Table C-1 (p.C-3). The annual average concentration of each radionuclide is divided by its corresponding Department of Energy (DOE) derived concentration guide (DCG) in order to determine what percentage of the DCG was released. (DOE standards and DCGs for radionuclides of interest at the WVDP are found in Appendix K [Table K-1, p.K-3].) As a DOE policy, the sum of the percentages calculated for all radionuclides released should not exceed 100%.

The combined annual average of radionuclide concentrations from the lagoon 3 effluent discharge weir in 2000 was approximately 34.0% of the DCGs. (See Table C-2 [p.C-4].) This is comparable to the average concentration over the last five years of approximately 31%.

The low-level waste treatment facility was designed to efficiently remove strontium-90 and cesium-137, the more prevalent of the long-lived fission products in WVDP wastewaters. Other radionuclides are also removed to a lesser extent by the low-level waste treatment facility. For example, one other major contributor to the total combined DCG in lagoon 3 effluent is uranium-232, which averaged about 13% of its

DCG in 2000. Uranium-232 and other uranium isotopes are found in WVDP liquid waste because they were present in the nuclear fuel that was once reprocessed at the site. Variations in liquid effluent radionuclide ratios continue to reflect the dynamic nature of the waste streams being processed through the low-level waste treatment facility.

(Outfall WNSP001, the lagoon 3 weir, is monitored also for nonradiological parameters under the New York State Pollutant Discharge Elimination System [SPDES] program. See Nonradiological Monitoring: Surface Water [p.2-26].)

Northeast Swamp and North Swamp Sampling Locations. The northeast and north swamp drainages on the site's north plateau conduct surface water and emergent groundwater off-site.

The northeast swamp sampling location (WNSWAMP) monitors surface water drainage from the site's north plateau. The north swamp sampling point (WNSW74A) monitors drainage to Quarry Creek from the northern end of the Project premises. (See Fig.A-2 [p.A-4].) Waters from the northeast swamp drainage run into Frank's Creek downstream of location WNSP006, the point in Frank's Creek where Project drainage leaves the security-fenced area. (See Other Surface Water Sampling Locations below.)

Samples from WNSWAMP and WNSW74A are collected weekly and analyzed for radiological parameters. Although DCGs are not directly applicable to these points, other than gross beta and strontium-90, concentrations of all radiological parameters detected at WNSWAMP and WNSW74A were less than 1% of the DCGs for these parameters. The maximum and minimum gross alpha and gross

beta results from WNSWAMP and WNSW74A are noted on Tables 2-1 and 2-2 (*facing page*). Complete data from these two locations are found in Tables C-7 and C-8 (pp.C-8 and C-9 in Appendix C). An upward trend in gross beta concentrations at WNSWAMP, first noted in 1993, continued through 1999. Concentrations in 2000 were lower than in 1999. Gross beta activity at this location is largely attributable to strontium-90. (See Special Groundwater Monitoring, p.3-16.)

Strontium-90 concentrations at WNSWAMP in 2000 ranged from a low of $9.00\text{E-}07$ $\mu\text{Ci/mL}$ to a high of $2.10\text{E-}06$ $\mu\text{Ci/mL}$ (33.3 Bq/L to 77.6 Bq/L), with an annual average of $1.48\text{E-}06$ $\mu\text{Ci/mL}$ (54.8 Bq/L). (See Chapter 3, Fig.3-4, p.3-17, for a graph of the annualized average strontium-90 concentration at WNSWAMP in 2000.) Even though waters with elevated strontium-90 concentrations drain from WNSWAMP into Frank's Creek, waters collected from Cattaraugus Creek downstream at the first point of public access (WFFELBR) averaged less than 1% of the DCG for strontium-90, $1\text{E-}06$ $\mu\text{Ci/mL}$ (37 Bq/L). Moreover, strontium-90 concentrations at WFFELBR were not significantly different from those at the background location, WFBIGBR, which is upstream of the location where site drainage enters Cattaraugus Creek. (See Off-site Surface Water Sampling Locations, p.2-9.)

Other Surface Water Sampling Locations. Samples taken from a point in Frank's Creek (WNSP006), from the sanitary and industrial wastewater treatment facility discharge (WNSP007), and from subsurface drainage from the perimeter of the low-level waste treatment facility storage lagoons (WNSP008) are routinely monitored for radiological parameters. (See Fig.A-2 [p.A-4].) Discharges from WNSP001, WNSP007, and WNSP008 leave the site through point WNSP006. Radiological

Table 2-1
2000 Gross Alpha Concentrations at Surface Water Sampling Locations

Location	Number of Samples	Range		Annual Average	
<i>Off-site</i>					
		<i>(μCi/mL)</i>	<i>(Bq/L)</i>	<i>(μCi/mL)</i>	<i>(Bq/L)</i>
WFBCBKG	12	<4.36E-10 to 8.99E-10	<1.61E-02 to 3.33E-02	0.80±6.86E-10	0.30±2.54E-02
WFBCTCB	12	<5.71E-10 to 4.64E-09	<2.11E-02 to 1.72E-01	1.39±1.07E-09	5.15±3.97E-02
WFBIGBR	12	<7.99E-10 to 4.62E-09	<2.96E-02 to 1.71E-01	5.91±9.71E-10	2.19±3.59E-02
WFFELBR	12	<6.49E-10 to 1.02E-08	<2.40E-02 to 3.78E-01	2.14±1.32E-09	7.92±4.89E-02
<i>On-site</i>					
WNNDADR	12	<6.94E-10 to 2.36E-09	<2.57E-02 to 8.74E-02	0.28±1.35E-09	1.02±5.01E-02
WNSP006	52	<7.10E-10 to 6.75E-09	<2.63E-02 to 2.50E-01	0.76±1.54E-09	2.81±5.69E-02
WNSW74A	52	<1.27E-09 to 1.14E-08	<4.70E-02 to 4.20E-01	-0.22±3.44E-09	-0.08±1.27E-01
WNSWAMP	52	<9.17E-10 to 7.25E-09	<3.39E-02 to 2.68E-01	0.60±1.83E-09	2.21±6.78E-02

Table 2-2
2000 Gross Beta Concentrations at Surface Water Sampling Locations

Location	Number of Samples	Range		Annual Average	
		<i>($\mu\text{Ci/mL}$)</i>	<i>(Bq/L)</i>	<i>($\mu\text{Ci/mL}$)</i>	<i>(Bq/L)</i>
<i>Off-site</i>					
WFBCBKG	12	<1.18E-09 to 3.45E-09	<4.36E-02 to 1.28E-01	2.12±1.22E-09	7.84±4.52E-02
WFBCTCB	12	5.39E-09 to 2.21E-08	2.00E-01 to 8.19E-01	8.93±1.57E-09	3.31±0.58E-01
WFBIGBR	12	<1.30E-09 to 8.17E-09	<4.80E-02 to 3.02E-01	3.05±1.19E-09	1.13±0.44E-01
WFFELBR	12	<1.27E-09 to 1.06E-08	<4.70E-02 to 3.92E-01	5.21±1.71E-09	1.93±0.63E-01
<i>On-site</i>					
WNNDADR	12	1.41E-07 to 2.26E-07	5.20E+00 to 8.36E+00	1.93±0.06E-07	7.15±0.23E+00
WNSP006	52	1.80E-08 to 1.94E-07	6.66E-01 to 7.16E+00	4.64±0.41E-08	1.72±0.15E+00
WNSW74A	52	<4.89E-09 to 3.31E-08	<1.81E-01 to 1.22E+00	1.17±0.47E-08	4.33±1.74E-01
WNSWAMP	52	7.30E-07 to 5.00E-06	2.70E+01 to 1.85E+02	2.91±0.03E-06	1.07±0.01E+02

results of analyses from WNSP006, WNSP007, and WNSP008 are summarized in Tables C-4, C-5, and C-6 (pp.C-6 and C-7). Samples from these points also are monitored for nonradiological parameters as part of the site's SPDES program. (See Nonradiological Monitoring: Surface Water [p.2-26].)


WNSP006. WNSP006 is located more than 4.0 kilometers (2.5 mi) upstream from Thomas Corners Road, which is the last monitoring point before Buttermilk Creek leaves the WNYNSC and before the public has access to the creek waters. Samples from WNSP006 are retrieved weekly and composited both monthly and quarterly and are analyzed for the same radionuclides as the effluent samples from WNSP001.

The highest monthly concentration of a beta-emitting radionuclide at WNSP006 was strontium-90 at $3.94\text{E-}08 \mu\text{Ci/mL}$ (1.46 Bq/L), which is less than 4% of the DCG for strontium-90. Average concentrations of gross beta (as strontium-90), strontium-90, cesium-137,

and tritium were each less than 5% of the comparable DCG. Averages of the radiological parameters monitored at WNSP007 (gross alpha, gross beta, tritium, and cesium-137) and at WNSP008 (gross alpha, gross beta, and tritium) in 2000 also were found at a small percentage of the DCG.

The average gross alpha and gross beta data from location WNSP006 and the maximum and minimum results are noted in Tables 2-1 and 2-2 (p.2-5) for comparison with sampling results from other on- and off-site surface water locations. Figure 2-1 (*below*) shows the fourteen-year trends of gross alpha, gross beta, and tritium concentrations at location WNSP006. Fluctuations in these long-term trends at WNSP006 reflect variable concentrations in treated WVDP liquid effluent being released from the site.

Concentrations observed farther downstream at Felton Bridge (WFFELBR), the sampling location that represents the first point of public access to surface waters leaving the WVDP



site, continue to be close to or indistinguishable from background.

WNSP005 and WNCoolW. Sampling point WNSP005, which monitors drainage from land on the east side of the main plant, and WNCoolW, which monitors facility coolant water, are sampled monthly for gross alpha, gross beta, and tritium concentrations. WNCoolW also is sampled quarterly for gamma isotopes, including cesium-137. Radiological data for WNSP005 and WNCoolW are found in Tables C-3 and C-11 (pp.C-5 and C-11).

Average gross alpha and tritium concentrations for both locations were below detection levels in 2000. Average gross beta concentrations at WNSP005 and WNCoolW were considerably lower than the strontium-90 DCG (<16% and <1% respectively). Average cesium concentrations at WNCoolW were below detection levels in 2000.

WN8D1DR. This sampling point is at the access to a storm sewer manhole that originally collected surface and shallow groundwater flow from the high-level waste tank farm area. (Notable increases in gross beta and tritium activity at this location, attributable to historical site contamination, have been described in previous annual site environmental reports.) In July 1993 the access was valved off from the original high-level waste tank farm drainage area to prevent collected waters from rising freely to the surface. Although samples from this location are thought to be not representative of either local groundwater or surface water, weekly sampling for gross alpha, gross beta, and tritium continues at this point. A monthly composite is analyzed for gamma radionuclides and strontium-90.

Average gross alpha, tritium, and cesium-137 concentrations from WN8D1DR were all be-

low detection levels in 2000. Gross beta concentrations, attributable largely to strontium-90, averaged less than 1% of the applicable DCG. Radiological data for WN8D1DR are found in Table C-13 (p.C-12).

NDA and SDA Sampling Locations. Two inactive underground disposal areas, the Nuclear Regulatory Commission (NRC)-licensed disposal area (NDA) and the state-licensed disposal area (SDA), lie on the south plateau of the site. (The SDA is managed by the New York State Energy and Research Development Authority [NYSERDA].) The drum cell, an above-ground structure used to store approximately 19,000 drums of processed low-level radioactive waste, is located nearby. Surface waters, which flow from the south to the north, are routinely monitored at several points around these sites. (See Fig.A-2 [p.A-4].) In addition to the routine samples collected by the WVDP, samples are collected and analyzed by the New York State Department of Health (NYSDOH) at the two stream sampling points that receive drainage from the south plateau, WNFRC67 and WNERB53.

NRC-licensed Disposal Area (NDA). Sampling point WNNDATR is a sump at the bottom of a steep-sided trench immediately downgradient of the NDA that intercepts groundwater from the NDA. If radiological or nonradiological contamination were to migrate through the NDA, it would most likely be first detected in samples from WNNDATR. Monthly samples from WNNDATR are taken under the auspices of the environmental monitoring program and quarterly samples under the auspices of the groundwater monitoring program.

Surface water drainage downstream of the NDA is monitored at WNNDADR, and water from sampling point WNERB53 in Erdman Brook, which represents surface waters further down-

stream from the NDA before they join with drainage from the main plant and lagoon areas, also is monitored. Some drainage from western and northwestern portions of the SDA also passes through sampling points WNNDADR and WNERB53.


Results from WNNDATR, the sump in the interceptor trench, are in Table C-20 (p.C-17). Results from WNNDADR, surface water drainage downstream of the NDA, are in Table C-19 (p.C-16), and results from WNERB53, the sampling location even further downstream of the NDA, are in Table C-10 (p.C-10). Parameters monitored at these three NDA sampling locations include gross alpha, gross beta, tritium, iodine-129, and cesium-137.

Gross alpha and gross beta results from WNNDADR are included in Tables 2-1 and 2-2 (p.2-5) for comparison with results from other surface water locations. In addition, fourteen-year trends of gross alpha, gross beta, and tritium concentrations at WNNDADR are plotted in Figure 2-2 (*below*).

Gross alpha. Gross alpha results from water samples taken at WNNDATR, WNNDADR, and WNERB53 in 2000 were indistinguishable from background results (WFBCBKG).

Gross beta. Gross beta results at all three locations were elevated with respect to background, but even the maximum concentrations were well below $1\text{E-}06 \mu\text{Ci/mL}$, the DCG for strontium-90 in water, at about 10%, 20%, and 2% respectively. Gross beta activity at these locations is attributable largely to strontium-90. Residual contamination from past waste burial activities in soils outside the NDA is thought to be the source of the activity.

Over the last ten years annual average gross beta concentrations at WNNDADR (surface water drainage downstream of the NDA) have generally decreased while those at WNNDATR (the sump in the interceptor trench) have generally increased. However, results in 2000 from both locations were within the range of historical values. No evident cause of these trends has been noted.



Tritium. Although tritium concentrations at WNNDATR and WNNDADR were also elevated with respect to background values (those from WNERB53 were not), the maximum concentrations from both WNNDATR and WNNDADR were less than 1% of the DCG for tritium in water ($2\text{E-}03\ \mu\text{Ci/mL}$). Allowing for seasonal variations, tritium concentrations seem to be generally decreasing at both WNNDATR and WNNDADR. Since the half-life of tritium is slightly longer than twelve years, decreasing tritium concentrations may be partially attributable to radioactive decay.

Iodine-129. A key indicator of possible migration of nonradiological organic contaminants from the NDA would be iodine-129, which is known to travel with the organic contaminants present in the NDA and is soluble in water. Although iodine-129 has been detected upon occasion at WNNDADR and WNNDATR in previous years, none was detected in 2000.

Cesium-137. No cesium-137 activity was detected at either location in 2000.

Total organic halides. Total organic halides (TOX) measurements are used to detect the presence of certain organic compounds and associated radionuclides. (See also Results of Monitoring at the NDA in Chapter 3, p. 3-14.) Average TOX concentrations were higher at WNNDATR in 2000 than in 1999, but average concentrations at WNNDADR were lower in 2000 than in 1999. However, at both locations TOX sampling results were within the range of historical values.

New York State-licensed Disposal Area (SDA). Point WNSDADR is used to monitor drainage from trench covers on the southwestern area of the SDA. Immediately south of the SDA, and upstream of WNSDADR, sampling point WNDCELD is used to monitor surface drain-

age from the area around the drum cell. (See Fig.A-2 [p.A-4].) To the northeast, sampling point WNFRC67, in Frank's Creek, is used to monitor drainage downstream of the drum cell and the eastern and southern borders of the SDA. Results from WNSDADR, WNDCELD, and WNFRC67 are in Tables C-12 (p.C-11), C-14 (p.C-12), and C-9 (p.C-10) respectively.

With the exception of tritium at WNSDADR, all radiological results in calendar year 2000 at sampling points WNSDADR, WNDCELD, and WNFRC67 were statistically indistinguishable from background surface water results at WFBCBKG. Tritium concentrations at WNSDADR were slightly higher than background values, but even the highest result — $2.92\text{E-}07\ \mu\text{Ci/mL}$ ($10.8\ \text{Bq/L}$) — was less than 0.02% of the tritium DCG — $2\text{E-}03\ \mu\text{Ci/mL}$ ($7.4\text{E+}4\ \text{Bq/L}$).

Standing Pond Water Sampling Locations.

In addition to samples from moving water (streams or seeps), samples from ponds within the retained premises (WYNNSC) are also collected and tested annually for various radiological and water quality parameters to confirm that no major changes are occurring in standing water within the Project environs.

Four ponds near the site were tested in 2000. For comparison, a background pond 14.1 kilometers (8.8 mi) north of the Project was also tested. (See Figs.A-2 and A-3 [pp.A-4 and A-5] for the locations of the five ponds and Table C-21 [p.C-18] for a summary of sampling results.) Gross alpha, gross beta, and tritium concentrations in samples from all on-site ponds were statistically the same as concentrations at the background pond.

Off-site Surface Water Sampling Locations.

Samples of surface water are collected at four off-site locations, two on Buttermilk Creek and

two on Cattaraugus Creek. Off-site surface water and sediment sampling locations are shown on Fig.A-3 (p.A-5). Tables 2-1 and 2-2 (p.2-5) list the ranges and annual averages for gross alpha and gross beta activity at off-site surface water locations, which may be compared with data from on-site locations.

Fox Valley Road and Thomas Corners Bridge Sampling Locations. Buttermilk Creek is the major surface drainage from the WYNESC. Two surface water monitoring stations are located on Buttermilk Creek, one upstream of the WVDP at Fox Valley Road (WFBCBKG) and one downstream of the WVDP at Thomas Corners bridge (WFBCTCB). The Thomas Corners bridge sampling location is also upstream of Buttermilk Creek's confluence with Cattaraugus Creek. The Thomas Corners bridge sampling location represents an important link in the pathway to humans because dairy cattle have access to the water here.

Samples collected every week are composited monthly and analyzed for tritium, gross alpha,

and gross beta radioactivity. A quarterly composite is analyzed for gamma-emitting radionuclides and strontium-90. Quarterly samples from WFBCBKG, the background location, also are analyzed for specific radionuclides as noted in Appendix B, p.B-29, and the results are used as a base for comparison with results of samples from site effluents.

Table C-22 (p.C-19) lists radionuclide concentrations at the Fox Valley Road background location; Table C-23 (p.C-20) lists radionuclide concentrations downstream of the site at Thomas Corners bridge.

Gross alpha and gross beta. Gross alpha and gross beta concentrations at Thomas Corners bridge were slightly higher than background concentrations in 2000. Because the monitoring point in Frank's Creek (WNBP006), which is upstream of Thomas Corners and much closer to the site, did not show elevated gross alpha concentrations, it is suspected that the elevated gross alpha concentrations at Thomas Corners were due to natural radioactivity in suspended



Springville Dam on Cattaraugus Creek

sediments. Gross beta concentrations, however, were elevated at both WNSP006 and Thomas Corners bridge and may be attributed to small amounts of radioactivity moving from the site, principally during periods of lagoon discharge, via Frank's Creek.

The highest gross alpha concentration noted at Thomas Corners bridge was $4.64\text{E-}09$ $\mu\text{Ci/mL}$ (0.17 Bq/L); the highest gross beta concentration was $2.21\text{E-}08$ $\mu\text{Ci/mL}$ (0.82 Bq/L). If compared to the most conservative guidelines for alpha and beta emitters in water (americium-241 at $3\text{E-}08\mu\text{Ci/mL}$ [1.1Bq/L] and strontium-90 at $1\text{E-}06\mu\text{Ci/mL}$ [37Bq/L]), these gross alpha and gross beta concentrations at Thomas Corners bridge would be about 15% and 2% of the respective DCGs.

Tritium, strontium-90, and cesium-137 concentrations were not significantly different from background results.

Cattaraugus Creek at Felton Bridge and Bigelow Bridge Sampling Locations. Buttermilk Creek flows through the WNYNSC and then off-site, where it flows into Cattaraugus Creek. An automated sampler is located on Cattaraugus Creek at Felton Bridge (WFFELBR), just downstream of the point where Buttermilk Creek enters. Samples are collected weekly and analyzed for gross alpha, gross beta, and tritium concentrations. A chart recorder registers the stream depth during the sampling period so that a flow-weighted weekly sample can be proportioned into a monthly composite, which is analyzed for gross alpha, gross beta, tritium, strontium-90, and gamma-emitting radionuclides. (See Table C-24 [p.C-20].)

Background samples are collected monthly from Cattaraugus Creek at Bigelow Bridge (WFBIGBR), which is upstream of the point where Buttermilk Creek enters Cattaraugus

Creek. These samples are analyzed for concentrations of gross alpha, gross beta, tritium, strontium-90, and gamma-emitting radionuclides. (See Table C-25 [p.C-21].)

No statistically significant differences were noted between results of analyses for gross alpha, tritium, strontium-90, and cesium-137 at either the upstream or downstream sampling locations. However, gross beta concentrations at Felton Bridge (WFFELBR) were higher than those at the background location at Bigelow Bridge (WFBIGBR). The highest gross beta concentration at Felton Bridge in 2000 was $1.06\text{E-}08$ $\mu\text{Ci/mL}$ (0.39 Bq/L), which is about 1% of the DCG for strontium-90. Figure 2-3 (p. 2-12) shows gross alpha, gross beta, and tritium results over the past fourteen years in Cattaraugus Creek samples taken at Felton Bridge. For the most part, tritium concentrations represent method detection limits and not detected radioactivity. (Method detection limit values are levels below which the analytical measurement could not detect any radioactivity. [See Data Reporting in Chapter 1, p.1-5.]) Taking into account seasonal fluctuations, gross beta activity appears to have remained relatively constant at this location since 1987.

Drinking Water Sampling Locations. Drinking water (potable water) is sampled both off-site (near the WVDP) and on-site. Off-site drinking water samples are taken from wells that represent the nearest unrestricted use of groundwater near the Project; none of these wells draw from groundwater units underlying the site. Drinking water and utility water for the Project are drawn from two on-site surface water reservoirs.

Off-site wells. Nine off-site private, residential wells between 1.5 kilometers (0.9 mi) and 7 kilometers (4.3 mi) from the facility were sampled for radiological parameters in 2000.




Figure 2-3. Fourteen-year Trends of Gross Alpha, Gross Beta, and Tritium Concentrations at Sampling Location WWFELBR

A tenth private well, 29 kilometers (18 mi) south of the site, provides a background sample. Sampling locations are shown in Figures A-9 and A-12 (pp.A-11 and A-14) in Appendix A. Results from the sampling are presented in Table C-26 (p.C-21). Radiological results in 2000 were within the range of historical values.

On-site drinking and utility water. On-site drinking water sources were also monitored for radionuclides at four locations: the Environmental Laboratory (WNDNKEL); the maintenance shop (WNDNKMS); the main plant (WNDNKMP); and the utility room (WNDNKUR). Monthly samples were analyzed for gross alpha, gross beta, and tritium concentrations. Results of analyses of samples from site locations were compared with those from the entry point location at the utility room, which serves as a background sampling location for these drinking water samples. No differences between background values and those from site locations were noted. (See Appendix C, Tables C-15 through C-18 [pp.C-13 through C-15].)

Radiological Monitoring: Sediments

Particulate matter in streams can adsorb radiological constituents in liquid effluents, settle on the bottom of the stream as sediment, and subsequently be eroded or resuspended, especially during periods of high stream flow. These resuspended sediments may provide a pathway for radiological constituents to reach humans either directly via exposure or indirectly through the food pathway.


On-site sediments. Sediment samples are taken from the same locations as surface water samples and are identified as sediment samples by the "SNS" or "SFS" prefix. (See Appendix B, p. B-iii.) Sediments are collected on-site at the three points where liquid effluents leaving the site are most likely to be radiologically contaminated: Frank's Creek where it leaves the security fence (SNSP006); the north swamp (SNSW74A); and the northeast swamp (SNSWAMP). Figure A-2 (p.A-4) shows the on-

site sediment sampling locations. (Note that swamp sediment samples may be partially composed of soils.) Results from radiological analyses of these samples are listed in Table C-28 (p.C-23). As expected, gross beta, cesium-137, and strontium-90 results were higher at the on-site sediment sampling points than at the off-site background sampling points; gross alpha concentrations were similar to background values.


Off-site sediments. Sediments are collected off-site at three locations downstream of the WVDP: Buttermilk Creek at Thomas Corners Road (SFTCSSED), Cattaraugus Creek at Felton Bridge (SFCCSED), and Cattaraugus Creek at the Springville dam (SFSDSED). The first two sampling points are located at automatic water samplers. The other is behind the Springville dam, where water would be expected to transport and deposit sediments that

had adsorbed radionuclides from the site. Locations upstream of the WVDP are Buttermilk Creek at Fox Valley Road (SFBCSED) and Cattaraugus Creek at Bigelow Bridge (SFBISED). The two upstream locations provide background data for comparison with downstream points. Figure A-3 (p.A-5) shows the off-site sediment sampling locations.

Although gross alpha, gross beta, and strontium-90 concentrations in sediments downstream of the WVDP were not statistically different from background concentrations, cesium-137 concentrations in downstream sediments were higher, as they have been historically. A comparison of annual averaged cesium-137 concentrations from 1986 through 2000 for the five off-site sampling locations is illustrated in Figure 2-4 (*below*). As the figure indicates, cesium-137 concentrations are relatively stable



at the two background locations (SFBCSED and SFBISED) and are either stable or declining at the three locations downstream of the WVDP (SFTCSED, SFCCSED, and SFSDSED). As noted in the 1999 Site Environmental Report, the level of cesium-137 observed behind the Springville dam (SFSDSED) was noticeably lower in 1998 and 1999 than in the past, and this may have been associated with the scouring of sediments during a flood on June 26, 1998. In 2000 the concentration of cesium-137 in samples from this same location rebounded to pre-flood levels. The rebound probably is attributable to upstream sediments being transported to and deposited at this location. The cesium-137 concentrations at the two other downstream locations (SFTCSED and SFCCSED) remained near historical levels.




Although cesium-137 activity historically is elevated in downstream Cattaraugus Creek sediments, relative to upstream sediments (see Appendix C, Table C-30 [p.C-25]), the levels are far lower than those of naturally occurring gamma emitters such as potassium-40. (See Fig. 2-5 [this page], which is a graphic comparison of cesium-137 to potassium-40 at the downstream location nearest the WVDP, i.e., Buttermilk Creek at Thomas Corners Road — SFTCSED.) Moreover, these downstream-sediment cesium-137 concentrations are still within the historical range of cesium-137 concentrations in background surface soil (Great Valley [SFGRVAL] and Nashville [SFNASHV]. See Appendix C, Table C-29 [p.C-24].)

Radiological Monitoring: Air

Permits obtained from the U.S. Environmental Protection Agency (EPA) allow air containing small amounts of radioactivity to be released from plant ventilation stacks during normal operations. The air released must meet criteria specified in the National Emission Standards for Hazardous Air Pollutants (NESHAP) regulations to ensure that the environment and the public's health and safety are protected. Dose-based comparisons of WVDP emissions against NESHAP criteria are presented in Chapter 4, Radiological Dose Assessment.

Unlike NESHAP dose criteria, the DOE DCGs are expressed in units of $\mu\text{Ci/mL}$ and therefore can be directly compared with concentrations of radionuclides in WVDP air emissions. DOE standards and DCGs for radionuclides of interest at the WVDP are found in Appendix K, Table K-1 (p.K-3).

Radiological parameters measured in air emissions include concentrations of gross alpha and gross beta, tritium, strontium-90, cesium-137,



and other radionuclides. When comparing concentrations with dose limits for screening purposes, gross alpha and beta radioactivities are assumed to come from americium-241 and strontium-90, respectively, because the dose effects for these radionuclides are the most limiting for major particulate emissions at the WVDP.

On-site Ventilation Systems. The exhaust from each EPA-permitted fixed ventilation system on-site is continuously filtered, monitored, and sampled as it is released to the atmosphere. Because concentrations of radionuclides in air emissions are quite low, a large volume of air must be sampled at each point in order to measure the quantity of specific radionuclides released from the facility. Specially designed sampling nozzles continuously remove a representative portion of the exhaust air, which is then drawn through very fine glass fiber or membrane filters to trap particulates. Sensi-

tive detectors continuously monitor these filters and provide readouts of alpha and beta radioactivity levels.

Separate sampling units on the ventilation stacks of the permitted systems contain another glass fiber filter that is removed every week and tested in the laboratory. These filters are analyzed routinely for the parameters delineated in Appendix B of this report.

Special samples also are collected in order to monitor gaseous (non-particulate) emissions of radioactivity. For example, six of the sampling systems contain an activated carbon cartridge that collects gaseous iodine-129, and at two locations water vapor is collected by trapping moisture in silica gel desiccant columns. The trapped water is distilled from the silica gel desiccant and analyzed for tritium. Figure A-4 (p.A-6) shows the locations of on-site air monitoring and sampling points.

The Main Plant Ventilation Stack. The main ventilation stack (ANSTACK) is the primary source of airborne releases at the WVDP. This stack, which vents to the atmosphere at a height of more than 60 meters (more than 200 ft), releases filtered ventilation from several facilities, including the liquid waste treatment system, the analytical laboratories, and off-gas from the vitrification system.

Samples from the main plant stack are collected weekly and analyzed for gross alpha, gross beta, and tritium concentrations. Weekly filters are composited quarterly and analyzed for strontium-90, gamma-emitting radionuclides, total uranium, uranium isotopes, plutonium isotopes, and americium-241. Charcoal cartridges collected weekly are composited quarterly and analyzed for iodine-129. In addition, filters from the main plant ventilation stack are routinely analyzed for strontium-89 and cesium-137 as part of operational-safety monitoring.

Monthly and quarterly total curies released from the main stack in 2000 are summarized in Table D-1 (p.D-3). Total curies released, annual averages, and a comparison of total curies released with the applicable DCGs are summarized in Table D-2 (p.D-4). As in previous years, 2000 results show that average radioactivity levels at the point of discharge from the stack were already below concentration guidelines for airborne radioactivity in an unrestricted environment. Airborne concentrations from the stack to the site boundary are further reduced via dispersion by a factor of more than 200,000. Results from air samples taken just outside the site boundary confirm that WVDP operations had no discernible effect on off-site air quality. (See Perimeter and Remote Air Sampling, p.2-18.)

Figure 2-6 (p. 2-15) shows the gross alpha and gross beta curies released per month from the main stack during the past fourteen years. The

figure indicates a steady five-year downward trend in both gross alpha and gross beta activity from 1987 to mid-1992 and a stabilization through mid-1995. Previtrification transfers of cesium-loaded zeolite from waste tank 8D-1 to 8D-2 began in late 1995, and releases increased.

In June 1998 the WVDP completed the first phase of high-level waste vitrification, processing the bulk of the waste in tank 8D-2. In the latter part of 1998 the focus of the vitrification program shifted to the second phase, vitrifying waste from the high-level waste residuals in the tank. Phase II vitrification continued throughout 2000. Forty-four glass canisters have been filled during this phase of vitrification, nine of them in 2000.

Since radioactive vitrification operations began in mid-1996 both gross alpha and gross beta releases have fluctuated while generally remaining higher than previtrification levels. In general, concentrations of gross beta, tritium, strontium-90, iodine-129, and cesium-137 have decreased during the second phase of vitrification. Gross alpha concentrations, on the other hand, have remained at relatively steady levels.

Vitrification HVAC Sampling System. Sampling point ANVITSK and the seismically protected backup sample point ANSEISK monitor emissions from the vitrification heating, ventilation, and air conditioning (HVAC) system. (Off-gas ventilation from the vitrification system itself is released through the main plant stack.)

Radioactivity concentrations were monitored at ANVITSK and ANSEISK before actual radioactive vitrification began in July 1996. The previtrification levels provide a baseline for comparison with concentrations of radionuclides in emissions during vitrification. Results

from 2000 are found in Tables D-3 and D-4 (pp.D-5 and D-6).

With the exception of iodine-129, concentrations of radionuclides measured during 2000 were indistinguishable from baseline values. Concentrations of iodine-129 increased during the fourth quarter of 1999 and remained elevated in 2000. Elevated results were thought to be associated with the maintenance of ventilation systems, in-cell waste storage activities, or wear of various components of the vitrification system (which was expected). Even so, the highest concentration observed in calendar year 2000 ($4.70\text{E-}15\ \mu\text{Ci/mL}$ [$1.74\text{E-}07\ \text{Bq/L}$]) was less than 0.01% of the DCG for iodine-129 ($7\text{E-}11\ \mu\text{Ci/mL}$ [$2.59\text{E-}03\ \text{Bq/L}$]).

Other On-site Air Sampling Systems. Sampling systems similar to those of the main stack monitor airborne effluents from the 01-14 building ventilation stack (ANCSSTK), the contact size-reduction facility ventilation stack (ANCSRFK), the supernatant treatment system ventilation stack (ANSTSTK), and the container sorting and packaging facility ventilation stack (ANCSPFK). (See Fig.A-4 [p.A-6].)

Tables D-5 through D-8 (pp.D-7 through D-10) show monthly totals of gross alpha and beta radioactivity and quarterly total radioactivity released for specific radionuclides at each of these sampling locations. Samples from these locations (ANCSSTK, ANCSRFK, ANSTSTK, and ANCSPFK) showed detectable concentrations of gross radioactivity in some cases as well as specific beta- and alpha-emitting radionuclides, but none approached any DOE effluent limitations.

Three other operations are routinely monitored for airborne radioactive releases: the new low-level waste treatment facility ventilation system (ANLLW2V), which came on-line in

1998; the old low-level waste treatment facility ventilation (ANLLWTVH); and the contaminated clothing laundry ventilation system (ANLAUNV).

The old and new low-level waste treatment facility ventilation points and the laundry ventilation system are sampled for gross alpha and gross beta radioactivity. These emission points are not required to be permitted because the potential magnitude of the emissions is so low. Although only semiannual grab sampling is required to verify the low level of emissions, all three points are sampled continuously while discharging to the environment. Data for these three facilities are presented in Tables D-9 through D-11 (pp.D-11 and D-12). Results from these calendar year 2000 samples were well below DOE effluent limitations.

Permitted portable outdoor ventilation enclosures (OVEs) are used occasionally to provide the ventilation necessary for the safety of personnel working with radioactive materials in areas outside permanently ventilated facilities. Air samples from OVEs are collected continuously while those emission points are discharging, and data from these units are included in annual airborne emission evaluations. (See Table D-15 [p.D-16].) Average discharges from OVEs were well below DOE guidelines for alpha and beta radioactivity in an unrestricted environment.

Three on-site air samplers collect samples of ambient air in the vicinity of three on-site waste storage units — the lag storage area (ANLAGAM), the NDA (ANNDAAAM), and the SDA (ANSDAT9). (See Fig.A-4 [p.A-6].) These samplers were put in place to monitor potential diffuse releases of radioactivity. Monitoring data from these locations are presented in Appendix D, Tables D-12 through D-14 (pp. D-13 through D-15).

Radiological data sets for these locations are statistically indistinguishable from background air monitoring location AFGRVAL, with the exception of tritium results at ANSDAT9. However, even the highest weekly tritium result from ANSDAT9 ($2.61\text{E-}12\ \mu\text{Ci/mL}$ [$9.66\text{E-}05\ \text{Bq/L}$]) was less than 0.003% of the DOE DCG for tritium in air ($1\text{E-}07\ \mu\text{Ci/mL}$).

Perimeter and Remote Air Sampling. Samples for radionuclides in air are collected continuously at six locations around the perimeter of the site and at four remote locations. Maps of perimeter and remote air sampling locations are found on Figure A-5 (p.A-7) and Figure A-12 (p.A-14).

The perimeter locations on Fox Valley Road (AFFXVRD), Rock Springs Road (AFRSPRD),

Route 240 (AFRT240), Thomas Corners Road (AFTCORD), Dutch Hill Road (AFBOEHN), and at the site's bulk storage warehouse (AFBLKST) were chosen because they provide historical continuity (as former NFS sampling locations) or because they represent the most likely locations for detecting off-site airborne concentrations of radioactivity.


The remote locations provide data from nearby communities— West Valley (AFWEVAL) and Springville (AFSPRVL) — and from more distant background areas. Concentrations measured at Great Valley (AFGRVAL, 30.9 km south of the site) and Nashville (AFNASHV, 39.8 km west of the site in the town of Hanover) are considered representative of regional background air.

At all locations airborne particulates are collected on filters for radiological analysis. Samplers maintain an average flow of approximately 40 L/min ($1.4\ \text{ft}^3/\text{min}$) through a 47-millimeter glass fiber filter. The sampler heads are set above the ground at the height of the average human breathing zone. Filters are collected weekly and analyzed after a seven-day “decay” period to remove interference from short-lived naturally occurring radionuclides. After weekly sample filters are measured for gross alpha and gross beta concentrations, they are combined in a quarterly composite consisting of thirteen weekly filters. The composite is analyzed for specific alpha-emitting, beta-emitting, and gamma-emitting radionuclides.

At two locations, the nearest perimeter location in the predominant downwind direction (Rock Springs Road) and the farthest background location (Great Valley), desiccant columns are used to collect airborne moisture for tritium analysis and charcoal cartridges are used to collect samples for iodine-129 analysis.



Changing an Air Filter at an Air Sampling Station



Trends of gross alpha and gross beta concentrations at the Rock Springs Road location are shown in Figure 2-7 (*above*). Within a range of seasonal and weekly fluctuations, the concentrations have been relatively constant over the past fourteen years. The gross alpha and gross beta ranges and annual averages for each of the off-site sampling points are noted on Tables 2-3 and 2-4 (p.2-20). All gross alpha averages were below detection levels. Gross beta results from samples taken at two near-site communities and from the site perimeter were similar to those from the background samplers, suggesting that there is no adverse site influence on the air quality at these near-site locations. Gross beta concentrations at all off-site and perimeter locations averaged about $1.84\text{E-}14\mu\text{Ci/mL}$, which is about 0.2% of the DCG for strontium-90 in air ($9\text{E-}12\mu\text{Ci/mL}$). The highest average gross beta concentration ($1.90\text{E-}14\mu\text{Ci/mL}$) was at Fox Valley Road. This represents less than 0.3% of the DCG.

Additional radionuclide data from these samplers are provided in Tables D-16 through D-25 (pp. D-17 to D-23).

Although low levels of tritium, strontium-90, iodine-129, and cesium-137 were detected in emissions from the main stack on-site, average results for these radionuclides at near-site locations were indistinguishable from background values, confirming that site releases have a negligible effect on near-site air quality.

Fallout Pot Sampling. Short-term global fallout is sampled for radionuclide concentrations each month at four of the perimeter air sampler locations and at one on-site location near the rain gauge outside the Environmental Laboratory. (See Figs.A-4 and A-5 [pp.A-6 and A-7].) Monthly gross alpha, gross beta, potassium-40, and cesium-137 results are reported in nCi/m^2 and tritium results are reported in $\mu\text{Ci/mL}$. Results from on-site and perimeter

Table 2-3
2000 Gross Alpha Concentrations at Off-site, Perimeter, and On-site
Ambient Air Sampling Locations

Location	Number of Samples	Range		Annual Average	
		($\mu\text{Ci/mL}$)	(Bq/m^3)	($\mu\text{Ci/mL}$)	(Bq/m^3)
AFBLKST	52	<7.56E-16 to 2.85E-15	<2.80E-05 to 1.05E-04	0.79±1.17E-15	2.93±4.34E-05
AFBOEHN	52	<5.86E-16 to 2.22E-15	<2.17E-05 to 8.20E-05	0.73±1.17E-15	2.71±4.34E-05
AFFXVRD	52	<7.53E-16 to 2.31E-15	<2.78E-05 to 8.56E-05	0.84±1.19E-15	3.10±4.39E-05
AFGRVAL	52	<7.00E-16 to 2.04E-15	<2.59E-05 to 7.54E-05	0.74±1.14E-15	2.74±4.20E-05
AFNASHV	52	<7.57E-16 to 2.24E-15	<2.80E-05 to 8.27E-05	0.70±1.18E-15	2.57±4.36E-05
AFRSPRD	52	<7.78E-16 to 2.08E-15	<2.88E-05 to 7.71E-05	0.72±1.16E-15	2.65±4.31E-05
AFRT240	52	<8.23E-16 to 2.05E-15	<3.05E-05 to 7.58E-05	0.76±1.17E-15	2.81±4.34E-05
AFSPRVL	52	<7.55E-16 to 2.42E-15	<2.79E-05 to 8.97E-05	0.77±1.18E-15	2.87±4.37E-05
AFTCORD	52	<7.99E-16 to 2.62E-15	<2.96E-05 to 9.70E-05	0.74±1.21E-15	2.73±4.48E-05
AFWEVAL	52	<7.58E-16 to 2.76E-15	<2.80E-05 to 1.02E-04	0.84±1.20E-15	3.10±4.43E-05
ANLAGAM	52	<4.96E-16 to 2.20E-15	<1.83E-05 to 8.15E-05	0.87±0.90E-15	3.22±3.28E-05
ANNDAAAM	52	<6.26E-16 to 1.89E-15	<2.32E-05 to 6.98E-05	0.78±0.90E-15	2.89±3.34E-05
ANSDAT9	52	<6.69E-16 to 7.24E-15	<2.47E-05 to 2.68E-04	0.67±1.50E-15	2.46±5.55E-05

Table 2-4
2000 Gross Beta Concentrations at Off-site, Perimeter, and On-site
Ambient Air Sampling Locations

Location	Number of Samples	Range		Annual Average	
		($\mu\text{Ci/mL}$)	(Bq/m^3)	($\mu\text{Ci/mL}$)	(Bq/m^3)
AFBLKST	52	7.94E-15 to 3.33E-14	2.94E-04 to 1.23E-03	1.83±0.33E-14	6.78±1.22E-04
AFBOEHN	52	2.79E-15 to 4.04E-14	1.03E-04 to 1.49E-03	1.87±0.33E-14	6.91±1.24E-04
AFFXVRD	52	6.28E-15 to 3.59E-14	2.32E-04 to 1.33E-03	1.90±0.33E-14	7.02±1.24E-04
AFGRVAL	52	7.42E-15 to 3.42E-14	2.75E-04 to 1.27E-03	1.68±0.32E-14	6.21±1.17E-04
AFNASHV	52	6.72E-15 to 3.76E-14	2.49E-04 to 1.39E-03	1.89±0.34E-14	6.98±1.25E-04
AFRSPRD	52	5.86E-15 to 3.35E-14	2.17E-04 to 1.24E-03	1.74±0.33E-14	6.43±1.21E-04
AFRT240	52	7.27E-15 to 3.62E-14	2.69E-04 to 1.34E-03	1.82±0.33E-14	6.75±1.23E-04
AFSPRVL	52	7.95E-15 to 3.64E-14	2.94E-04 to 1.35E-03	1.84±0.33E-14	6.80±1.23E-04
AFTCORD	52	9.79E-15 to 3.81E-14	3.62E-04 to 1.41E-03	1.86±0.34E-14	6.90±1.26E-04
AFWEVAL	52	7.02E-15 to 3.57E-14	2.60E-04 to 1.32E-03	1.75±0.33E-14	6.47±1.22E-04
ANLAGAM	52	7.32E-15 to 3.66E-14	2.71E-04 to 1.35E-03	1.84±0.26E-14	6.82±0.96E-04
ANNDAAAM	52	8.54E-15 to 3.87E-14	3.16E-04 to 1.43E-03	1.94±0.27E-14	7.18±1.02E-04
ANSDAT9	52	8.22E-15 to 3.58E-14	3.04E-04 to 1.32E-03	1.79±0.37E-14	6.64±1.36E-04

locations were similar to each other and to results noted in previous years. The small levels of tritium and cesium-137 detected in main stack emissions did not measurably affect on-site or perimeter fallout pot samples in 2000. The data from these analyses and the pH in precipitation are summarized in Tables D-26 through D-30 (pp.D-24 through D-26).

Off-site Surface Soil Sampling. In order to assess long-term fallout deposition, surface soil near the off-site air samplers is collected annually and analyzed for radioactivity. Samples were collected from ten locations: six near-site points on the perimeter of the WNYNSC, two in nearby communities, and two in locations 30 to 40 kilometers distant from the Project. Maps of the off-site surface soil sampling locations are on Figures A-3 and A-12 (pp.A-5 and A-14).

Concentrations of gross alpha and beta radioactivity, strontium-90, cesium-137, plutonium-239/240, and americium-241 were determined at all ten locations; concentrations of uranium radionuclides and total uranium were determined at two perimeter locations and one background location. The measured concentrations of most site-related radionuclides in soils from the perimeter and community locations (Table C-29 [p.C-24]) were statistically indistinguishable from normal regional background concentrations. However, cesium-137 concentrations from the Rock Springs Road location — northwest of the site — remained marginally higher than background concentrations. Soils collected near the Rock Springs Road air sampler have consistently shown higher than background cesium-137 concentrations.

Historically, cesium-137 concentrations at background locations SFGRVAL and SFNASHV have ranged from 6.54E-08 to 4.38 E-06 $\mu\text{Ci/g}$. The results for calendar year 2000 at these two

locations were 5.20E-07 and 6.54E-08 $\mu\text{Ci/g}$ respectively. Annual cesium-137 concentrations at SFRSPRD have ranged from 1.06E-06 to 2.08E-06 $\mu\text{Ci/g}$. The result for calendar year 2000 was 1.06E-06 $\mu\text{Ci/g}$, higher than background results for 2000 but well within the historical range at background locations.

Radiological Monitoring: Food Chain

Each year food and forage samples are collected from locations near the site (Fig. A-9 [p.A-11]) and from remote locations (Fig.A-12 [p.A-14] in Appendix A). Fish and deer are collected during periods when they would normally be taken by sportsmen for consumption. Most milk samples are collected monthly; beef is collected semiannually. Hay, corn, apples, and beans are collected at the time of harvest.

Fish. Fish are obtained under a collector's permit by electrofishing, a method that temporarily stuns the fish, allowing them to be netted for collection. Electrofishing allows a more species-selective control than sport fishing, with unwanted fish being returned to the creek essentially unharmed.

Fish are collected from three locations in Cataraugus Creek: Two locations are downstream of WNYNSC drainage — one above the Springville dam (BFFCATC) and one below the Springville dam (BFFCATD) — and one location is upstream of the site (BFFCTRL). (See Fig.A-12, p.A-14.)

Twenty fish samples were collected in 2000 (ten the first half of the year and ten the second half of the year) immediately downstream (above the Springville dam at BFFCATC), and another twenty were collected from the control location upstream of the site (BFFCTRL). Ten fish



Electrofishing in Cattaraugus Creek

samples were collected from Cattaraugus Creek below the dam (BFFCATD), including species that migrate more than 60 kilometers (nearly 40 mi) upstream from Lake Erie.

The edible portion of each fish was analyzed for strontium-90 content and the gamma-emitting radionuclide cesium-137. (See Table F-4 [pp. F-6 through F-8] in Appendix F for a summary of the results.) Although many of the strontium-90 results, especially at sampling location BFFCATD below the dam, were lost because of analytical problems at the vendor laboratory, two results from BFFCATD were available. These results were within the historical range at this location.

Strontium-90 results from fish above the Springville dam (at BFFCATC) were elevated in comparison with the background samples (from BFFCTRL), but these results also were within the range of historical results.

No differences in cesium-137 concentrations in fish collected above and below the point at

which site effluents enter Cattaraugus Creek were noted.

Venison. Venison from vehicle-deer accidents around the WNYNSC and from deer collected far from the site in the towns of Little Genesee, Alexander, and Portville, New York was analyzed for tritium, potassium-40, strontium-90, and cesium-137 concentrations. (See Figs. A-9 and A-12 [pp. A-11 and A-14].) Results from these samples are shown in Table F-2 (p. F-4) in Appendix F.

Low levels of radioactivity from cesium-137, strontium-90, and naturally occurring potassium-40 were detected in both near-site and control samples. Although results vary from year to year, data from the last ten years show no statistical differences between radionuclide concentrations in near-site and control samples.

For the seventh year, during the large-game hunting season, hunters were allowed access to the WNYNSC, excluding the WVDP premises, in a controlled hunting program established by

NYSERDA. There were no requests from hunters to analyze deer from the 2000 hunt. However, data from previous hunts have shown that concentrations of radioactivity in deer flesh have been very low, indicating that Project activities have little or no effect on the local herd.

Beef. Beef samples are taken semiannually from both near-site and remote locations (Figs.A-9 and A-12 [pp.A-11 and A-14] in Appendix A) and are analyzed for tritium, potassium-40, strontium-90, and cesium-137. Results are presented in Table F-2 (p.F-4) in Appendix F. No significant differences were found between results from near-site and background samples.

Milk. Monthly milk samples were taken from dairy farms near the site to the north and west — downwind in the prevailing wind direction from the WVDP — and from farms more than 25 kilometers from the site and used as control locations. Annual milk samples were collected at two near-site farms to the south and east of the site. The locations of the near-site and remote sampling points are shown in Figure A-9 (p.A-11) and Figure A-12 (p.A-14) in Appendix A.

The monthly samples from each location were composited into single quarterly samples for analysis. These quarterly composites and annual samples were analyzed for tritium, potassium-40, strontium-90, iodine-129, and cesium-137. Results are presented in Table F-1 (p.F-3) in Appendix F. Near-site sample results were indistinguishable from background control sample results.

Vegetables, Fruit, and Forage. Sweet corn, beans, apples, and hay were collected at near-site and background locations at harvest time. Sampling locations are shown on Figures A-9 (p.A-11) and A-12 (p.A-14) in Appendix A. Samples were analyzed for tritium, potassium-

40, cobalt-60, strontium-90, and cesium-137. Results are presented in Table F-3 (p.F-5) in Appendix F.

Low levels of radioactivity — in particular, strontium-90 — were noted in both background and near-site samples. However, none of the measurements of radionuclides in near-site samples, including strontium-90, were significantly higher than measurements from background samples.

Direct Environmental Radiation Monitoring

This was the seventeenth full year in which direct penetrating radiation was monitored at the WVDP. Thermoluminescent dosimeters (TLDs) are placed at each monitoring location for one calendar quarter (three months) and are then processed to obtain the integrated gamma radiation exposure at that location.

Monitoring points are located on-site at the waste management units, at the site security fence, around the WNYNSC perimeter and the access road, and at background locations remote from the WVDP (Figs.A-10, A-11, and A-12 [pp.A-12, A-13, and A-14]). The identification numbers associated with each location were assigned in chronological order of original installation. (See TLD Locations and Identification Numbers on p.2-24.)

Quarterly and annual averages of TLD measurements at off-site and on-site locations are noted in Appendix H, Tables H-1 and H-2 (pp.H-3 and H-4). The results of measurements in 2000 show typical seasonal variations and are similar to results from previous years.

On-Site Radiation Monitoring. Table H-2 (p.H-4) shows the average quarterly exposure rate at each on-site TLD. The on-site monitor-

ing point with the highest dose readings was location #24. Sealed containers of radioactive components and debris from the plant decontamination work are stored nearby. This storage area is well within the WNYNSC boundary, just inside the WVDP fenced area, and is not accessible by the public.


The average exposure rate at location #24 was about 627 milliroentgens (mR) per quarter (0.29 mR/hr) during 2000, which is almost identical to the exposure rate noted at this location in 1999 (0.27 mR/hr). Exposure rates at this location are gradually decreasing because the radioactivity in the materials stored nearby is decaying. (The average mR/hr for the first two years that TLD measurements were taken —

1987 and 1988 — was about 0.8 mR/hr. See Fig. 1-1 [p.1-10] in Chapter 1.)

The average penetrating radiation exposure rate in 2000 at locations 100 to 400 feet (30 to 120m) distant from the integrated radwaste treatment storage building — the drum cell — including TLDs #18, #32, #34, #35, #36, and #43, was 0.02 mR/hr, about the same as in 1999. Exposure rates around the drum cell are above background levels (approximately 0.01 mR/hr) because the building contains drums filled with decontaminated supernatant mixed with cement. (See also Fig. 1-2 [p.1-10] in Chapter 1.) The drum cell and the surrounding TLD locations are well within the WNYNSC boundary and are not accessible by the public.

TLD Locations and Identification Numbers

Perimeter of the WNYNSC	1-16, 20
Perimeter of the WVDP security fence	24, 26-34
On-site sources or waste management units (Note: some TLDs monitor more than one waste management unit)	18, 32-36, 43 (drum cell) 18, 19, 33, 42, 43 (SDA) 24 (component storage, near WVDP security fence) 25 (maximum measured exposure rate at the closest point of public access) 38 (main plant and, in previous years, the cement solidification system) 39 (parking lot security fence closest to the vitrification facility) 40 (high-level waste tank farm)
Near-site communities	21 (Springville) 22 (West Valley)
Background	17 (Five Points Landfill in Mansfield) 23 (Great Valley) 37 (Nashville) 41 (Sardinia)



Perimeter and Off-Site Radiation Monitoring. Table H-1 (p.H-3) lists the average quarterly exposure rate at each off-site TLD location. The perimeter TLDs (TLDs #1-16 and #20) are located in the sixteen compass sectors around the facility near the WNYNSC boundary. Results from the background and community TLDs were essentially the same as results from the perimeter TLDs. The perimeter TLD quarterly averages since 1985 (expressed in microrentgen per hour [$\mu\text{R/hr}$]) shown on Figure 2-8 (*above*) indicate seasonal fluctuations but no long-term trends. The quarterly average of the seventeen WNYNSC-perimeter TLDs was 21.4 mR per quarter (9.8 $\mu\text{R/hr}$) in 2000, slightly higher than in 1999.

Confirmation of Results. The performance of the environmental TLDs is confirmed periodically using a portable high-pressure ion chamber (HPIC) detection system. In the third quarter of 2000 the HPIC was taken to each of the forty-three environmental TLD locations and instantaneous dose readings (in $\mu\text{R/hr}$) were obtained. These readings and the comparable

third-quarter environmental TLD results are listed in Table H-3 (p.H-5). The TLD results include the entire third quarter of 2000; the HPIC results were collected over a period of less than 30 minutes.

Because the measurements are made with different systems and over differing periods of time, they are not directly comparable. Even so, the average relative percent difference between the two sets of measurements was less than 12%, indicating good agreement between these two different measurement methods. (Guidance in ANSI N545-1975, the standard for environmental dosimetry, uses less than 30% total uncertainty as a performance specification for TLD measurements.)

Meteorological Monitoring

Meteorological monitoring at the WVDP provides representative and verifiable data that characterize the local and regional climatology of the site. These data are used primarily to assess potential effects of routine and nonrou-



On-site Meteorological Tower

tine releases of airborne radioactive materials and to develop dispersion models used to calculate the effective dose equivalent to off-site residents. Since dispersive capabilities of the atmosphere are dependent upon wind speed, wind direction, and atmospheric stability (which is a function of the difference in temperature between two elevations), these parameters are closely monitored and are available to the emergency response organization at the WVDP.

The on-site 60-meter meteorological tower (Fig. A-1 [p.A-3]) continuously monitors wind speed, wind direction, and temperature at both the 60-meter and 10-meter elevations. In addition, an independent, remote 10-meter meteorological station located approximately 8 kilometers south of the site on a hillcrest on Dutch Hill Road continuously monitors wind speed and wind direction. (See Fig.A-12 [p.A-14].) Dewpoint,

precipitation, and barometric pressure are also monitored on-site.

The two meteorological locations supply data to the primary digital and analog data acquisition systems located within the Environmental Laboratory. On-site systems are provided with either uninterruptible or standby power backup in case of site power failures. In 2000 the on-site system data recovery rate (time valid data were logged versus total elapsed time) was approximately 95.7%. Regional data at the 10-meter elevation are shown on Figure I-1 (p.I-3). Figures I-2 and I-3 (pp. I-4 and I-5) illustrate the mean wind speed and wind direction at the 10-meter and 60-meter elevations on the on-site tower during 2000.

Weekly and cumulative total precipitation data are illustrated in Figures I-4 and I-5 (p.I-6) in Appendix I. Precipitation in 2000 was about 96.6 centimeters (38 in), about 7.2% below the annual average of 104 centimeters (41 in).

Documentation such as meteorological system calibration records, site log books, and analog strip charts are stored in protected archives. Meteorological towers and instruments are examined three times per week for proper function and are calibrated semiannually and/or whenever instrument maintenance might affect calibration.

Nonradiological Monitoring: Surface Water

Liquid discharges are regulated under the State Pollutant Discharge Elimination System (SPDES). The WVDP holds a SPDES permit that identifies the outfalls where liquid effluents are released to Erdman Brook (Fig.A-2 [p.A-4]) and specifies the sampling and analytical requirements for each outfall. The cur-

rent SPDES permit (effective June 1995) was administratively renewed without changes by NYSDEC and was issued to the WVDP in September 1998 with an effective date of February 1, 1999 and an expiration date of February 1, 2004. The conditions and requirements of the SPDES permit are summarized in Table G-1 (pp.G-3 and G-4) in Appendix G. The permit identifies four outfalls:

- outfall WNSP001, discharge from the low-level waste treatment facility
- outfall WNSP007, discharge from the sanitary and industrial wastewater treatment facility
- outfall WNSP008, groundwater effluent from the perimeter of the low-level waste treatment facility storage lagoons
- outfall 116, a sampling location in Frank's Creek that represents the confluence of outfalls WNSP001, WNSP007, and WNSP008 as well as storm water runoff, groundwater surface seepage, and augmentation water. Samples from upstream sources (WNSP001, WNSP007, and WNSP008) are used to calculate total dissolved solids at this location and to demonstrate compliance with the SPDES permit limit for this parameter. (Outfall 116 is referred to as a "pseudo-monitoring" point on the SPDES permit. [See p.7 in the Glossary.])

Some of the more significant features of the SPDES permit are the requirements to report five-day biochemical oxygen demand (BOD₅), total dissolved solids, iron, and ammonia data as flow-weighted concentrations and to apply a net discharge limit for iron. The net limit allows the Project to account for the iron that is naturally present in the site's incoming water. The flow-weighted limits apply to the flow-proportioned sum of the Project effluents.

The SPDES monitoring data for 2000 are displayed in Tables G-2 through G-10 (pp.G-5 through G-15). The WVDP reported no permit exceedances in 2000, the third consecutive year for which no exceedances were noted. (See also the Environmental Compliance Summary: Calendar Year 2000, SPDES-permitted Outfalls [pp. ECS-11 through ECS-12].)

Semiannual grab samples at WNSP006 (Frank's Creek at the security fence), WNSWAMP (north-east swamp drainage), WNSW74A (north swamp drainage), and WFBCBKG (Buttermilk Creek at Fox Valley) were taken in 2000. These samples are screened for organic constituents and selected anions, cations, and metals. Results of these measurements for all of these locations are found in Table C-27 (p.C-22).

Nonradiological Monitoring: Drinking Water

Site drinking water is monitored to verify compliance with EPA and NYSDOH regulations. (See Safe Drinking Water Act [p.ECS-13] in the Environmental Compliance Summary: Calendar Year 2000.) Samples are collected annually and analyzed for nitrate, fluoride, and metals concentrations. Sampling and analysis for copper and lead are conducted according to Cattaraugus County Health Department guidance. The 2000 monitoring results indicated that the Project's drinking water met NYSDOH, EPA, and Cattaraugus County Health Department drinking water quality standards.

Nonradiological Monitoring: Air

Nonradiological air emissions and plant effluents are permitted under NYSDEC and EPA regulations. (The regulations that apply to the WVDP are listed in Table K-2 [p. K-4] in

Appendix K. The New York State Facility Air Permit held by the WVDP is described in the West Valley Demonstration Project Environmental Permits table on p.ECS-22 in the Environmental Compliance Summary: Calendar Year 2000.)

The nonradiological air permits are for emissions of regulated pollutants that include particulates, ammonia, nitrogen oxides, and sulfur dioxide. Emissions of oxides of nitrogen and sulfur are each limited to 99 tons per year and are reported to NYSDEC annually. Nitrogen oxide emissions from the vitrification off-gas system are continuously monitored. All other nitrogen oxides and sulfur dioxide emissions data are calculated using process knowledge and fuel usage information. Nitrogen oxides emissions for 2000 were approximately 7.44 tons; sulfur dioxide emissions were approximately 0.77 tons, well below the 99-ton limit. Compliance with New York State and EPA opacity requirements is verified by certified visible-emissions observers.

Special Monitoring


Special monitoring comprises sampling and analyses not covered by the routine environmental monitoring program but that address items of environmental interest. Special monitoring programs are used to verify and/or track these items.

Iodine Emissions from the Main Stack.

When radioactive vitrification operations began in 1996, emission rates of radioactive isotopes of iodine increased at the main stack. The increase occurred because gaseous iodine is not as efficiently removed by the vitrification process off-gas treatment system as are most other radionuclides.

Iodine-129 is a long-lived radionuclide that has always been present in main stack emissions, and in 1996 iodine-131 also was detected. Iodine-131, an isotope with a half-life of eight days, originates from the decay of curium-244, which is present in the high-level waste. Iodine-131 gas was not detectable until vitrification began because the previtrification storage and management of high-level waste had prevented detectable levels of iodine-131 from reaching the air effluent. In the process of preparing the high-level waste for vitrification, the quantities of iodine-129 increased compared to previtrification levels and a very small — yet detectable — quantity of iodine-131 was released.

Iodine-129 was monitored closely during 2000 and the results compared to the operation of the vitrification facility. Weekly iodine-129 concentrations were within the range of values observed since vitrification began. In 2000 the total quantity of iodine-129 decreased slightly from the 1999 total. (See Fig. 2-9 [below]. For more information on the off-site effective dose from airborne emissions see Predicted Dose from Airborne Emissions [p.4-7] in Chapter 4.)



Mercury at the Low-level Waste Treatment Facility. Increasing concentrations of total mercury were observed in 1999 in process water collected in the low-level waste treatment facility. The source of the mercury was determined to be the evaporator effluent from the liquid waste treatment system.

At that time, New York State water quality standards were modified, defining toxicity-based standards that in some cases are several orders of magnitude lower than previous standards. Thus, in 2000, equipment was put in place to remove mercury from the process water to a greater extent. In addition, using EPA guidance on sampling techniques, procedures were developed and put into place to provide sampling for trace levels of mercury in site effluents, surface waters, and precipitation. New subcontracted analytical services were obtained to analyze for mercury to levels much lower than previously available. Sampling began in 2001.

GROUNDWATER MONITORING

Groundwater Monitoring Program Overview

Groundwater at the West Valley Demonstration Project (WVDP) is monitored according to a comprehensive program developed to comply with all applicable state and federal regulations. The monitoring program also meets requirements of Department of Energy (DOE) Order 5400.1 to obtain data for determining baseline conditions of groundwater quality and quantity, to provide data that will allow the early detection of groundwater contamination, to identify existing and potential groundwater contamination sources and maintain surveillance of these sources, and to provide data upon which decisions can be made concerning the integrity of existing disposal areas and the management and protection of groundwater resources.

Current groundwater monitoring activities at the WVDP are summarized in two primary documents, the Groundwater Monitoring Plan (West Valley Nuclear Services Co., Inc. December 1998) and the Groundwater Protection Management Program Plan (West Valley Nuclear Services Co. May 2, 2000). The Groundwater Monitoring Plan outlines the

WVDP's plans for groundwater characterization, current groundwater sampling requirements, and support of long-term monitoring requirements identified in the Resource Conservation and Recovery Act (RCRA) facilities investigation (RFI) and DOE programs. The Groundwater Protection Management Program Plan provides additional information regarding protection of groundwater from on-site activities.

Geologic History of the West Valley Site

The Western New York Nuclear Service Center (WNYNSC) is located on the Allegheny Plateau near the northern border of Cattaraugus County in Western New York. Beneath the WNYNSC site is a sequence of Holocene (recent age) and Pleistocene (ice age) sediments filling a steep-sided valley incised in the bedrock. The bedrock is composed of shales and interbedded siltstones of the upper Devonian Canadaway and Conneaut Groups that dip southward at about 5 m/km (Rickard 1975).

The Pleistocene sediments overlying the bedrock typically consist of a sequence of three

glacial tills of Lavery, Kent, and possibly Olean age. The tills are separated by stratified fluvio-lacustrine deposits. In the northern part of the site the Lavery till is capped by coarse-grained alluvial-fluvial deposits.

Repeated glaciations of the ancestral bedrock valley occurred between 24,000 and 15,000 years ago (Albanese et al. 1984), ending with the deposition of up to 40 meters (130 ft) of Lavery till. Post-Lavery outwash and alluvial fans, including the sand and gravel unit that covers the northern portion of the WVDP site, were deposited on the Lavery till between 15,000 and 14,200 years ago (La Fleur 1979).

A summary of the site hydrology is below. Hydrologic conditions of the site are more fully described in Environmental Information Document Volume III, Part 4 (West Valley Nuclear Services Co., Inc. March 1996) and in the RCRA Facility Investigation Report: Introduction and General Site Overview (West Valley Nuclear Services Co., Inc. July 1997).

Surface Water Hydrology of the West Valley Site

The WNYNSC lies within the Cattaraugus Creek watershed, which empties into Lake Erie about 43 kilometers (27 mi) southwest of Buffalo. Buttermilk Creek, a tributary of Cattaraugus Creek, drains most of the WNYNSC and all of the WVDP site.

The 80-hectare (200-acre) WVDP site, located on the WNYNSC, is contained within the smaller Frank's Creek watershed. Frank's Creek, a tributary of Buttermilk Creek, forms the eastern and southern boundary of the WVDP; Quarry Creek, a tributary of Frank's Creek, forms the northern boundary. (See Fig.A-6 [p.A-8].)

Another tributary of Frank's Creek, Erdman Brook, bisects the WVDP into a north and south plateau. The main plant, waste tanks, and lagoons are located on the north plateau. The drum cell, the U.S. Nuclear Regulatory Commission (NRC)-licensed disposal area (NDA), and the New York State-licensed disposal area (SDA) are located on the south plateau.

Hydrogeology of the West Valley Site

As noted above, the WVDP site area is underlain by a sequence of glacial tills comprised primarily of clays and silts separated by coarser-grained interstadial sediments. Because the bottommost layer, the Kent till, is less permeable than the other geological units and does not provide a pathway for contaminant movement from the WVDP, it is not discussed here.

The sediments above the Kent till — the Kent recessional sequence, the Lavery till and the intra-Lavery till-sand, and the surficial sand and gravel — are generally regarded as containing all of the potential routes for the migration of contaminants (via groundwater) from the WVDP site. (Figs. 3-1 and 3-2 [facing page] show the relative locations of these sediments on the north and south plateaus.) The Kent recessional sequence and the Lavery till are common to both the north and south plateaus.

Kent Recessional Sequence. The Kent recessional sequence consists of a fine-grained lacustrine unit of interbedded clay and silty clay layers locally overlain by coarse-grained glacial sands and gravels. These deposits underlie the Lavery till beneath most of the site, pinching out along the southwestern margin of the site where the walls of the bedrock valley intersect the sequence.




Figure 3-1. Geologic Cross Section through the North Plateau




Figure 3-2. Geologic Cross Section through the South Plateau

Groundwater flow in the Kent recessional sequence is predominantly to the northeast, toward Buttermilk Creek. Hydraulic conductivity testing completed during the last several years indicates a mean value of 1E-06 cm/sec (1E-03 ft/day) or 0.01 in/day. Recharge comes from the overlying Lavery till and the bedrock in the southwest, and discharge is to Buttermilk Creek.

Lavery Till. The Lavery till is predominantly an olive-gray, silty clay glacial till with scattered lenses of silt and sand. It underlies both the north and south plateaus and ranges up to 40 meters (130 ft) in thickness beneath the active areas of the site, generally increasing north-eastward towards Buttermilk Creek and the center of the bedrock valley.

Hydraulic head distributions in the unweathered Lavery till indicate that groundwater flow is predominantly vertically downward at a relatively slow rate, towards the underlying Kent recessional sequence. Hydraulic conductivity testing in the Lavery till during the last several years indicates a mean value of 1E-07 cm/sec (1E-04 ft/day) or 0.001 in/day.

On the south plateau the upper zone of the Lavery till is exposed at the ground surface and is weathered and fractured to a depth of 0.9 meters to 4.9 meters (3 ft to 16 ft). This layer is referred to as the *weathered Lavery till* and is unique to the south plateau. The weathered Lavery till has been oxidized to a brown color and contains numerous fractures and root tubes.

Groundwater flow in the weathered till has both horizontal and vertical components. This enables the groundwater to move laterally across the south plateau before moving downward into the unweathered Lavery till or discharging to nearby incised stream channels. Hydraulic conductivity testing in the weathered Lavery till

completed during the last several years indicates a mean value of 1E-05 cm/sec (1E-02 ft/day) or 0.1 in/day. The highest conductivities are associated with the dense fracture zones found within the upper 2 meters (7 ft) of the unit.

On the north plateau, where the main plant, waste tanks, and lagoons are located, the weathered till layer is much thinner or nonexistent and the unweathered Lavery till is immediately overlain by the sand and gravel unit.

Sand and Gravel and Till-sand Units. The *sand and gravel unit* and the *Lavery till-sand* are unique to the north plateau. The sand and gravel unit is a silty sand and gravel layer composed of younger Holocene alluvial deposits that overlie older Pleistocene-age glaciofluvial deposits. Together these two layers range up to 12.5 meters (41 ft) in thickness near the center of the plateau and pinch out along the northern, eastern, and southern edges of the plateau, where they have been truncated by the downward erosion of stream channels.

Depth to groundwater within the sand and gravel unit varies from 0 meters to 5 meters (0 ft to 16 ft), being deepest generally beneath the central north plateau (beneath the main plant facilities) and intersecting the ground surface farther north towards the security fence.

Groundwater in this unit generally flows north-eastward across the plateau towards Frank's Creek. Groundwater near the northwestern and southeastern margins of the sand and gravel layer also flows radially outward toward Quarry Creek and Erdman Brook, respectively. There is minimal groundwater flow downward into the underlying Lavery till. The mean hydraulic conductivity is 1E-04 cm/sec (1E-01 ft/day) or 1.2 in/day, based on testing completed during the last several years.

Within the unweathered Lavery till on the north plateau is another unit, the Lavery till-sand. On-site investigations from 1989 through 1990 identified this thin sandy unit of limited areal extent and variable thickness within the Lavery till, primarily beneath the southeastern portion of the north plateau. Groundwater flow through this unit is in an east-southeast direction. Surface discharge locations have not been observed. The mean hydraulic conductivity of 1E-04 cm/sec (1E-01 ft/day) or 1.2 in/day for this unit is based on testing completed during the last several years.

Routine Groundwater Monitoring Program

The purpose of groundwater monitoring at the WVDP is to detect changes in groundwater quality within the five different hydrogeologic units described above: the sand and gravel, the weathered Lavery till, the unweathered Lavery till, the Lavery till-sand, and the Kent recessional sequence.

Monitoring Well Network. Table E-1 (Appendix E [p.E-3 through E-6]) lists the eleven super solid waste management units (SSWMUs) monitored by the well network, the hydraulic position of each well relative to the waste management unit, the geologic unit monitored, and the analytes measured in 2000. Note that monitoring of certain wells, marked by an asterisk, is required by the RCRA §3008(h) Administrative Order on Consent for the WVDP.

Figures A-7 and A-8 (pp.A-9 and A-10) show the boundaries of ten of the SSWMUs at the WVDP. (Twenty-one additional wells in an eleventh SSWMU monitor the SDA and are the responsibility of the New York State Energy Research and Development Authority [NYSERDA]. Locations of NYSERDA wells

are shown on Fig.A-8 [p.A-10] in Appendix A. The SDA, a closed radioactive waste landfill, is contiguous with the Project premises, but the WVDP is not responsible for the facilities or activities relating to it. Under a joint agreement with the DOE, NYSERDA contracts with the Project to obtain specifically requested technical support in SDA-related matters. Groundwater monitoring results from the SDA are reported in this document in Appendix L [pp.L-3 through L-10] but are not discussed here.)

Table E-1 (pp.E-3 through E-6) identifies the hydraulic positions of monitoring locations relative to the SSWMUs. The wells monitoring a given hydrogeologic unit (e.g., sand and gravel, weathered Lavery till) also are arranged in a generalized upgradient to downgradient order based upon their location within the entire hydrogeologic unit. The hydraulic position of a well relative to a SSWMU, i.e., upgradient or downgradient, does not necessarily match that same well's position within its hydrogeologic unit. For example, a well that is upgradient in relation to a SSWMU may be located at any position within a hydrogeologic unit within the boundaries of the WVDP, depending on the geographic position of the SSWMU relative to the hydrogeologic unit. In general, the following text and graphics refer to the hydraulic position of monitoring wells within their respective hydrogeologic units, thus providing a site-wide perspective rather than a perspective centered on SSWMUs. Information provided in Appendix E (pp.E-7 through E-19) also follows this convention.

Potentiometric (water level) measurements also are collected from the wells listed in Table E-1 in conjunction with the quarterly analytical sampling schedule. (See Table 3-1, p. 3-6.) Groundwater elevation data are used to produce groundwater contour maps, which delineate

Table 3-1
2000 Groundwater Sampling and Analysis Agenda

Analyte Group	Description of Parameters¹	Location of Sampling Results in Appendix E
Contamination Indicator Parameters (I)	pH, specific conductance (field measurement)	Tables E-2 through E-8 (pp. E-7 through E-15)
Radiological Indicator Parameters (RI)	Gross alpha, gross beta, tritium	Tables E-2 through E-8 (pp. E-7 through E-15)
Volatile Organic Compounds (V)	Appendix 33 VOCs (Volatile Organic Compounds) (See Table E-14 [p. E-20].)	Table E-9 (p. E-15)
Semivolatile Organic Compounds (SV)	Appendix 33 SVOCs (Semi-volatile Organic Compounds) and tributyl phosphate (See Table E-14 [p. E-20].)	Table E-10 (p. E-16)
Appendix 33 Metals (M33)	Antimony, arsenic, barium, beryllium, cadmium, chromium, cobalt, copper, lead, mercury, nickel, selenium, silver, thallium, tin, vanadium, zinc	Table E-11 (pp. E-16 through E-17)
Special Monitoring Parameters for Early Warning Wells (SM)	Aluminum, iron, manganese	Table E-12 (p. E-17)
Radioisotopic Analyses: alpha- , beta- , and gamma-emitters (R)	C-14, Cs-137, I-129, Ra-226, Ra-228, Sr-90, Tc-99, U-232, U-233/234, U-235/236, U-238, total uranium	Table E-13 (pp. E-18 through E-19)
Strontium-90 (S)	Sr-90	Table E-13 (pp. E-18 through E-19)

2000 Quarterly Monitoring Schedule:

1st Qtr - December 1, 1999 to February 29, 2000

2nd Qtr - March 1, 2000 to May 31, 2000

3rd Qtr - June 1, 2000 to August 31, 2000

4th Qtr - September 1, 2000 to November 30, 2000

¹Analysis completed for selected active monitoring locations only. See Table E-1 (pp. E-3 through E-6) for the analytes assigned to each monitoring location.

Groundwater Sampling Methodology

Groundwater samples are collected from monitoring wells using either dedicated Teflon® well bailers or bladder pumps. (Dedicated bailers are equipped with Teflon® -coated stainless steel leaders.)

The method of collection depends on well construction, water depth, and the water-yielding characteristics of the well. Bailers are used in low-yield wells; bladder pumps are used in wells with good water-yielding characteristics.

To ensure that only representative groundwater is sampled, three well volumes are removed (purged) from the well before the actual samples are collected. If three well volumes cannot be removed because of limited recharge, purging the well to dryness provides sufficient purging. Conductivity and pH are measured before sampling and after sampling, if sufficient water is still available, to confirm the geochemical stability of the groundwater during sampling.

The bailer, a tube with a check valve at the bottom, is lowered into the well until it reaches the desired point in the water column. The bailer is lowered slowly to minimize agitation of the water column and is then withdrawn from the well with a sample and emptied into a sample container. The bailer, bailer line, and bottom-emptying device used to drain the bailer are dedicated to the well, i.e., are not used for any other well.

Bladder pumps use compressed air to gently squeeze a Teflon® bladder that is encased in a stainless steel tube located near the bottom of the well. When the pressure is released, new groundwater flows into the bladder. A series of check valves ensures that the water flows only in one direction. The operating air is always separated from the sample and is expelled to the surface by a separate line.

Bladder pumps reduce mixing and agitation of the water in the well. Each bladder pump system is dedicated to an individual well to reduce the likelihood of sample contamination from external materials or cross contamination. The air compressor and pump control box can be used from well to well because they do not contact the sample.

Immediately after the samples are collected they are put into a cooler and returned to the Project's Environmental Laboratory. The samples are preserved with chemicals, if necessary, and stored under controlled conditions to minimize chemical and/or biological changes after sample collection. The samples are then either packaged for expedited delivery to an off-site contract laboratory or kept in controlled storage to await on-site testing. A strict chain-of-custody protocol is followed for all samples collected by the WVDP.

flow directions and gradients, and long-term trend graphs, which illustrate seasonal fluctuations and other changes in the groundwater system.

Measurements are also collected at eleven surface water elevation stakes located on the north plateau where the water table in the sand and gravel unit intersects the ground surface, forming pools or puddles of standing water. Surface water elevation measurements taken at these locations were found to correlate with groundwater elevation measurements taken at monitoring wells and are used routinely to help define groundwater flow-direction and gradients in the sand and gravel unit in areas where monitoring well coverage is sparse or nonexistent.

Groundwater Monitoring Program Highlights 1982 to 2000. The groundwater monitoring program is designed to support DOE Order 5400.1 requirements and the RCRA §3008(h) Administrative Order on Consent for the WVDP. In general, the content of the program is dictated by these requirements in conjunction with current operating practices and historical knowledge of previous site activities.

- Groundwater monitoring at the WVDP began in 1982 with the monitoring of tritium in the sand and gravel unit in the area of the lagoon system.
- By 1984 twenty wells in the vicinity of the main plant and the NDA provided monitoring coverage.
- Fourteen new wells, a groundwater seep location, and the french drain outfall were added in 1986 to monitor additional site facilities.
- In 1990 ninety-six new wells were installed for data collection for the environmental impact statement and RCRA facility investigations.

- A RCRA facility investigation expanded-characterization program was conducted during 1993 and 1994 to fully assess potential releases of hazardous wastes or constituents from on-site SSWMUs. This investigation, which consisted of two rounds of sampling for a wide range of radiological and chemical parameters, yielded valuable information regarding the presence or absence of groundwater contamination near each SSWMU and was also used to guide later monitoring program modifications.

- In 1993 monitoring results indicated elevated gross beta activity in groundwater in the sand and gravel unit on the north plateau. Subsequent investigation of this area delineated a plume of contamination with a southwest to northeast orientation. (See Special Groundwater Monitoring, p. 3-16, for more detail.)

- Long-term monitoring needs were the focus of a 1995 groundwater monitoring program evaluation. After a comprehensive assessment, the number of sampling locations was reduced from ninety-one to sixty-five and analytical parameters were tailored for each sampling location, for a more focused, efficient, and cost-effective program.

- In 1996 several groundwater seep monitoring locations on the northeast edge of the north plateau were added to the monitoring program.

- From 1996 through 2000, in response to current sampling results and DOE and RCRA monitoring requirements, wells, analytes, and sampling frequencies were modified.

Annual Analytical Trigger Level Review. A computerized data-evaluation program using “trigger levels” for chemical and radiological analytes was instituted in 1995. These pre-set

levels — conservative values for chemical or radiological concentrations — were developed to identify and expedite a prompt focus on any anomalies in monitoring results. These values are based on regulatory limits, detection limits, or statistically derived levels. Trigger levels are reviewed and updated every year, if necessary, using all pre-existing data as well as data collected during the year. The trigger levels were updated before the start of the first-quarter 2000 groundwater monitoring.

Upper and lower trigger levels for groundwater elevation measurements were introduced in 1999. These levels are used to identify field measurement anomalies, allowing prompt investigation and remeasurement, if necessary. Groundwater-elevation trigger levels were updated before the start of the first-quarter 2000 groundwater monitoring.

Results of Routine Groundwater Monitoring

Each component of the groundwater monitoring program is completed in accordance with regulatory protocols. These components include locating and installing wells, collecting groundwater samples, incorporating quality assurance methods, and evaluating data.

The tables in Appendix E (pp.E-7 through E-19) group the results of groundwater monitoring according to the five hydrogeologic units monitored: the sand and gravel unit, the Lavery till-sand unit, the weathered Lavery till unit, the unweathered Lavery till unit, and the Kent recessional sequence. These tables contain the results of sampling for the radiological and nonradiological analyte groups noted on Table 3-1 (p.3-6). In addition, Table E-14 (pp.E-20 through E-22) lists the practical quantitation limits (PQLs) for individual NYCRR [New York



Using a Datalogger to Record Hydraulic Conductivity Data from an On-site Monitoring Well

Official Compilation of Codes, Rules, and Regulations] Title 6, Appendix 33 analytes. (The PQL is the lowest level of an analyte that can be measured within specified limits of precision during routine laboratory operations [New York State Department of Environmental Conservation 1991].)

Appendix E tables also display each well's hydraulic position relative to other wells within the same hydrogeologic unit. Wells identified as UP refer to either background wells or wells that are upgradient of other wells in the same hydrogeologic unit. Downgradient locations are designated B, C, or D to indicate their positions along the groundwater flow path relative

to each other. Wells denoted as DOWN - B are closest to the UP wells. Wells denoted as DOWN - C are downgradient of DOWN - B wells but are upgradient of DOWN - D wells. DOWN - D wells are downgradient of all other wells in that hydrogeologic unit. Grouping the wells by hydraulic position provides the basis for presenting the groundwater monitoring data in the tables and figures in this report.

Sample collection periods also are noted. The 2000 sampling year covers the period from December 1999 (the beginning of the first quarter of 2000) through September 2000 (the beginning of the fourth quarter of 2000).

High-low graphs. Graphs showing the range of values for contamination and radiological indicator parameters (pH, conductivity, gross alpha, gross beta, and tritium) have been prepared for all active monitoring locations in each geologic unit. (See Appendix E [pp.E-23 through E-31].) These high-low graphs allow results for all wells within a given hydrogeologic unit to be compared to each other. All of the high-low graphs present the upgradient wells on the left side of the figure. Downgradient locations are plotted to the right according to their relative position along the groundwater flow path.

On the high-low graphs depicting contamination indicator nonradiological results (pH and conductivity), the upper and lower tick marks on the vertical bar indicate the highest and lowest measurements recorded during 2000 for a particular well. The middle tick represents the arithmetic mean of all 2000 results for that well. The vertical bar indicates the total range of the data set for each monitoring location during the year.

On the high-low graphs depicting radiological indicator results (gross alpha, gross beta, and tritium), the middle tick is again used to repre-

sent the arithmetic mean of all 2000 results. However, the upper and lower tick marks on the vertical bar indicate the upper and lower ranges of the pooled error terms for all 2000 results. This format illustrates the relative amount of uncertainty associated with the radiological measurements. By displaying the uncertainty together with the mean, a more realistic perspective is obtained. (See also Data Reporting [p.1-5] in Chapter 1, Environmental Program Information.) On magnified-scale graphs, markers for some locations can not be shown because the magnitude of the concentration is larger than the upper range of the graph.

The analytical results for gross alpha, gross beta, and tritium, even if below the minimum detectable concentrations, were used to generate the high-low graphs. Thus, negative values were included. This is most common for the gross alpha analyses, where sample radiological counting results may be lower than the associated background.

The wells used to provide background values are noted on each graph. All of the geologic units except the sand and gravel unit use a single well for background. In previous years well NB1S was used as the single background reference well for the sand and gravel unit. However, in 1997 the collective monitoring results from three upgradient wells (301, 401, and 706) were substituted for NB1S to use for comparison with other sand and gravel wells as a way of better representing the natural spatial variability within this geologic unit. Both the DOE and NYSDEC have accepted the use of this collective background reference instead of well NB1S.

Trend-line graphs. Trend-line graphs have been used to show concentrations of a particular parameter over time at monitoring locations that have historically shown radiological concentra-

tions above background values or volatile organic compound (VOC) concentrations above practical quantitation limits. Graphs are included for gross beta and tritium at selected groundwater monitoring locations (104, 105, 111, 408, 501, 502, 801, 8603, 8604, and 8605) and for the VOCs 1,1-dichloroethane (1,1-DCA) at wells 803, 8609, and 8612; dichlorodifluoromethane (DCDFMeth) at wells 803 and 8612; 1,2-dichloroethylene (1,2-DCE-t) and 1,1,1-trichloroethane (1,1,1-TCA) at well 8612; and tributyl phosphate (TBP) at wells 111 and 8605. (See Volatile and Semivolatile Organic Compounds Sampling [p.3-15].)

Long-term Trends of Gross Beta and Tritium at Selected Groundwater Monitoring Locations. Figures 3-5 through 3-10 (pp.3-19 through 3-21) show the trends of gross beta and tritium concentrations at selected monitoring locations in the sand and gravel unit. These specific groundwater monitoring locations were selected for trending because they have shown elevated or rising levels of gross beta concentrations, with some also showing elevated levels of tritium concentrations. Results are presented on a logarithmic scale to allow locations of widely differing concentrations to be compared to the average background concentrations plotted on each graph.

Gross Beta. The groundwater plume of gross beta activity in the sand and gravel unit on the north plateau (Fig.3-3 [p.3-12]) continues to be monitored closely. The source of the plume's activity can be traced to the subsurface beneath the southwest corner of the former process building. In 2000 ten wells (104, 105, 111, 408, 501, 502, 801, 8603, 8604, and 8605) showed elevated levels of gross beta concentrations, i.e., concentrations that exceeded the DOE derived concentration guide (DCG) for strontium-90, $1.0\text{E-}06 \mu\text{Ci/mL}$.

- Figures 3-5 and 3-6 (p.3-19) show gross beta concentrations in wells 104, 105, 111, 408, 501, 502, and 801 over the last ten years. As in previous years, samples from well 408 continued to show the highest gross beta concentrations of all the wells within the north plateau gross beta plume area: Gross beta results for well 408 were approximately the same in 2000 as in 1999.

Gross beta at well 111 was about the same in 2000 as in 1999. Wells 501, 502, and 801 showed slight increases relative to 1999, and wells 104 and 105 showed somewhat greater increases relative to 1999 values.

- Figure 3-7 (p.3-20) is a graph of gross beta concentrations at sand and gravel unit monitoring locations 8603, 8604, and 8605. After several years of increases in gross beta concentrations in well 8604, the trend showed slight decreases during 1997 and 1998 and leveled off during 1999 and 2000. Results from well 8603 showed a steady upward trend until early 2000, apparently due to migration of strontium-90 within the eastern lobe of the north plateau plume. Moderate decreases were reported later during 2000.

Lagoon 1, formerly part of the low-level waste treatment facility, has been identified as a source of the gross beta activity at wells 8605 and 111. The gross beta concentrations at well 8605 have been slowly but steadily decreasing over the past several years while concentrations at 111 continued to fluctuate within historical levels.

Tritium. Tritium in sand and gravel wells also is routinely monitored under the groundwater monitoring program.

- Figure 3-8 (p.3-20) shows the tritium concentrations in wells 111, 408, 501, and 502




Figure 3-3. North Plateau Gross Beta Plume Area: Fourth-Quarter 2000 Results.

over the ten-year period that the WVDP's current groundwater monitoring program has been in place. The figure indicates that tritium concentrations in these wells show slight decreases or relatively steady concentration trends.

- Figure 3-9 (p. 3-21) shows tritium concentrations in wells 104, 105 and 801 over the past ten years. Well 801 shows a general decrease over the entire monitoring period; wells 104 and 105 show a slight decrease over the past three years.

- Figure 3-10 (p. 3-21) shows fifteen-year trends of tritium concentrations at monitoring locations 8603, 8604, and 8605. Wells 8603 and 8604 indicate gradually declining trends in tritium; 8605 shows a significant decrease over time.

North Plateau Seeps. Analytical results of sampling for radiological parameters from the sand and gravel unit seepage monitoring locations were compared with the results from GSEEP, a seep monitored since 1991 that has not been affected by the gross beta plume. (Seep monitoring locations are noted on Fig. A-7 [p. A-9].)

Gross beta. Radiological monitoring results continue to indicate that the gross beta plume has not migrated to these seepage areas. With the exception of SP11, gross beta concentrations from all seep monitoring locations were less than or similar to GSEEP concentrations during 2000. The gross beta concentration at SP11 shows a slightly increasing trend since early 1999; although somewhat greater than values typically obtained at GSEEP, it is still well below the gross beta DCG. (See Table E-7 [p. E-14].)

Gross alpha. Gross alpha concentrations at all of the seep sampling locations were very low — generally below the associated uncertainty or less than the detection limit.

Tritium. Tritium concentrations at the seeps remained similar in magnitude or were less than concentrations at GSEEP. Tritium concentrations in the north plateau seeps, including GSEEP, are slightly above the levels reported in background wells of the sand and gravel unit. The concentrations are similar to those seen in sand and gravel unit wells monitoring the lagoon areas of the north plateau but are still far below the DCG for tritium.

Historical sampling results at the seep monitoring locations were evaluated to determine the most efficient and effective monitoring program with respect to locations, analytical parameters, and frequency. Six of the eight active seeps showed either gross beta concentrations similar to or less than GSEEP or were consistently dry. It was recommended that monitoring at four of the seeps (SP02, SP05, SP18, and SP23) be discontinued and that monitoring at all other active seeps be continued according to the current protocol (West Valley Nuclear Services Co. and Dames & Moore March 1999). These recommendations were reviewed and approved by the DOE and NYSDEC and were instituted with the first-quarter 2000 sampling round.

The north plateau seep monitoring locations are inspected periodically and repaired as necessary to maintain optimum seepage flow. This ensures the quality, quantity, and representativeness of the groundwater samples. Minor repairs were required during 1999 at seep monitoring locations SP04 and SP11, including some repositioning of the sampling pipes and clearing of root growth within the pipes. The conditions at all seep monitoring locations are checked during routine sampling and during the annual inspection.

North Plateau Well Points. Seven well points were installed in 1990 downgradient of the process building and were sampled annually be-

tween 1993 and 1996 for radiological indicator parameters. This area east of the process building and west of inactive lagoon 1 appears to be an area of localized contamination and is routinely monitored for contamination indicator and radiological indicator parameters. Data from these seven well points were used to supplement data collected from groundwater monitoring wells. Four well points were removed from the sampling program in 1997 because sufficient coverage was provided by active monitoring wells.

Sampling at well points A, C, and H (Fig. A-6 [p.A-8]) monitors tritium concentrations in the area east of the process building and west of inactive lagoon 1. Samples from these three locations have yielded concentrations of tritium that, while elevated with respect to historical monitoring of wells in the area, are well below the DCG of $2.0\text{E-}03 \mu\text{Ci/mL}$. (See Table E-8 [p.E-15].) Data from downgradient monitoring wells have not indicated similarly elevated levels of tritium.

Results of Radioisotopic Sampling. Groundwater samples for radioisotopic analyses are collected regularly from selected monitoring points in the sand and gravel unit and the weathered Lavery till. (See Table E-13 [pp.E-18 through E-19].) Results in 2000 were generally similar to historical findings. Strontium-90 remained the major contributor to elevated gross beta activity in the plume on the north plateau, as indicated by the similarity between strontium-90 trends and gross beta trends in wells showing elevated gross beta results.

Technetium-99, iodine-129, and carbon-14, which have been detected at several monitoring locations at concentrations above background levels (in specific wells within the gross beta plume and downgradient of inactive lagoon

1 and the NRC-licensed Disposal Area [NDA]), contribute very small percentages to total gross beta concentrations. None of the concentrations of technetium-99, iodine-129, or carbon-14 have been above DCGs, and gross beta analyses continue to provide surveillance on a quarterly basis.

Results of Monitoring at the NDA. A trench was constructed around two sides of the NDA to collect groundwater that may contain a mixture of n-dodecane and tributyl phosphate (TBP). (See also Chapter 1, Environmental Program Information, NRC-licensed Disposal Area [NDA] Interceptor Trench and Pretreatment System [p.1-11].) There were no monitoring results in 2000 that indicated the presence of TBP or n-dodecane in groundwater in the vicinity of the NDA. Groundwater levels are monitored quarterly in and around the trench to ensure that an inward gradient is maintained, thereby minimizing the likelihood for outward migration of potentially contaminated groundwater.

Gross beta and tritium concentrations in samples from location NDATR, a sump at the bottom of the interceptor trench, and from well 909 (Fig.A-6 [p.A-8]), which is downgradient of NDATR, were elevated with respect to background monitoring locations on the south plateau but were still well below the DCGs.

NDATR. During 2000 gross beta concentrations at NDATR remained similar to those seen during 1999, but tritium, while still higher than at other NDA monitoring locations, declined and then leveled off during 1999 and 2000.

Well 909. Radiological indicator results have historically fluctuated at this location but, in general, upward long-term trends in both gross beta and tritium are discernible at well 909,

although the trends show a decrease and then a leveling off during 2000. Gross beta concentrations from well 909 are considerably higher than at NDATR. Residual soil contamination near well 909 is the suspected source of elevated gross beta concentrations at well 909.

Volatile and Semivolatile Organic Compounds Sampling

Volatile and semivolatile organic compounds were sampled at specific locations (wells 8612, 8609, 803, and seep sampling location SP12 [Fig.A-6, p.A-8]) that have shown historical results above their respective practical quantitation limits (PQLs). (See Table E-14 [pp.E-20 through E-22] for a list of PQLs.) Other monitoring locations are sampled for volatile and/or semivolatile organic compounds because they are downgradient of locations that have shown positive results or to comply with the RCRA §3008(h) Administrative Order on Consent.

1,1-dichloroethane. Trends in concentrations of the compound 1,1-dichloroethane (1,1-DCA) from 1991 through 2000 are illustrated in Figure 3-11 (p.3-22). Concentrations of 1,1-DCA at well 8612 have decreased somewhat over the past five years. The compound was not detected at wells 8609, 803, or groundwater seep SP12 during 2000. (See Table E-9 [p. E-15].)

Dichlorodifluoromethane. Trends of dichlorodifluoromethane (DCDFMeth) concentrations are shown in Figure 3-12 (p.3-22). DCDFMeth was not detected at wells 803 or 8612 during 2000.

1,2-dichloroethylene. Positive detections of 1,2-dichloroethylene (1,2-DCE-t) were first noticed at well 8612 (Fig. 3-13 [p.3-23]) in 1995.

Concentrations of 1,2-DCE-t during 2000 were similar to those of 1999 and somewhat lower than concentrations measured during 1998.

1,1,1-trichloroethane. The compound 1,1,1-trichloroethane (1,1,1-TCA) was not detected above the PQL of 5 µg/L in 8612 (Fig. 3-13 [p. 3-23]) or wells 803, 8609, and seep SP12 (Table E-9 [p. E-15]).

The VOCs 1,1-DCA, DCDFMeth, and 1,1,1-TCA are often found in combination with each other and with 1,2-DCE-t. In well 8612 each of these three compounds first exhibited an increasing trend that, over the past few years, was then followed by a decreasing trend. It is expected that 1,2-DCE-t will exhibit similar behavior, and routine monitoring will evaluate future trends.

Tributyl phosphate. Aqueous concentrations of tributyl phosphate (TBP) were detected in 2000 at well 8605, near former lagoon 1, at concentrations similar to or less than those in 1999. During 1999 TBP also was detected in well 111, which is next to and downgradient of well 8605, but at levels much lower than those at well 8605. (See Fig. 3-14 [p. 3-23] and Table E-10 [p.E-16].) TBP was not detected above the PQL in well 111 during 2000.

The ongoing detection of TBP in this localized area may be related to previously detected low, positive concentrations of iodine-129 and uranium-232 in wells 111 and 8605, as noted in previous annual site environmental reports. The presence of these three contaminants reflects residual contamination from waste disposal activities in the former lagoon 1 area during earlier fuel reprocessing. Future trends of TBP will be evaluated as part of the routine groundwater monitoring program.

Special Groundwater Monitoring

Gross Beta Plume on the North Plateau. Elevated gross beta activity has been detected in groundwater from the surficial sand and gravel unit in areas north and east of the building where NFS reprocessed nuclear fuel (Fig. 3-3 [p.3-12]). In December 1993 elevated gross beta concentrations were detected in surface water at former sampling location WNDMPNE, located at the edge of the plateau. This detection initiated a subsurface investigation in 1994. Groundwater and soil were sampled using a Geoprobe®, a mobile sampling system. The investigation was used to estimate the extent of the gross beta plume beneath and downgradient of the process building. The gross beta plume delineated in 1994 was approximately 300 feet wide and 800 feet long.

The highest gross beta concentrations in groundwater and soil were near the southeast corner of the process building. The maximum concentration in groundwater was $3.6\text{E-}03\ \mu\text{Ci/mL}$, and the maximum concentration in soil reached $2.4\text{E-}02\ \mu\text{Ci/g}$. Strontium-90 and its daughter product, yttrium-90, were determined to be the isotopes responsible for most of this elevated gross beta activity (West Valley Nuclear Services Co., Inc. 1995).


In 1995 the north plateau groundwater recovery system (NPGRS) was installed to minimize the spread of the gross beta plume. The NPGRS is located near the leading edge of the main lobe of the plume where groundwater flows preferentially towards the edge of the plateau. The NPGRS consists of three extraction wells (RW-01, RW-02, and RW-03) that recover the contaminated groundwater and then treat it by ion exchange to remove strontium-90. Treated water is transferred to lagoon 4 or

5 and then to lagoon 3 and ultimately is discharged to Erdman Brook.

The north plateau groundwater recovery system operated successfully throughout 2000, processing about 16 million liters (4.2 million gal). The system has recovered and processed approximately 83 million liters (22.0 million gal) since November 1995.

As a result of recommendations from a 1997 external review of WVDP response actions on the north plateau, more attention was given in 1998 to the core area of the plume. A summary report, 1998 Geoprobe® Investigation in the Core Area of the North Plateau Groundwater Plume (West Valley Nuclear Services Co., Inc. June 1999) discusses groundwater and soil sampling data in the core area and compares radiological sampling results with a 1994 sampling. The 1998 study verified that strontium-90 continues to be the predominant beta-emitter in groundwater and saturated soil within the north plateau groundwater plume. The report also noted that while the overall distribution of strontium-90 in groundwater within the plume was similar to 1994, concentrations detected in 1998 Geoprobe® samples were generally lower than in the 1994 Geoprobe® samples due to radioactive decay and continuing migration and dispersion of the plume.

Permeable Treatment Wall. A pilot-scale permeable treatment wall (PTW) was completed in the fall of 1999 in the eastern lobe of the north plateau strontium-90 groundwater plume in order to test this passive, in situ remediation technology. The PTW is a trench constructed in the subsurface and backfilled with clinoptilolite, a medium selected for its ability to adsorb strontium-90 ions from groundwater. The PTW extends vertically downward through the sand and gravel unit to the top of the underlying Lavery



till and is approximately 30 feet long and 10 feet wide.

Monitoring and evaluation of water levels and radiological concentrations upgradient, within, and downgradient of the PTW continued during 2000 in order to assess its effectiveness. During a short-term study groundwater was pumped out of the PTW in order to evaluate hydraulic response in the immediate vicinity of the wall. During 2001 additional evaluation of PTW effectiveness will continue. This evaluation is expected to provide data relevant to development of a full-scale treatment wall.

Northeast Swamp Drainage Monitoring. Routine surface water sampling during 2000 continued to monitor radiological discharges through the northeast swamp drainage at location WNSWAMP. (See Appendix C, Table C-7 [p.C-8].) Gross beta and strontium-90 concentrations continued to fluctuate due to seasonal effects. The annualized average strontium-90

concentrations were generally consistent through mid-2000 and then steadily decreased until leveling off late in the year. (See Fig. 3-4 [above].)

Although the annualized averaged concentration of strontium-90 in surface water was elevated at sampling location WNSWAMP (on the WVDP premises), monitoring downstream at the first point of public access (WFFELBR) continued to show strontium-90 concentrations that were not significantly different from background (WFBIGBR) concentrations. (See also Off-site Surface Water Sampling Locations, p.2-9, in Chapter 2, Environmental Monitoring.)

North Plateau Groundwater Quality Early Warning Sampling. An early warning evaluation of selected monitoring well data was devised to identify possible changes in the quality of the groundwater recovered by the NPGRS that might affect compliance with site effluent limitations on pollutants specified in the SPDES

permit for outfall 001 (Dames & Moore May 1995). This monitoring is important because water recovered by the NPGRS ultimately is discharged through outfall 001.

The early warning system compares quarterly monitoring results from three wells (116, 602A, and 502) in the vicinity of the NPGRS to early warning levels (multiples of the SPDES permit levels) in order to identify concentrations that may affect compliance with SPDES effluent limits. Routine results for two of the wells, 116 and 602A, are used to monitor groundwater in the area affected by NPGRS drawdown. The third well, 502, is directly up-gradient of the NPGRS and is sampled for additional metals not routinely analyzed under the current groundwater monitoring program. Analytical results of sampling of well 502 for additional metals can be found in Table E-12 (pp.E-17 in Appendix E).

Investigation of Chromium and Nickel in the Sand and Gravel Unit and Evaluation of Corrosion in Groundwater Monitoring Wells. A 1997 and 1998 study of the effect of modifying sampling equipment and methodology on the concentrations of chromium and nickel in samples of groundwater from the sand and gravel unit noted that such modifications did produce decreases in chromium and nickel concentrations. This supported the hypothesis (which is well documented in the technical literature) that the apparently elevated concentrations were not representative of actual groundwater conditions but were caused by the release of metals from subsurface corrosion of stainless steel well materials (West Valley Nuclear Services, Inc. and Dames & Moore June 1998b).

To ensure continued monitoring well integrity and the collection of high-quality samples representative of actual groundwater conditions,

in 1999 and 2000 the WVDP evaluated current corrosion and corrosion-removal methods by inspecting the inside of the wells with a down-hole video camera, documenting the observed conditions, and attempting to remove corrosion, where present. A second video inspection was made after cleaning to evaluate the effectiveness of the work. Simple brushing and well-purging proved to be successful in removing corrosion from all wells. No degradation of the well casings or screens was evident after corrosion was removed.

Long-term corrosion management will begin during 2001 and will include annual video inspections and corrosion removal, where appropriate (West Valley Nuclear Services Co. January 2001).




Figure 3-5. Ten-year Trends of Averaged Gross Beta Concentrations (µCi/mL) at Selected Locations in the Sand and Gravel Unit




Figure 3-6. Ten-year Trends of Averaged Gross Beta Concentrations (µCi/mL) at Selected Locations in the Sand and Gravel Unit




Figure 3-7. Fifteen-year Trends of Averaged Gross Beta Concentrations ($\mu\text{Ci/mL}$) at Selected Locations in the Sand and Gravel Unit




Figure 3-8. Ten-year Trends of Averaged Tritium Concentrations ($\mu\text{Ci/mL}$) at Selected Locations in the Sand and Gravel Unit




Figure 3-9. Ten-year Trends of Averaged Tritium Concentrations (µCi/mL) at Selected Locations in the Sand and Gravel Unit




Figure 3-10. Fifteen-year Trends of Averaged Tritium Concentrations (µCi/mL) at Selected Locations in the Sand and Gravel Unit




Figure 3-11. Ten-year Trends of 1,1-DCA (µg/L) at Selected Locations in the Sand and Gravel Unit




Figure 3-12. Ten-year Trends of Dichlorodifluoromethane (µg/L) at Selected Locations in the Sand and Gravel Unit




Figure 3-13. Ten-year Trends of 1,2-DCE-t and 1,1,1-TCA ($\mu\text{g/L}$) at Well 8612 in the Sand and Gravel Unit




Figure 3-14. Trends of Tributyl Phosphate ($\mu\text{g/L}$) at Selected Locations in the Sand and Gravel Unit

RADIOLOGICAL DOSE ASSESSMENT

Introduction

Each year the potential radiological dose to the public that is attributable to operations and effluents from the West Valley Demonstration Project (WVDP) is assessed to verify that no individual could credibly have received a dose exceeding the limits established by the regulatory agencies. The results of these conservative dose calculations demonstrate that the potential maximum dose to an off-site resident was well below permissible standards and was consistent with the as-low-as-reasonably achievable (ALARA) philosophy of radiation protection.

This chapter describes the methods used to estimate the dose to the general public resulting from exposure to radiation and radionuclides originating at the Project during calendar year 2000. The resulting estimated doses are compared directly with current radiation standards established by the U.S. Department of Energy (DOE) and the U.S. Environmental Protection Agency (EPA) for protection of the public. These values are also compared with the annual dose the average resident of the U.S. receives from natural background radiation and

to doses reported in previous years for the Project.

Sources of Radiation. Members of the public are routinely exposed to different sources of ionizing radiation from both natural and man-made sources. Figure 4-1 (p.4-2) shows the relative contribution to the annual dose in millirem from these sources in comparison with the estimated calendar year 2000 maximum individual dose from the WVDP. The National Council on Radiation Protection and Measurements (NCRP) Report 93 (1987) estimates that the average annual effective dose equivalent received by an individual living in the U.S. is about 360 mrem (3.6 mSv) from both natural and manmade sources of radiation.

While most of the radiation dose received by the general public is natural background radiation, manmade sources of radiation also contribute to the average dose. Such sources include diagnostic and therapeutic x-rays, nuclear medicine, fallout from atmospheric nuclear weapons tests, effluents from nuclear fuel cycle facilities, and consumer products such as smoke detectors and cigarettes.

As can be seen in Figure 4-1 (*below*), natural sources of radiation contribute 295 mrem (2.95 mSv) and manmade sources contribute 65 mrem (0.65 mSv) of the total annual U.S. average dose of 360 mrem (3.60 mSv). The WVDP contributed a very small amount (0.061 mrem [0.00061 mSv]) to the total annual manmade radiation dose to the maximally exposed individual residing near the WVDP. This is much less than the average dose received from using consumer products and is insignificant compared to the federal standard of 100 mrem allowed from any DOE site operations in a calendar year or the 295 mrem received annually from natural sources. The dose from WVDP operations also is small compared to the average dose an airline crew member typically receives from cosmic radiation (200 mrem/year).

Exposure Pathways

The radionuclides present at the WVDP site are residues from the reprocessing of commercial nuclear fuel during the 1960s and early 1970s. A very small fraction of these radionuclides is released off-site during the year through ventilation systems and liquid discharges. These releases make a negligible contribution to the radiation dose to the surrounding population through several exposure pathways.

An exposure pathway consists of a way for a source of contamination or radiation to be transported by environmental media to a receptor where exposure to contaminants may occur. For example, a member of the public could be exposed to low concentrations of radioactive particulates carried by prevailing winds.

The potential pathways of exposure from Project emissions are inhalation of gases and particulates, ingestion of locally grown food products, ingestion of fish, beef, and deer tissues, and exposure to external penetrating radiation emanating from contaminated materials. The drinking water pathway is excluded from calculations of potential maximum dose to individuals because surveys revealed that local residents do not use Cattaraugus Creek as a source of drinking water. Table 4-1 (*facing page*) summarizes the potential exposure pathways for the local off-site population.

Land Use Survey

Periodic surveys of local residents provide information about local family sizes, sources of food, and gardening practices. Information from the most recent survey, conducted in 1996, was used to confirm the locations of the nearest resi-




Table 4-1
Potential Local Off-Site Exposure Pathways Under Existing WVDP Conditions

Exposure Pathway and Transporting Medium	Reason for Inclusion/Exclusion
Inhalation: gases and particulates in air (included)	Off-site transport of contaminants from WVDP stacks or resuspended particulates from soils or water
Ingestion: cultivated crops (included)	Local agricultural products irrigated with contaminated ground- or surface water; foliar deposition and uptake of airborne contaminants
Ingestion: surface and groundwater (excluded)	No documented use of local surface water or down-gradient groundwater wells as drinking water by local residents
Ingestion: fish, beef, venison, and milk (included)	Fish exposed to contaminants in water or sediments may be consumed; beef, venison, and milk consumption following deposition of transported airborne and surface water contaminants
External exposure: radiation emanating from particulates and gases from air or surface water (included)	Transport of air particulates and gases to off-site receptors; transport of contaminants in surface water and direct exposure during stream use and swimming

dences and other population parameters. These parameters are required for computer models that are used for the annual dose assessments. (See the discussion of Dose Assessment Methodology below for more information on the computer model used.)

Radioactive Vitrification Operations

The start of radioactive vitrification operations in July 1996 resulted in an increase of radioactive emissions from the main plant stack. Specifically, the release rate of iodine-129 increased from a 1993 to 1995 average of 25 microcuries (μCi) per year to 1,200 μCi in 1996 and 7,430 μCi in 1997 as a result of the processing of the high-level waste.

In 1998 the yearly release of iodine-129 fell to 4,970 $\mu\text{Ci}/\text{yr}$ due to the completion of Phase I of vitrification; in 1999 the total iodine-129 release was 1,900 μCi . The iodine-129 levels continued to decrease in calendar year 2000 — to 1,260 μCi , a level consistent with reduced vitrification activity. (See Chapter 2, Special Monitoring, [p.2-28] for a discussion of iodine-129 emissions from the main plant stack.)

Dose Assessment Methodology

The potential radiation dose to the general public from activities at the WVDP is evaluated by using a two-part methodology and following the requirements in DOE Order 5400.5. The first part uses the measurements of radionuclide

Radioactivity

Atoms that emit radiation are called radionuclides. Radionuclides are unstable isotopes that have the same number of protons as any other isotope of the element but different numbers of neutrons, resulting in different atomic masses. For example, the element hydrogen has two stable isotopes, H-1 and H-2 (deuterium), and one radioactive isotope, H-3 (tritium). The numbers following the element's symbol identify the atomic mass, which is the number of protons plus neutrons in the nucleus. Thus, H-1 has one proton and no neutrons, H-2 has one proton and one neutron, and H-3 has one proton and two neutrons.

When radioactive atoms decay by emitting radiation, the daughter products that result may be either radioactive or stable. Generally, radionuclides with high atomic numbers, such as uranium-238 and plutonium-239, have many generations of radioactive progeny. For example, the radioactive decay of plutonium-239 creates uranium-235, thorium-231, protactinium-231, and so on through eleven progeny until only the stable isotope lead-207 remains.

Radionuclides with lower atomic numbers often have no more than one daughter. For example, strontium-90 has one radioactive daughter, yttrium-90, which finally decays into stable zirconium; cobalt-60 decays directly to stable nickel with no intermediate nuclide.

The time required for half of the radioactivity of a radionuclide to decay is referred to as the radionuclide's half-life. Each radionuclide has a unique half-life; both strontium-90 and cesium-137 have half-lives of approximately 30 years while plutonium-239 has a half-life of 24,400 years. Knowledge of radionuclide half-lives is often used to estimate past and future inventories of radioactive material. For example, a 1.0-millicurie source of cesium-137 in 2000 would have measured 2.0 millicuries in 1970 and will be 0.5 millicuries in 2030.

Radiation emitted by radionuclides may consist of electromagnetic rays such as x-rays and gamma rays or charged particles such as alpha and beta particles. A radionuclide may emit one or more of these radiations at characteristic energies that can be used to identify them.

Health Effects of Low-level Radiation

Radionuclides entering the body through air, water, or food are distributed in different organs of the body. For example, isotopes of iodine concentrate in the thyroid. Strontium, plutonium, and americium isotopes concentrate in the skeleton. When inhaled, uranium and plutonium isotopes remain in the lungs for a long period of time. Some radionuclides such as tritium, carbon-14, or cesium-137 are distributed uniformly throughout the body. Thus, depending on the radionuclide, some organs may receive quite different doses. Moreover, at the same dose levels, certain organs (such as the breast) are more prone to developing a fatal cancer than other organs (such as the thyroid).

Because of the uncertainty and difficulty in measuring the incidence of increased cancer resulting from exposure to ionizing radiation, to be conservative, a linear model is used to predict health risks from low levels of radiation. This model assumes that there is a risk associated with all dose levels even though the body may effectively repair damage incurred from low levels of alpha, beta, and gamma radiations.

concentrations in liquid and air released from the Project. The second part uses measurements of radioactivity in food from locations near the Project boundaries.

Radiological dose is evaluated for all major exposure pathways, including external irradiation, inhalation, and ingestion of local food products. The dose contributions from each radionuclide and pathway combination are then summed to obtain the total dose estimates reported in Table 4-2 (p.4-6).

Measurement of Radionuclide Concentrations in Liquid and Air Releases. Because of the difficulty of distinguishing the small amount of radioactivity emitted from the site from that which occurs naturally in the environment, computer codes are used to model the environmental dispersion of radionuclides emitted from on-site monitored ventilation stacks and liquid discharge points.

First, actual data from release-monitoring samples (see Appendix C and Appendix D) are collected, together with annual weather measurements and the latest demographic information. The effective dose equivalent (EDE) to the maximally exposed off-site individual and the collective EDE to the population within a 50-mile radius are then calculated using conservative models that have been approved by the DOE and the EPA to demonstrate compliance with radiation standards. (See Radiation Dose on this page and Units of Measurement on p. 4-8.)

Measurement of Radionuclide Concentrations in Food. The second part of the dose assessment is based on actual measurements of radioactivity in samples of foodstuffs grown in the vicinity of the WVDP and the comparison of these values with measurements of samples

Radiation Dose

The energy released from a radionuclide is eventually deposited in matter encountered along the path of the radiation. The radiation energy absorbed by a unit mass of material is referred to as the absorbed dose. The absorbing material can be either inanimate matter or living tissue.

Alpha particles leave a dense track of ionization as they travel through tissue and thus deliver the most dose per unit-path length. However, alpha particles are not penetrating and must be taken into the body by inhalation or ingestion to cause harm. Beta and gamma radiation can penetrate the protective dead skin layer of the body from the outside, resulting in exposure of the internal organs to radiation.

Because beta and gamma radiations deposit much less energy in tissue per unit-path length relative to alpha radiation, they produce fewer biological effects for the same absorbed dose. To allow for the different biological effects of different kinds of radiation, the absorbed dose is multiplied by a quality factor to yield a unit called the dose equivalent. A radiation dose expressed as a dose equivalent, rather than as an absorbed dose, permits the risks from different types of radiation exposure to be compared with each other (e.g., exposure to alpha radiation compared with exposure to gamma radiation). For this reason, regulatory agencies limit the dose to individuals in terms of total dose equivalent.

collected from locations well beyond the potential influence of site effluents. These measurements of environmental media show that the concentrations of radioactivity are small — usually near the analytical detection limits — thereby providing additional assurance that operations at the WVDP are not adversely affecting the public.

Table 4-2

**Summary of Annual Effective Dose Equivalents to an Individual
and Population from WVDP Releases in 2000**

Exposure Pathways	Annual Effective Dose Equivalent	
	Maximally Exposed Off-Site Individual ¹ mrem (mSv)	Collective Effective Dose Equivalent ² person-rem (person-Sv)
Airborne Releases ³	8.1E-03 (8.1E-05)	6.9E-02 (6.9E-04)
% EPA standard (10 mrem)	0.081%	NA
Waterborne Releases ⁴		
Effluents only	3.0E-02 (3.0E-04)	1.9E-02 (1.9E-04)
Effluents plus north plateau drainage	5.3E-02 (5.3E-04)	1.5E-01 (1.5E-03)
Total from all Pathways	6.1E-02 (6.1E-04)	2.2E-01 (2.2E-03)
% DOE standard (100 mrem) — air and water combined	0.061%	
% of natural background (295 mrem; 380,980 person-rem) — received from air and water combined	0.02%	0.00006%
Estimated Rn-220 ⁵	3E-02 (3E-04) ⁶	2.5E-01 (2.5E-03)

Exponents are expressed as “E” in this report: a value of 1.2×10^{-4} in scientific notation is reported as 1.2E-04 in the text and tables.

NA — Not applicable. Numerical regulatory standards are not set for the collective EDE to the population.

¹ Modeled data estimates the maximum exposure to air discharges occurs at a residence 1.8 kilometers northwest of the main plant.

² Population of 1.35 million within 80 kilometers of the site.

³ From atmospheric release non-radon point sources. Calculated using CAP88-PC for individual and population. EPA and DOE limits for individual airborne dose are the same.

⁴ Calculated using methodology described in Manual for Radiological Assessment of Environmental Releases at the WVDP (Spector 2000).

⁵ Estimated releases based on indicator measurements and vitrification processing values: dose estimates calculated using CAP88-PC.

⁶ Estimated dose from Rn-220 specifically excluded by rule from NESHAP totals. (See p. 4-9.)

If any of the near-site food samples were to contain radionuclide concentrations that are statistically higher than the concentrations in control samples, separate dose calculations would be performed to verify that the calculated foodstuff dose is within the dose range estimated by computer modeling. These calculated doses are not added to the computer-modeled estimates (Table 4-2 [*facing page*]) because the models already include contributions from all environmental pathways.

Comparison of Near-site and Background Environmental Media Concentrations. Both near-site and control (background) samples of fish, milk, beef, venison, and local produce are collected and analyzed for various radionuclides, including tritium, cobalt-60, strontium-90, iodine-129, and cesium-137. The measured radionuclide concentrations reported in Appendix F, Tables F-1 through F-4 (pp. F-3 through F-8) are the basis for comparing near-site and background concentrations.

If differences are found between near-site and background sample concentrations, the amount by which the near-site sample concentration exceeds background is used to calculate a potential maximum individual dose for comparison with dose limits and the dose from background alone. If no statistical differences in concentrations are found, then no further assessment is conducted.

The maximum potential dose to nearby residents from the consumption of foods with radionuclide concentrations above background is calculated by multiplying the net concentrations (concentration in a sample minus background concentration) by the maximum adult annual consumption rate for each type of food and the unit dose conversion factor for ingestion of the measured radionuclide. The consumption rates are based on site-specific data and recommendations

in NRC Regulatory Guide 1.109 for terrestrial food chain dose assessments (U.S. Nuclear Regulatory Commission October 1977). The internal dose conversion factors were obtained from Internal Dose Conversion Factors for Calculation of Dose to the Public (DOE/EH-0071 [U.S. Department of Energy July 1988]).

Note that foodstuffs are weighed when received at the laboratory and the percent moisture is determined from the difference between the mass of the dried sample weighed after preparation for radiological measurement and the original "wet" as-measured mass. Doses are calculated based on the reconstituted "wet" mass of the original sample as it would be before preparation as food.

Predicted Dose from Airborne Emissions

Airborne emissions of radionuclides are regulated by the EPA under the Clean Air Act and its implementing regulations. DOE facilities are subject to 40 CFR 61, Subpart H, National Emission Standards for Hazardous Air Pollutants (NESHAP). Subpart H constitutes the national emission standards for emissions of radionuclides other than radon from DOE facilities. The applicable standard for radionuclides is a maximum of 10 mrem (0.1 mSv) EDE to any member of the public in any year.

Releases of airborne radioactive materials from nominal ground level stacks (1- to 24-meters high) and from the main 60-meter stack are modeled using the EPA-approved CAP88-PC computer code (U.S. Environmental Protection Agency March 1992). This air dispersion code estimates effective dose equivalents for the ingestion, inhalation, air immersion, and ground surface pathways. Site-specific data for non-radon radionuclide release rates in curies per year, wind data, and the current local popula-

Units of Measurement

The unit for dose equivalent in common use in the U.S. is the rem, which stands for roentgen-equivalent-man. The international unit of dose equivalent is the sievert (Sv), which is equal to 100 rem. The millirem (mrem) and millisievert (mSv), used more frequently to report the low dose equivalents encountered in environmental exposures, are equal to one-thousandth of a rem or sievert.

The effective dose equivalent (EDE), also expressed in units of rem or sievert, provides a means of combining unequal organ and tissue doses into a single "effective" whole body dose that represents a comparable probability of inducing a fatal cancer. The probability that a given dose will result in the induction of a fatal cancer is referred to as the risk associated with that dose. The EDE is calculated by multiplying the organ dose equivalent by the organ-weighting factors developed by the International Commission on Radiological Protection (ICRP) in Publications 26 (1977) and 30 (1979). The weighting factor is a ratio of the risk from a specific organ or tissue dose to the total risk resulting from an equal whole body dose. All organ-weighted dose equivalents are then summed to obtain the EDE.

The dose from internally deposited radionuclides calculated for a fifty-year period following intake is called the fifty-year committed effective dose equivalent (CEDE). The CEDE sums the dose to an individual over fifty years to account for the biological retention of radionuclides in the body. The total EDE for one year of exposure to radioactivity is calculated by adding the CEDE to the dose equivalent from external, penetrating radiation received during the year. Unless otherwise specified, all doses discussed here are EDE values, which include the CEDE for internal emitters.

A collective population dose is expressed in units of person-rem or person-sievert because the individual doses are summed over the entire potentially exposed population. The average individual dose can therefore be obtained by dividing the collective dose by the number in the population.

tion distribution are used as input parameters. Resulting output from the CAP88-PC code is then used to determine the total EDE to a maximally exposed individual and the collective dose to the population within an 80-kilometer (50-mi) radius of the WVDP.

As reported in Chapter 2, Environmental Monitoring, the main 60-meter stack and several shorter stacks were monitored for radioactive air emissions during 2000. The activity that was released to the atmosphere from these emission points is listed in Tables D-1 through D-11 and D-15. (See Appendix D [pp.D-3

through D-12 and D-16].) Appropriate information from these tables was used as input to the CAP88-PC code.

Wind data collected from the on-site meteorological tower during 2000 were used as input to the CAP88-PC code. Data collected at the 60-meter and 10-meter heights were used in combination with the main plant stack and ground-level effluent release data, respectively.

Maximum Dose to an Off-site Individual. Based on the non-radon airborne radioactivity released from all point sources at the site


Radon-220

Radon-220 is a naturally occurring gaseous decay product of thorium-232 present in the airborne emissions from the WVDP main plant. Radon-220, also known as thoron, is associated with the THOREX-related thorium-232 and uranium-232 in the high-level waste.

As reported in Chapter 2 of the 1996 WVDP Site Environmental Report, thoron levels were observed to increase during startup of the 1996 high-level waste vitrification process. An estimate of the thoron released during each waste concentration cycle was developed and used to determine a theoretical annual release. During the vitrification phase an average of about 12 curies per day were released. In 2000, because of the substantially reduced number of concentration cycles, the average was a bit less than seven and a half curies of thoron released per day.

Although large numbers of curies were released relative to other radionuclides, the calculated dose from thoron is quite small because of its short decay half-life and other characteristics. The NESHAP rule specifically excludes thoron from air emission dose calculations at the WVDP, so a dose estimate using CAP88-PC was calculated separately. The theoretical dose to the maximally exposed off-site individual (MEOSI) located 1.8 kilometers northwest of the site in 2000 would have been 0.03 mrem, and the collective dose to the population within an 80-kilometer radius would have been 0.25 person-rem. (See Table 4-2, p. 4-6.) These theoretical doses are less than or about the same as doses from the manmade radionuclide WVDP effluents.

As the final stages of vitrification are completed, thoron releases are expected to decrease to below pre-vitrification levels. The figure presented here provides a relative indication of recent trends in the estimated annual thoron releases.



during 2000, it was estimated that a person living in the vicinity of the WVDP could have received a total EDE of 0.0081 mrem (0.000081 mSv). The computer model estimates that this maximally exposed off-site individual was located 1.8 kilometers northwest of the site and was assumed to eat only locally produced foods. Approximately 99% of the dose was from iodine-129 emitted from the main stack.

The maximum total EDE of 0.0081 mrem (0.000081 mSv) from the permitted stacks and vents is far below levels that could be directly measured at the exposed individual's resi-

dence. This dose is comparable to about fifteen minutes of natural background radiation received by an average member of the U.S. population and is well below the 10 mrem (0.1 mSv) NESHAP limit promulgated by the EPA and required by DOE Order 5400.5.

Collective Population Dose. The CAP88-PC program was used to estimate the collective EDE to the population. Because the latest U.S. census population data are not yet available, the population data that were used for the 2000 assessment are from the 1990 census projection for the year 2000. In this ten-year projec-

tion, 1.35 million people were estimated to reside within 80 kilometers (50 mi) of the WVDP. This population received an estimated 0.069 person-rem (0.00069 person-Sv) total EDE from radioactive non-radon airborne effluents released from the permitted WVDP point sources during 2000. The resulting average EDE per individual was 0.00005 mrem (0.000005 mSv).

Predicted Dose from Waterborne Releases

Currently there are no EPA standards establishing limits on the radiation dose to members of the public from liquid effluents except as applied in 40 CFR 141 and 40 CFR 143, Drinking Water Guidelines (U.S. Environmental Protection Agency 1984a; 1984b). The potable-water wells sampled for radionuclides are upgradient of the WVDP and therefore are not a potential source of exposure to radiation from Project activities.

Since Cattaraugus Creek is not used as a drinking water supply, a comparison of the predicted concentrations and doses with the EPA drinking water limits established in 40 CFR 141 and 40 CFR 143 is not truly appropriate (although the values in creek samples are well below the EPA drinking water limits). The estimated radiation dose was compared to the applicable guidelines provided in DOE Order 5400.5. The EDE to the maximally exposed off-site individual and the collective EDE to the population due to routine waterborne releases and natural drainage are calculated using dose conversion factors as tabulated in the WVDP Manual for Radiological Assessment of Environmental Releases at the WVDP (Spector 2000).

Since the Project's liquid effluents eventually reach Cattaraugus Creek, which is not used directly as a source of drinking water, the most

important individual exposure pathway is the consumption of fish from this creek by local sportsmen. It is assumed that a person may consume annually as much as 21 kilograms (46 lbs) of fish caught in the creek. Exposure to external radiation from shoreline or water contamination also is included in the model for estimating radiation dose. Population dose estimates assume that radionuclides are further diluted in Lake Erie before reaching municipal drinking water supplies.

The computer codes GENII version 1.485 (Pacific Northwest Laboratory 1982), which implements the models in U.S. NRC Regulatory Guide 1.109, and LADTAP II (Simpson and McGill 1980) were used to calculate the site-specific unit dose factors for routine waterborne releases and dispersion of these effluents. Input data included local stream flow and dilution, drinking water usage, and stream usage factors. A detailed description of GENII is given in the WVDP Manual for Radiological Assessment of Environmental Releases at the WVDP (Spector 2000).

Six planned batch releases of liquid radioactive effluents from lagoon 3 occurred during 2000. The radioactivity discharged in these effluents, listed in Appendix C, Table C-1 [p. C-3], was used with the unit dose factors to calculate the EDE to the maximally exposed off-site individual and the collective EDE to the population living within an 80-kilometer radius of the WVDP.

In addition to the batch releases from lagoon 3 (WNSP001), effluents from the sewage treatment facility (WNSP007) and the french drain (WNSP008) are routinely released. The activities measured from these release points were included in the EDE calculations. The measured radioactivity concentrations from the sewage treatment facility and french drain

are presented in Appendix C, Tables C-5 and C-6 (p.C-7).

Besides the three release points listed above, there are two natural drainage channels originating on the Project premises that have measurable concentrations of radioactivity in the water. These are drainages from the northeast swamp (WNSWAMP) and north swamp (WNSW74A). The measured radioactivity from these points is reported in Tables C-7 and C-8 (pp.C-8 and C-9). Radioactivity measured at these drainage sample points is included in the EDE calculations for the maximally exposed off-site individual and the collective population.

Maximum Dose to an Off-site Individual.

Based on the radioactivity in liquid effluents released from the WVDP (lagoon 3, the sewage treatment plant, and the french drain) during 2000 an off-site individual could have received a maximum EDE of 0.030 mrem (0.00030 mSv). Approximately 90% of this dose was from cesium-137. This 0.030 mrem (0.00030 mSv) dose is negligible in comparison to the 295 mrem (2.95 mSv) that an average member of the U.S. population receives in one year from natural background radiation.

The maximum off-site individual EDE due to drainage from the north plateau (north swamp and northeast swamp) is 0.024 mrem (0.00024 mSv). The combined EDE to the maximally exposed individual from liquid effluents and drainage is 0.053 mrem (0.00053 mSv). This annual dose is virtually unchanged from 1999 and is negligible in comparison to the 295 mrem (2.95 mSv) that an average member of the U.S. population receives in one year from natural background radiation.

Collective Dose to the Population. As a result of radioactivity released in liquid effluents from the WVDP (lagoon 3, the sewage

treatment plant, and the french drain) during 2000, the population living within 80 kilometers (50 mi) of the site received a collective EDE of 0.019 person-rem (0.00019 person-Sv). The collective dose to the population from the north plateau drainage is 0.135 person-rem (0.00135 person-Sv). This estimate is based on a population of 1.35 million living within the 80-kilometer radius. The resulting average EDE from lagoon 3, the sewage treatment plant, the french drain, and north plateau drainage (north swamp and northeast swamp) per individual is 1.1E-04 mrem (1.1E-06 mSv). This dose of 0.00011 mrem (0.0000011 mSv) is an inconsequential addition to the dose that an average person receives in one year from natural background radiation.

Calculated Dose from Local Foodstuff Tests

Fish. Samples of fish were collected from Cataaugus Creek from May 2000 through November 2000. Twenty fish were collected both at background locations upstream of the site and at locations downstream of the site above the Springville dam. Ten fish were collected at points downstream of the site below the dam. Edible portions of fish samples were analyzed for strontium-90 and cesium-137, and the values were compared with background values. (See Table F-4 [pp.F-6 through F-8].)

Most of the strontium-90 data for fish collected downstream of the dam failed quality assurance tests during laboratory processing, but the remaining data indicate that no changes from previous levels of strontium-90 are likely. Cesium-137 concentrations were not statistically different from concentrations at control locations.

Strontium-90 in individual fish collected downstream of the site, above the Springville dam, was detectable at slightly above the average me-

dian control sample concentrations. The calculated maximum dose to an individual from consuming 21 kilograms (46 lbs) of near-site fish was 0.009 mrem (0.00009 mSv). This annual dose is roughly equivalent to the dose received every sixteen minutes from natural background radiation.

Milk. Milk samples were collected from various nearby dairy farms throughout 2000. Control samples were collected from farms 25 to 30 kilometers (15-20 mi) to the south and north of the WVDP. Milk samples were analyzed for tritium, strontium-90, iodine-129, cesium-137, and potassium-40. (See Table F-1 [p.F-3].) Ten near-site milk samples were collected and compared with eight background samples. Average values for tritium, strontium-90, iodine-129, and cesium-137 were either below detection limits or not statistically different from control concentrations. Naturally occurring potassium-40 was used as an intrinsic reference point for the samples.

Beef. Near-site and control samples of locally raised beef were collected in 2000. These samples were analyzed for tritium, strontium-90, and cesium-137. Two samples of beef muscle tissue were collected from background locations and two from near-site locations. Individual concentrations of measured radionuclides in near-site samples were either below detection limits or not statistically different from concentrations at control locations. (See Table F-2 [p.F-4].)

Venison. Meat samples from three near-site and three control deer were collected during the fall of 2000. (See Table F-2 [p.F-4].) These samples were measured for tritium, strontium-90, cesium-137, and other gamma-emitting radionuclides. Individual concentrations of measured radionuclides in near-site venison

samples were either below detection limits or not statistically different from concentrations at control locations.

Produce (corn, beans, and apples). Near-site and background samples of corn, beans, and apples were collected during 2000 and analyzed for tritium, potassium-40, cobalt-60, strontium-90, and cesium-137. (See Appendix F, Table F-3 [p.F-5].) Individual concentrations of all the measured radionuclides in near-site produce samples were either below detection limits or not statistically different from concentrations at control locations.


See Appendix B (pp.B-37 through B-40) for the locations from which background biological samples are collected.

Predicted Dose from All Pathways

The potential dose to the public from both airborne and liquid effluents released from the Project during 2000 is the sum of the individual dose contributions. The calculated maximum EDE from all pathways to a nearby resident was 0.061 mrem (0.00061 mSv). This dose is approximately 0.061% of the 100 mrem (1 mSv) annual limit in DOE Order 5400.5. The estimated dose from radon-220 to the same nearby resident was approximately 0.03 mrem.

The total collective EDE to the population within 80 kilometers (50 mi) of the site was 0.22 person-rem (0.0022 person-Sv), with an average EDE of 0.00016 mrem (0.0000016 mSv) per individual. The estimated radon-220 dose to the population was approximately 0.25 person-rem.

Table 4-2 (p.4-6) summarizes the dose contributions from all pathways and compares the in-



dividual doses with the applicable standards. The low doses calculated using computer modeling are corroborated by the low or non-detectable doses calculated from local foodstuff test data. Table 4-3 (p.4-15) provides a summary of WVDP releases and calculated doses.

Figure 4-2 (*above*) shows the calculated annual dose to the hypothetical maximally exposed individual over the last thirteen years. The estimated dose for 2000 (0.061 mrem) is lower than the annual dose reported for 1999 (0.065). The slight decrease in dose fraction from air emissions in 2000 is attributed to the decrease in iodine-129 emissions. The increased dose from the liquid pathway is the result of a combined increase in strontium-90 released from the north plateau drainage and releases from the water treatment system. This small increase reflects the continuing effect of the migration of the gross beta plume. (See Special Ground-water Monitoring in Chapter 3, p.3-16.)

Figure 4-3 (p.4-14) shows the collective dose to the population over the last eleven years. (See Fig. A-13 [p.A-15] for a map of the population sectors.) A five-year upward trend, primarily

from an increase in vitrification activities, reversed in 1998 and then in 1999 and 2000 continued down towards previtrification levels.


A slight upward trend (less than 5%) in dose from treated liquid effluents, directly linked to a noticeable increase in the volume of water treated, continued in 2000.

The overall radioactivity represented by these data confirm the continued inconsequential addition to the natural background radiation dose that the individuals and population around the WVDP receive from Project activities.

No off-site unplanned releases of radioactive materials in air or liquid effluents were identified or reported in 2000.

Risk Assessment

Estimates of cancer risk from ionizing radiation have been presented by the National Council on Radiation Protection and Measurements (1987) and the National Research Council's Committee on Biological Effects of Ionizing Radiation (1990).



These reports estimate that the probability of fatal cancer induction to the public, averaged over all ages, ranges from 0.0001 to 0.0005 cancer fatalities/rem. The most recent risk coefficient of 0.0005 (International Commission on Radiological Protection 1991) was used to estimate risk to a maximally exposed off-site individual. The resulting estimated risk to this hypothetical individual from airborne and waterborne releases was a 0.000000031 probability of a cancer fatality (1 chance in 32 million). This risk is well below the range of 0.000001 to 0.00001 per year considered by the International Commission on Radiological Protection in Report 26 (1977) to be a reasonable level of risk for any individual member of the public.

active materials and dose to individual members of the public. The collective population dose also was assessed and found to be orders of magnitude below the natural background radiation dose. Based on the overall dose assessment, the WVDP was found to be in compliance with applicable effluent radiological guidelines and standards during calendar year 2000.

Summary

Predictive computer modeling of airborne and waterborne releases resulted in estimated hypothetical doses to the maximally exposed individual that were orders of magnitude below all applicable EPA standards and DOE Orders, which place limitations on the release of radio-

Table 4-3
WVDP Radiological Dose and Release Summary

WVDP Radiological Dose Reporting Table CY 2000

Dose to the Maximally Exposed Individual		% of DOE 100-mrem limit	Estimated Population Dose		Population within 80 km 2000 projection	Estimated Natural Radiation Population Dose
0.061 <i>mrem</i>	0.00061 <i>(mSv)</i>	0.061	0.22 <i>person-rem</i>	0.0022 <i>(person-Sv)</i>	1,350,000	398,000 <i>person-rem</i>

WVDP Radiological Atmospheric Releases⁺ CY 2000 in curies (Bq)

Tritium	Kr-85	Noble Gases ($T_{1/2} < 40$ dy)	Short-lived Fission and Activation Products ($T_{1/2} < 3$ hr)	Fission and Activation Products ($T_{1/2} > 3$ hr)	Total Radioiodine	Total Radiostrontium	Total Uranium*	Total Plutonium	Total Other Actinides	Other (Rn-220)
5.08E-03 (1.88E+ 08)	NA	NA	NA	1.68E-05 (6.23E+ 05)	1.26E-03 (4.68E+ 07)	7.10E-06 (2.63E+ 05)	2.00E-07 (7.42E+ 03)	2.98E-07 (1.10E+ 04)	4.27E-07 (1.58E+ 04)	2.72E+ 03 (1.01E+ 14)

WVDP Liquid Effluent Releases⁺ of Radionuclide Material CY 2000 in curies (Bq)

Tritium	Fission and Activation Products ($T_{1/2} > 3$ hr)	Total Radioiodine	Total Radiostrontium	Total Uranium**	Total Plutonium	Total Other Actinides
1.39E-01 (5.16E+ 09)	1.05E-02 (3.88E+ 08)	1.47E-04 (5.44E+ 06)	5.79E-03 (2.14E+ 08)	1.08E-03 (4.00E+ 07)	8.77E-06 (3.24E+ 05)	1.84E-05 (6.80E+ 05)

+ The WVDP air and water releases are from point sources and controlled liquid effluent releases, respectively.

* Total uranium (grams) = 3.04E-01

** Total uranium (grams) = 5.49E+ 02

Note: These tables have been included to provide a standardized format for data collected from all Department of Energy sites.

QUALITY ASSURANCE

The quality assurance (QA) program at the West Valley Demonstration Project (WVDP) provides for and documents consistency, precision, and accuracy in collecting and analyzing environmental samples and in interpreting and reporting environmental monitoring data.

Organizational Responsibilities

West Valley Nuclear Services Company (WVNS) is contractually obligated to implement a nuclear quality assurance program at the WVDP. Managers of programs, projects, and tasks are responsible for determining and documenting the applicability of quality assurance requirements to their activities and for implementing those requirements. For example, Environmental Laboratory management and staff are directly responsible for carrying out sampling and analytical activities in a manner consistent with good quality assurance practices and for following approved procedures.

Program Design

The quality assurance rule 10 CFR Part 830.120, Quality Assurance (U.S. Department

of Energy [DOE]), and DOE Order 414.1A, Quality Assurance (U.S. Department of Energy 1999) provide the quality assurance program policies and requirements applicable to activities at the WVDP.

The integrated quality assurance program applicable to environmental monitoring at the WVDP also incorporates requirements from Quality Assurance Program Requirements for Nuclear Facilities (American Society of Mechanical Engineers [ASME NQA-1] 1989) and Specifications and Guidelines for Quality Systems for Environmental Data Collection and Environmental Technology Programs (American National Standards Institute and American Society for Quality Control [ANSI/ASQC E4-1994] 1994).

The quality assurance program focuses upon assigning responsibilities and upon thorough planning, specification, control, and documentation of all aspects of an activity in order to ensure the quality of both radiological and non-radiological monitoring data. The quality assurance program includes requirements in the following areas:

✓ Responsibility. Responsibilities involving overseeing, managing, and conducting an activity must be clearly defined. Personnel who verify that the activity has been completed correctly must be independent of those who performed it.

✓ Planning. An activity must be planned beforehand and the plan followed. All activities must be documented. Similarly, purchases of any equipment or items must be planned, specified precisely, and verified for correctness upon receipt.

✓ Control of design, procedures, items, and documents. Any activity, equipment, or construction must be clearly described or defined and tested, and changes in the design must be tested and documented. Procedures must clearly state how activities will be conducted. Only approved procedures may be used. Equipment or particular items affecting the quality of environmental data must be identified, inspected, calibrated, and tested before use. Calibration status must be clearly indicated. Items that do not conform to requirements must be identified and separated from other items and the nonconformity documented.

✓ Documentation. Records of all activities must be kept in order to verify what was done and by whom. Records must be clearly traceable to an item or activity.

✓ Corrective action. If a problem should arise the cause of the problem must be identified, a corrective action planned, responsibility assigned, and the problem remedied.

✓ Audits. Scheduled audits and assessments must be conducted to verify compliance with all aspects of the quality assurance program and determine its effectiveness.

Subcontractor laboratories providing analytical services for the environmental monitoring program are contractually required to maintain a quality assurance program consistent with WVDP requirements.

Procedures

Those activities that affect the quality of environmental monitoring data are conducted according to approved procedures that clearly describe how the activity should be performed and what precautions are to be taken in connection with the activity. Any person performing an activity that could affect the quality of environmental monitoring data is trained in that procedure and must demonstrate proficiency.

New procedures are developed each time an activity is added to the monitoring program. Procedures are reviewed periodically and updated when necessary. Documents are controlled so that only current procedures are used.

Quality Control in the Field

Quality control (QC), an integral component of environmental monitoring quality assurance, is a way of verifying that samples are being collected and analyzed according to established quality assurance procedures. Quality control ensures that sample collection and analysis are consistent and repeatable and is a means of tracking down possible sources of error. For example, sample locations at the WVDP are clearly marked in the field to ensure that future samples are collected in the same locations; collection equipment in place in the field is routinely inspected, calibrated, and maintained; and automated sampling stations are kept locked to prevent tampering and to ensure sample integrity. Samples are collected into certified pre-cleaned containers of an appropriate material

and capacity and are labeled immediately with the pertinent information. Date, time, person doing the collecting, and special field sampling conditions are recorded and kept as part of the record for that sample.

Chain-of-custody protocols are followed to ensure that samples are controlled and tracked for traceability. If necessary, samples are preserved as soon as possible after collection.

In order to assess quality problems that might be introduced by the sampling process, duplicate field samples, field blank samples, and trip blank samples are collected. Background samples are collected for baseline environmental information.

Field Duplicates. Field duplicates are samples collected simultaneously for the same analyte at one location, after which they are treated as separate samples. If the sampling matrix is homogeneous, field duplicates provide a means of assessing the precision of collection methods. Field duplicates are collected at a minimum rate of one per twenty analyses.

Field Blanks. A field blank is a sample of laboratory-distilled water that is put into a sample container at a field collection site and is processed from that point as a routine sample. Field blanks are used to detect contamination introduced by the sampling procedure. They are processed at a minimum rate of one per twenty analyses.

If the same collection equipment is used for more than one site, a special form of field blank known as an equipment blank may be collected by pouring laboratory-distilled water through cleaned collecting equipment and into a sample container. Equipment blanks are collected to detect any cross-contamination that

may be passed from one sampling location to another by the equipment. Many wells and surface water collection stations have dedicated collecting equipment that remains at that location; equipment blanks are not necessary at these locations.

Trip Blanks. Trip blanks are prepared by pouring laboratory-distilled water into sample bottles in the laboratory. The bottles are then placed into sample coolers where they remain throughout the sampling event. Trip blanks are collected in order to detect any volatile organic contamination that may be introduced from handling during collection, storage, or shipping. Trip blanks are prepared once per day when volatile organic samples are being collected.

Environmental Background Samples. To monitor each pathway for possible radiological contamination, samples of air, water, vegetation, meat, and milk are taken from locations remote from the site for comparison with samples from near-site locations. Samples that are clearly outside site influence show ambient radiological concentrations and serve as backgrounds or “controls,” another form of field quality control sample. Background samples provide baseline information to compare with information from near-site or on-site samples so that site influences can be evaluated.

Quality Control in the Laboratory

More than 10,000 samples were handled as part of site monitoring in 2000. Samples for routine radiological analysis were analyzed on-site, with the rest being sent to subcontract laboratories.

Off-site, subcontract laboratories must maintain a level of quality control as specified in

contracts with WVNS and are required to participate in all applicable crosscheck programs and to maintain all relevant certifications.

In order to monitor the accuracy and precision of data, laboratory quality control practices specific to each analytical method are clearly described in approved references or procedures. Examples of laboratory quality control activities at the WVDP include proper training of analysts, maintaining and calibrating measuring equipment and instrumentation, and processing samples in accordance with specific methods as a means of monitoring laboratory performance.

Analytical instruments and counting systems are calibrated at specified frequencies, and logs of instrument calibration and maintenance are kept. Calibration methods for each instrument are specified in procedures or in manufacturers' directions. Standards traceable to the National Institute of Standards and Technology (NIST) are used to calibrate counting and test instrumentation.

Laboratory quality control samples consist of three general types: standards (including spikes), used to assess accuracy; blanks, to assess the possibility of contamination; and duplicates, to assess precision.

Standards. Laboratory standards are materials containing known concentrations of an analyte of interest such as a pH buffer or a plutonium-239 counting standard. Standards used at the WVDP for environmental monitoring activities are either NIST-traceable or reference materials from other nationally recognized sources.

At a minimum, one reference standard is analyzed for every twenty sample analyses. The results of the analyses are plotted on control

charts, which specify acceptable limits. If the results lie within these limits, then analysis of actual environmental samples may proceed and the results are deemed usable.

Spikes. Another form of standard analysis is a laboratory spike. In a laboratory spike, a known amount of analyte is added to a sample or blank before the sample is analyzed. The percent recovery of the analyte indicates how much of the analyte of interest is being detected in the analysis of actual samples; hence, a spike also is an assessment of the accuracy of the method. Spike recoveries are recorded on control charts with documented acceptance limits.

Blanks. Laboratory blanks are prepared from a matrix similar to that of the sample but known to contain none of the analyte of interest. For instance, distilled water, taken through the same preparatory procedure as a sample, may serve as a laboratory blank for both radiological and chemical analyses of water samples. A positive result for an analyte in a blank indicates that something is wrong with the analysis and that corrective action should be taken. In general, one laboratory blank is processed daily or with each batch of samples for a given analyte.

A special form of laboratory blank for radiological samples is an instrument background count, which is a count taken of a planchet or vial containing no sample. The count serves three purposes: to determine if contamination is present in the counting instrument; to determine if the instrument is responding in an acceptable manner; and to determine the background correction that should be applied when calculating radiological activity in certain samples.

Environmental samples containing little or no radioactivity must be measured with very sensitive instruments. For example, gross alpha and

gross beta measurements must be made with a low-background proportional counter. An instrument background count is taken before each day's counting or with each batch of twenty samples. Background counts are recorded on control charts with defined acceptance limits. An unacceptable count requires corrective action before analyses can proceed.

Duplicates. Duplicates are analyzed to assess precision in the analytical process. Laboratory duplicates are created by splitting existing samples before analysis; each split is treated as a separate sample. If the analytical process is in control, results for each split should be within documented acceptance criteria.

Crosschecks. WVNS participates in a formal radiological crosscheck program conducted by the U.S. Department of Energy (DOE). The DOE recommends that all organizations performing effluent or environmental monitoring participate in the semiannual Environmental Measurements Laboratory (EML) Quality Assessment Program (QAP). This program is designed to test the quality of environmental measurements being reported to the DOE by its contractors.

An informal crosscheck program uses results from samples of air filters, water, milk, fish, vegetation, and sediments that have been split or separately collected and sent to the New York State Department of Health (NYSDOH) for independent measurement. (Co-located samples are listed in Appendix B of this report.) Results from NYSDOH are compared with WVDP results as an independent verification of environmental monitoring program data.

Crosscheck samples for radiological analyses are analyzed by both the Environmental Laboratory on-site and by the subcontract laboratory. Results from radiological crosschecks are

summarized in Appendix J, Tables J-1 and J-2 (pp. J-3 through J-6). A total of 120 radiological crosscheck analyses were performed by or for the WVDP and reported in 2000. One hundred fifteen results (95.8%) were within control limits. Twenty-five of the results were produced by the on-site Environmental Laboratory; 100% were within control limits.

Two nonradiological crosscheck samples (from Environmental Research Associates) for the National Pollutant Discharge Elimination System (NPDES) Discharge Monitoring Report-Quality Assurance Study #20 were analyzed for pH and residual chlorine by the WVDP wastewater facility laboratory. Twenty crosscheck samples provided by NYSDOH for additional parameters were analyzed by an off-site vendor laboratory. Nonradiological crosscheck results are summarized in Appendix J, Table J-3 (p. J-7).

Results from both crosschecks analyzed at the WVDP were within acceptance limits (100%). Of the twenty-one results reported by the vendor laboratory, eighteen were within acceptance limits (85.7%), for a combined 87.0% in control.

WVNS subcontracted laboratories are required to perform satisfactorily on crosschecks, defined as 80% of results falling within control limits. Crosscheck results that fall outside control limits are addressed by formal corrective actions in order to determine any conditions that could adversely affect sample data and to ensure that actual sample results are reliable.

Personnel Training

Anyone performing environmental monitoring program activities is trained in the appropriate procedures and qualified accordingly before carrying out the activity as part of the site environmental monitoring program.

Record Keeping

Control of records is an integral part of the environmental monitoring program. Field data sheets, chain-of-custody forms, requests for analysis, sample-shipping documents, sample logs, bench logs, laboratory data sheets, equipment maintenance logs, calibration logs, training records, crosscheck performance records, data packages, and weather measurements, in addition to other records, are maintained as documentation of the environmental monitoring program. All records pertaining to the program are routinely reviewed and securely stored.

A Laboratory Information Management System (LIMS) is used to log samples, print labels, store and process data, track quality control samples, track samples, produce sampling and analytical worklists, and generate reports. Subcontract laboratories, where possible, provide data in electronic form for direct entry into the LIMS.

Chain-of-Custody Procedures

Chain-of-custody records begin with sample collection. Samples brought in from the field are transferred under signature from the sampler to the sample custodian and are logged at the sample receiving station, after which they are stored in a sample lockup before analysis or shipping. Samples sent off-site for analysis are accompanied by an additional chain-of-custody/analytical request form. Subcontract laboratories are required by contract to maintain internal chain-of-custody records and to store the samples under secure conditions.

Audits and Appraisals

In 2000 the WVNS Quality Assurance and Environmental Affairs departments conducted

audits, assessments, surveillances, and inspections. Some of the areas examined were the operation of the Environmental Laboratory fume hoods, testing of the hydraulic conductivity of groundwater, the calibration status of materials and testing equipment, activities pertaining to the discovery of mercury in samples from the liquid waste treatment system, compliance with requirements for stack monitoring, monitoring for nitrogen oxides (NO_x), and packaging of samples being shipped for radiological analysis.

The DOE's Ohio Field Office conducted a surveillance of the WVDP environmental monitoring program in November 2000 and reviewed sampling of ambient air for particulate radioactivity and collection of composite samples from off-site surface waters. Procedures for transferring samples from field personnel to laboratory personnel and maintenance of the chain-of-custody were reviewed. The activities reviewed were found to be in compliance with applicable requirements.

The New York State Department of Environmental Conservation (NYSDEC) inspected the site for compliance with RCRA and SPDES, and the Cattaraugus County Health Department inspected the potable water supply system. No deficiencies were noted. (See also Project Assessment Activities in 2000 [p. ECS-18] in the Environmental Compliance Summary.)

Any corrective actions generated as a result of internal or external program reviews are addressed and tracked to closure.

Self-Assessments

Routine self-assessments of the environmental monitoring program were conducted in 2000. The primary topics addressed by the assess-

ments were compliance with sampling requirements pertaining to the environmental monitoring program; compliance with quality assurance requirements pertaining to the environmental monitoring program; implementation of conduct of operations principles for field activities; and safe practices for using on-site and off-site monitoring and sampling equipment.

No findings were noted, although one observation and several comments regarding possible program improvements were noted and corrective actions were scheduled and implemented. Several good practices were identified. Nothing was found during the course of these routine self-assessments that would compromise the program in general or the data in this report.

Lessons Learned Program

Information from audits, appraisals, and self-assessments are shared with other departments through the WVDP Lessons Learned Program. The WVDP maintains this system in order to identify, document, disseminate, and use this information to improve the safety, efficiency, and effectiveness of all WVNS operations.

Data Management and Data Validation

Information about environmental monitoring program samples is maintained and tracked in the LIMS and includes date and time of collection, chain-of-custody transfer, shipping information, analytical results, and final validation status.

All software used to generate data is verified and validated before use. All analytical data produced in the Environmental Laboratory at the bench level are reviewed and signed off by a qualified person other than the one who per-

formed the analysis. A similar in-house review is contractually required from subcontractor laboratories.

Analytical data from both on- and off-site laboratories are formally validated by the data validation group. As part of the validation procedure, quality control samples analyzed in conjunction with a batch of samples are checked for acceptability. After validation is complete and transcription between hard copy and the LIMS is verified, the sample result is formally approved and released for use in reports.

Data Assessment and Reporting

Radiological and nonradiological data from the environmental monitoring program are evaluated in order to assess the effect, if any, of the site on the environment and the public. Data from each sampling location are compared to applicable standards or background measurements.

- Radiological concentrations in liquid effluent releases or air emissions are compared with DOE derived concentration guides (DCGs) for release of water or air to an unrestricted environment. DCGs for specific radionuclides are listed in Table K-1 (p.K-3).
- Calculated doses from air emissions are compared with National Emissions Standards for Hazardous Air Pollutants (NESHAP) limits.
- Nonradiological releases from liquid effluents covered by the SPDES permit are compared with the limits specified in the permit. (See Table G-1 [pp.G-3 and G-4].)
- Near-site radiological results are compared to results from background locations far from the site.

- Results from surface waters downgradient of the site are compared with results from upgradient locations.

Standard statistical methods are used to compare the data. Where possible, the underlying distribution of the data set is assessed before determining the appropriate statistical tests to be used.

Once the data have been evaluated reports are prepared. Calculations summarizing the data, e.g., summing the total curies released from an effluent point, averaging the annual concentration of a radionuclide at a monitoring point, or pooling confidence intervals from a series of measurements, are made in accordance with formally approved procedures. Final data are reported as described elsewhere in this report. (See Data Reporting [p.1-5] and the section on Scientific Notation at the back of this report.)

Before each technical report is issued, the document, including the data, is comprehensively reviewed by one or more persons who are knowledgeable in the necessary technical aspects of the field of work.

Summary

The multiple levels of scrutiny built into generating, validating, evaluating, and reporting data from the environmental monitoring program ensure that reliable data are reported. The quality assurance elements described in this chapter ensure that environmental monitoring data are consistent, precise, and accurate. The effectiveness of the monitoring program is evidenced by continuing favorable quality assurance assessments.

Appendix A

Maps





Figure A-1. Project Base Map.






Figure A-3. Off-site Surface Water and Soil/Sediment Sampling Locations.




Figure A-4. On-site Air Monitoring and Sampling Points.




Figure A-5. Off-site Air and Fallout Sampling Points.
A-7




Figure A-6. Active WVDP Groundwater Monitoring Points.




Figure A-7. North Plateau On-Site Groundwater Monitoring Network.
(Includes wells used for water-level measurements)





Figure A-8. South Plateau On-Site Groundwater Monitoring Network.
(Includes wells used for water-level measurements)
A-10






Figure A-10. Location of On-site Thermoluminescent Dosimeters (TLDs).





Figure A-11. Location of Off-site Thermoluminescent Dosimeters (TLDs).
A-13



REF. NYSDOT, New York State Map — West Sheet.
1:250,000, Revised 1982

Figure A-12. Environmental Sample Points more than 5 kilometers from the WVDP Site.




Figure A-13. Projected 2000 Census Population by Sector Within 80 Kilometers of the Site.

Appendix B

2000 Environmental Monitoring Program



***The WVDP Supports a Bluebird and Wood Duck Nesting-box Program
Sponsored by the Springville Field and Stream Club***

2000 Environmental Monitoring Program

The following schedule represents the West Valley Demonstration Project (WVDP) routine environmental monitoring program for 2000. This schedule met or exceeded the minimum program specifications needed to satisfy the requirements of DOE Order 5400.1. It also met the requirements of DOE 5400.5 and DOE/EH-0173T. Specific methods and recommended monitoring program elements are found in DOE/EP-0096, *A Guide for Effluent Radiological Measurements at DOE Installations*, and DOE/EP-0023, *A Guide for Environmental Radiological Surveillance at U.S. Department of Energy Installations*, which were the bases for selecting most of the schedule specifics. Additional monitoring was mandated by air and water discharge permits (40 CFR 61 and SPDES), which also required formal reports. Specifics are identified in the schedule under Monitoring/Reporting Requirements.

A computerized environmental data-screening system identifies analytical data that exceed pre-set limits. All locations are checked monthly for trends or notable results in accordance with criteria established in Documentation and Reporting of Environmental Monitoring Data (West Valley Nuclear Services Co., Inc. August 19, 1998). Reportable results are then described in a monthly trend analysis report together with possible causes and corrective actions, if indicated. A WVDP effluent summary report is transmitted with each monthly trend analysis report.

Schedule of Environmental Sampling

The index on pages B-v through B-vii is a list of the codes used to identify the various sampling locations, which are shown on Figures A-1 through A-12 (pp.A-3 through A-14 in Appendix A). The schedule of environmental sampling at the WVDP is found in this appendix on pages B-1 through B-44. Table headings in the schedule are as follows:

- ***Sample Location Code.*** Describes the physical location where the sample is collected. The code consists of seven or eight characters: The first character identifies the sample medium as **A**ir, **W**ater, **S**oil/**S**ediment, **B**iological, or **D**irect Measurement. The second character specifies **o**n-site or **o**ff-site. The remaining characters describe the specific location (e.g., **AFGRVAL** is **A**ir **o**ff-site at **G**reat **V**ALley). Distances noted at sampling locations are as measured in a straight line from the main stack on-site.
- ***Monitoring/Reporting Requirements.*** Notes the bases for monitoring the location, any additional references to permits, and the reports that are generated from the sample data. Routine reports cited in this appendix are the Effluent Summary Report (ESR), the Monthly Trend Analysis Report (MTAR), the Air Emissions Report (NESHAP), and the annual Site Environmental Report (SER).
- ***Sampling Type/Medium.*** Describes the collection method and the physical characteristics of the medium.
- ***Collection Frequency.*** Indicates how often the samples are collected or retrieved.
- ***Total Annual Sample Collections.*** Specifies the number of discrete physical samples collected annually for each group of analytes.
- ***Analyses Performed/Composite Frequency.*** Notes the type of analyses of the samples taken at each collection, the frequency of composite, and the analytes determined for the composite samples.

Summary of Monitoring Program Changes in 2000

Location Code

Description of Changes

WNDNKUR

The following analyses of the annual sample were added: beryllium, nickel, antimony, thallium, and cyanide. The annual sample for nitrate is now being collected by the Cattaraugus County Health Department.

WNWSP02
WNWSP05
WNWSP18
WNWSP23

These seepage monitoring points were deleted from the program in 2000.

Index of Environmental Monitoring Program Sample Points

Air Effluent and On-site Ambient Air (Fig. A-4 [p. A-6])

ANSTACK	Main Plant	B-1
ANSTSTK	Supernatant Treatment System	B-1
ANCSSTK	01-14 Building	B-1
ANCSRFK	Size-reduction Facility	B-1
ANCSPFK	Container Sorting and Packaging Facility	B-1
ANVITSK	Vitrification Heating, Ventilation, and Air Conditioning Exhaust	B-1
ANSEISK	Seismic Sampler (Vitrification backup)	B-1
OVEs/PVUs	Outdoor Ventilated Enclosures/Portable Ventilation Units*	B-3
ANLLW2V	Low-level Waste Treatment Ventilation	B-5
ANLLWTVH	Low-level Waste Treatment Ventilation (radioactive operations)	B-5
ANLAUNV	Contaminated Clothing Laundry Ventilation	B-5
ANLAGAM	Lag Storage Area (ambient air)	B-5
ANNDAAAM	NDA Area (ambient air)	B-5
ANSDAT9	SDA Trench 9 (ambient air)	B-5

Liquid Effluent and On-site Water (Figs. A-2 [p. A-4], A-3 [p.A-5], and A-12 [p. A-14])

WNSP001	Lagoon 3 Weir Point	B-7
WNSP006	Facility Main Drainage	B-9
WNURRAW	Utility Room Raw Water*	B-9
WNSP007	Sanitary Waste Discharge	B-9
WNSWAMP	Northeast Swamp Drainage Point	B-11
WNSW74A	North Swamp Drainage Point	B-11
WN8D1DR	Waste Farm Underdrain	B-11
WNSDADR	SDA Run-off	B-11
WNSP008	French Drain LLWTF Area	B-13
WNSP005	South Facility Drainage	B-13
WNCoolW	Cooling Tower	B-13
WNFRC67	Frank's Creek East	B-15
WNERB53	Erdman Brook	B-15
WNNADR	Disposal Area Drainage	B-15
WNDCELD	Drum Cell Drainage	B-15
WNNATR	NDA Trench Interceptor Project	B-15
WNSTAW Series	Standing Water	B-17
WNDNK Series	Site Potable Water*	B-19

* Not detailed on map

Index of Environmental Monitoring Program Sample Points

(continued)

On-site Groundwater and Seeps (Figs. A-7 and A-8 [pp.A-9 and A-10])

SSWMU #1	Low-level Waste Treatment Facility Wells	B-21
SSWMU #2	Miscellaneous Small Units Wells	B-21
SSWMU #3	Liquid Waste Treatment System Wells	B-21
SSWMU #4	HLW Storage and Processing Tank Wells	B-23
SSWMU #5	Maintenance Shop Leach Field Wells	B-23
SSWMU #6	Low-level Waste Storage Area Wells	B-23
SSWMU #7	CPC Waste Storage Area Wells	B-23
SSWMU #8	CDDL Wells	B-25
SSWMU #9	NDA Unit Wells and NDATR	B-25
SSWMU #10	IRTS Drum Cell Wells	B-25
SSWMU #11	SDA Unit Wells	B-27
North Plateau Seeps	Northeastern Edge of North Plateau	B-27
Well Points	Downgradient of Main Plant	B-27
WNWNB1S	Former North Plateau Background Well	B-27

Off-site Surface Water (Fig. A-3 [p.A-5])

WFBCTCB	Buttermilk Creek at Thomas Corners	B-29
WFFELBR	Cattaraugus Creek at Felton Bridge	B-29
WFBCBKG	Buttermilk Creek near Fox Valley (background)	B-29
WFBIGBR	Cattaraugus Creek at Bigelow Bridge (background)	B-29

Off-site Drinking Water (Figs. A-9 and A-12 [pp.A-11 and A-14])

WFWEL Series	Private Local Wells	B-31
--------------	---------------------	------

Off-site Ambient Air (Figs. A-5 and A-12 [pp. A-7 and A-14])

AFFXVRD	Fox Valley Sampler	B-33
AFTCORD	Thomas Corners Sampler	B-33
AFRT240	Route 240 Sampler	B-33
AFSPRVL	Springville Sampler	B-33
AFWEVAL	West Valley Sampler	B-33
AFNASHV	Nashville Sampler (background)	B-33
AFBOEHN	Dutch Hill Road Sampler	B-33
AFRSPRD	Rock Springs Road Sampler	B-33
AFGRVAL	Great Valley Sampler (background)	B-33
AFBLKST	Bulk Storage Warehouse Sampler	B-33

Index of Environmental Monitoring Program Sample Points (concluded)

Fallout, Sediment, and Soil (Figs. A-2 through A-5 [pp. A-4 through A-7] and A-12 [p. A-14])

AFDHFOP	Dutch Hill Fallout	B-35
AFFXFOP	Fox Valley Fallout	B-35
AFTCFOP	Thomas Corners Fallout	B-35
AF24FOP	Route 240 Fallout	B-35
ANRGFOP	Rain Gauge Fallout	B-35
SF Soil Series	Air Sampler Area Soil	B-35
SFCCSED	Cattaraugus Creek at Felton Bridge, Sediment	B-35
SFSDSED	Cattaraugus Creek at Springville Dam, Sediment	B-35
SFBISED	Cattaraugus Creek at Bigelow Bridge, Background Sediment	B-35
SFTCSSED	Buttermilk Creek at Thomas Corners, Sediment	B-35
SFBCESED	Buttermilk Creek at Fox Valley Road, Background Sediment	B-35
SN Soil Series:	On-site Soils/Sediments	B-35
SNSW74A		
SNSWAMP		
SNSP006		

Off-site Biological (Figs. A-9 and A-12 [pp. A-11 and A-14])

BFFCATC	Cattaraugus Creek Fish, Downstream	B-37
BFFCATD	Cattaraugus Creek Fish, Downstream of Springville Dam	B-37
BFFCTRL	Cattaraugus Creek Fish, Background	B-37
BFMREED	NNW Milk	B-37
BFMCOBO	WNW Milk	B-37
BFMCTLS	Milk, South, Background	B-37
BFMCTLN	Milk, North, Background	B-37
BFMWIDR	Southeast Milk, Near-site	B-37
BFMSCHT	South Milk, Near-site	B-37
BFVNEAR	Produce, Near-site	B-39
BFVCTRL	Produce, Background	B-39
BFHNEAR	Forage, Near-site	B-39
BFHCTLS	Forage, South, Background	B-39
BFHCTLN	Forage, North, Background	B-39
BFBNEAR	Beef, Near-site	B-39
BFBCTRL	Beef, Background	B-39
BFDNEAR	Venison, Near-site	B-39
BFDCTRL	Venison, Background	B-39

Direct Measurement Dosimetry (Figs. A-10 through A-12 [pp. A-12 through A-14])

DFTLD Series	Off-site Direct Radiation	B-41
DNTLD Series	On-site Direct Radiation	B-43

2000 Monitoring Program On-site Effluent Monitoring

Air Effluents

Sample Location Code	Monitoring/Reporting Requirements	Sampling Type/Medium	Collection Frequency	Total Annual Sample Collections	Analyses Performed/Composite Frequency
ANSTACK <i>Main Plant Ventilation Exhaust Stack</i>	Airborne radioactive effluent points, including the LWTS and vitrification off-gas Required by: • 40 CFR 61 Reported in: • ESR • MTAR • SER • Air Emissions Annual Report (NESHAP)	Continuous off-line air particulate monitors	→ Continuous measurement of fixed filter; replaced weekly	→ NA	→ Real-time alpha and beta monitoring
ANSTSTK <i>Supernatant Treatment System (STS) Ventilation Exhaust</i>		Continuous off-line air particulate filters	→ Weekly	→ 52 each location Weekly filters composited to 4 each location	→ Gross alpha/beta, gamma isotopic* → Quarterly composites for Sr-90, U-232, U-233/234, U-235/236, U-238, total U, Pu-238, Pu-239/240, Am-241, gamma isotopic
ANCSSTK <i>01-14 Building Ventilation Exhaust</i>					
ANCSRFK <i>Contact Size-reduction Facility Exhaust</i>		Continuous off-line desiccant columns for water vapor collection	→ Weekly	→ 52 at each of two locations	→ H-3 (ANSTACK and ANSTSTK only)
ANCSPFK <i>Container Sorting and Packaging Facility Exhaust</i>		Continuous off-line charcoal cartridges	→ Weekly	→ Weekly cartridges composited to 4 each location	→ Quarterly composite for I-129
ANVITSK <i>Vitrification HVAC Exhaust</i>					
ANSEISK <i>Seismic Sampler, Vitrification Backup</i>	Airborne radioactive effluent point Required by: • 40 CFR 61 Reported in: • ESR • MTAR • SER	Continuous off-line air particulate filter	→ Weekly	→ 52	→ Filters for gross alpha/beta, gamma isotopic* upon collection

* Weekly gamma isotopic only if gross activity rises significantly.
 NA Not applicable.

Sampling Rationale

ANSTACK DOE/EH-0173T, 3.0; DOE/EP-0096, 3.3

Monitors and samples HEPA-filtered ventilation from most process areas, including cell ventilation, vessel off-gas, fuel receiving and storage (FRS), head end ventilation, and an analytical aisle. Requires continuous effluent monitoring per 40 CFR Subpart H, Section 61.93(b) because potential emissions may exceed the 0.1 mrem limit.

ANSTSTK DOE/EH-0173T, 3.0; DOE/EP-0096, 3.3

Monitors and samples HEPA-filtered ventilation from building areas involved in treatment of high-level waste supernatant. Requires continuous effluent monitoring per 40 CFR Subpart H, Section 61.93(b) because potential emissions may exceed the 0.1 mrem limit.

ANCSSTK DOE/EH-0173T, 3.0; DOE-EP-0096, 3.3

Monitors and samples HEPA-filtered ventilation from the 01-14 building, which houses equipment used to treat the ceramic melter off-gas. Requires effluent monitoring per 40 CFR Subpart H, Section 61.93(b) to confirm that emissions are less than the 0.1 mrem limit.

ANCSRFK DOE/EH-0173T, 3.0; DOE-EP-0096, 3.3

Monitors and samples HEPA-filtered ventilation from a process area where radioactive tanks, pipes, and other equipment are cut up with a plasma torch to reduce volume.

ANCSPFK DOE/EH-0173T, 3.0; DOE-EP-0096, 3.3

Monitors and samples ventilation from lag storage area 4, the container sorting and packaging facility.

ANVITSK DOE/EH-0173T, 3.0; DOE-EP-0096, 3.3

Vitrification facility heating, ventilation, and air conditioning (HVAC) effluent exhaust stack. Sampler brought on-line in late 1995 when nonradioactive operations began. Radioactive operation began with the first high-level waste transfer in June 1996 and vitrification startup in July 1996. Monitors and samples HEPA-filtered ventilation from building areas involved in treatment of high-level waste supernatant. Requires effluent monitoring per 40 CFR Subpart H, Section 61.93(b) because potential emissions may exceed the 0.1 mrem limit.

ANSEISK DOE/EH-0173T, 3.0; DOE-EP-0096, 3.3

Vitrification system back-up filter for catastrophic-event monitoring in case the primary vitrification HVAC stack ventilation fails.

■ Sampling locations are shown on Figure A-4 (p.A-6).

**2000 Monitoring Program
On-site Effluent Monitoring**

Air Effluents

Sample Location Code	Monitoring/Reporting Requirements	Sampling Type/Medium	Collection Frequency	Total Annual Sample Collections	Analyses Performed/Composite Frequency
OVes/PVUs <i>Outdoor Ventilated Enclosures/Portable Ventilation Units</i>	Airborne radioactive effluent points Required by: • 40 CFR 61 Reported in: • ESR • MTAR • SER • Air Emissions Annual Report (NESHAP)	Continuous off-line air particulate filter	→ As required	→ 1 each location	→ Filters for gross alpha/beta, gamma isotopic* upon collection
				Collected filters** composited to 4	→ Quarterly composites for Sr-90, U-232, U-233/234, U-235/236, U-238, total U, Pu-238, Pu-239/240, Am-241, gamma isotopic

* Gamma isotopic only if gross activity rises significantly.

** If gross determination of individual filter is significantly higher than background, the individual sample would be submitted immediately for isotopic analysis.

Sampling Rationale

OVes/PVUs DOE/EH-0173T, 3.0; DOE/EP-0096, 3.3

Outdoor ventilated enclosures; portable ventilation units used for handling radioactive materials or for decontamination in areas not having containment ventilation. Emissions are monitored to confirm that they are below the 0.1 mrem limit.

■ Sampling locations are not shown on figures.

2000 Monitoring Program On-site Effluent Monitoring

Air Effluents and On-site Ambient Air

Sample Location Code	Monitoring/Reporting Requirements	Sampling Type/Medium	Collection Frequency	Total Annual Sample Collections	Analyses Performed/Composite Frequency
ANLLW2V <i>Low-level Waste Treatment and Ventilation (new facility)</i>	Airborne radioactive effluent point Required by: <ul style="list-style-type: none"> • 40 CFR 61 	Continuous off-line air particulate filter	→ Quarterly	→ 4	Gross alpha/beta, gamma isotopic* upon collection
ANLLWTVH <i>Low-level Waste Treatment and Ventilation, "hot" side (former facility)</i>	Reported in: <ul style="list-style-type: none"> • ESR • MTAR • SER • Air Emissions Annual Report (NESHAP) 	Continuous off-line air particulate filter	→ Weekly	→ 52	
ANLAUNV <i>Laundry Change Room Ventilation</i>		Continuous off-line air particulate filter	→ Monthly	→ 12	
ANLAGAM <i>Lag Storage Area Ambient Air</i>	Ambient "diffuse source" air emissions Reported in: <ul style="list-style-type: none"> • MTAR • SER • Air Emissions Annual Report (NESHAP) 	Continuous air particulate filter	→ Weekly	→ 52 each location	→ Gross alpha/beta
ANNDAAAM <i>NDA Ambient Air</i>				Weekly filter composited to 4 each location	→ Quarterly composites for Sr-90, U-232, U-233/234, U-235/236, U-238, total U, Pu-238, Pu-239/240, Am-241, gamma isotopic
ANSDAT9** <i>SDA Trench 9 Ambient Air</i>	Ambient "diffuse source" air emissions Reported in: <ul style="list-style-type: none"> • MTAR • SER • Reported to NYSERDA 	Continuous air particulate filter	→ Weekly	→ 52	→ Gross alpha/beta
		Continuous off-line desiccant columns for water vapor	→ Weekly	→ 52	Weekly filter composited to 4 → Quarterly composite for gamma isotopic → H-3
		Continuous off-line charcoal cartridges	→ Monthly	→ Monthly cartridges composited to 4	→ Quarterly composite for I-129

* Gamma isotopic only if gross activity rises significantly.

** Sampling frequency and analytical parameters as directed by NYSERDA.

Sampling Rationale

ANLLW2V	DOE/EH-0173T, 3.0; DOE/EP-0096, 3.3 Samples ventilation exhaust from the new low-level waste treatment facility. System started up in April 1998.
ANLLWTVH	DOE/EH-0173T, 3.0; DOE/EP-0096, 3.3 Samples radioactive side of ventilation exhaust from the former low-level waste treatment facility.
ANLAUNV	DOE/EH-0173T, 3.0; DOE/EP-0096, 3.3 Samples ventilation from the contaminated clothing laundry.
ANLAGAM	DOE/EH-0173T, 3.3.2 Monitors ambient air in the lag storage area, a possible diffuse source of air emissions.
ANNDAAM	DOE/EH-0173T, 3.3.2 Monitors ambient air in the NDA area, a possible diffuse source of air emissions.
ANSDAT9	DOE/EH-0173T, 3.3.2 Monitors ambient air by SDA trench 9, a possible diffuse source of air emissions. WVDP support of NYSERDA.

■ Sampling locations are shown on Figure A-4 (p. A-6).

2000 Monitoring Program On-site Effluent Monitoring

Liquid Effluents

Sample Location Code	Monitoring/Reporting Requirements	Sampling Type/Medium	Collection Frequency	Total Annual Sample Collections	Analyses Performed/Composite Frequency
WNSP001 <i>Lagoon 3 Discharge Weir</i>	Primary point of liquid effluent batch release Required by: <ul style="list-style-type: none"> • SPDES permit Reported in: <ul style="list-style-type: none"> • Monthly SPDES DMR • ESR • MTAR • SER 	Grab liquid	→ Daily, during lagoon 3 discharge*	→ 24-56	→ Daily for gross beta, conductivity, flow
				4-10	→ Every 6 days a sample is analyzed for gross alpha/beta, H-3, Sr-90, gamma isotopic
				Composite of daily samples for each discharge, 4-8	→ Weighted composite for gross alpha/beta, H-3, C-14, Sr-90, Tc-99, I-129, gamma isotopic, U-232, U-233/234, U-235/236, U-238, total U, Pu-238, Pu-239/240, and Am-241 for each month of discharge
		Composite liquid	→ Twice during discharge, near start and near end	→ 8-16	→ Two 24-hour composites for BOD ₅ , suspended solids, SO ₄ , NO ₃ , NO ₂ , NH ₃ , total Al, Fe, and Mn, total recoverable Cd, Cr, Cu, Ni, Pb, and Zn, dissolved As and Cu, dissolved sulfide
		Grab liquid	→ Twice during discharge, near start and near end	→ 8-16	→ Settleable solids, total dissolved solids, pH, cyanide amenable to chlorination, oil & grease, surfactant (as LAS), total recoverable Co, Cr ⁺ 6, Se, and V, dichlorodifluoromethane, trichlorofluoromethane, 3,3-dichlorobenzidine, tributyl phosphate, hexachlorobenzene, alpha-BHC, heptachlor, xylene, 2-butanone
		Composite liquid	→ Semiannual	→ 2	→ A 24-hour composite for titanium
		Composite liquid	→ Annual	→ 1	→ A 24-hour composite for Ba and Sb
		Grab liquid	→ Semiannual	→ 2	→ Bis(2-ethylhexyl) phthalate, 4-dodecene
		Grab liquid	→ Annual	→ 1	→ Chloroform

* Lagoon 3 is discharged four to eight times per year, as necessary, averaging six to seven days per discharge.

Sampling Rationale

WNSP001

DOE 5400.5; DOE/EH-0173T, 2.3.3; SPDES permit no. NY0000973

By DOE Order all liquid effluent streams from DOE facilities shall be evaluated and their potential for release of radionuclides addressed.

These requirements for radiological parameters are met by daily grab sampling during periods of lagoon 3 discharge. Sampling for chemical constituents is performed near the beginning and end of each discharge period to meet the site SPDES permit. Both grab samples and 24-hour composite samples are collected.

- Sampling location is shown on Figure A-2 (p. A-4).

**2000 Monitoring Program
On-site Effluent Monitoring**

Liquid Effluents

Sample Location Code	Monitoring/Reporting Requirements	Sampling Type/Medium	Collection Frequency	Total Annual Sample Collections	Analyses Performed/ Composite Frequency
WNSP006 <i>Frank's Creek at the Security Fence</i>	Combined facility liquid discharge Required by: <ul style="list-style-type: none"> • SPDES Permit Reported in: <ul style="list-style-type: none"> • Monthly SPDES DMR • MTAR • SER 	Timed continuous composite liquid	→ Weekly	→ 52 Weekly samples composited to 12 Weekly samples composited to 4	→ Gross alpha/beta, H-3, pH, conductivity → Monthly composite for gamma isotopic and Sr-90 (shared with NYSDOH) → Quarterly composite for C-14, Tc-99, I-129, U-232, U-233/234, U-235/236, U-238, total U, Pu-238, Pu-239/240, Am-241
		Grab liquid	→ Twice during discharge, near start and near end	→ 8-16	→ TDS
		Grab liquid	→ Semiannual	→ 2	→ NPOC, TOX, Ca, Mg, Na, K, Ba, Mn, Fe, Cl, SO ₄ , NO ₃ +NO ₂ -N, F, HCO ₃ , CO ₃
WNURRAW <i>Utility Room Raw Water</i>	Source water Required by: <ul style="list-style-type: none"> • SPDES Permit Reported in: <ul style="list-style-type: none"> • Monthly SPDES DMR 	Grab liquid	→ Weekly	→ 52	→ Total Fe
		Grab liquid	→ Twice during discharge, near start and near end	→ 8-16	→ TDS
WNSP007 <i>Sanitary Waste Discharge</i>	Liquid effluent point for sanitary and utility plant combined discharge Required by: <ul style="list-style-type: none"> • SPDES Permit Reported in: <ul style="list-style-type: none"> • Monthly SPDES DMR • ESR • MTAR • SER 	24-hour composite liquid	→ 3 each month	→ 36 Monthly samples composited to 4	→ Gross alpha/beta, H-3, pH, suspended solids, NH ₃ , NO ₂ -N, BOD ₅ , total Fe → Quarterly composite for gamma isotopic
		Grab liquid	→ 3 each month	→ 36	→ Oil & grease
		Grab liquid	→ Weekly	→ 52	→ pH, settleable solids, total residual chlorine
		Grab liquid	→ Annual	→ 1	→ Chloroform

Sampling Rationale

WNSP006 DOE/EH-0173T, 5.10.1.1; SPDES permit no. NY0000973

By DOE Order all liquid effluent streams from DOE facilities shall be evaluated and their potential for release of radionuclides addressed.

In accordance with the WVDP SPDES permit no. NY0000973, outfall 116 (pseudo-monitoring point) uses flow data from WNSP006. Flow augmentation parameters (flow and total dissolved solids [TDS]) are monitored at location WNSP006; calculated TDS and flow data related to sample point WNSP006 are reported for pseudo-monitoring point 116 in the monthly SPDES Discharge Monitoring Report (DMR).

WNURRAW SPDES permit no. NY0000973

TDS is measured near the beginning and end of each lagoon 3 discharge. Results are used for outfall 116 calculations. (See **WNSP006** above.)

WNSP007 DOE 5400.5; DOE/EH-0173T, 2.3.3

Sampling rationale is based on New York State SPDES permit no. NY0000973 and DOE 5400.5 criteria.

■ Sampling locations are shown on Figure A-2 (p. A-4).

2000 Monitoring Program Environmental Surveillance

On-site Surface Water

Sample Location Code	Monitoring/Reporting Requirements	Sampling Type/Medium	Collection Frequency	Total Annual Sample Collections	Analyses Performed/Composite Frequency
WNSWAMP <i>Northeast Swamp Drainage</i>	Site surface drainage Reported in: • ESR • MTAR • SER	Timed continuous composite liquid	→ Weekly	→ 52 Weekly samples composited to 12 Weekly samples composited to 4	→ Gross alpha/beta, H-3, pH, conductivity → Monthly composite for gamma isotopic and Sr-90 (shared with NYSDOH) → Quarterly composite for C-14, I-129, U-232, U-233/234, U-235/236, U-238, total U, Pu-238, Pu-239/240, Am-241
		Grab liquid	→ Semiannual	→ 2	→ NPOC, TOX, Ca, Mg, Na, K, Ba, Mn, Fe, Cl, SO ₄ , NO ₃ +NO ₂ -N, F, HCO ₃ , CO ₃
WNSW74A <i>North Swamp Drainage</i>	Site surface drainage Reported in: • ESR • MTAR • SER	Timed continuous composite liquid	→ Weekly	→ 52 Weekly samples composited to 12 Weekly samples composited to 4	→ Gross alpha/beta, H-3, pH, conductivity → Monthly composite for gamma isotopic and Sr-90 → Quarterly composite for C-14, I-129, U-232, U-233/234, U-235/236, U-238, total U, Pu-238, Pu-239/240, Am-241
		Grab liquid	→ Semiannual	→ 2	→ NPOC, TOX, Ca, Mg, Na, K, Ba, Mn, Fe, Cl, SO ₄ , NO ₃ +NO ₂ -N, F, HCO ₃ , CO ₃
WN8D1DR <i>High-level Waste Farm Underdrain</i>	Drains subsurface water from HLW storage tank area Reported in: • MTAR • SER	Grab liquid	→ Weekly	→ 52 Weekly samples composited to 12	→ Gross alpha/beta, H-3, pH → Monthly composite for gamma isotopic and Sr-90
		Grab liquid	→ Monthly	→ 12 maximum	→ pH, total suspended solids, oil & grease, flow, gross alpha/beta, H-3, gamma isotopic
WNSDADR <i>SDA Run-off</i>	Surface water run-off from south portion of SDA Required by: • Interim Measures Compliance Reported in: • MTAR • SER • Reported to NYSERDA	Grab liquid	→ Monthly	→ 12 maximum	→ pH, total suspended solids, oil & grease, flow, gross alpha/beta, H-3, gamma isotopic

Sampling Rationale

WNSWAMP DOE/EH-0173T, 5.10.1.1

Northeast site surface water drainage; provides for sampling of uncontrolled surface waters from this discrete drainage path just before they leave the site's controlled boundary. Waters represent surface and subsurface drainages from the construction and demolition debris landfill (CDDL), old hardstand areas, and other possible north plateau sources of radiological or nonradiological contamination.

WNSW74A DOE/EH-0173T, 5.10.1.1

North site surface water drainage; provides for sampling of uncontrolled surface waters from this discrete drainage path just before they leave the site's controlled boundary. Waters represent surface and subsurface drainages from lag storage areas and other possible north plateau sources of radiological or nonradiological contamination.

WN8D1DR DOE/EH-0173T, 5.10.1.3

Monitors the potential influence on subsurface drainage surrounding the high-level waste tank farm.

WNSDADR NYSERDA interim measures compliance.

WVDP support of NYSERDA. Monitors surface water run-off from south portion of the SDA.

■ Sampling locations are shown on Figure A-2 (p. A-4).

2000 Monitoring Program Environmental Surveillance

On-site Surface Water

Sample Location Code	Monitoring/Reporting Requirements	Sampling Type/Medium	Collection Frequency	Total Annual Sample Collections	Analyses Performed/Composite Frequency
WNSP008 <i>French Drain</i>	Drains subsurface water from LLWTF lagoon area	Grab liquid	→ Monthly	→ 12	→ Gross alpha/beta, H-3
	Required by: • SPDES Permit	Grab liquid	→ 3 each month	→ 36	→ Conductivity, pH, BOD ₅ , total Fe, total recoverable Cd and Pb
	Reported in: • Monthly SPDES DMR • ESR • MTAR • SER	Grab liquid	→ Annual	→ 1	→ As, Cr, total Ag and Zn
WNSP005 <i>Facility Yard Drainage</i>	Combined drainage from facility yard area	Grab liquid	→ Monthly	→ 12	→ Gross alpha/beta, H-3, pH
	Reported in: • MTAR • SER				
WNCOOLW <i>Cooling Tower Basin</i>	Cools plant utility steam system water	Grab liquid	→ Monthly	→ 12	→ Gross alpha/beta, H-3, pH
	Reported in: • MTAR • SER			Monthly samples composited to 4	→ Quarterly composite for gamma isotopic

Sampling Rationale

WNSP008 DOE/EH-0173T, 5.10.1.3; SPDES permit no. NY0000973.

French drain of subsurface water from lagoon (LLWTF) area. The SPDES permit also provides for sampling of uncontrolled subsurface water from this discrete drainage path before these waters flow into Erdman Brook. Waters represent subsurface drainages from downward infiltration around the LLWTF and lagoon systems. This point would also monitor any subsurface spillover from the overfilling of lagoons 2 and 3. Sampling is of significance for both radiological and nonradiological contamination.

WNSP005 Facility yard surface water drainage; generally in accordance with DOE/EH-0173T, 5.10.1.1. Previously in accordance with SPDES permit no. NY0000973.

Provides for the sampling of uncontrolled surface waters from this discrete drainage path after outfall 007 discharge into the drainage and before these waters flow into Erdman Brook. Waters represent surface and subsurface drainages primarily from the main plant yard area. Historically, this point was used to monitor sludge pond and utility room discharges to the drainage. These two sources have been rerouted. Migration of residual site contamination around the main plant dictates surveillance of this point, primarily for radiological parameters.

WNCOOLW Facility cooling tower circulation water; generally in accordance with DOE/EH-0173T, 5.10.1.1.

Operational sampling carried out to confirm that radiological contamination is not migrating into the primary coolant loop of the HLWTF and/or plant utility steam systems. Migration from either source might indicate radiological control failure.

■ Sampling locations are shown on Figure A-2 (p. A-4).

2000 Monitoring Program Environmental Surveillance

On-site Surface Water

Sample Location Code	Monitoring/Reporting Requirements	Sampling Type/Medium	Collection Frequency	Total Annual Sample Collections	Analyses Performed/Composite Frequency
WNFRC67* <i>Frank's Creek East of the SDA</i>	Drains NYS Low-level Waste Disposal Area Reported in: • MTAR • SER • Reported to NYSERDA	Grab liquid	→ Monthly	→ 12	→ Gross alpha/beta, H-3, pH
WNERB53* <i>Erdman Brook North of Disposal Areas</i>	Drains NYS and WVDP disposal areas Reported in: • MTAR • SER • Reported to NYSERDA	Grab liquid	→ Weekly	→ 52	→ Gross alpha/beta, H-3, pH
WNNDADR <i>Drainage between NDA and SDA</i>	Drains WVDP disposal and storage area Reported in: • MTAR • SER • Reported to NYSERDA	Timed continuous composite liquid	→ Weekly	→ 52 Weekly samples composited to 12	→ pH → Monthly composite for gross alpha/beta, gamma isotopic, H-3
		Grab liquid	→ Weekly	→ 52	→ Quarterly composite for Sr-90, I-129 → NPOC, TOX
WNDCELD <i>Drainage South of Drum Cell</i>	Drains WVDP storage area Reported in: • MTAR • SER • Reported to NYSERDA	Grab liquid	→ Monthly	→ 12 Monthly samples composited to 4	→ pH, gross alpha/beta → Quarterly composite for H-3, Sr-90, I-129, gamma isotopic
WNNDATR** <i>NDA Trench Interceptor Project</i>	On-site groundwater interception Reported in: • MTAR • SER	Grab liquid	→ Monthly	→ 12 Monthly samples composited to 4	→ Gross alpha/beta, H-3, gamma isotopic, NPOC, TOX → Quarterly composite for I-129

* Monthly sample also collected by NYSDOH.

** Coordinated with Waste Management Operations.

Sampling Rationale

WNFRC67 DOE/EH-0173T, 5.10.1.1

Monitors the potential influence of both the SDA and drum cell drainage into Frank's Creek east of the SDA and upstream of its confluence with Erdman Brook.

WNERB53 DOE/EH-0173T, 5.10.1.1

Monitors the potential influence of the drainages from the SDA and the WVDP storage and disposal area into Erdman Brook upstream of its confluence with Frank's Creek.

WNNDADR DOE/EH-0173T, 5.10.1.1

Monitors the potential influence of the drainages from the SDA and the WVDP storage and disposal area into Lagoon Road Creek upstream of the creek's confluence with Erdman Brook.

WNDCELD DOE/EH-0173T, 5.10.1.1

Monitors the potential influence of drum cell drainage into Frank's Creek south of the SDA and upstream of WNFRC67.

WNNDATR DOE 5400.1, IV.9

Monitors groundwater in the vicinity of the NDA interceptor trench project. The grab sample is taken directly from the trench collection system.

■ Sampling locations are shown on Figure A-2 (p. A-4).

2000 Monitoring Program Environmental Surveillance

On-site Surface Water

Sample Location Code	Monitoring/Reporting Requirements	Sampling Type/Medium	Collection Frequency	Total Annual Sample Collections	Analyses Performed/ Composite Frequency
WNSTAW Series <i>On-site standing water ponds not receiving effluent</i> WNSTAW4 <i>Border Pond Southwest of AFRT240</i> WNSTAW5 <i>Border Pond Southwest of DFTLD13</i> WNSTAW6 <i>Borrow Pit Northeast of Project Facilities</i> WNSTAW9 <i>North Reservoir near Intake</i> WNSTAWB <i>Background Pond at Sprague Brook Maintenance Building</i>	Water within vicinity of airborne or water effluent from the plant Reported in: <ul style="list-style-type: none"> • MTAR • SER 	Grab liquid	→ Annual	→ 1 each location*	→ Gross alpha/beta, H-3, pH, conductivity, Cl, Fe, Mn, Na, NO ₃ +NO ₂ -N, SO ₄

* Sampling depends upon on-site ponding conditions during the year.

Sampling Rationale

WNSTAW Series DOE/EH-0173T, 5.10.1.1

Monitoring of on- and off-site standing waters at locations listed below. Although none receive effluent directly, the potential for contamination is present except at the background location. Former collecting sites 1,2,3,7, and 8 were deleted from the monitoring program because they were either built over or are now dry.

WNSTAW4 Border pond located south of AFRT240. Chosen as a location for showing potentially high concentrations, based on meteorological data. This perimeter location is next to a working farm. Drainage extends through private property and is accessible by the public.

WNSTAW5 Border pond located west of Project facilities near the perimeter fence and DFTLD13. Chosen as a location for showing potentially high concentrations, based on meteorological data. Location is next to a private residence and potentially accessible by the general public.

WNSTAW6 Borrow pit northeast of Project facilities just outside the inner security fence. Considered the closest standing water to the main plant and high-level waste facilities.

WNSTAW9 North reservoir near intake. Chosen to provide data in the event of potentially contaminated site potable water supply. Location is south of main plant facilities.

WNSTAWB Pond located near the Sprague Brook maintenance building. Considered a background location; approximately 14 kilometers north of the WVDP.

■ Sampling locations are shown on Figures A-2, A-3, and A-12 (pp. A-4, A-5, and A-14).

2000 Monitoring Program Environmental Surveillance

On-site Potable Water

Sample Location Code	Monitoring/Reporting Requirements	Sampling Type/Medium	Collection Frequency	Total Annual Sample Collections	Analyses Performed/Composite Frequency
WNDNK Series <i>Site Potable Water</i>	Sources of potable water within site perimeter	Grab liquid	→ Monthly	→ 12 per location	→ Gross alpha/beta, H-3, pH, conductivity
WNDNKMS <i>Maintenance Shop Drinking Water</i>	Reported in: <ul style="list-style-type: none"> • MTAR • SER • Also reported to Cattaraugus County 				
WNDNKMP <i>Main Plant Drinking Water</i>					
WNDNKEL <i>Environmental Laboratory Drinking Water</i>					
WNDNKUR <i>Utility Room (EP-1) Potable Water Storage Tank</i>		Grab liquid*	→ Annual	→ 1	→ As, Ba, Be, Cd, Cr, Hg, Ni, Sb, Se, Tl, cyanide, fluoride

* WNDNKUR only. Sample for NO₃ (as total nitrate) is collected by the Cattaraugus County Health Department. Pb and Cu also are sampled at this site based upon Cattaraugus County Health Department guidance.

Sampling Rationale

WNDNK Series	Site drinking water; generally according to DOE/EH-0173T, 5.10.1.2 Potable-water sampling to confirm no migration of radiological and/or nonradiological contamination into the site's drinking water supply.
WNDNKMS	Potable water sampled at the maintenance shop in order to monitor a point that is at an intermediate distance from the point of potable water generation and that is used heavily by site personnel.
WNDNKMP	Same rationale as WNDNKMS but sampled at the break room sink.
WNDNKEL	Potable water sampled at the Environmental Laboratory.
WNDNKUR	Sampled at the utility room potable water storage tank before the site drinking water distribution system. Sample location is entry point EP-1.

- Sampling locations are within the site facilities and are not detailed on figures.

2000 Monitoring Program Environmental Surveillance

On-site Groundwater

Sample Location Code	Monitoring/Reporting Requirements	Sampling Type/Medium	Collection Frequency	Total Annual Sample Collections	Analyses Performed/Composite Frequency
Low-level Waste Treatment Facilities <i>(SSWMU #1)</i> 103 104 C 105 C 106 107 108 110 111 116 U 8604 C 8605	Groundwater monitoring points around site super solid waste management units (SSWMUs) Reported in: <ul style="list-style-type: none"> SER Quarterly Groundwater Reports 	Grab liquid → Direct field measurement of sample discharge water →	4 times per year (generally)* → Each sampling event* →	4 each well (generally)* → Twice each sampling event →	Gross alpha, gross beta, H-3 * Conductivity, pH
Miscellaneous Small Units <i>(SSWMU #2)</i> 201 U 204 205 206 C 208					
Liquid Waste Treatment System <i>(SSWMU #3)</i> 301 B 302 U					

NOTE: "U" designates upgradient, "B" designates background, and "C" designates crossgradient wells. The remainder are downgradient.

* Sampling frequency and analytes vary from point to point. See Table 3-1 (p.3-6) for a summary listing of all monitored analytes. See Table E-1 (Appendix E, p. E-3) for a listing of analytes monitored at each location. See Appendix E for results from each location.

Sampling Rationale

On-site Groundwater	DOE Order 5400.1, IV.9; DOE/EH-0173T, 5.10.1.3; 40 CFR Parts 264 and 265, Subpart F The on-site WVDP groundwater monitoring program provides for the determination of water quality, focusing on radiological and chemical surveillance of both active and inactive super solid waste management units (SSWMUs). In addition, using wells situated hydraulically upgradient (background) and downgradient of SSWMUs allows both detection of groundwater contamination and evaluation of the effects associated with the individual SSWMUs. Groundwater protection is addressed in the Groundwater Protection Management Program Plan, WVDP-091. Groundwater monitoring is detailed in the Groundwater Monitoring Plan, WVDP-239.
SSWMU #1	Low-level waste treatment facilities, including four active lagoons — lagoons 2, 3, 4, and 5 — and an inactive, filled-in lagoon — lagoon 1.
SSWMU #2	Miscellaneous small units, including the sludge pond, the solvent dike, the paper incinerator, the equalization basin, and the kerosene tank.
SSWMU #3	Liquid waste treatment system containing effluent from the supernatant treatment system.

- Sampling locations are shown on Figure A-7 (p.A-9).

2000 Monitoring Program Environmental Surveillance

On-site Groundwater

Sample Location Code	Monitoring/Reporting Requirements	Sampling Type/Medium	Collection Frequency	Total Annual Sample Collections	Analyses Performed/Composite Frequency
HLW Storage and Processing Tank <i>(SSWMU #4)</i> 401 B 402 U 403 U 405 C 406 408 409	Groundwater monitoring points around site super solid waste management units (SSWMUs) Reported in: <ul style="list-style-type: none"> • SER • Quarterly Groundwater Reports 	Grab liquid	→ 4 times per year (generally)*	→ 4 each well (generally)*	→ Gross alpha, gross beta, H-3 *
Maintenance Shop Leach Field <i>(SSWMU #5)</i> 501 U 502		Direct field measurement of sample discharge water	→ Each sampling event*	→ Twice each sampling event	→ Conductivity, pH
Low-level Waste Storage Area <i>(SSWMU #6)</i> 602A 604 605 8607 U 8609 U					
Chemical Process Cell Waste Storage Area <i>(SSWMU #7)</i> 704 706 B 707 C					

NOTE: "U" designates upgradient, "B" designates background, and "C" designates crossgradient wells. The remainder are downgradient.

* Sampling frequency and analytes vary from point to point. See Table 3-1 (p. 3-6) for a summary listing of all monitored analytes. See Table E-1 (Appendix E, p. E-3) for a listing of analytes monitored at each location. See Appendix E for results from each location.

Sampling Rationale

On-site Groundwater	<p>DOE Order 5400.1, IV.9; DOE/EH-0173T, 5.10.1.3; 40 CFR Parts 264 and 265, Subpart F</p> <p>The on-site WVDP groundwater monitoring program provides for the determination of water quality, focusing on radiological and chemical surveillance of both active and inactive super solid waste management units (SSWMUs). In addition, using wells situated hydraulically upgradient (background) and downgradient of SSWMUs allows both detection of groundwater contamination and evaluation of the effects associated with the individual SSWMUs. Groundwater protection is addressed in the Groundwater Protection Management Program Plan, WVDP-091. Groundwater monitoring is detailed in the Groundwater Monitoring Plan, WVDP-239.</p>
SSWMU #4	High-level waste storage and processing area, including the high-level radioactive waste tanks, the supernatant treatment system, and the vitrification facility.
SSWMU #5	Maintenance shop sanitary leach field, formerly used by NFS and the WVDP to process domestic sewage generated by the maintenance shop.
SSWMU #6	Low-level waste storage area; includes metal and fabric structures housing low-level radioactive waste being stored for future disposal.
SSWMU #7	Chemical process cell (CPC) waste storage area, which contains packages of pipes, vessels, and debris from decontamination and cleanup of the chemical process cell in the former reprocessing plant.

■ Sampling locations are shown on Figure A-7 (p.A-9).

On-site Groundwater

Calendar Year 2000

Sampling Rationale

**On-site
Groundwater**

DOE Order 5400.1, IV.9; DOE/EH-0173T, 5.10.1.3; 40 CFR Parts 264 and 265, Subpart F

The on-site WVDP groundwater monitoring program provides for the determination of water quality, focusing on radiological and chemical surveillance of both active and inactive super solid waste management units (SSWMUs). In addition, using wells situated hydraulically upgradient (background) and downgradient of SSWMUs allows both detection of groundwater contamination and evaluation of the effects associated with the individual SSWMUs. Groundwater protection is addressed in the Groundwater Protection Management Program Plan, WVDP-091. Groundwater monitoring is detailed in the Groundwater Monitoring Plan, WVDP-239.

SSWMU #8

The construction and demolition debris landfill (CDDL); used by NFS and the WVDP to dispose of nonhazardous and nonradioactive materials.

SSWMU #9

The NRC-licensed disposal area (NDA); contains radioactive wastes generated by NFS and the WVDP. The NDA is bounded on its downgradient (northwest and northeast) perimeters by the interceptor trench, which is sampled at monitoring point NDATR.

SSWMU #10

The integrated radioactive waste system (IRTS) treatment drum cell; stores cement-stabilized low-level radioactive waste.



Sampling locations are shown on Figures A-6 through A-8 (pp. A-8 through A-10).

2000 Monitoring Program Environmental Surveillance

On-site Groundwater and Seeps

Sample Location Code	Monitoring/Reporting Requirements	Sampling Type/Medium	Collection Frequency	Total Annual Sample Collections	Analyses Performed/Composite Frequency
State-licensed Disposal Area <i>(SSWMU #11)*</i> 1101a U 1101b U 1101c U 1102a 1102b 1103a 1103b 1103c 1104a 1104b 1104c 1105a 1105b 1106a U 1106b U 1107a 1108a U 1109a U 1109b U 1110a 1111a	Groundwater monitoring points around site super solid waste management units (SSWMUs) Reported in: <ul style="list-style-type: none">SER	Grab liquid → Semiannual Grab liquid → Annual	→ 2 each well → 1 each well	→ Gross alpha/beta, H-3, pH, conductivity, turbidity → Gamma scan, beta-emitters (C-14, Sr-90, TC-99, I-129), VOCs	
North Plateau Seeps <i>(Not in a SSWMU)</i> GSEEP SP04 SP06 SP11 SP12	Groundwater seepage points along the northeastern edge of the north plateau Reported in: <ul style="list-style-type: none">SERQuarterly Groundwater Reports	Grab liquid → Semiannual	→ 2 each seep	→ Gross alpha/beta, H-3 (pH, conductivity, and VOCs at SP12)	
Miscellaneous <i>Well Points</i> <i>(Not in a SSWMU)</i> WP-A WP-C WP-H NBIS <i>(Former background well)</i>	Well points downgradient of main plant and the former sand and gravel unit back-ground well Reported in: <ul style="list-style-type: none">SERQuarterly Groundwater Reports	Grab liquid → Annual Field measurement → Quarterly Grab liquid → Quarterly	→ 1 each well → 4 → 4	→ Gross alpha/beta, H-3, pH, conductivity → pH, conductivity → Gross alpha/beta, H-3	

NOTE: "U" designates upgradient, "B" designates background, and "C" designates crossgradient wells. The remainder are downgradient.

* SSWMU #11 is sampled by NYSERDA under a separate program.

Sampling Rationale

On-site Groundwater	DOE Order 5400.1, IV.9; DOE/EH-0173T, 5.10.1.3; 40 CFR Parts 264 and 265, Subpart F The on-site WVDP groundwater monitoring program provides for the determination of water quality, focusing on radiological and chemical surveillance of both active and inactive super solid waste management units (SSWMUs). In addition, using wells situated hydraulically upgradient (background) and downgradient of SSWMUs allows both detection of groundwater contamination and evaluation of the effects associated with the individual SSWMUs. Groundwater protection is addressed in the Groundwater Protection Management Program Plan, WVDP-091. Groundwater monitoring is detailed in the Groundwater Monitoring Plan, WVDP-239.
SSWMU #11	The New York State-licensed disposal area (SDA) was operated by NFS as a commercial low-level disposal facility; it also received wastes from NFS reprocessing operations.
North Plateau Seeps	Monitor groundwater emanating from the ground surface along the edge of the site's north plateau.
Well Points	Monitor groundwater of known subsurface contamination in the north plateau area. All well points are downgradient of the main plant.
WNWNB1S	Former background well on the north plateau.

- Sampling locations are shown on Figures A-7 and A-8 (pp.A-9 and A-10).

2000 Monitoring Program Environmental Surveillance

Off-site Surface Water

Sample Location Code	Monitoring/Reporting Requirements	Sampling Type/Medium	Collection Frequency	Total Annual Sample Collections	Analyses Performed/ Composite Frequency
WFBCTCB* <i>Buttermilk Creek Upstream of Confluence with Cattaraugus Creek at Thomas Corners Road</i>	Restricted surface waters receiving plant effluents Reported in: <ul style="list-style-type: none">• MTAR• SER	Timed continuous composite liquid	→ Weekly	→ 52	→ pH, conductivity
				Weekly samples composited to 12	→ Monthly composite for gross alpha/beta, H-3
				Weekly samples composited to 4	→ Quarterly composite for gamma isotopic and Sr-90
WFFELBR* <i>Cattaraugus Creek at Felton Bridge</i>	Unrestricted surface waters receiving plant effluents Reported in: <ul style="list-style-type: none">• MTAR• SER	Timed continuous composite liquid	→ Weekly	→ 52	→ Gross alpha/beta, H-3, pH
				Weekly samples composited to 12	→ Flow-weighted monthly composite for gamma isotopic, H-3, Sr-90, and gross alpha/beta
WFBCBKG* <i>Buttermilk Creek near Fox Valley (background)</i>	Unrestricted surface water, background Reported in: <ul style="list-style-type: none">• MTAR• SER• Reported to NYSERDA	Timed continuous composite liquid	→ Weekly	→ 52	→ pH, conductivity
				Weekly samples composited to 12	→ Monthly composite for gross alpha/beta, H-3
				Weekly samples composited to 4	→ Quarterly composite for gamma isotopic, C-14, Sr-90, Tc-99, I-129, U-232, U-233/234, U-235/236, U-238, total U, Pu-238, Pu-239/240, Am-241
				Grab liquid	→ Semiannual
WFBIGBR <i>Cattaraugus Creek at Bigelow Bridge (background)</i>	Unrestricted surface water, background Reported in: <ul style="list-style-type: none">• MTAR• SER	Grab liquid	→ Monthly	→ 12	→ Gross alpha/beta, H-3, Sr-90, gamma isotopic

* Monthly composites are also sent to NYSDOH.

Sampling Rationale

WFBCTCB DOE/EH-0173T, 5.10.1.1

Buttermilk Creek is the surface water that receives all WVDP effluents. WFBCTCB monitors the potential influence of WVDP drainage into Buttermilk Creek upstream of Buttermilk Creek's confluence with Cattaraugus Creek.

WFFELBR DOE/EH-0173T, 5.10.1.1

Because Buttermilk Creek empties into Cattaraugus Creek, WFFELBR monitors the potential influence of WVDP drainage into Cattaraugus Creek directly downstream of the Cattaraugus Creek confluence with Buttermilk Creek.

WFBCBKG DOE/EH-0173T, 5.10.1.1

Monitors background conditions of Buttermilk Creek upstream of the WVDP; allows comparison to downstream conditions.

WFBIGBR DOE/EH-0173T, 5.10.1.1

Monitors background conditions of Cattaraugus Creek at Bigelow Bridge, upstream of the WVDP; allows comparison to downstream conditions.

■ Sampling locations are shown on Figure A-3 (p. A-5).

2000 Monitoring Program Environmental Surveillance

Off-site Drinking Water

Sample Location Code	Monitoring/Reporting Requirements	Sampling Type/Medium	Collection Frequency	Total Annual Sample Collections	Analyses Performed/Composite Frequency
WFWEL Series <i>Wells outside the WYNSC perimeter but near the WVDP</i>	Drinking water supply; groundwater near facility*	Grab liquid	→ Annual	→ 1 each location	→ Gross alpha/beta, H-3, gamma isotopic, pH, conductivity
WFWEL01 <i>3.0 km West-Northwest</i>	Reported in: <ul style="list-style-type: none"> • MTAR • SER 				
WFWEL02 <i>1.5 km Northwest</i>					
WFWEL03 <i>3.5 km Northwest</i>					
WFWEL04 <i>3.0 km Northwest</i>					
WFWEL05 <i>2.5 km Southwest</i>					
WFWEL06 <i>(background)</i> <i>29 km South</i>					
WFWEL07 <i>4.4 km North-Northeast</i>					
WFWEL08 <i>2.5 km East-Northeast</i>					
WFWEL09 <i>3.0 km Southeast</i>					
WFWEL10 <i>7.0 km North</i>					

* No drinking water wells are located in hydrogeological units affected by site activity.

Sampling Rationale

Off-site

Drinking Water

WFWEL Series DOE 5400.1, IV.9; DOE/EH-0173T, 5.10.1.2

Eight of the ten listed off-site private residential drinking water wells represent the nearest unrestricted uses of ground-water close to the WVDP. The ninth sample (**WFWEL10**) is taken from a public water supply from deep wells. The tenth drinking water well, **WFWEL06**, is located 29 kilometers south of the Project and is considered a background drinking water source.

■ Sampling locations are shown on Figures A-9 and A-12 (pp. A-11 and A-14).

2000 Monitoring Program Environmental Surveillance

Off-site Air

Sample Location Code	Monitoring/Reporting Requirements	Sampling Type/Medium	Collection Frequency	Total Annual Sample Collections	Analyses Performed/ Composite Frequency
AFEXVRD <i>3.0 km South-Southeast at Fox Valley</i>	Particulate air samples around WNYNSC perimeter Reported in: <ul style="list-style-type: none"> • MTAR • SER 	Continuous air particulate filter	→ Weekly	→ 52 each location	→ Gross alpha/beta
AFTCORD <i>3.7 km North-Northwest at Thomas Corners Road</i>					→ Quarterly composite for Sr-90 and gamma isotopic
AFRT240* <i>2.0 km Northeast on Route 240</i>					In addition, quarterly composite at AFRSPRD and AFGRVAL for U-232, U-233/234, U-235/236, U-238, total U, Pu-238, Pu-239/240, and Am-241
AFSPRVL <i>9.4 km North at Springville</i>					
AFWEVAL <i>6.2 km South-Southeast at West Valley</i>					
AFNASHV <i>39.8 km West at Village of Nashville, Town of Hanover (background)</i>					
AFBOEHN <i>2.3 km Southwest on Dutch Hill Road</i>					
AFRSPRD <i>1.5 km Northwest on Rock Springs Road</i>		Continuous desiccant column for water vapor collection at AFRSPRD and AFGRVAL	→ Weekly	→ 52 each location	→ H-3
AFGRVAL <i>30.9 km South at Great Valley (background)</i>					
AFBLKST <i>Bulk Storage Warehouse 2.2 km East-Southeast at Buttermilk Road</i>					
		Continuous charcoal cartridge at AFRSPRD and AFGRVAL	→ Monthly	→ 12 composited to 4 each location	→ Quarterly composite for I-129

* Filter from duplicate sampler sent to NYSDOH.

Sampling Rationale

**AFFXVRD
AFTCORD
AFRT240**

DOE/EH-0173T, 5.7.4

Air samplers put into service by NFS as part of the site's original monitoring program at perimeter locations chosen to obtain data from places most likely to provide highest concentrations. Choice of location based on meteorological data.

AFSPRVL

DOE/EH-0173T, 5.7.4; DOE/EP-0023, 4.2.3

Off-site (remote) sampler located on private property in nearby community within 15 kilometers of the site (north).

AFWEVAL

DOE/EH-0173T, 5.7.4; DOE/EP-0023, 4.2.3

Off-site (remote) sampler located on private property in nearby community within 15 kilometers of the site (southeast).

AFNASHV

DOE/EH-0173T, 5.7.4; DOE/EP-0023, 4.2.3

Off-site (remote) sampler considered representative of natural background radiation. Located 39.8 kilometers west of the site (upwind) on privately owned property.

AFBOEHN

DOE/EH-0173T, 5.7.4; DOE/EP-0023, 4.2.3

Perimeter location chosen to obtain data from the place most likely to provide the highest elevated release concentrations. AFBOEHN is located on NYSERDA property at the perimeter. Choice of location based on meteorological data.

AFRSPRD

DOE/EH-0173T, 5.7.4

Perimeter location chosen to obtain data from the place most likely to provide the highest ground-level release concentrations. AFRSPRD is on WNYNSC property outside the main plant operations fenceline. H-3 and I-129 are sampled here because the sampling trains were easy to incorporate and the location was most likely to receive effluent releases. Choice of location based on meteorological data.

AFGRVAL

DOE/EH-0173T, 5.7.4; DOE/EP-0023, 4.2.3

Off-site (remote) sampler considered representative of natural background radiation. Located on privately owned property 30.9 kilometers south of the site (typically upwind). H-3 and I-129 sampled here also.

AFBLKST

DOE/EH-0173T, 5.7.4

Off-site monitoring of bulk storage warehouse, near the site perimeter.



Sampling locations are shown on Figures A-5 and A-12 (pp. A-7 and A-14).

2000 Monitoring Program Environmental Surveillance

Fallout, Sediment, and Soil

Sample Location Code	Monitoring/Reporting Requirements	Sampling Type/Medium	Collection Frequency	Total Annual Sample Collections	Analyses Performed/Composite Frequency
AFDHFOP <i>2.3 km Southwest</i> AFFXFOP <i>3.0 km South-Southeast</i> AFTCFOP <i>3.7 km North-Northwest</i> AF24FOP <i>2.0 km Northeast</i> ANRGFOP <i>Rain gauge on-site</i>	Collection of fallout particulates and precipitation around the WNYNSC perimeter Reported in: <ul style="list-style-type: none"> • MTAR • SER 	Integrated precipitation	→ Monthly	→ 12 each location	→ Gross alpha/beta, H-3, pH, gamma isotopic
SF Soil Series <i>Surface soil at each of 10 air samplers</i>	Long-term fallout accumulation Reported in: <ul style="list-style-type: none"> • MTAR • SER 	Surface plug composite soil	→ Annual	→ 1 each location	→ Gross alpha/beta, gamma isotopic, Sr-90, Pu-239/240, Am-241 In addition at SFRSPRD, S F B O E H N , a n d SFGRVAL: U-232, U-233/234, U-235/236, U-238, and total U
SFCCSED <i>Cattaraugus Creek at Felton Bridge</i> SFSDSED <i>Cattaraugus Creek at Springville Dam</i> SFBISED <i>Cattaraugus Creek at Bigelow Bridge (background)</i> SFTCSED <i>Buttermilk Creek at Thomas Corners Road</i> SFBCSED <i>Buttermilk Creek at Fox Valley Road (background)</i>	Deposition in sediment downstream of facility effluents Reported in: <ul style="list-style-type: none"> • MTAR • SER 	Grab stream sediment	→ Annual (Split SFSDSED and SFBCSED with NYSDOH)	→ 1 each location	→ Gross alpha/beta, gamma isotopic, Sr-90, U-232, U-233/234, U-235/236, U-238, total U, Pu-238, Pu-239/240, Am-241
SN On-site Soil Series: SNSW74A <i>(Near WNSW74A)</i> SNSWAMP <i>(Near WNSWAMP)</i> SNSP006 <i>(Near WNSP006)</i>	Reported in: <ul style="list-style-type: none"> • MTAR • SER 	Surface plug or grab	→ Annual	→ 1 each location	→ Gross alpha/beta, gamma isotopic, Sr-90, U-232, U-233/234, U-235/236, U-238, total U, Pu-239/240, and Am-241, Al, Sb, As, Ba, Be, Cd, Ca, Cr, Co, Cu, Fe, Pb, Mg, Mn, Hg, Ni, K, Se, Ag, Na, Tl, V, Zn

Sampling Rationale

AFDHFOP AFFXFOP AFTCFOP AF24FOP	DOE/EP-0023, 4.7 Collection of fallout particles and precipitation around the site perimeter at established air sampling locations: AFDHFOP (Dutch Hill at Boehn Road), AFFXFOP (Fox Valley Road), AFTCFOP (Thomas Corners), AF24FOP (Route 240). Indicates short-term effects.
ANRGFOP	Fallout particles and precipitation collected on-site by the Environmental Laboratory at the rain gauge. Indicates short-term effects.
SF Soil Series	DOE/EH-0173T, 5.9.1 Off-site soils collected at air sampling locations. SFWEVAL (West Valley), SFFXVRD (Fox Valley Road), SFSPRVL (Springville), SFTCORD (Thomas Corners), SFRT240 (Route 240), SFNASHV (Nashville), SFBOEHN (Boehn Road-Dutch Hill), SFGRVAL (Great Valley), SFRSPRD (Rock Springs Road), SFBLKST (bulk storage warehouse): Collection of long-term fallout data at established air sampler locations via soil sampling.
SFCCSED	DOE/EH-0173T, 5.12.1 Sediment deposition at Cattaraugus Creek at Felton Bridge. Location is first point of public access to Cattaraugus Creek downstream of its confluence with Buttermilk Creek.
SFSDSED	DOE/EH-0173T, 5.12.1 Sediment deposition in Cattaraugus Creek at Springville Dam. Reservoir provides ideal settling and collection location for sediments downstream of Buttermilk Creek confluence with Cattaraugus Creek. Located downstream of SFCCSED .
SFBISED	DOE/EH-0173T, 5.12.1 Sediment deposition in Cattaraugus Creek at Bigelow Bridge. Location is upstream of the Buttermilk Creek confluence and serves as the Cattaraugus Creek background location.
SFTCSED	DOE/EH-0173T, 5.12.1 Sediment deposition in Thomas Corners in Buttermilk Creek immediately downstream of all facility liquid effluents.
SFBCSED	DOE/EH-0173T, 5.12.1 Sediment deposition in Buttermilk Creek upstream of facility effluents (background).
SN Soil Series	DOE/EH-0173T, 5.9.1. On-site soil. (Samples may be partially composed of sediments.) SNSW74A (surface soil near WNSW74A), SNSWAMP (surface soil near WNSWAMP), and SNSP006 (surface soil near WNSP006): Locations to be specifically defined by geographic coordinates. Correspond to site drainage pattern flows (i.e., most likely area of radiological deposition/accumulation).

■ Sampling locations are shown on Figures A-2 through A-5 and A-12 (pp.A-4 through A-7 and A-14).

2000 Monitoring Program Environmental Surveillance

Off-site Biological

Sample Location Code	Monitoring/Reporting Requirements	Sampling Type/Medium	Collection Frequency	Total Annual Sample Collections	Analyses Performed/ Composite Frequency
BFFCATC <i>Fish from Cattaraugus Creek downstream of its confluence with Buttermilk Creek</i> BFFCATD <i>Fish from Cattaraugus Creek downstream of the Springville Dam</i> BFFCTRL <i>Control fish sample from nearby stream not affected by the WVDP (7 km or more upstream of site effluent point; background)</i>	Fish in waters up- and downstream of facility effluents Reported in: <ul style="list-style-type: none"> • MTAR • SER 	Individual collection, biological	→ Semiannual (samples at BFFCATC and BFFCTRL shared with NYSDOH) Annual (BFFCATD only)	→ 20 fish each location → 10 fish	→ Gamma isotopic and Sr-90 in edible portions of each individual fish; % moisture → Gamma isotopic and Sr-90 in edible portions of each individual fish; % moisture
BFMREED <i>Dairy farm 3.8 km North-Northwest</i> BFMCOBO <i>Dairy farm 1.9 km West-Northwest</i> BFMCTLN <i>Control location 25 km South (background)</i> BFMCTLN <i>Control location 30 km North (background)</i>	Milk from animals foraging at locations near the facility perimeter and at background sites Milk from animals foraging at background sites Reported in: <ul style="list-style-type: none"> • MTAR • SER 	Grab biological	→ Monthly (samples at BFMREED and BFMCOBO shared with NYSDOH)	→ 12 monthly samples composited to 4 each location	→ Quarterly composite for gamma isotopic, H-3, Sr-90, and I-129
BFMWIDR <i>Dairy farm 3.0 km Southeast</i> BFMSCHT <i>Dairy farm 4.8 km South</i>	Milk from animals foraging near the site perimeter Reported in: <ul style="list-style-type: none"> • MTAR • SER 	Grab biological	→ Annual	→ 1 each location	→ Gamma isotopic, H-3 Sr-90, and I-129

Sampling Rationale

BFFCATC BFTCATD	DOE/EH-0173T, 5.11.1.1 Radioactivity may enter a food chain in which fish are a major component and are consumed by the local population.
BFFCTRL	Control fish sample; provide background data for comparison with data from fish caught downstream of facility effluents.
BFMREED BFMCOBO BFMCTLS BFMCTLN	DOE/EH-0173T, 5.8.2.1 Milk is consumed by all age groups and is frequently the most important food that could contribute to the radiation dose. Dairy animals pastured near the site and at two background locations allow adequate monitoring. Control milk samples are collected far from the site to provide background data for comparison with data from near-site milk samples.
BFMWIDR BFMSCHT	Milk from animals foraging around facility perimeter.

- Sampling locations are shown on Figures A-9 and A-12 (pp. A-11 and A-14).

2000 Monitoring Program Environmental Surveillance

Off-site Biological

Sample Location Code	Monitoring/Reporting Requirements	Sampling Type/Medium	Collection Frequency	Total Annual Sample Collections	Analyses Performed/ Composite Frequency
BFVNEAR <i>Nearby locations</i> BFVCTRL <i>Remote locations (16 km or more from facility; background)</i>	Fruit and vegetables grown near facility perimeter, downwind if possible, and at background locations Reported in: <ul style="list-style-type: none"> • MTAR • SER 	Grab biological (fruits and vegetables)	→ Annual (at harvest)	→ 3 each (split with NYSDOH)	→ Gamma isotopic and Sr-90 analysis of edible portions, H-3 in free moisture; % moisture
BFHNEAR <i>Forage for beef cattle/ milk cows from near-site location</i> BFHCTLS or BFHCTLN <i>Forage for beef cattle/ milk cows from control location south or north (background)</i>	Forage (hay) grown near facility perimeter, downwind if possible, and at background locations Reported in: <ul style="list-style-type: none"> • MTAR • SER 	Grab biological	→ Annual	→ 1 each location	→ Gamma isotopic, Sr-90
BFBNEAR <i>Beef animal from nearby farm in downwind direction</i> BFBCTRL <i>Beef animal from control location 16 km or more from facility (background)</i>	Meat (beef foraging near facility perimeter, downwind if possible, and a background location) Reported in: <ul style="list-style-type: none"> • MTAR • SER 	Grab biological	→ Semiannual	→ 2 each location	→ Gamma isotopic and Sr-90 analysis of meat, H-3 in free moisture; % moisture
BFDNEAR <i>Deer in vicinity of the site</i> BFDCTRL <i>Control deer 16 km or more from the facility (background)</i>	Venison (deer foraging near facility perimeter and at background locations) Reported in: <ul style="list-style-type: none"> • MTAR • SER 	Individual collection, biological	→ Annual, during hunting season (BFDNEAR sample split with NYSDOH) During year as available (BFDCTRL sample split with NYSDOH)	→ 3 → 3	→ Gamma isotopic and Sr-90 analysis of meat, H-3 in free moisture; % moisture

Sampling Rationale

BFVNEAR	DOE/EH-0173T, 5.8.2.2
	Fruits and vegetables (corn, apples, and beans or leafy vegetables, if available) collected from areas near the site. These samples are collected, if possible, from areas near the site predicted to have worst-case downwind concentrations of radionuclides in air and soil. Sample analysis reflects steady state/chronic uptake or contamination of foodstuffs as a result of site activities. Possible pathway directly to humans or indirectly through animals.
BFVCTRL	DOE/EH-0173T, 5.8.2.2
	Fruits and vegetables collected from an area remote from the site. Background fruits and vegetables collected for comparison with near-site samples. Collected in area(s) of no possible site effects.
BFHNEAR	DOE/EH-0173T, 5.8.2.2
	Hay collected from area near the site. Same as for near-site fruits and vegetables (BFVNEAR). Indirect pathway to humans through animals. Collected from same location as beef or milk sample.
BFHCTL BFHCTLN	DOE/EH-0173T, 5.8.2.2
	Hay collected from areas remote from the site. Background hay collected for comparison with near-site samples. Collected in area(s) of no possible effects from the site.
BFBNear	DOE/EH-0173T, 5.8.2.3
	Beef collected from animals raised near the site and foraging downwind of the site in areas of maximum probable effects. Following the rationale for vegetable matter collected near the site (BFVNEAR and BFHNEAR), edible flesh portion of beef animals is analyzed to determine possible radionuclide content passable directly to humans.
BFBCTRL	DOE/EH-0173T, 5.8.2.3
	Beef collected from animals raised far from the site. Background beef collected for comparison with near-site samples. Collected in area(s) of no possible site effects.
BFDNEAR	DOE/EH-0173T, 5.8.3
	Venison from near-site deer. Samples are taken from deer killed in collisions with vehicles. Sample rationale is similar to BFBNear .
BFDCTRL	DOE/EH-0173T, 5.8.3
	Venison from deer living far from the site. Background deer meat collected for comparison with near-site samples. Collected in area(s) of no possible site effects.

■ Sampling locations are shown on Figures A-9 and A-12 (pp. A-11 and A-14).

2000 Monitoring Program Environmental Surveillance

Off-site Direct Radiation

Sample Location Code	Monitoring/Reporting Requirements	Sampling Type/Medium	Collection Frequency	Total Annual Sample Collections	Analyses Performed/Composite Frequency
DFTLD Series <i>Thermoluminescent Dosimetry (TLD)</i> <i>Off-site:</i> #1-#16 <i>Each of 16 Compass Sectors at Nearest Accessible Perimeter Point</i> #17 <i>"5 points" Landfill 19.6 km Southwest (background)</i> #20 <i>1,500 m Northwest (downwind receptor)</i> #21 <i>Springville 9.4 km North</i> #22 <i>West Valley 6.2 km South-Southeast</i> #23 <i>Great Valley 30.9 km South (background)</i> #37 <i>Nashville 39.8 km Northwest (background)</i> #41 <i>Sardinia-Savage Road 15.5 km Northeast (background)</i>	Direct radiation around facility Reported in: <ul style="list-style-type: none"> • MTAR • SER 	Integrating LiF TLD	→ Quarterly	→ TLD cards at each of 23 locations collected 4 times per year	→ Quarterly gamma radiation exposure

Sampling Rationale

Direct Radiation DOE/EH-0173T, 5.5; DOE/EP-0023, 4.6.3
Off-site

TLDs offer continuous integrated environmental gamma-ray monitoring and have been deployed systematically about the site. Off-site TLDs are used to verify that site activities have not adversely affected the surrounding environs.

An annual high-pressure ion chamber (HPIC) gamma radiation measurement is completed at all locations in order to confirm TLD measurements.

■ Sampling locations are shown on Figures A-11 and A-12 (pp. A-13 and A-14).

2000 Monitoring Program Environmental Surveillance

On-site Direct Radiation

Sample Location Code	Monitoring/Reporting Requirements	Sampling Type/Medium	Collection Frequency	Total Annual Sample Collections	Analyses Performed/ Composite Frequency
DNTLD Series <i>Thermoluminescent Dosimetry (TLD) On-site:</i> #18, #19, #33 <i>At three corners of the SDA</i> #24, #26-#32, #34 <i>9 TLDs at the security fence around the site</i> #35, #36, #38-#40 <i>5 TLDs on-site near operational areas</i> #25 <i>Rock Springs Road 500 m North-Northwest of the plant</i> #42 <i>SDA T-1 building</i> #43 <i>SDA west perimeter fence</i>	Direct radiation around facility Reported in: <ul style="list-style-type: none"> • MTAR • SER 	Integrating LiF TLD	→ Quarterly	→ TLD cards at each of 20 locations collected 4 times per year	→ Quarterly gamma radiation exposure

Sampling Rationale

Direct Radiation DOE/EH-0173T, 5.4 and 5.5
On-site

On-site TLDs monitor waste management units and verify that the potential dose rate to the general public (i.e., at Rock Springs Road) is below 100 mrem/year (1 mSv/year) from site activities.

An annual high-pressure ion chamber (HPIC) gamma radiation measurement is completed at all locations in order to confirm TLD measurements.

Potential TLD sampling locations are continually evaluated with respect to site activities.

- Sampling locations are shown on Figure A-10 (p. A-12).

Appendix C

Summary of Water, Sediment, and Soil Monitoring Data



Collecting a Sample at a WVDP Stream Sampling Location

The following tables contain a bolding convention devised to help the reader, when viewing the data, to quickly see the range of detectable measurements within a data series. A data series is a set of chemical or radionuclide measurements (e.g., gross alpha, gross beta, tritium) from a single location or from similar locations. Note that some tables contain data that should not be technically evaluated under this convention.

Key to bolding convention:

Results for each constituent constitute a single data series. If a radiological result is larger than the uncertainty term, the measurement is considered positive. Otherwise, a result is considered nondetectable. Chemical results preceded by “less than” (<) are considered nondetectable.

If all results in a data series are positive, the lowest and highest values are bolded.

If a data series contains some positive results, the highest value is bolded.

If all values in a data series are nondetectable, no values are bolded.

Table C-1
Total Radioactivity (curies) of Liquid Effluents Released from Lagoon 3 (WNSP001)
in 2000

Isotope	1st Quarter	2nd Quarter	3rd Quarter	4th Quarter	Annual Total
Alpha	4.42±0.42E-04	9.37±2.85E-05	3.32±1.05E-04	1.12±0.18E-04	9.80±1.18E-04
Beta	6.09±0.12E-03	2.34±0.09E-03	6.62±0.24E-03	3.03±0.07E-03	1.81±0.03E-02
H-3	5.62±0.18E-02	1.75±0.10E-02	4.13±0.14E-02	2.00±0.10E-02	1.35±0.03E-01
C-14	3.11±0.72E-04	1.03±0.42E-04	2.94±0.59E-04	2.15±0.38E-04	9.22±1.09E-04
K-40	1.49±4.98E-04	1.49±4.45E-04	2.63±3.88E-04	-3.91±3.03E-04	1.70±8.30E-04
Co-60	0.74±2.63E-05	-0.75±1.85E-05	1.08±3.15E-05	0.81±1.81E-05	1.87±4.86E-05
Sr-90	9.41±0.64E-04	6.89±0.42E-04	2.89±0.08E-03	1.18±0.07E-03	5.70±0.13E-03
Tc-99	1.43±0.05E-03	2.02±0.52E-04	1.37±0.05E-03	4.80±0.49E-04	3.48±0.10E-03
I-129	6.31±1.45E-05	2.01±0.66E-05	4.20±1.21E-05	2.19±0.61E-05	1.47±0.21E-04
Cs-137	3.99±0.11E-03	1.03±0.06E-03	4.88±0.70E-04	3.75±0.38E-04	5.88±0.15E-03
U-232	2.58±0.20E-04	8.34±1.05E-05	1.49±0.14E-04	5.76±0.81E-05	5.48±0.28E-04
U-233/234	1.61±0.13E-04	4.69±0.64E-05	8.86±0.83E-05	3.37±0.49E-05	3.30±0.17E-04
U-235/236	5.25±1.32E-06	9.48±6.63E-07	2.99±0.99E-06	1.78±0.85E-06	1.10±0.20E-05
U-238	9.41±0.82E-05	2.75±0.44E-05	5.13±0.55E-05	1.87±0.33E-05	1.92±0.11E-04
Total U (g)	2.54±0.02E+02	8.72±0.39E+01	1.53±0.04E+02	5.47±0.07E+01	5.49±0.06E+02
Pu-238	1.10±0.54E-06	1.61±0.64E-06	3.27±0.88E-06	8.84±4.87E-07	6.86±1.31E-06
Pu-239/240	6.71±3.57E-07	1.40±2.01E-07	7.35±3.85E-07	3.65±3.01E-07	1.91±0.64E-06
Am-241	1.50±0.58E-06	1.42±2.01E-07	2.57±2.70E-07	4.74±3.62E-07	2.38±0.76E-06

Note: Bolding convention applied to these data. See page C-2.

Table C-2
Comparison of 2000 Lagoon 3 (WNSP001) Liquid Effluent Radioactivity
Concentrations with Department of Energy Guidelines

Isotope ^a	Discharge Activity ^b (Ci)	Radioactivity ^c (Becquerels)	Average Concentration (μ Ci/mL)	DCG (μ Ci/mL)	% of DCG
Alpha	9.80 \pm 1.18E-04	3.63 \pm 0.44E+07	2.24 \pm 0.27E-08	NA ^d	NA
Beta	1.81 \pm 0.03E-02	6.69 \pm 0.11E+08	4.14 \pm 0.07E-07	NA ^d	NA
H-3	1.35 \pm 0.03E-01	4.99 \pm 0.10E+09	3.09 \pm 0.06E-06	2E-3	0.15
C-14	9.22 \pm 1.09E-04	3.41 \pm 0.40E+07	2.11 \pm 0.25E-08	7E-5	0.03
K-40	1.70 \pm 8.30E-04	0.63 \pm 3.07E+07	0.39 \pm 1.90E-08	NA ^e	NA
Co-60	1.87 \pm 4.86E-05	0.69 \pm 1.80E+06	0.43 \pm 1.11E-09	5E-6	< 0.02
Sr-90	5.70 \pm 0.13E-03	2.11 \pm 0.05E+08	1.30 \pm 0.03E-07	1E-6	13.03
Tc-99	3.48 \pm 0.10E-03	1.29 \pm 0.04E+08	7.97 \pm 0.23E-08	1E-4	0.08
I-129	1.47 \pm 0.21E-04	5.44 \pm 0.77E+06	3.36 \pm 0.48E-09	5E-7	0.67
Cs-137	5.88 \pm 0.15E-03	2.18 \pm 0.05E+08	1.35 \pm 0.03E-07	3E-6	4.49
U-232^f	5.48 \pm 0.28E-04	2.03 \pm 0.10E+07	1.25 \pm 0.06E-08	1E-7	12.54
U-233/234^f	3.30 \pm 0.17E-04	1.22 \pm 0.06E+07	7.55 \pm 0.40E-09	5E-7	1.51
U-235/236^f	1.10 \pm 0.20E-05	4.06 \pm 0.73E+05	2.51 \pm 0.45E-10	5E-7 ^g	0.05
U-238^f	1.92 \pm 0.11E-04	7.09 \pm 0.42E+06	4.38 \pm 0.26E-09	6E-7	0.73
Pu-238	6.86 \pm 1.31E-06	2.54 \pm 0.48E+05	1.57 \pm 0.30E-10	4E-8	0.39
Pu-239/240	1.91 \pm 0.64E-06	7.07 \pm 2.36E+04	4.37 \pm 1.46E-11	3E-8	0.15
Am-241	2.38 \pm 0.76E-06	8.80 \pm 2.82E+04	5.44 \pm 1.74E-11	3E-8	0.18
Total % of DCGs					34.02

^a Half-lives are listed in Table K-1.

^b Total volume released: 4.37E+ 10 mL (1.15E+ 07 gal)

^c 1 curie (Ci) = 3.7E+ 10 becquerels (Bq); 1Bq = 2.7E-11 Ci.

^d Derived concentration guides (DCGs) are not applicable (NA) to gross alpha and gross beta.

^e Potassium-40 activity is not applicable because of its natural origin.

^f Total U (g) = 5.49 \pm 0.06E+02; Average U (μ g/mL) = 1.26 \pm 0.01E-02

^g DCG for U-236 is used for this comparison.

Note: Bolding convention not applicable to these data.

Table C-3
2000 Radioactivity Concentrations ($\mu\text{Ci/mL}$) and pH in Surface Water
Facility Yard Drainage (WNSP005)

Month	Alpha	Beta	H-3	pH (standard units)
January	1.99 \pm 2.28E-09	1.33 \pm 0.10E-07	6.38 \pm 8.30E-08	7.49
February	1.63 \pm 2.71E-09	1.31 \pm 0.08E-07	9.78 \pm 8.52E-08	7.89
March	2.71 \pm 2.27E-09	2.12 \pm 0.12E-07	1.49\pm0.84E-07	6.89
April	-1.41 \pm 1.50E-09	1.50 \pm 0.07E-07	9.40 \pm 8.35E-08	6.74
May	2.70 \pm 3.05E-09	1.53 \pm 0.10E-07	7.52 \pm 8.33E-08	6.90
June	1.75 \pm 3.43E-09	1.71 \pm 0.10E-07	6.44 \pm 8.30E-08	7.44
July	5.83\pm3.56E-09	1.83 \pm 0.12E-07	1.49 \pm 8.14E-08	7.01
August	-1.32 \pm 3.31E-09	1.86 \pm 0.11E-07	5.46 \pm 8.17E-08	7.49
September	-0.83 \pm 2.13E-09	1.36 \pm 0.08E-07	0.23 \pm 8.31E-08	7.20
October	2.13 \pm 1.77E-09	2.13\pm0.06E-07	9.57 \pm 8.26E-08	8.20
November	0.77 \pm 2.35E-09	9.96\pm0.61E-08	-1.10 \pm 0.80E-07	7.28
December	0.27 \pm 1.87E-09	1.42 \pm 0.07E-07	-1.08 \pm 0.80E-07	8.28

Note: Bolding convention applied to these data. See page C-2.

Table C-4
2000 Radioactivity Concentrations ($\mu\text{Ci/mL}$) in Surface Water
Downstream of the WVDP at Frank's Creek (WNSP006)

Month	Alpha	Beta	H-3	Sr-90	Cs-137
January*	1.71±1.17E-09	4.17±0.35E-08	2.37±0.73E-07	1.38±0.29E-08	1.02±0.79E-08
February	-0.45±1.19E-09	2.39±0.31E-08	7.57±8.12E-08	1.52±0.27E-08	1.86±1.67E-08
March*	1.26±2.10E-09	4.88±0.46E-08	2.22±0.81E-07	1.89±0.28E-08	5.49±1.09E-08
April	0.64±1.18E-09	2.74±0.31E-08	-1.81±8.33E-08	1.18±0.26E-08	2.11±1.14E-08
May*	1.64±1.31E-09	5.80±0.46E-08	1.85±0.86E-07	2.16±0.29E-08	1.71±1.17E-08
June	-0.07±1.28E-09	3.41±0.38E-08	-9.59±7.96E-08	1.38±0.24E-08	0.24±7.99E-09
July*	1.59±1.58E-09	7.53±0.44E-08	3.48±0.81E-07	3.18±0.27E-08	1.04±6.12E-09
August	0.88±1.78E-09	4.51±0.42E-08	9.45±7.74E-08	2.60±0.38E-08	8.06±7.73E-09
September*	0.40±1.91E-09	7.71±0.53E-08	1.73±0.80E-07	3.94±0.53E-08	-0.35±1.13E-08
October	0.85±1.61E-09	3.34±0.38E-08	0.92±8.33E-08	1.43±0.31E-08	4.37±7.45E-09
November*	1.00±1.61E-09	6.74±0.50E-08	2.79±0.86E-07	2.70±0.43E-08	0.81±1.05E-08
December	0.02±1.24E-09	2.50±0.34E-08	-1.13±8.32E-08	9.68±2.17E-09	0.26±1.16E-08

Quarter	C-14	Tc-99	I-129	U-232	U-233/234
1st Quarter	-0.86±4.00E-09	6.69±1.82E-09	8.76±8.07E-10	6.21±2.28E-10	6.87±2.60E-10
2nd Quarter	0.73±1.25E-08	1.28±1.58E-09	2.15±8.85E-10	3.16±1.52E-10	4.02±1.73E-10
3rd Quarter	7.97±8.61E-09	6.86±2.24E-09	1.85±5.10E-10	7.51±2.10E-10	5.07±1.99E-10
4th Quarter	-1.61±2.42E-08	1.97±1.82E-09	0.90±5.42E-10	3.17±0.80E-10	3.67±0.86E-10

	U-235/236	U-238	Total U ($\mu\text{g/mL}$)	Pu-238	Pu-239/240
1st Quarter	4.25±7.52E-11	3.85±1.89E-10	1.27±0.02E-03	4.95±3.79E-11	0.00±2.12E-11
2nd Quarter	0.00±4.93E-11	2.91±1.45E-10	6.80±0.10E-04	6.37±4.05E-11	1.13±1.60E-11
3rd Quarter	4.45±7.05E-11	3.33±1.55E-10	1.11±0.01E-03	6.10±4.59E-11	0.00±2.21E-11
4th Quarter	1.62±1.99E-11	2.22±0.66E-10	6.32±0.13E-04	4.68±3.60E-11	2.26±2.63E-11

	Am-241
1st Quarter	1.85±2.62E-11
2nd Quarter	5.36±6.24E-11
3rd Quarter	7.73±5.90E-11
4th Quarter	0.00±3.36E-11

* Lagoon 3 discharged through WNSP001 during these months.
See Table C-27 for a summary of water quality data at WNSP006.

Note: Bolding convention applied to these data. See page C-2.

Table C-5
2000 Radioactivity Concentrations ($\mu\text{Ci/mL}$) in Surface Water
Sewage Treatment Facility (WNSP007)

Month	Alpha	Beta	H-3
January	-0.54 \pm 2.69E-09	1.27 \pm 0.62E-08	5.24 \pm 8.32E-08
February	-1.44 \pm 2.89E-09	1.19\pm0.34E-08	0.80 \pm 8.26E-08
March	0.53 \pm 2.34E-09	1.73\pm0.51E-08	2.33 \pm 8.36E-08
April	-1.70 \pm 2.73E-09	1.40 \pm 0.42E-08	2.11 \pm 8.45E-08
May	1.23 \pm 3.16E-09	1.57 \pm 0.56E-08	2.74 \pm 8.24E-08
June	-2.54 \pm 3.69E-09	1.52 \pm 0.54E-08	-5.49 \pm 8.01E-08
July	1.54 \pm 2.18E-09	1.49 \pm 0.44E-08	-1.45 \pm 8.21E-08
August	-0.52 \pm 2.64E-09	1.55 \pm 0.41E-08	1.09 \pm 8.01E-08
September	-0.95 \pm 1.92E-09	1.60 \pm 0.37E-08	3.02 \pm 8.20E-08
October	1.52 \pm 2.94E-09	1.64 \pm 0.44E-08	0.17 \pm 8.27E-08
November	1.15 \pm 3.24E-09	1.70 \pm 0.42E-08	4.90 \pm 8.23E-08
December	0.88 \pm 3.49E-09	1.60 \pm 0.58E-08	5.69 \pm 8.17E-08

Quarter	Cs-137
1st Quarter	0.00 \pm 3.47E-09
2nd Quarter	2.46\pm2.18E-09
3rd Quarter	0.83 \pm 3.43E-09
4th Quarter	3.40 \pm 4.34E-09

Table C-6
2000 Radioactivity Concentrations ($\mu\text{Ci/mL}$) in Surface Water
French Drain (WNSP008)

Month	Alpha	Beta	H-3
January	0.87 \pm 1.56E-09	3.90 \pm 0.41E-08	1.26 \pm 0.10E-06
February	-2.47 \pm 1.86E-09	4.57 \pm 0.45E-08	1.92 \pm 0.12E-06
March	0.54 \pm 1.63E-09	4.42 \pm 0.43E-08	1.52 \pm 0.11E-06
April	-1.43 \pm 2.04E-09	3.49\pm0.39E-08	9.13\pm0.95E-07
May	1.56 \pm 2.28E-09	5.26 \pm 0.47E-08	1.62 \pm 0.11E-06
June	2.41\pm2.06E-09	5.31 \pm 0.46E-08	1.73 \pm 0.11E-06
July	1.58 \pm 2.45E-09	4.70 \pm 0.47E-08	1.55 \pm 0.08E-06
August	-3.34 \pm 2.43E-09	4.92 \pm 0.45E-08	1.40 \pm 0.10E-06
September	0.50 \pm 2.47E-09	6.61 \pm 0.62E-08	1.86 \pm 0.08E-06
October	0.49 \pm 2.30E-09	5.19 \pm 0.59E-08	1.20 \pm 0.10E-06
November	0.20 \pm 3.02E-09	7.33\pm0.68E-08	1.93\pm0.12E-06
December	-1.36 \pm 1.71E-09	6.26 \pm 0.43E-08	1.37 \pm 0.11E-06

Note: Bolding convention applied to these data. See page C-2.

Table C-7
2000 Radioactivity Concentrations (μCi/mL) and pH in Surface Water
Northeast Swamp (WNSWAMP)

Month	Alpha	Beta	H-3	Sr-90	Cs-137	pH (standard units)
<i>January</i>	-0.30±1.57E-09	1.80±0.02E-06	1.07±0.83E-07	9.00±0.25E-07	3.48±3.73E-09	6.99
<i>February</i>	1.46±1.69E-09	3.54±0.03E-06	1.58±0.83E-07	1.79±0.04E-06	-0.41±3.52E-09	6.92
<i>March</i>	2.74±1.86E-09	3.11±0.03E-06	1.31±0.80E-07	1.62±0.03E-06	0.59±2.27E-09	7.01
<i>April</i>	4.27±1.96E-09	2.79±0.03E-06	8.04±7.18E-08	1.38±0.03E-06	2.83±3.69E-09	6.99
<i>May</i>	-0.15±2.00E-09	3.34±0.03E-06	6.11±7.46E-08	1.73±0.03E-06	-0.36±3.51E-09	7.03
<i>June</i>	-0.09±2.33E-09	2.57±0.03E-06	1.59±0.78E-07	1.34±0.03E-06	1.86±2.15E-09	7.10
<i>July</i>	-1.67±2.26E-09	4.18±0.03E-06	1.21±0.77E-07	2.10±0.05E-06	5.74±3.55E-09	7.08
<i>August</i>	-0.24±1.70E-09	3.41±0.03E-06	1.06±0.71E-07	1.72±0.04E-06	1.82±2.16E-09	7.09
<i>September</i>	0.28±1.60E-09	3.60±0.03E-06	1.10±0.83E-07	1.86±0.04E-06	0.28±2.27E-09	7.25
<i>October</i>	-0.46±1.71E-09	2.35±0.02E-06	1.53±0.82E-07	1.09±0.04E-06	-1.21±2.19E-09	7.47
<i>November</i>	0.43±1.63E-09	2.47±0.02E-06	1.02±0.76E-07	1.31±0.03E-06	0.22±4.25E-09	6.91
<i>December</i>	0.62±1.44E-09	1.81±0.02E-06	0.05±8.20E-08	9.09±0.19E-07	2.20±4.28E-09	7.30
Quarter	C-14	I-129	U-232	U-233/234	U-235/236	
<i>1st Quarter</i>	5.30±5.16E-09	-5.93±7.30E-10	1.73±6.56E-11	3.02±1.73E-10	-2.07±2.09E-11	
<i>2nd Quarter</i>	0.96±2.45E-08	5.81±9.05E-10	0.50±2.29E-10	3.57±1.52E-10	2.87±8.11E-11	
<i>3rd Quarter</i>	5.52±8.56E-09	3.20±6.97E-10	0.50±1.08E-10	1.64±1.20E-10	2.50±6.61E-11	
<i>4th Quarter</i>	0.20±2.40E-08	7.19±5.37E-10	-0.27±2.59E-10	2.71±1.75E-10	0.43±1.03E-10	
	U-238	Total U (μg/mL)	Pu-238	Pu-239/240	Am-241	
<i>1st Quarter</i>	5.43±7.64E-11	5.54±0.28E-04	1.04±2.08E-11	-0.52±1.05E-11	3.01±3.57E-11	
<i>2nd Quarter</i>	1.86±1.19E-10	5.20±0.21E-04	1.34±4.66E-11	1.34±4.65E-11	1.11±1.00E-10	
<i>3rd Quarter</i>	1.40±1.02E-10	2.46±0.07E-04	1.50±1.19E-10	6.66±6.70E-11	1.33±2.56E-11	
<i>4th Quarter</i>	7.13±9.48E-11	1.63±0.03E-04	0.00±2.39E-11	1.69±2.40E-11	2.94±4.17E-11	

See Table C-27 for a summary of water quality data at WNSWAMP.

Note: Bolding convention applied to these data. See page C-2.

Table C-8
2000 Radioactivity Concentrations (μCi/mL) in Surface Water
North Swamp (WNSW74A)

Month	Alpha	Beta	H-3	Sr-90	Cs-137
January	-2.17±3.85E-09	1.10±0.51E-08	-1.60±8.13E-08	5.61±2.33E-09	4.35±7.35E-09
February	-1.51±8.55E-09	1.97±0.88E-08	1.86±8.19E-08	1.20±0.24E-08	0.36±1.10E-08
March	-0.50±3.63E-09	1.48±0.60E-08	-1.09±7.78E-08	6.13±1.82E-09	-1.65±7.68E-09
April	-0.06±2.35E-09	1.21±0.48E-08	-2.15±8.27E-08	5.20±2.84E-09	0.15±1.27E-08
May	0.35±2.20E-09	9.80±5.65E-09	-8.45±8.35E-08	5.93±1.82E-09	-0.30±1.14E-08
June	0.22±1.39E-09	9.08±2.59E-09	-9.25±8.29E-08	4.36±1.14E-09	0.08±6.52E-09
July	1.26±1.68E-09	7.20±2.44E-09	0.13±8.03E-08	3.81±2.26E-09	-6.61±6.96E-09
August	-0.26±1.59E-09	1.07±0.23E-08	1.08±7.57E-08	5.36±1.91E-09	6.93±9.23E-09
September	-0.62±2.14E-09	7.68±3.79E-09	0.19±7.34E-08	6.43±1.98E-09	0.31±1.09E-08
October	0.37±1.76E-09	1.23±0.29E-08	-1.99±7.65E-08	4.85±2.38E-09	2.68±6.95E-09
November	0.87±2.07E-09	1.90±0.34E-08	-5.78±7.66E-08	5.23±2.81E-09	0.88±1.12E-08
December	-0.51±3.80E-09	8.78±4.60E-09	-7.82±7.77E-08	4.04±1.70E-09	-4.65±8.10E-09

Quarter	C-14	I-129	U-232	U-233/234	U-235/236
1st Quarter	-1.67±3.94E-09	1.33±7.42E-10	-1.27±4.84E-11	1.24±1.05E-10	1.48±4.96E-11
2nd Quarter	0.00±1.19E-08	-0.80±4.57E-10	0.78±8.55E-11	1.01±0.78E-10	1.45±2.91E-11
3rd Quarter	1.15±3.05E-09	-3.02±5.85E-10	2.73±7.34E-11	1.12±0.81E-10	0.05±2.84E-11
4th Quarter	0.57±2.57E-08	-0.38±3.62E-10	2.05±3.48E-11	1.58±0.48E-10	0.97±1.12E-11

	U-238	Total U (μg/mL)	Pu-238	Pu-239/240	Am-241
1st Quarter	1.33±1.05E-10	3.58±0.06E-04	1.72±5.24E-11	1.43±1.76E-11	4.84±4.70E-11
2nd Quarter	4.34±5.04E-11	2.59±0.06E-04	5.92±5.98E-11	1.48±2.97E-11	1.89±3.79E-11
3rd Quarter	1.41±0.87E-10	3.00±0.07E-04	0.00±2.97E-11	0.00±2.96E-11	0.70±3.71E-11
4th Quarter	1.39±0.45E-10	4.06±0.09E-04	1.16±1.07E-10	4.87±6.94E-11	0.00±2.13E-11

See Table C-27 for a summary of water quality data at WNSW74A.

Note: Bolding convention applied to these data. See page C-2.

Table C-9
2000 Radioactivity Concentrations ($\mu\text{Ci/mL}$) and pH in Surface Water
Frank's Creek East of the SDA (WNFRC67)

Month	Alpha	Beta	H-3	pH (standard units)
January	-1.04 \pm 2.73E-10	2.45 \pm 0.89E-09	5.59 \pm 5.90E-08	7.50
February	-2.30 \pm 5.17E-10	2.78 \pm 1.34E-09	-0.40 \pm 8.30E-08	7.66
March	1.67 \pm 3.07E-10	3.00 \pm 0.89E-09	-4.30 \pm 8.10E-08	6.80
April	1.71 \pm 5.29E-10	1.41 \pm 1.16E-09	6.26 \pm 5.89E-08	5.82
May	3.21 \pm 3.73E-10	9.00\pm1.13E-09	1.06\pm0.84E-07	7.10
June	0.61 \pm 6.65E-10	2.63 \pm 1.34E-09	1.68 \pm 8.36E-08	7.35
July	-2.07 \pm 8.85E-10	1.01 \pm 1.30E-09	-4.28 \pm 8.22E-08	6.98
August	-7.42 \pm 7.06E-10	2.65 \pm 1.19E-09	0.50 \pm 5.77E-08	7.02
September	6.16 \pm 9.60E-10	3.77 \pm 1.28E-09	-3.25 \pm 8.24E-08	7.06
October	-3.27 \pm 7.38E-10	3.00 \pm 1.21E-09	-6.80 \pm 8.11E-08	8.41
November	-2.02 \pm 7.12E-10	2.68 \pm 1.34E-09	-1.65 \pm 0.78E-07	6.75
December	6.15 \pm 6.88E-10	3.15 \pm 1.36E-09	-2.39 \pm 8.22E-08	8.34

Table C-10
2000 Radioactivity Concentrations ($\mu\text{Ci/mL}$) and pH in Surface Water
Erdman Brook (WNERB53)

Month	Alpha	Beta	H-3	pH (standard units)
January	-0.16 \pm 1.26E-09	1.95 \pm 0.31E-08	0.47 \pm 8.15E-08	7.04
February	-1.07 \pm 1.50E-09	2.18 \pm 0.31E-08	7.49 \pm 8.23E-08	6.87
March	-0.19 \pm 3.24E-09	2.12 \pm 0.46E-08	3.04 \pm 7.84E-08	6.96
April	-0.32 \pm 1.49E-09	1.34\pm0.27E-08	3.92 \pm 8.31E-08	7.02
May	0.25 \pm 1.11E-09	1.57 \pm 0.25E-08	-1.79 \pm 8.41E-08	7.17
June	0.11 \pm 1.25E-09	1.73 \pm 0.26E-08	2.13 \pm 7.75E-08	7.31
July	0.45 \pm 1.88E-09	1.40 \pm 0.26E-08	0.84 \pm 8.15E-08	7.15
August	0.00 \pm 1.44E-09	2.47\pm0.29E-08	5.12 \pm 8.20E-08	7.23
September	-0.60 \pm 1.76E-09	1.93 \pm 0.33E-08	-1.33 \pm 8.21E-08	7.33
October	0.06 \pm 1.40E-09	1.86 \pm 0.31E-08	-0.70 \pm 8.28E-08	7.62
November	-1.34 \pm 3.44E-09	1.98 \pm 0.47E-08	2.42 \pm 8.23E-08	6.64
December	-0.40 \pm 1.22E-09	2.02 \pm 0.31E-08	-5.52 \pm 8.23E-08	7.12

Note: Bolding convention applied to these data. See page C-2.

Table C-11
2000 Radioactivity Concentrations ($\mu\text{Ci/mL}$) and pH in Surface Water
Cooling Tower Basin (WNCoolW)

Month	Alpha	Beta	H-3	pH (standard units)
January	-2.91 \pm 8.70E-10	3.27 \pm 2.46E-09	-1.23 \pm 8.15E-08	7.92
February	-0.68 \pm 1.07E-09	2.16 \pm 2.51E-09	-2.18 \pm 8.26E-08	8.47
March	1.10 \pm 1.38E-09	4.47 \pm 3.49E-09	1.72 \pm 8.19E-08	7.33
April	-0.27 \pm 1.53E-09	3.48 \pm 3.44E-09	5.47 \pm 8.30E-08	7.81
May	0.88 \pm 1.86E-09	7.34 \pm 3.77E-09	8.68\pm8.26E-08	8.28
June	0.09 \pm 1.44E-09	4.41 \pm 3.15E-09	-4.23 \pm 8.13E-08	8.19
July	3.39\pm2.61E-09	3.68 \pm 3.88E-09	1.71 \pm 8.13E-08	8.30
August	-1.89 \pm 2.85E-09	7.14 \pm 3.62E-09	-3.20 \pm 8.06E-08	8.83
September	-0.43 \pm 2.84E-09	1.38\pm0.38E-08	4.20 \pm 8.34E-08	8.64
October	0.74 \pm 2.60E-09	1.13 \pm 0.41E-08	0.80 \pm 8.15E-08	8.88
November	-0.95 \pm 2.18E-09	3.44 \pm 3.75E-09	7.93 \pm 5.78E-08	8.47
December	-0.43 \pm 1.41E-09	5.58 \pm 2.73E-09	-7.02 \pm 7.98E-08	7.94
Quarter	Cs-137			
1st Quarter	3.02 \pm 6.70E-09			
2nd Quarter	-0.13 \pm 1.22E-08			
3rd Quarter	-5.98 \pm 7.30E-09			
4th Quarter	0.40 \pm 1.20E-08			

Table C-12
2000 Radioactivity Concentrations ($\mu\text{Ci/mL}$) and pH in Surface Water
SDA Drainage (WNSDADR)

Month	Alpha	Beta	H-3	Cs-137	pH (standard units)
January	3.90 \pm 2.75E-10	6.08 \pm 0.97E-09	9.52 \pm 5.88E-08	-4.63 \pm 7.18E-09	6.66
February	-2.38 \pm 7.51E-10	3.11 \pm 0.82E-09	2.92\pm0.86E-07	0.41 \pm 1.06E-08	6.97
March	1.78\pm0.45E-09	8.89\pm1.07E-09	2.85 \pm 0.86E-07	0.05 \pm 1.17E-08	7.22
April	4.29 \pm 2.91E-10	3.65 \pm 0.83E-09	6.47 \pm 8.28E-08	0.41 \pm 1.16E-08	6.62
May	8.26 \pm 3.18E-10	4.84 \pm 0.90E-09	2.22 \pm 0.84E-07	6.71\pm6.00E-09	7.22
June	8.77 \pm 4.33E-10	1.50 \pm 0.79E-09	2.44 \pm 0.60E-07	0.36 \pm 8.53E-09	5.96
July	8.96 \pm 3.48E-10	1.31\pm0.77E-09	2.65 \pm 0.59E-07	-1.04 \pm 1.21E-08	6.02
August	6.74 \pm 3.50E-10	3.77 \pm 0.85E-09	1.75 \pm 0.82E-07	0.72 \pm 1.18E-08	6.41
September	4.58 \pm 2.86E-10	1.86 \pm 0.70E-09	-0.95 \pm 8.14E-08	0.19 \pm 1.11E-08	7.24
October	0.00 \pm 5.28E-10	3.35 \pm 0.82E-09	1.07 \pm 0.84E-07	-0.66 \pm 1.11E-08	7.10
November	7.79 \pm 3.20E-10	3.25 \pm 0.85E-09	1.26 \pm 0.82E-07	-0.69 \pm 7.20E-09	7.72
December	0.60 \pm 4.29E-10	2.10 \pm 0.81E-09	1.98 \pm 0.60E-07	-4.07 \pm 8.00E-09	7.68

Note: Bolding convention applied to these data. See page C-2.

Table C-13
2000 Radioactivity Concentrations ($\mu\text{Ci/mL}$) and pH in Surface Water
Waste Tank Farm Underdrain (WN8D1DR)

Month	Alpha	Beta	H-3	Sr-90	Cs-137	pH (standard units)
January	-1.65 \pm 4.58E-09	1.69 \pm 0.81E-08	-4.92 \pm 7.56E-08	3.82 \pm 2.04E-09	3.72 \pm 7.93E-09	7.28
February	-1.66 \pm 7.72E-09	1.99\pm0.81E-08	-0.68 \pm 7.51E-08	8.53\pm2.15E-09	0.57 \pm 7.23E-09	7.11
March	-1.55 \pm 6.53E-09	1.02 \pm 0.74E-08	-1.81 \pm 8.16E-08	2.94 \pm 1.49E-09	-0.61 \pm 1.07E-08	7.19
April	1.54 \pm 7.07E-09	5.90 \pm 7.45E-09	-1.64 \pm 8.28E-08	0.96 \pm 2.14E-09	0.83 \pm 5.95E-09	7.22
May	1.68 \pm 4.26E-09	6.56 \pm 6.20E-09	-1.02 \pm 0.77E-07	5.52 \pm 1.79E-09	4.44 \pm 6.08E-09	7.28
June	-0.35 \pm 2.99E-09	6.47 \pm 6.36E-09	-6.21 \pm 8.23E-08	0.79 \pm 1.18E-09	0.05 \pm 3.44E-09	7.21
July	1.33 \pm 3.06E-09	-2.17 \pm 5.62E-09	-2.82 \pm 7.50E-08	1.40 \pm 1.77E-09	2.58 \pm 6.11E-09	7.09
August	0.60 \pm 3.07E-09	4.17 \pm 5.85E-09	4.73 \pm 8.15E-08	2.96 \pm 1.61E-09	-0.36 \pm 4.67E-09	6.81
September	-0.64 \pm 3.73E-09	3.60 \pm 7.13E-09	-5.88 \pm 7.69E-08	0.74 \pm 1.94E-09	-2.87 \pm 6.80E-09	6.95
October	-1.47 \pm 3.84E-09	7.59 \pm 7.04E-09	-0.05 \pm 8.12E-08	1.83 \pm 1.92E-09	0.12 \pm 1.14E-08	7.60
November	-0.21 \pm 4.95E-09	9.68 \pm 7.58E-09	0.75 \pm 8.28E-08	0.38 \pm 2.28E-09	0.80 \pm 7.04E-09	7.00
December	-0.93 \pm 7.30E-09	1.78 \pm 0.83E-08	-4.94 \pm 8.22E-08	3.96 \pm 2.02E-09	0.67 \pm 1.02E-08	7.27

Table C-14
2000 Radioactivity Concentrations ($\mu\text{Ci/mL}$) in Surface Water
Drum Cell Drainage (WNDCELD)

Month	Alpha	Beta			
January	1.02\pm0.46E-09	3.69 \pm 0.92E-09			
February	-3.81 \pm 5.21E-10	3.10 \pm 1.16E-09			
March	-2.21 \pm 5.94E-10	3.89 \pm 1.26E-09			
April	-0.46 \pm 4.88E-10	1.20 \pm 1.14E-09			
May	6.37 \pm 4.80E-10	3.27 \pm 1.21E-09			
June	0.00 \pm 6.95E-10	0.04 \pm 1.21E-09			
July	-0.32 \pm 1.01E-09	0.75 \pm 1.31E-09			
August	-4.32 \pm 6.92E-10	5.36\pm1.12E-09			
September	7.77 \pm 6.70E-10	3.34 \pm 1.21E-09			
October	-1.65 \pm 8.93E-10	3.32 \pm 1.43E-09			
November	-4.02 \pm 6.36E-10	4.28 \pm 1.32E-09			
December	2.47 \pm 4.27E-10	1.36 \pm 0.89E-09			
Quarter	H-3	Sr-90	I-129	Cs-137	
1st Quarter	-4.33 \pm 8.34E-08	2.46\pm1.15E-09	0.23 \pm 1.08E-09	6.63 \pm 8.09E-09	
2nd Quarter	1.12\pm0.57E-07	0.15 \pm 1.01E-09	0.90 \pm 7.06E-10	-5.30 \pm 6.70E-09	
3rd Quarter	-2.70 \pm 8.18E-08	1.59 \pm 2.02E-09	-3.25 \pm 6.53E-10	-1.56 \pm 6.92E-09	
4th Quarter	-8.25 \pm 8.25E-08	0.42 \pm 1.31E-09	4.92 \pm 6.43E-10	6.14 \pm 6.19E-09	

Note: Bolding convention applied to these data. See page C-2.

Table C-15
2000 Radioactivity Concentrations ($\mu\text{Ci/mL}$), pH, and Conductivity
Environmental Laboratory Potable Water (WNDNKEL)

Month	Alpha	Beta	H-3	pH (standard units)	Conductivity ($\mu\text{mhos/cm@25}^\circ\text{C}$)
January	0.00 \pm 2.94E-10	1.59 \pm 0.78E-09	-1.57 \pm 8.13E-08	7.64	199
February	-2.82 \pm 3.78E-10	6.36 \pm 7.65E-10	-1.83 \pm 5.80E-08	7.94	209
March	-0.67 \pm 2.62E-10	1.07 \pm 0.72E-09	0.20 \pm 8.17E-08	7.25	219
April	-1.73 \pm 3.83E-10	1.46 \pm 0.71E-09	-1.78 \pm 8.17E-08	7.03	194
May	2.09 \pm 3.83E-10	1.97 \pm 0.78E-09	8.87\pm8.17E-08	7.62	183
June	-1.36 \pm 2.91E-10	2.88 \pm 0.57E-09	2.54 \pm 8.19E-08	7.14	205
July	-0.27 \pm 3.37E-10	4.54\pm0.65E-09	2.24 \pm 8.12E-08	7.29	219
August	-4.21 \pm 5.57E-10	1.85 \pm 0.74E-09	1.59 \pm 7.94E-08	7.13	223
September	3.32 \pm 5.92E-10	2.67 \pm 0.79E-09	-5.32 \pm 8.09E-08	7.83	224
October	-5.48 \pm 5.41E-10	2.20 \pm 0.76E-09	5.57 \pm 8.16E-08	8.33	227
November	0.75 \pm 4.04E-10	7.86 \pm 7.60E-10	-1.31 \pm 0.78E-07	7.39	236
December	0.29 \pm 4.72E-10	1.90 \pm 0.74E-09	5.51 \pm 8.16E-08	6.91	201

Table C-16
2000 Radioactivity Concentrations ($\mu\text{Ci/mL}$), pH, and Conductivity
Maintenance Shop Potable Water (WNDNKMS)

Month	Alpha	Beta	H-3	pH (standard units)	Conductivity ($\mu\text{mhos/cm@25}^\circ\text{C}$)
January	0.00 \pm 3.24E-10	1.72 \pm 0.79E-09	4.15 \pm 8.24E-08	7.82	218
February	-2.49 \pm 3.88E-10	4.77 \pm 7.56E-10	-3.01 \pm 8.32E-08	7.76	624
March	1.04 \pm 3.11E-10	1.16 \pm 0.73E-09	4.25 \pm 8.23E-08	7.07	221
April	-3.14 \pm 3.55E-10	7.57 \pm 7.08E-10	5.45 \pm 8.28E-08	7.31	221
May	0.37 \pm 2.40E-10	3.71\pm0.62E-09	4.79 \pm 8.16E-08	7.18	190
June	2.19 \pm 3.03E-10	2.23 \pm 0.75E-09	4.07 \pm 8.29E-08	7.70	215
July	0.54 \pm 3.53E-10	3.34 \pm 0.63E-09	0.58 \pm 8.14E-08	7.12	229
August	-5.67 \pm 4.49E-10	2.18 \pm 0.76E-09	-0.37 \pm 7.92E-08	7.50	210
September	-1.56 \pm 5.60E-10	2.42 \pm 0.78E-09	-2.20 \pm 8.19E-08	7.29	222
October	-2.76 \pm 6.22E-10	2.15 \pm 0.77E-09	1.79 \pm 8.14E-08	8.66	223
November	-1.54 \pm 3.69E-10	1.89 \pm 0.82E-09	-1.36 \pm 0.78E-07	7.03	246
December	-1.20 \pm 4.71E-10	2.28 \pm 0.76E-09	3.52 \pm 8.10E-08	6.64	215

Note: Bolding convention applied to these data. See page C-2.

Table C-17
2000 Radioactivity Concentrations ($\mu\text{Ci/mL}$), pH, and Conductivity
Main Plant Potable Water (WNDNKMP)

Month	Alpha	Beta	H-3	pH (standard units) ($\mu\text{mhos/cm@25}^\circ\text{C}$)	Conductivity
January	2.33 \pm 3.63E-10	2.55 \pm 0.83E-09	8.55 \pm 8.27E-08	7.70	189
February	-2.13 \pm 3.92E-10	9.08\pm7.80E-10	3.88 \pm 8.35E-08	7.22	226
March	-0.34 \pm 2.73E-10	1.82 \pm 0.76E-09	1.30\pm0.83E-07	7.14	212
April	1.74 \pm 4.34E-10	1.13 \pm 0.69E-09	9.37 \pm 8.35E-08	6.95	192
May	4.23\pm4.18E-10	3.93 \pm 0.89E-09	1.00 \pm 0.82E-07	7.29	182
June	2.94 \pm 3.22E-10	1.31 \pm 0.70E-09	-0.72 \pm 8.13E-08	7.60	210
July	0.53 \pm 3.57E-10	3.51 \pm 0.66E-09	8.14 \pm 8.21E-08	7.02	226
August	-2.49 \pm 3.98E-10	4.07\pm0.62E-09	-3.46 \pm 7.92E-08	7.30	230
September	-1.57 \pm 5.65E-10	2.75 \pm 0.79E-09	-0.03 \pm 8.23E-08	7.23	225
October	-0.72 \pm 5.88E-10	2.52 \pm 0.78E-09	-5.93 \pm 8.05E-08	8.39	229
November	0.77 \pm 4.13E-10	1.12 \pm 0.78E-09	-9.89 \pm 7.89E-08	6.89	244
December	-3.30 \pm 4.44E-10	2.09 \pm 0.75E-09	-1.73 \pm 8.10E-08	6.64	211

Note: Bolding convention applied to these data. See page C-2.

Table C-18
2000 Radioactivity Concentrations ($\mu\text{Ci/mL}$) and Water Quality Parameters
Utility Room Potable Water (WNDNKUR)

Month	Alpha	Beta	H-3	pH (standard units)	Conductivity ($\mu\text{mhos/cm@25}^\circ\text{C}$)
January	0.00 \pm 3.16E-10	4.55 \pm 0.93E-09	4.64 \pm 8.20E-08	7.80	192
February	-2.00 \pm 3.68E-10	8.80\pm7.74E-10	4.86 \pm 8.38E-08	7.80	220
March	3.92\pm3.50E-10	1.68 \pm 0.75E-09	-2.61 \pm 5.71E-08	7.14	225
April	-1.15 \pm 3.90E-10	1.71 \pm 0.73E-09	4.41 \pm 8.25E-08	6.88	199
May	3.92\pm2.73E-10	5.84\pm0.70E-09	-3.86 \pm 5.89E-08	7.40	184
June	1.20 \pm 3.05E-10	2.17 \pm 0.75E-09	5.02 \pm 8.24E-08	7.60	204
July	2.46 \pm 5.80E-10	1.35 \pm 0.83E-09	-1.69 \pm 8.07E-08	7.08	229
August	-3.11 \pm 5.43E-10	4.98 \pm 0.91E-09	-3.56 \pm 8.08E-08	7.54	220
September	3.84 \pm 6.20E-10	2.76 \pm 0.79E-09	-3.73 \pm 8.08E-08	7.15	220
October	-2.14 \pm 5.68E-10	2.55 \pm 0.78E-09	4.36 \pm 8.15E-08	8.37	229
November	3.42 \pm 4.52E-10	2.02 \pm 0.83E-09	-6.59 \pm 7.96E-08	7.13	233
December	-3.59 \pm 4.39E-10	1.79 \pm 0.73E-09	-1.03 \pm 5.70E-08	6.91	196

March	Fluoride Total (mg/L)	Nitrate-N (mg/L)	Cyanide Total (mg/L)	Antimony Total ($\mu\text{g/L}$)	Arsenic Total ($\mu\text{g/L}$)	Barium Total ($\mu\text{g/L}$)
	< 0.10	NA	< 0.01	< 60.0	< 25.0	< 200

March	Beryllium Total ($\mu\text{g/L}$)	Cadmium Total ($\mu\text{g/L}$)	Chromium Total ($\mu\text{g/L}$)	Mercury Total ($\mu\text{g/L}$)	Nickel Total ($\mu\text{g/L}$)	Selenium Total ($\mu\text{g/L}$)
	< 5.00	< 2.00	< 10.0	< 0.40	< 40.0	< 0.60

March	Thallium Total ($\mu\text{g/L}$)
	< 3.00

NA - NO_3 collected and analyzed by the Cattaraugus County Health Department.

Note: Bolding convention applied to these data. See page C-2.

Table C-19
2000 Radioactivity Concentrations ($\mu\text{Ci/mL}$) and Water Quality Parameters
Storage and Disposal Area Drainage (WNNDADR)

Month	Alpha	Beta	H-3	Cs-137	NPOC* (mg/L)
January	-0.52 \pm 9.35E-10	2.18 \pm 0.06E-07	7.69 \pm 0.92E-07	-4.52 \pm 6.15E-09	11.18
February	1.04 \pm 2.02E-09	1.58 \pm 0.06E-07	1.02 \pm 0.10E-06	-0.41 \pm 1.07E-08	9.22
March	2.65 \pm 6.94E-10	1.41\pm0.04E-07	1.05 \pm 0.10E-06	0.07 \pm 1.08E-08	6.08
April	0.23 \pm 1.29E-09	1.80 \pm 0.06E-07	9.15 \pm 0.95E-07	-0.16 \pm 1.25E-08	9.38
May	1.17 \pm 0.90E-09	2.01 \pm 0.05E-07	1.58 \pm 0.11E-06	2.87 \pm 7.49E-09	6.98
June	0.19 \pm 1.00E-09	2.00 \pm 0.05E-07	1.66 \pm 0.10E-06	-2.73 \pm 8.92E-09	8.30
July	0.64 \pm 1.80E-09	2.20 \pm 0.07E-07	2.10\pm0.12E-06	0.19 \pm 6.72E-09	8.44
August	-2.08 \pm 9.65E-10	2.05 \pm 0.05E-07	1.77 \pm 0.11E-06	-0.44 \pm 5.20E-09	9.53
September	2.36\pm1.83E-09	2.13 \pm 0.08E-07	1.67 \pm 0.11E-06	-1.11 \pm 9.36E-09	7.56
October	-1.12 \pm 1.23E-09	2.26\pm0.06E-07	1.16 \pm 0.07E-06	0.53 \pm 1.18E-08	6.98
November	-0.70 \pm 1.44E-09	1.98 \pm 0.08E-07	1.08 \pm 0.10E-06	-0.77 \pm 7.59E-09	5.00
December	-0.53 \pm 1.42E-09	1.59 \pm 0.07E-07	7.37\pm0.93E-07	0.93 \pm 6.85E-09	5.50

	TOX* ($\mu\text{g/L}$)	pH* (standard units)
January	12.7	7.13
February	27.3	6.82
March	21.1	7.10
April	9.20	7.15
May	13.1	7.22
June	15.8	7.39
July	16.0	7.10
August	15.5	7.26
September	17.7	7.37
October	30.3	7.56
November	17.7	6.83
December	10.3	7.44

Quarter	Sr-90**	I-129**
1st Quarter	9.12 \pm 0.57E-08	3.75 \pm 7.75E-10
2nd Quarter	9.35 \pm 0.57E-08	0.35 \pm 9.01E-10
3rd Quarter	1.04\pm0.07E-07	-0.28 \pm 1.10E-09
4th Quarter	8.92\pm0.55E-08	0.43 \pm 3.92E-10

* Monthly average of weekly measurements.

** Monthly samples are composited and analyzed quarterly.

Note: Bolding convention applied to these data. See page C-2.

Table C-20
2000 Radioactivity Concentrations ($\mu\text{Ci/mL}$), NPOC, and TOX
in Groundwater at the NDA Interceptor Trench (WNNDATR)

Month	Alpha	Beta	H-3	Cs-137	NPOC (mg/L)	TOX ($\mu\text{g/L}$)
January	1.59 \pm 1.68E-09	1.08 \pm 0.06E-07	5.04 \pm 0.20E-06	0.06 \pm 7.20E-09	23.0	13.6
February	0.88 \pm 1.54E-09	8.47 \pm 0.40E-08	1.02 \pm 0.03E-05	-0.72 \pm 5.94E-09	4.2	184.0
March	2.67 \pm 2.11E-09	1.16 \pm 0.06E-07	5.96 \pm 0.23E-06	0.10 \pm 1.04E-08	3.3	14.8
April	0.92 \pm 1.97E-09	1.20\pm0.06E-07	3.49 \pm 0.16E-06	2.24 \pm 6.30E-09	7.4	26.8
May	3.43 \pm 2.47E-09	8.73 \pm 0.56E-08	9.40 \pm 0.33E-06	0.70 \pm 7.31E-09	4.8	11.5
June	3.70 \pm 1.68E-09	7.89\pm0.38E-08	1.32\pm0.04E-05	2.24 \pm 7.38E-09	4.7	11.3
July	4.22\pm2.42E-09	8.29 \pm 0.57E-08	1.02 \pm 0.03E-05	0.79 \pm 1.10E-08	6.9	17.3
August	-0.73 \pm 1.27E-09	9.61 \pm 0.56E-08	9.83\pm0.94E-07	-2.98 \pm 9.96E-09	11.7	14.4
September	1.50 \pm 2.07E-09	9.82 \pm 0.58E-08	1.02 \pm 0.03E-05	0.85 \pm 7.26E-09	5.9	19.8
October	1.57 \pm 1.41E-09	9.64 \pm 0.42E-08	6.81 \pm 0.18E-06	0.37 \pm 1.00E-08	1.0	23.4
November	2.94 \pm 2.51E-09	9.17 \pm 0.58E-08	1.20 \pm 0.04E-05	5.37 \pm 8.00E-09	5.1	26.8
December	2.81 \pm 1.91E-09	1.19 \pm 0.06E-07	3.73 \pm 0.16E-06	0.39 \pm 1.15E-08	7.5	15.7
Quarter	I-129					
1st Quarter	-1.13 \pm 7.97E-10					
2nd Quarter	3.66 \pm 7.52E-10					
3rd Quarter	3.61 \pm 8.10E-10					
4th Quarter	1.48 \pm 4.87E-10					

Note: Bolding convention applied to these data. See page C-2.

Table C-21
2000 Radioactivity Concentrations ($\mu\text{Ci/mL}$) and Water Quality Parameters in
Surface Water at the Standing Water (WNSTAW-series) Sampling Locations

Location	Date	Alpha	Beta	H-3	pH*	Conductivity*
					(standard units)	($\mu\text{mhos/cm@25}^\circ\text{C}$)
WNSTAW4	10/31	0.15 \pm 3.09E-10	4.08 \pm 1.07E-09	3.24 \pm 8.38E-08	7.26	105
WNSTAW5	10/31	1.76 \pm 2.92E-10	8.51 \pm 8.96E-10	-4.08 \pm 8.37E-08	7.47	56
WNSTAW6	10/31	0.45 \pm 4.73E-10	3.37 \pm 1.07E-09	1.42 \pm 5.89E-08	7.95	238
WNSTAW9	10/31	0.00 \pm 4.31E-10	1.44 \pm 0.96E-09	-6.89 \pm 8.24E-08	7.30	224
WNSTAWB**	10/31	-3.29 \pm 6.17E-10	2.73 \pm 1.08E-09	-7.69 \pm 8.18E-08	8.46	399

		Chloride	Nitrate +Nitrite	Sulfate	Iron Total	Manganese Total	Sodium Total
		(mg/L)	(mg/L)	(mg/L)	($\mu\text{g/L}$)	($\mu\text{g/L}$)	($\mu\text{g/L}$)
WNSTAW4	10/31	5.8	<0.05	6.5	367	64	4,130
WNSTAW5	10/31	<1.0	<0.05	6.8	1,160	154	1,130
WNSTAW6	10/31	2.3	<0.05	11.6	100	32	1,090
WNSTAW9	10/31	7.8	<0.05	14.7	160	88	5,410
WNSTAWB**	10/31	24.5	<0.05	11.8	127	129	15,100

* Average of two measurements.

** Background location.

Note: Bolding convention not applicable to these data.

Table C-22
2000 Radioactivity Concentrations ($\mu\text{Ci/mL}$), pH, and Conductivity in Surface
Water Upstream of the WVDP in Buttermilk Creek at Fox Valley (WFBCBKG)**

Month	Alpha	Beta	H-3	pH* (standard units) ($\mu\text{mhos/cm@25}^\circ\text{C}$)	Conductivity*
January	-1.79 \pm 5.25E-10	1.63 \pm 1.24E-09	0.43 \pm 8.23E-08	7.09	254
February	-8.20 \pm 6.88E-10	2.33 \pm 1.15E-09	-7.71 \pm 8.12E-08	7.03	304
March	2.41 \pm 7.14E-10	3.24 \pm 1.23E-09	3.70 \pm 8.38E-08	7.23	252
April	1.06 \pm 5.89E-10	2.53 \pm 1.23E-09	0.73 \pm 8.34E-08	7.55	212
May	0.00 \pm 4.36E-10	2.31 \pm 1.21E-09	4.76 \pm 8.21E-08	7.54	235
June	2.28 \pm 6.52E-10	1.73 \pm 1.29E-09	5.48 \pm 7.92E-08	7.10	244
July	0.57 \pm 7.65E-10	0.76 \pm 1.27E-09	-3.20 \pm 8.04E-08	7.02	277
August	1.86 \pm 6.97E-10	2.01 \pm 1.24E-09	2.74 \pm 8.01E-08	7.16	255
September	6.44 \pm 7.35E-10	2.72 \pm 1.19E-09	2.26 \pm 8.16E-08	7.35	304
October	4.59 \pm 8.99E-10	3.45\pm1.24E-09	1.60 \pm 8.07E-08	7.47	279
November	-1.46 \pm 7.32E-10	2.25 \pm 1.20E-09	-1.26 \pm 0.82E-07	6.76	281
December	1.87 \pm 6.85E-10	0.47 \pm 1.18E-09	-1.39 \pm 0.81E-07	6.80	223

Quarter	C-14	Sr-90	Tc-99	I-129	Cs-137
1st Quarter	4.47\pm4.14E-09	8.58 \pm 7.47E-10	2.28\pm1.83E-09	4.88\pm4.74E-10	2.51\pm2.23E-09
2nd Quarter	0.40 \pm 1.21E-08	1.14 \pm 1.14E-09	-0.51 \pm 1.10E-09	0.68 \pm 8.54E-10	1.11 \pm 3.42E-09
3rd Quarter	-0.36 \pm 2.99E-09	6.66\pm1.98E-09	0.89 \pm 1.67E-09	-0.42 \pm 1.06E-09	2.99 \pm 3.51E-09
4th Quarter	1.09 \pm 2.55E-08	2.88 \pm 8.94E-10	1.52 \pm 1.88E-09	1.81 \pm 5.05E-10	1.97 \pm 4.24E-09

	U-232	U-233/234	U-235/236	U-238	Total U ($\mu\text{g/mL}$)
1st Quarter	5.48 \pm 6.22E-11	9.94 \pm 5.83E-11	-0.84 \pm 1.19E-11	2.48 \pm 3.53E-11	8.88\pm0.21E-05
2nd Quarter	-2.97 \pm 6.29E-11	9.12 \pm 7.55E-11	1.16 \pm 3.14E-11	5.72 \pm 6.17E-11	1.30 \pm 0.03E-04
3rd Quarter	-3.16 \pm 2.60E-11	1.42\pm0.97E-10	1.87 \pm 3.67E-11	1.04\pm0.75E-10	2.58\pm0.08E-04
4th Quarter	3.14 \pm 3.77E-11	9.05\pm3.78E-11	-0.35 \pm 1.21E-11	6.26 \pm 3.32E-11	1.52 \pm 0.04E-04

	Pu-238	Pu-239/240	Am-241
1st Quarter	1.83 \pm 5.64E-11	-0.46 \pm 2.04E-11	1.85 \pm 2.62E-11
2nd Quarter	1.07 \pm 2.75E-11	0.19 \pm 1.69E-11	1.55 \pm 3.10E-11
3rd Quarter	4.75 \pm 4.87E-11	0.72 \pm 3.64E-11	2.85 \pm 4.08E-11
4th Quarter	4.77\pm3.96E-11	4.48\pm4.04E-11	1.89 \pm 1.90E-11

* Monthly average of weekly results.

**Background location. See Table C-27 for a summary of water quality data at WFBCBKG.

Note: Bolding convention applied to these data. See page C-2.

Table C-23
2000 Radioactivity Concentrations ($\mu\text{Ci/mL}$), pH, and Conductivity in Surface Water Downstream of the WVDP in Buttermilk Creek at Thomas Corners Bridge (WFBCTCB)

Month	Alpha	Beta	H-3	pH*	Conductivity*
				(standard units)	(µmhos/cm@25°C)
January	5.17±6.57E-10	6.20±1.48E-09	-6.00±8.15E-08	7.06	258
February	-3.61±5.71E-10	7.52±1.02E-09	2.45±8.21E-08	7.28	315
March	1.31±1.04E-09	7.25±1.47E-09	2.80±8.34E-08	6.78	282
April	2.77±1.34E-09	9.01±1.62E-09	-1.56±8.26E-08	7.45	234
May	1.32±0.74E-09	8.24±1.53E-09	9.92±8.27E-08	7.59	278
June	2.34±1.13E-09	5.44±1.51E-09	1.02±0.79E-07	7.11	274
July	2.76±1.57E-09	8.52±1.74E-09	1.03±8.11E-08	7.00	328
August	4.64±1.75E-09	2.21±0.22E-08	6.27±8.00E-08	7.04	295
September	8.56±8.38E-10	8.64±1.51E-09	6.80±8.27E-08	7.35	340
October	-1.11±9.09E-10	7.50±1.47E-09	7.96±8.12E-08	7.49	304
November	4.03±8.24E-10	1.14±0.17E-08	-9.43±8.18E-08	6.91	335
December	2.67±7.90E-10	5.39±1.45E-09	-6.31±8.23E-08	6.84	224
Quarter	Sr-90	Cs-137			
1st Quarter	3.58±1.04E-09	5.65±3.65E-09			
2nd Quarter	4.11±1.48E-09	-0.28±2.25E-09			
3rd Quarter	5.76±1.87E-09	1.05±2.23E-09			
4th Quarter	2.35±1.53E-09	4.28±2.33E-09			

Table C-24
2000 Radioactivity Concentrations ($\mu\text{Ci/mL}$) and pH in Surface Water Downstream of the WVDP in Cattaraugus Creek at Felton Bridge (WFFELBR)

Month	Alpha	Beta	H-3	Sr-90	Cs-137	pH* (standard units)
January**	2.48 \pm 6.49E-10	1.14 \pm 1.27E-09	-1.20 \pm 0.85E-07	0.48 \pm 1.75E-09	0.21 \pm 2.24E-09	7.33
February	-0.87 \pm 1.19E-09	3.52 \pm 1.74E-09	1.05\pm0.84E-07	0.53 \pm 1.37E-09	2.48 \pm 2.43E-09	7.57
March**	0.16 \pm 1.18E-09	6.16 \pm 1.93E-09	-7.85 \pm 8.78E-08	2.51 \pm 1.49E-09	0.46 \pm 2.35E-09	7.17
April	1.02\pm0.19E-08	5.82 \pm 1.50E-09	-1.90 \pm 0.91E-07	3.78 \pm 1.72E-09	0.79 \pm 2.20E-09	7.64
May**	1.39 \pm 0.70E-09	7.69 \pm 1.42E-09	2.99 \pm 8.33E-08	2.07 \pm 1.44E-09	1.36 \pm 2.19E-09	7.60
June	1.21 \pm 1.28E-09	-0.45 \pm 1.79E-09	-3.66 \pm 8.10E-08	1.82 \pm 1.22E-09	2.35 \pm 2.26E-09	7.14
July**	2.41 \pm 1.23E-09	2.10 \pm 1.41E-09	-3.76 \pm 8.33E-08	2.52 \pm 1.62E-09	1.33 \pm 2.25E-09	7.28
August	0.94 \pm 1.26E-09	4.97 \pm 1.87E-09	-0.55 \pm 8.67E-08	2.96 \pm 1.59E-09	0.46 \pm 3.45E-09	7.49
September**	6.67 \pm 2.28E-09	1.06\pm0.22E-08	-7.30 \pm 8.57E-08	0.87 \pm 1.97E-09	0.78 \pm 1.64E-09	7.48
October	3.37 \pm 1.22E-09	1.04 \pm 0.17E-08	-1.98 \pm 8.60E-08	5.65\pm2.36E-09	3.75\pm3.49E-09	7.47
November**	-0.33 \pm 1.23E-09	8.18 \pm 2.09E-09	-1.17 \pm 0.83E-07	0.40 \pm 1.22E-09	1.94 \pm 2.27E-09	6.93
December	2.93 \pm 8.57E-10	2.40 \pm 1.34E-09	-9.10 \pm 8.32E-08	0.76 \pm 1.35E-09	-0.77 \pm 4.15E-09	6.95

* Average of weekly results.

** Lagoon 3 discharged through WNSP001 during these months.

Note: Bolding convention applied to these data. See page C-2.

Table C-25
2000 Radioactivity Concentrations ($\mu\text{Ci/mL}$) in Surface Water
Upstream of the WVDP in Cattaraugus Creek at Bigelow Bridge (WFBIGBR)*

Month	Alpha	Beta	H-3	Sr-90	Cs-137
January	0.00 \pm 9.15E-10	2.03 \pm 1.26E-09	-1.02 \pm 0.80E-07	0.79 \pm 1.39E-09	0.16 \pm 2.31E-09
February	4.62\pm1.27E-09	8.17\pm1.09E-09	3.38 \pm 8.69E-08	1.14 \pm 1.45E-09	3.27 \pm 3.48E-09
March	-3.38 \pm 9.06E-10	2.34 \pm 1.20E-09	9.16 \pm 5.99E-08	3.54 \pm 6.80E-10	2.54 \pm 3.51E-09
April	0.00 \pm 7.99E-10	2.24 \pm 1.26E-09	1.18\pm0.84E-07	0.18 \pm 1.35E-09	1.89 \pm 3.40E-09
May	9.09 \pm 7.26E-10	3.25 \pm 1.25E-09	2.04 \pm 8.15E-08	0.70 \pm 1.12E-09	0.91 \pm 2.20E-09
June	4.86 \pm 9.51E-10	1.00 \pm 1.30E-09	-1.05 \pm 0.58E-07	1.78 \pm 1.34E-09	1.61 \pm 3.20E-09
July	0.94 \pm 1.17E-09	3.21 \pm 1.45E-09	-0.28 \pm 8.04E-08	3.22 \pm 1.56E-09	2.26 \pm 3.49E-09
August	3.48 \pm 9.65E-10	2.71 \pm 0.90E-09	-1.87 \pm 8.18E-08	2.09 \pm 1.47E-09	1.99 \pm 2.19E-09
September	1.05 \pm 1.03E-09	3.23 \pm 1.25E-09	5.87 \pm 8.38E-08	7.40\pm2.62E-09	3.08 \pm 3.67E-09
October	-2.93 \pm 8.29E-10	3.58 \pm 0.91E-09	8.18 \pm 8.23E-08	2.95 \pm 1.80E-09	2.49 \pm 2.24E-09
November	-0.05 \pm 1.02E-09	3.35 \pm 0.96E-09	-1.10 \pm 0.81E-07	1.50 \pm 1.17E-09	0.11 \pm 4.18E-09
December	-5.83 \pm 9.47E-10	1.51 \pm 1.29E-09	-1.99 \pm 8.27E-08	0.42 \pm 1.31E-09	2.70\pm2.32E-09

* Background location.

Table C-26
2000 Radioactivity Concentrations ($\mu\text{Ci/mL}$), pH, and Conductivity
in Potable Well Water around the WVDP

Well	Alpha	Beta	H-3	Cs-137	pH	Conductivity
						(standard units) ($\mu\text{mhos/cm@25}^\circ\text{C}$)
WFWEL01	3.99 \pm 7.59E-10	2.14 \pm 1.32E-09	1.52 \pm 8.26E-08	-8.51 \pm 8.59E-09	7.55	406
WFWEL02	0.14 \pm 1.09E-09	2.52 \pm 1.46E-09	-5.85 \pm 8.27E-08	0.45 \pm 1.16E-08	7.07	435
WFWEL03	0.00 \pm 1.01E-09	2.87 \pm 1.47E-09	-9.62 \pm 8.19E-08	-0.67 \pm 1.06E-08	7.33	465
WFWEL04	1.41 \pm 2.68E-09	2.29 \pm 3.78E-09	1.19 \pm 8.03E-08	6.05\pm5.26E-09	8.25	1,600
WFWEL05	-2.57 \pm 6.61E-10	3.73\pm1.01E-09	-5.42 \pm 8.32E-08	0.09 \pm 6.63E-09	6.85	345
WFWEL06*	3.83 \pm 5.63E-10	-0.28 \pm 8.92E-10	-0.81 \pm 8.27E-08	5.90 \pm 7.11E-09	6.77	288
WFWEL07	0.56 \pm 5.89E-10	1.11 \pm 0.97E-09	-0.60 \pm 5.71E-08	-0.74 \pm 1.42E-08	7.75	363
WFWEL08	-0.36 \pm 1.07E-09	3.51 \pm 1.53E-09	-1.64 \pm 0.57E-07	6.31 \pm 9.34E-09	7.38	480
WFWEL09	0.85 \pm 1.12E-09	1.24 \pm 1.53E-09	0.88 \pm 5.68E-08	0.38 \pm 1.28E-08	6.89	644
WFWEL10	0.00 \pm 1.09E-09	1.22 \pm 1.56E-09	6.80 \pm 8.31E-08	3.24 \pm 6.85E-09	6.72	681

* Background location.

Note: Bolding convention applied to these data. See page C-2.

Table C-27
2000 Surface Water Quality at Locations WFBCBKG*, WNSP006,
WNSWAMP, and WNSW74A

Location	Date	pH**	Conductivity**	Bicarbonate	Carbonate	Chloride	Fluoride
		(standard units)	(µmhos/cm@25°C)	Alkalinity (as CaCO ₃) (mg/L)	Alkalinity (as CaCO ₃) (mg/L)	(mg/L)	(mg/L)
WFBCBKG	05/09	7.65	245	89	< 1	12	< 0.10
WFBCBKG	10/02	7.35	308	101	< 1	13	< 0.10
WNSP006	05/09	6.95	573	120	< 1	168	0.19
WNSP006	10/02	7.35	263	130	< 1	92	< 0.10
WNSW74A	05/09	6.78	1,128	110	< 1	255	< 0.10
WNSW74A	10/02	7.19	607	174	< 1	118	< 0.10
WNSWAMP	05/09	6.96	1,035	179	< 2	162	0.12
WNSWAMP	10/02	7.25	534	205	< 1	134	0.10
		Nitrate+Nitrite (mg/L)	Sulfate (mg/L)	NPOC (mg/L)	TOX (µg/L)	Barium, Total (µg/L)	Calcium, Total (µg/L)
WFBCBKG	05/09	0.15	21.5	2.8	6.4	79	33,100
WFBCBKG	10/02	< 0.05	23.4	3.2	6.6	< 200	45,100
WNSP006	05/09	9.88	51.5	4.7	65.0	65	61,100
WNSP006	10/02	3.80	149.0	5.3	46.6	< 200	65,250
WNSW74A	05/09	0.31	54.0	4.2	36.5	115	85,800
WNSW74A	10/02	0.15	44.6	4.8	19.0	< 200	92,400
WNSWAMP	05/09	0.01	28.7	4.8	36.0	121	119,000
WNSWAMP	10/02	0.08	36.4	4.7	33.0	105	115,000
		Iron, Total (µg/L)	Magnesium, Total (µg/L)	Manganese, Total (µg/L)	Potassium, Total (µg/L)	Sodium, Total (µg/L)	
WFBCBKG	05/09	327	4,500	20	1,240	7,075	
WFBCBKG	10/02	1,180	6,410	50	1,820	8,680	
WNSP006	05/09	299	8,980	28	4,140	101,000	
WNSP006	10/02	1,305	8,795	44	4,445	124,500	
WNSW74A	05/09	34	12,000	16	< 1,000	98,500	
WNSW74A	10/02	< 100	11,200	21	1,050	57,400	
WNSWAMP	05/09	280	15,500	840	< 1,000	53,900	
WNSWAMP	10/02	487	14,800	400	1,310	54,900	

* Background location.

** pH and conductivity data are from a separate sample collected within one week of the sample analyzed for other nonradiological parameters.

Note: Bolding convention not applicable to these data.

Table C-28
2000 Radioactivity Concentrations ($\mu\text{Ci/g}$ dry weight from upper 5 cm) and
Metals Concentrations (mg/kg dry) in On-site Soils/Sediments

Location	Alpha	Beta	K-40	Co-60	Sr-90	
SNSP006	1.10±0.27E-05	5.26±0.40E-05	1.73±0.18E-05	1.56±2.67E-08	2.04±0.13E-06	
SNSW74A	1.19±0.30E-05	2.63±0.33E-05	1.71±0.18E-05	1.80±1.45E-08	2.41±0.71E-07	
SNSWAMP	1.71±0.34E-05	6.77±0.43E-05	2.26±0.22E-05	1.12±2.64E-08	1.72±0.09E-06	
	Cs-137	U-232	U-233/234	U-235/236	U-238	
SNSP006	2.58±0.32E-05	1.16±2.12E-07	8.28±5.40E-07	-0.19±1.67E-07	7.92±5.16E-07	
SNSW74A	2.28±0.32E-06	-1.14±0.18E-08	8.51±4.94E-07	-1.49±2.98E-08	1.08±0.54E-06	
SNSWAMP	3.14±0.42E-05	-7.20±1.14E-08	1.08±0.49E-06	0.66±1.53E-07	7.10±3.98E-07	
	Total U (µg/g)	Pu-238	Pu-239/240	Am-241		
SNSP006	1.81±0.03E+00	2.20±1.68E-08	2.04±1.51E-08	1.93±1.35E-07		
SNSW74A	2.18±0.04E+00	3.76±2.04E-08	6.17±2.64E-08	1.79±1.25E-07		
SNSWAMP	2.53±0.07E+00	4.32±0.86E-07	6.42±1.07E-07	1.29±0.30E-06		
	Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium
SNSP006	6,210	<6	6.5	64.4	0.3	<0.6
SNSW74A	9,460	<6	11.3	95.6	0.5	<0.9
SNSWAMP	14,500	<6	11.7	87.4	0.7	<0.7
	Calcium	Chromium	Cobalt	Copper	Iron	Lead
SNSP006	18,350	9.3	10	14.6	17,200	10
SNSW74A	42,300	18	10.3	36.7	26,100	22.9
SNSWAMP	9,630	19.6	13.7	27.8	32,400	24.7
	Magnesium	Manganese	Mercury	Nickel	Potassium	Selenium
SNSP006	6,695	694	0.035	18.1	834.5	1.4
SNSW74A	10,900	1670	0.045	26.8	1,310	2.4
SNSWAMP	7,260	661	0.074	30.1	1,430	2.4
	Silver	Sodium	Thallium	Vanadium	Zinc	
SNSP006	<1	75.6	0.8	11.4	55	
SNSW74A	<1	213	1.9	18.3	346	
SNSWAMP	<1	64	<1.3	21.7	109	

Note: Bolding convention not applicable to these data.

Table C-29
2000 Radioactivity Concentrations ($\mu\text{Ci/g}$ dry weight from upper 5 cm)
in Surface Soil Collected at Air Sampling Stations around the WVDP

Location	Alpha	Beta	K-40	Co-60	Sr-90
SFBLKST	1.61 \pm 0.17E-05	3.00 \pm 0.20E-05	1.62 \pm 0.07E-05	0.34 \pm 1.85E-08	3.89 \pm 1.57E-08
SFBOEHN	1.22 \pm 0.26E-05	2.28 \pm 0.31E-05	1.46 \pm 0.08E-05	0.22 \pm 1.92E-08	8.24 \pm 1.82E-08
SFFXVRD	1.19 \pm 0.29E-05	1.93 \pm 0.32E-05	1.11 \pm 0.07E-05	-0.94 \pm 1.73E-08	1.15 \pm 0.22E-07
SFGRVAL *	1.16\pm0.32E-05	2.32 \pm 0.38E-05	1.38 \pm 0.07E-05	0.39 \pm 1.65E-08	1.32\pm0.17E-07
SFNASHV*	1.64 \pm 0.36E-05	2.37 \pm 0.37E-05	1.89 \pm 0.08E-05	-0.22 \pm 1.89E-08	0.87 \pm 1.71E-08
SFRSPRD	1.37 \pm 0.33E-05	2.01 \pm 0.36E-05	1.46 \pm 0.08E-05	1.56 \pm 2.50E-08	1.30 \pm 0.20E-07
SFRT240	1.30 \pm 0.29E-05	1.99 \pm 0.33E-05	8.88\pm0.57E-06	0.68 \pm 1.82E-08	1.07 \pm 0.19E-07
SFSPRVL	1.42 \pm 0.31E-05	1.93 \pm 0.32E-05	1.38 \pm 0.14E-05	0.02 \pm 1.30E-08	1.10 \pm 0.18E-07
SFTCORD	1.77\pm0.38E-05	3.49\pm0.42E-05	2.11\pm0.10E-05	1.39 \pm 2.35E-08	4.56 \pm 2.04E-08
SFWEVAL	1.22 \pm 0.30E-05	1.64\pm0.32E-05	1.17 \pm 0.06E-05	0.01 \pm 1.47E-08	4.29 \pm 4.36E-08
	Cs-137	Pu-238	Pu-239/240	Am-241	
SFBLKST	2.58 \pm 0.33E-07	7.21 \pm 8.36E-09	1.68 \pm 1.28E-08	0.98 \pm 1.19E-08	
SFBOEHN	5.18 \pm 0.43E-07	5.02 \pm 5.98E-09	1.55 \pm 1.24E-08	8.86 \pm 9.77E-09	
SFFXVRD	3.89 \pm 0.38E-07	2.27 \pm 4.55E-09	0.81 \pm 1.12E-08	1.52 \pm 1.14E-08	
SFGRVAL *	5.20 \pm 0.46E-07	0.42 \pm 3.72E-09	1.06 \pm 0.80E-08	2.17 \pm 9.53E-09	
SFNASHV*	6.54\pm2.77E-08	0.00 \pm 6.54E-09	7.15 \pm 9.30E-09	0.74 \pm 1.06E-08	
SFRSPRD	1.06\pm0.07E-06	3.26 \pm 5.37E-09	2.71 \pm 1.27E-08	2.99 \pm 1.44E-08	
SFRT240	6.17 \pm 0.51E-07	8.04\pm7.82E-09	2.52 \pm 1.35E-08	3.01\pm1.67E-08	
SFSPRVL	5.30 \pm 0.72E-07	3.04 \pm 4.31E-09	2.93\pm1.41E-08	7.99 \pm 7.19E-09	
SFTCORD	5.01 \pm 0.52E-07	0.54 \pm 4.79E-09	1.22 \pm 1.07E-08	1.53 \pm 1.34E-08	
SFWEVAL	4.46 \pm 0.34E-07	-1.05 \pm 8.30E-09	0.72 \pm 1.06E-08	1.70 \pm 1.14E-08	
	U-232	U-233/234	U-235/236	U-238	Total U ($\mu\text{g/g}$)
SFBOEHN	3.36 \pm 5.41E-08	6.84\pm1.31E-07	4.46 \pm 3.60E-08	6.96 \pm 1.32E-07	2.60\pm0.03E+00
SFGRVAL	0.49 \pm 3.53E-08	7.79\pm1.52E-07	6.87\pm3.87E-08	7.48\pm1.48E-07	3.41\pm0.05E+00
SFRSPRD	0.60 \pm 6.01E-08	7.20 \pm 1.33E-07	3.50 \pm 3.93E-08	6.59\pm1.26E-07	2.83 \pm 0.04E+00

* Background location.

Note: Bolding convention applied to these data. See page C-2.

Table C-30
2000 Radioactivity Concentrations ($\mu\text{Ci/g}$ dry weight from upper 5 cm)
in Stream Sediments around the WVDP

Location	Alpha	Beta	K-40	Co-60	Sr-90
SFBCSED*	1.00±0.34E-05	1.91±0.32E-05	1.64±0.16E-05	1.73±8.73E-09	1.57±1.39E-07
SFBISED*	1.14±0.35E-05	1.79±0.30E-05	1.50±0.16E-05	1.63±9.79E-09	0.24±1.21E-07
SFCCSED	8.52±2.92E-06	1.96±0.31E-05	1.60±0.17E-05	0.01±1.70E-08	0.38±1.29E-07
SFSDSED	8.12±2.77E-06	1.86±0.30E-05	1.58±0.17E-05	0.83±1.13E-08	0.58±1.37E-07
SFTCSSED	7.54±3.05E-06	1.95±0.31E-05	1.68±0.20E-05	1.82±2.58E-08	-0.67±1.37E-07
	Cs-137	U-232	U-233/234	U-235/236	U-238
SFBCSED*	3.76±1.33E-08	1.05±1.62E-07	6.81±1.79E-07	7.30±6.14E-08	5.35±1.55E-07
SFBISED*	3.18±1.24E-08	-0.21±1.41E-07	6.90±1.89E-07	-0.55±1.10E-08	5.60±1.70E-07
SFCCSED	2.41±0.44E-07	0.09±1.43E-07	5.77±1.67E-07	4.37±4.83E-08	6.40±1.77E-07
SFSDSED	1.99±0.39E-07	-1.66±5.79E-08	7.43±1.95E-07	3.60±5.60E-08	6.40±1.75E-07
SFTCSSED	1.16±0.15E-06	0.23±9.17E-08	6.90±2.73E-07	5.96±8.38E-08	8.43±3.02E-07
	Total U ($\mu\text{g/g}$)	Pu-238	Pu-239/240	Am-241	
SFBCSED*	4.60±0.08E+00	1.42±4.94E-09	1.42±4.93E-09	1.84±1.16E-08	
SFBISED*	2.09±0.04E+00	-5.77±8.43E-09	-0.36±8.36E-09	1.30±1.46E-08	
SFCCSED	2.12±0.04E+00	-0.33±1.82E-08	0.93±1.08E-08	1.35±1.07E-08	
SFSDSED	2.08±0.04E+00	0.86±1.26E-08	6.82±8.87E-09	2.27±1.37E-08	
SFTCSSED	2.16±0.04E+00	4.05±1.87E-08	0.00±2.29E-08	1.24±0.94E-08	

* Background location.

Note: Bolding convention applied to these data. See page C-2.

Appendix D

Summary of Air Monitoring Data



***Ambient Air and Atmospheric Fallout Samples are Collected
from Numerous Locations in the West Valley Area***

The following tables contain a bolding convention devised to help the reader, when viewing the data, to quickly see the range of detectable measurements within a data series. A data series is a set of chemical or radionuclide measurements (e.g., gross alpha, gross beta, tritium) from a single location or from similar locations. Note that some tables contain data that should not be technically evaluated under this convention.

Key to bolding convention:

Results for each constituent constitute a single data series. If a radiological result is larger than the uncertainty term, the measurement is considered positive. Otherwise, a result is considered non-detectable. Chemical results preceded by "less than" (<) are considered nondetectable.

If all results in a data series are positive, the lowest and highest values are bolded.

If a data series contains some positive results, the highest value is bolded.

If all values in a data series are nondetectable, no values are bolded.

Table D-1
2000 Airborne Radioactive Effluent Totals (curies)
Released from the Main Ventilation Stack (ANSTACK)

Month	Alpha	Beta	H-3		
January	4.81±2.68E-08	3.00±0.11E-06	1.42±0.46E-03		
February	9.50±2.91E-08	4.29±0.14E-06	5.14±3.19E-04		
March	1.64±0.39E-07	6.18±0.16E-06	1.82±8.97E-04		
April	5.01±2.96E-08	2.45±0.11E-06	1.97±0.96E-04		
May	6.79±2.92E-08	2.23±0.10E-06	-4.11±8.74E-05		
June	7.34±2.91E-08	3.57±0.13E-06	-1.66±1.20E-04		
July	5.73±2.50E-08	1.94±0.10E-06	2.53±0.35E-04		
August	5.76±2.70E-08	2.33±0.10E-06	1.33±0.04E-03		
September	2.10±0.42E-07	4.25±0.14E-06	5.78±0.50E-04		
October	8.34±2.77E-08	6.14±0.16E-06	2.75±0.36E-04		
November	4.72±2.53E-08	1.02±0.02E-05	2.20±1.43E-04		
December	9.91±3.27E-08	9.90±0.21E-06	2.43±0.57E-04		
Annual Total	1.05±0.11E-06	5.65±0.05E-05	5.00±1.09E-03		

Quarter	Co-60	Sr-90	I-129	Cs-137	Eu-154
1st Quarter	1.90±2.37E-08	2.01±0.09E-06	3.13±0.36E-04	2.16±0.24E-06	3.42±7.03E-08
2nd Quarter	0.77±2.65E-08	1.15±0.08E-06	2.01±0.23E-04	1.61±0.20E-06	-2.60±7.67E-08
3rd Quarter	-0.73±3.32E-08	1.11±0.05E-06	2.79±0.32E-04	2.19±0.12E-06	0.17±9.92E-08
4th Quarter	0.98±3.66E-08	1.67±0.06E-06	4.70±0.55E-04	1.05±0.02E-05	0.29±1.06E-07
Annual Total	2.92±6.09E-08	5.94±0.14E-06	1.26±0.08E-03	1.65±0.04E-05	0.38±1.78E-07

	U-232	U-233/234	U-235/236	U-238	Total U (g)
1st Quarter	2.50±3.79E-09	1.91±0.72E-08	-0.88±2.62E-09	1.06±0.54E-08	5.57±0.07E-02
2nd Quarter	-1.08±2.65E-09	1.46±0.47E-08	1.61±1.45E-09	1.80±0.51E-08	4.17±0.06E-02
3rd Quarter	-0.32±2.67E-09	1.14±0.46E-08	1.41±1.67E-09	1.16±0.46E-08	3.63±0.06E-02
4th Quarter	2.93±2.85E-09	7.90±3.32E-09	0.49±1.26E-09	1.13±0.39E-08	3.74±0.05E-02
Annual Total	4.03±6.05E-09	5.31±1.03E-08	2.63±3.66E-09	5.15±0.96E-08	1.71±0.01E-01

	Pu-238	Pu-239/240	Am-241
1st Quarter	2.30±0.72E-08	5.69±1.28E-08	1.23±0.20E-07
2nd Quarter	2.81±0.99E-08	3.70±1.15E-08	9.92±1.77E-08
3rd Quarter	3.45±0.73E-08	5.49±0.98E-08	1.18±0.20E-07
4th Quarter	2.29±0.62E-08	3.74±0.76E-08	8.09±1.34E-08
Annual Total	1.08±0.16E-07	1.86±0.21E-07	4.21±0.36E-07

Note: Bolding convention applied to these data. See page D-2.

Table D-2
Comparison of 2000 Main Stack (ANSTACK) Exhaust Radioactivity
Concentrations with Department of Energy Guidelines

Isotope ^a	Exhaust Activity ^b (Ci)	Radioactivity ^c (Bq)	Average Concentration (μ Ci/mL)	DCG ^d (μ Ci/mL)	% of DCG
Alpha	1.05 \pm 0.11E-06	3.89 \pm 0.39E+04	1.42 \pm 0.14E-15	NA ^e	NA
Beta	5.65 \pm 0.05E-05	2.09 \pm 0.02E+06	7.61 \pm 0.07E-14	NA ^e	NA
H-3	5.00 \pm 1.09E-03	1.85 \pm 0.40E+08	7.01 \pm 1.52E-12	1E-07	0.01
Co-60	2.92 \pm 6.09E-08	1.08 \pm 2.25E+03	3.94 \pm 8.21E-17	8E-11	<0.01
Sr-90	5.94 \pm 0.14E-06	2.20 \pm 0.05E+05	8.01 \pm 0.19E-15	9E-12	0.09
I-129	1.26 \pm 0.08E-03	4.67 \pm 0.28E+07	1.70 \pm 0.10E-12	7E-11	2.43
Cs-137	1.65 \pm 0.04E-05	6.09 \pm 0.15E+05	2.22 \pm 0.06E-14	4E-10	0.01
Eu-154	0.38 \pm 1.78E-07	1.42 \pm 6.60E+03	0.52 \pm 2.40E-16	5E-11	<0.01
U-232 ^f	4.03 \pm 6.05E-09	1.49 \pm 2.24E+02	5.43 \pm 8.16E-18	2E-14	<0.04
U-233/234 ^f	5.31 \pm 1.03E-08	1.96 \pm 0.38E+03	7.15 \pm 1.39E-17	9E-14	0.08
U-235/236 ^f	2.63 \pm 3.66E-09	0.97 \pm 1.35E+02	3.54 \pm 4.93E-18	1E-13	<0.01
U-238 ^f	5.15 \pm 0.96E-08	1.91 \pm 0.36E+03	6.94 \pm 1.30E-17	1E-13	0.07
Pu-238	1.08 \pm 0.16E-07	4.01 \pm 0.57E+03	1.46 \pm 0.21E-16	3E-14	0.49
Pu-239/240	1.86 \pm 0.21E-07	6.89 \pm 0.79E+03	2.51 \pm 0.29E-16	2E-14	1.25
Am-241	4.21 \pm 0.36E-07	1.56 \pm 0.13E+04	5.68 \pm 0.49E-16	2E-14	2.84
Total % of DCGs					7.31

^a Half-lives are listed in Table K-1 (p. K-3).

^b Total volume released at 50,000 cfm = 7.42E+14 mL/year.

^c 1 curie (Ci) = 3.7E+10 becquerels (Bq); 1 Bq = 2.7E-11 Ci.

^d Derived concentration guides (DCGs) are listed for reference only. They are applicable to average concentrations at the site boundary but not to stack concentrations, as might be inferred from their inclusion in this table.

^e NA - Not applicable: DCGs are not specified for gross alpha and gross beta activity.

^f Total uranium = 1.71 \pm 0.01E-01 g; average = 2.30E-10 μ g/mL.

Note: Bolding convention not applicable to these data.

Table D-3
2000 Airborne Radioactive Effluent Totals (curies)
from the Vitrification System (HVAC) Ventilation Stack (ANVITSK)

Month	Alpha	Beta
January	-5.42±9.35E-09	0.27±1.92E-08
February	8.76±9.33E-09	-0.54±1.91E-08
March	0.45±1.19E-08	-1.74±2.21E-08
April	-0.19±1.04E-08	0.00±1.85E-08
May	-2.47±8.73E-09	1.34±1.80E-08
June	2.64±9.39E-09	-1.37±2.05E-08
July	3.47±8.43E-09	-1.05±1.85E-08
August	-1.39±9.19E-09	-0.77±1.85E-08
September	-1.12±0.99E-08	1.54±2.08E-08
October	1.13±8.75E-09	-0.81±1.79E-08
November	1.45±9.38E-09	-1.36±1.78E-08
December	0.43±1.05E-08	-1.70±1.95E-08
Annual Total	0.39±3.34E-08	-6.18±6.67E-08

Quarter	Co-60	Sr-90	I-129	Cs-137	Eu-154
1st Quarter	0.18±1.03E-08	-7.45±9.67E-09	3.67±0.81E-07	0.00±1.20E-08	-1.24±2.86E-08
2nd Quarter	0.89±1.64E-08	1.80±1.20E-08	4.54±1.18E-07	-0.37±1.60E-08	0.49±4.91E-08
3rd Quarter	-0.51±1.48E-08	-5.82±9.86E-09	2.95±0.67E-07	0.84±2.40E-08	-2.93±3.85E-08
4th Quarter	-0.03±1.28E-08	1.60±1.13E-08	3.12±0.91E-07	0.12±1.17E-08	2.31±3.39E-08
Annual Total	0.54±2.75E-08	2.08±2.15E-08	1.43±0.18E-06	0.58±3.34E-08	-1.36±7.66E-08

	U-232	U-233/234	U-235/236	U-238	Total U (g)
1st Quarter	0.99±1.32E-09	5.24±2.62E-09	-1.16±2.33E-10	7.98±2.97E-09	2.55±0.03E-02
2nd Quarter	1.01±1.18E-09	5.57±3.24E-09	2.18±8.89E-10	6.72±3.59E-09	1.65±0.02E-02
3rd Quarter	0.31±9.49E-10	4.53±2.17E-09	0.00±6.82E-10	6.68±2.66E-09	1.59±0.03E-02
4th Quarter	-2.52±9.01E-10	3.58±1.86E-09	1.36±1.13E-09	5.12±1.96E-09	1.57±0.02E-02
Annual Total	1.78±2.20E-09	1.89±0.50E-08	1.46±1.61E-09	2.65±0.57E-08	7.35±0.05E-02

	Pu-238	Pu-239/240	Am-241
1st Quarter	3.42±4.85E-10	5.97±7.09E-10	2.46±4.93E-10
2nd Quarter	-0.09±1.07E-09	-1.10±6.49E-10	0.87±1.02E-09
3rd Quarter	3.14±3.64E-10	0.00±3.13E-10	0.89±1.03E-09
4th Quarter	4.86±4.89E-10	1.22±2.43E-10	8.97±9.02E-10
Annual Total	1.05±1.33E-09	0.61±1.04E-09	2.91±1.78E-09

Note: Bolding convention applied to these data. See page D-2.

Table D-4
2000 Airborne Radioactive Effluent Totals (curies)
from the Seismic Sampler (ANSEISK)
for the Vitrification System (HVAC) Ventilation Stack

Month	Alpha	Beta
<i>January</i>	-1.13±9.80E-09	0.64±1.92E-08
<i>February</i>	1.02±0.95E-08	-0.91±1.87E-08
<i>March</i>	0.79±1.23E-08	-1.53±2.19E-08
<i>April</i>	-0.36±1.01E-08	1.00±1.90E-08
<i>May</i>	-2.95±8.90E-09	0.73±1.83E-08
<i>June</i>	0.81±9.26E-09	0.03±2.13E-08
<i>July</i>	2.13±8.07E-09	-0.43±1.85E-08
<i>August</i>	-4.04±8.55E-09	-0.88±1.79E-08
<i>September</i>	-1.24±0.97E-08	1.05±2.03E-08
<i>October</i>	-1.31±7.98E-09	0.83±1.81E-08
<i>November</i>	3.27±9.76E-09	-1.14±1.81E-08
<i>December</i>	0.29±1.05E-08	0.28±2.08E-08
Annual Total	0.17±3.32E-08	-0.34±6.72E-08

ANSEISK provides back-up samples for the primary vitrification sampler (ANVITSK).

Note: Bolding convention applied to these data. See page D-2.

Table D-5
2000 Airborne Radioactive Effluent Totals (curies) from the 01-14 Building
Ventilation Exhaust (ANCSSTK)

Month	Alpha	Beta
January	0.60±3.98E-09	5.24±7.65E-09
February	3.71±4.06E-09	1.72±8.61E-09
March	0.09±4.75E-09	-0.06±9.52E-09
April	3.77±5.08E-09	1.35±8.11E-09
May	-1.89±3.70E-09	1.27±0.83E-08
June	-0.04±3.99E-09	3.35±9.47E-09
July	0.92±3.43E-09	-3.66±7.72E-09
August	0.04±3.69E-09	1.39±7.45E-09
September	-3.42±3.92E-09	9.59±8.13E-09
October	-0.23±3.54E-09	8.66±8.12E-09
November	1.58±4.00E-09	-2.81±7.46E-09
December	5.29±5.26E-09	1.56±1.04E-08
Annual Total	1.04±1.44E-08	5.32±2.93E-08

Quarter	Co-60	Sr-90	I-129	Cs-137	Eu-154
1st Quarter	5.51±4.41E-09	-0.81±5.16E-09	4.65±1.86E-08	1.71±5.02E-09	1.47±1.19E-08
2nd Quarter	1.30±5.19E-09	-2.12±5.14E-09	0.00±2.03E-08	3.18±4.99E-09	-0.73±1.51E-08
3rd Quarter	0.28±6.97E-09	5.54±6.67E-09	7.10±2.42E-08	-1.26±6.65E-09	0.99±1.95E-08
4th Quarter	5.20±6.22E-09	2.55±5.25E-09	1.70±2.84E-08	0.73±5.44E-09	-0.03±1.64E-08
Annual Total	1.23±1.16E-08	0.52±1.12E-08	1.35±0.46E-07	0.44±1.11E-08	1.70±3.19E-08

	U-232	U-233/234	U-235/236	U-238	Total U (g)
1st Quarter	2.60±4.53E-10	2.15±1.33E-09	2.35±6.90E-10	3.25±1.25E-09	1.13±0.01E-02
2nd Quarter	0.82±5.04E-10	3.70±1.62E-09	-3.82±7.64E-11	3.01±1.43E-09	9.78±0.14E-03
3rd Quarter	5.89±5.56E-10	3.00±1.30E-09	2.36±4.37E-10	4.25±1.46E-09	8.77±0.14E-03
4th Quarter	0.05±4.17E-10	2.99±0.91E-09	-0.43±3.39E-10	3.18±0.93E-09	8.50±0.11E-03
Annual Total	9.35±9.70E-10	1.18±0.26E-08	3.91±8.88E-10	1.37±0.26E-08	3.83±0.03E-02

	Pu-238	Pu-239/240	Am-241
1st Quarter	1.42±2.01E-10	2.12±2.46E-10	3.29±3.85E-10
2nd Quarter	1.60±3.15E-10	1.64±4.04E-10	0.83±3.40E-10
3rd Quarter	2.83±2.68E-10	1.20±2.31E-10	1.83±2.84E-10
4th Quarter	1.88±1.89E-10	2.49±2.42E-10	-0.13±3.11E-10
Annual Total	7.73±4.97E-10	7.45±5.80E-10	5.82±6.64E-10

Note: Bolding convention applied to these data. See page D-2.

Table D-6
2000 Airborne Radioactive Effluent Totals (curies) from the
Contact Size-reduction Facility Ventilation Stack (ANCSRFK)

Month	Alpha	Beta
January	NA	NA
February	NA	NA
March	NA	NA
April	NA	NA
May	NA	NA
June	0.56±2.90E-10	8.14±7.77E-10
July	NA	NA
August	NA	NA
September	NA	NA
October	NA	NA
November	NA	NA
December	NA	NA
Annual Total	0.56±2.90E-10	8.14±7.77E-10

Quarter	Co-60	Sr-90	I-129	Cs-137	Eu-154
1st Quarter	NA	NA	NA	NA	NA
2nd Quarter	-0.10±1.18E-09	2.68±0.97E-09	1.81±5.94E-10	1.18±1.52E-09	-0.79±2.97E-09
3rd Quarter	NA	NA	NA	NA	NA
4th Quarter	NA	NA	NA	NA	NA
Annual Total	-0.10±1.18E-09	2.68±0.97E-09	1.81±5.94E-10	1.18±1.52E-09	-0.79±2.97E-09

	U-232	U-233/234	U-235/236	U-238	Total U (g)
1st Quarter	NA	NA	NA	NA	NA
2nd Quarter	-0.56±1.01E-10	0.92±1.18E-10	-1.61±2.28E-11	5.89±9.65E-11	1.36±0.03E-04
3rd Quarter	NA	NA	NA	NA	NA
4th Quarter	NA	NA	NA	NA	NA
Annual Total	-0.56±1.01E-10	0.92±1.18E-10	-1.61±2.28E-11	5.89±9.65E-11	1.36±0.03E-04

	Pu-238	Pu-239/240	Am-241
1st Quarter	NA	NA	NA
2nd Quarter	-4.00±4.65E-11	4.22±8.31E-11	1.09±0.98E-10
3rd Quarter	NA	NA	NA
4th Quarter	NA	NA	NA
Annual Total	-4.00±4.65E-11	4.22±8.31E-11	1.09±0.98E-10

NA - Not applicable. Ventilation off.

Note: Bolding convention not applicable to these data.

Table D-7
2000 Airborne Radioactive Effluent Totals (curies) from the
Supernatant Treatment System Ventilation Stack (ANSTSTK)

Month	Alpha	Beta	H-3		
January	1.29±2.24E-09	2.97±4.06E-09	1.38±0.52E-06		
February	1.35±1.86E-09	1.81±4.08E-09	1.15±0.47E-06		
March	0.12±2.41E-09	0.01±4.83E-09	5.63±1.16E-06		
April	0.12±2.33E-09	1.49±4.11E-09	3.37±1.08E-06		
May	0.75±2.10E-09	5.22±4.05E-09	0.12±1.22E-06		
June	2.33±2.34E-09	-1.77±4.64E-09	1.68±0.21E-05		
July	1.42±1.94E-09	0.70±4.16E-09	1.45±0.77E-06		
August	0.14±1.99E-09	2.99±4.08E-09	2.54±1.20E-06		
September	0.65±2.48E-09	3.51±4.47E-09	5.56±1.74E-06		
October	0.96±1.98E-09	1.27±3.97E-09	7.57±0.99E-06		
November	1.48±2.17E-09	4.24±4.15E-09	6.30±0.72E-06		
December	-0.03±2.09E-09	1.10±0.08E-07	3.02±0.15E-05		
Annual Total	1.06±0.75E-08	1.32±0.16E-07	8.21±0.42E-05		

Quarter	Co-60	Sr-90	I-129	Cs-137	Eu-154
1st Quarter	0.58±2.43E-09	1.12±2.07E-09	1.90±0.35E-07	1.33±2.26E-09	3.46±4.35E-09
2nd Quarter	2.90±2.75E-09	5.04±2.55E-09	8.40±1.12E-07	1.51±2.52E-09	-1.54±7.12E-09
3rd Quarter	0.79±3.19E-09	-0.52±2.00E-09	4.63±0.71E-07	4.57±4.93E-09	0.92±9.42E-09
4th Quarter	-0.94±3.72E-09	9.21±2.83E-09	1.18±0.16E-06	2.63±0.81E-08	-6.08±9.55E-09
Annual Total	3.33±6.12E-09	1.48±0.48E-08	2.67±0.21E-06	3.38±1.00E-08	-0.32±1.58E-08

	U-232	U-233/234	U-235/236	U-238	Total U (g)
1st Quarter	0.79±2.66E-10	9.52±4.55E-10	0.69±1.36E-10	1.33±0.52E-09	4.42±0.07E-03
2nd Quarter	-1.23±2.44E-10	1.91±0.85E-09	0.66±1.80E-10	1.91±0.85E-09	4.63±0.07E-03
3rd Quarter	0.56±2.94E-10	1.36±0.54E-09	1.39±1.98E-10	1.36±0.53E-09	3.92±0.07E-03
4th Quarter	-0.64±1.86E-10	1.07±0.40E-09	-1.23±8.00E-11	1.14±0.38E-09	3.64±0.05E-03
Annual Total	-0.53±5.01E-10	5.30±1.18E-09	2.62±3.10E-10	5.75±1.19E-09	1.66±0.01E-02

	Pu-238	Pu-239/240	Am-241
1st Quarter	6.56±9.32E-11	4.90±9.87E-11	0.79±1.55E-10
2nd Quarter	1.26±1.80E-10	0.26±1.10E-10	1.27±1.50E-10
3rd Quarter	1.76±1.83E-10	0.00±1.23E-10	0.30±1.26E-10
4th Quarter	1.49±9.28E-11	0.42±1.07E-10	2.01±1.96E-10
Annual Total	3.83±2.88E-10	1.17±2.20E-10	4.36±3.17E-10

Note: Bolding convention applied to these data. See page D-2.

Table D-8
2000 Airborne Radioactive Effluent Totals (curies) from the
Container Sorting and Packaging Facility Ventilation Stack (ANCSPFK)

Month	Alpha	Beta			
January	-2.47±4.31E-10	1.09±0.84E-09			
February	7.48±4.99E-10	4.20±9.63E-10			
March	0.99±5.59E-10	-0.25±1.09E-09			
April	1.78±5.42E-10	5.49±9.32E-10			
May	3.48±4.97E-10	7.33±8.90E-10			
June	3.03±4.87E-10	0.42±1.05E-09			
July	4.01±4.42E-10	-3.32±9.02E-10			
August	-2.59±3.98E-10	-4.94±8.54E-10			
September	-4.28±4.73E-10	1.52±9.27E-10			
October	-0.30±3.93E-10	-0.91±8.46E-10			
November	1.30±4.67E-10	-3.09±8.90E-10			
December	-2.36±4.11E-10	5.68±9.28E-10			
Annual Total	1.01±1.63E-09	2.46±3.22E-09			

Quarter	Co-60	Sr-90	I-129	Cs-137	Eu-154
1st Quarter	3.89±5.71E-10	-3.62±4.69E-10	3.41±0.59E-08	2.49±5.60E-10	0.54±1.58E-09
2nd Quarter	0.64±8.43E-10	-4.03±7.41E-10	6.26±1.09E-08	3.77±8.26E-10	-0.33±2.31E-09
3rd Quarter	5.13±5.85E-10	1.05±0.71E-09	1.57±0.44E-08	0.62±1.33E-09	-0.52±1.58E-09
4th Quarter	0.58±5.98E-10	2.79±5.21E-10	6.49±0.88E-08	1.08±5.81E-10	2.13±2.29E-09
Annual Total	1.02±1.32E-09	0.56±1.24E-09	1.77±0.16E-07	1.35±1.76E-09	1.82±3.94E-09

	U-232	U-233/234	U-235/236	U-238	Total U (g)
1st Quarter	3.75±7.57E-11	2.99±1.26E-10	0.65±2.77E-11	2.12±1.10E-10	1.28±0.02E-03
2nd Quarter	4.45±7.12E-11	4.89±2.07E-10	3.01±5.75E-11	3.31±1.69E-10	1.08±0.02E-03
3rd Quarter	5.10±7.40E-11	3.55±1.17E-10	2.15±3.79E-11	2.81±1.04E-10	7.35±0.13E-04
4th Quarter	1.57±5.98E-11	1.97±0.79E-10	1.45±2.39E-11	1.90±0.72E-10	6.93±0.09E-04
Annual Total	1.49±1.41E-10	1.34±0.28E-09	7.26±7.80E-11	1.01±0.24E-09	3.78±0.03E-03

	Pu-238	Pu-239/240	Am-241
1st Quarter	2.49±3.61E-11	0.99±1.99E-11	0.56±2.39E-11
2nd Quarter	9.17±7.01E-11	2.22±1.11E-10	1.91±1.01E-10
3rd Quarter	0.71±1.41E-11	-0.71±2.45E-11	6.13±5.58E-11
4th Quarter	-0.65±6.20E-11	7.21±5.76E-11	6.04±4.95E-11
Annual Total	1.17±1.01E-10	2.97±1.29E-10	3.19±1.28E-10

Note: Bolding convention applied to these data. See page D-2.

Table D-9
2000 Airborne Radioactive Effluent Totals (curies) from the
Former Low-level Waste Treatment Facility Hot Side Ventilation (ANLLWTVH)

Month	Alpha	Beta
January	NA	NA
February	NA	NA
March	1.79±5.54E-10	0.12±1.18E-09
April	NA	NA
May	NA	NA
June	4.90±5.53E-10	1.19±1.13E-09
July	NA	NA
August	NA	NA
September	NA	NA
October	NA	NA
November	NA	NA
December	6.81±8.73E-10	1.22±0.20E-08
Annual Total	1.35±1.17E-09	1.35±0.26E-08

Table D-10
2000 Airborne Radioactive Effluent Totals (curies) from the
New Low-level Waste Treatment Facility Ventilation (ANLLW2V)

Month	Alpha	Beta
January	NA	NA
February	NA	NA
March	0.36±2.13E-10	1.71±4.90E-10
April	NA	NA
May	NA	NA
June	2.55±2.34E-10	1.10±4.07E-10
July	NA	NA
August	NA	NA
September	-0.99±1.71E-10	0.69±4.31E-10
October	NA	NA
November	NA	NA
December	0.32±2.42E-10	0.86±3.57E-10
Annual Total	2.24±4.33E-10	4.35±8.48E-10

NA - Not applicable. Ventilation off.

Note: Bolding convention applied to these data. See page D-2.

Table D-11
2000 Airborne Radioactive Effluent Totals (curies) from the
Laundry Change Room (ANLAUNV)

Month	Alpha	Beta
<i>January</i>	-2.87±6.21E-10	0.52±1.35E-09
<i>February</i>	3.93±5.96E-10	0.37±1.13E-09
<i>March</i>	3.63±5.13E-10	0.00±9.49E-10
<i>April</i>	-4.11±4.24E-10	3.69±8.28E-10
<i>May</i>	0.74±3.85E-10	-1.00±9.51E-10
<i>June</i>	-0.77±3.38E-10	1.50±1.11E-09
<i>July</i>	-0.66±3.87E-10	7.75±9.41E-10
<i>August</i>	0.93±5.46E-10	0.26±1.27E-09
<i>September</i>	-0.69±4.04E-10	-0.95±8.73E-10
<i>October</i>	1.60±4.44E-10	3.19±9.65E-10
<i>November</i>	-3.48±9.38E-10	-0.24±1.47E-09
<i>December</i>	0.45±1.21E-09	1.01±1.74E-09
Annual Total	0.28±2.14E-09	4.67±4.02E-09

Note: Bolding convention applied to these data. See page D-2.

Table D-12
2000 Radioactivity Concentrations ($\mu\text{Ci/mL}$) in Airborne Particulates
at the Lag Storage Air Sampler (ANLAGAM)

Month	Alpha	Beta			
January	9.54 \pm 9.96E-16	2.55 \pm 0.31E-14			
February	1.47\pm0.95E-15	2.62 \pm 0.30E-14			
March	1.13 \pm 0.98E-15	1.70 \pm 0.26E-14			
April	6.08 \pm 9.22E-16	1.25\pm0.23E-14			
May	7.41 \pm 8.66E-16	1.81 \pm 0.26E-14			
June	6.55 \pm 8.02E-16	1.38 \pm 0.24E-14			
July	4.33 \pm 7.01E-16	1.28 \pm 0.23E-14			
August	6.37 \pm 8.24E-16	1.57 \pm 0.24E-14			
September	7.00 \pm 8.80E-16	1.65 \pm 0.24E-14			
October	9.32 \pm 8.55E-16	2.64\pm0.29E-14			
November	1.18 \pm 0.92E-15	2.12 \pm 0.27E-14			
December	1.01 \pm 0.88E-15	1.74 \pm 0.25E-14			

Quarter	K-40	Co-60	Sr-90	Cs-137	U-232
1st Quarter	0.00 \pm 2.50E-15	-0.93 \pm 1.80E-16	0.60 \pm 1.07E-16	1.47 \pm 1.86E-16	0.17 \pm 1.40E-17
2nd Quarter	2.52 \pm 3.33E-15	1.02 \pm 1.49E-16	2.56\pm1.21E-16	-1.56 \pm 1.45E-16	1.00 \pm 8.68E-18
3rd Quarter	0.00 \pm 1.74E-15	0.82 \pm 1.50E-16	2.09 \pm 8.77E-17	1.00 \pm 1.39E-16	1.26 \pm 1.61E-17
4th Quarter	0.22 \pm 3.46E-15	0.49 \pm 1.48E-16	0.00 \pm 1.13E-16	0.30 \pm 1.28E-16	1.24 \pm 1.87E-17

	U-233/234	U-235/236	U-238	Total U ($\mu\text{g/mL}$)	Pu-238
1st Quarter	5.95 \pm 2.32E-17	1.09\pm1.00E-17	6.95\pm2.50E-17	2.61\pm0.03E-10	8.21 \pm 9.75E-18
2nd Quarter	9.32\pm4.24E-17	-4.17 \pm 4.20E-18	6.40 \pm 3.45E-17	1.92 \pm 0.03E-10	1.44 \pm 8.46E-18
3rd Quarter	5.91\pm2.36E-17	4.70 \pm 6.82E-18	4.14\pm1.87E-17	1.68\pm0.02E-10	0.00 \pm 3.72E-18
4th Quarter	6.04 \pm 2.11E-17	6.67 \pm 7.35E-18	5.22 \pm 1.94E-17	1.75 \pm 0.02E-10	2.81 \pm 4.65E-18

	Pu-239/240	Am-241
1st Quarter	5.85 \pm 8.50E-18	5.71 \pm 8.17E-18
2nd Quarter	-1.13 \pm 6.70E-18	1.37 \pm 1.24E-17
3rd Quarter	-0.93 \pm 4.15E-18	4.99 \pm 7.08E-18
4th Quarter	-1.77 \pm 2.52E-18	1.56\pm1.19E-17

Note: Bolding convention applied to these data. See page D-2.

Table D-13
2000 Radioactivity Concentrations ($\mu\text{Ci/mL}$) in Airborne Particulates
at the NDA Air Sampler (ANNDAAAM)

Month	Alpha	Beta				
January	8.90 \pm 9.99E-16	2.65 \pm 0.32E-14				
February	1.29\pm0.99E-15	3.05\pm0.34E-14				
March	7.45 \pm 9.89E-16	1.93 \pm 0.29E-14				
April	5.10 \pm 9.30E-16	1.35 \pm 0.24E-14				
May	6.01 \pm 8.79E-16	1.77 \pm 0.27E-14				
June	6.40 \pm 8.11E-16	1.44 \pm 0.25E-14				
July	7.38 \pm 7.97E-16	1.20\pm0.23E-14				
August	4.11 \pm 7.65E-16	1.48 \pm 0.24E-14				
September	4.75 \pm 8.46E-16	1.82 \pm 0.25E-14				
October	1.04 \pm 0.91E-15	2.54 \pm 0.30E-14				
November	1.04 \pm 0.94E-15	2.23 \pm 0.28E-14				
December	1.03 \pm 0.94E-15	1.97 \pm 0.27E-14				

Quarter	K-40	Co-60	Sr-90	Cs-137	U-232
1st Quarter	0.26 \pm 3.41E-15	-1.13 \pm 1.35E-16	-0.54 \pm 1.24E-16	1.48 \pm 1.37E-16	0.60 \pm 1.01E-17
2nd Quarter	0.07 \pm 3.31E-15	0.03 \pm 1.47E-16	-0.39 \pm 1.10E-16	0.22 \pm 3.92E-16	1.82 \pm 1.86E-17
3rd Quarter	3.39 \pm 4.75E-15	0.87 \pm 1.83E-16	0.43 \pm 1.11E-16	2.48\pm1.84E-16	-0.27 \pm 1.53E-17
4th Quarter	0.00 \pm 2.23E-15	-0.09 \pm 1.51E-16	-0.69 \pm 1.45E-16	0.40 \pm 1.45E-16	-5.11 \pm 9.43E-18

	U-233/234	U-235/236	U-238	Total U ($\mu\text{g/mL}$)	Pu-238
1st Quarter	1.10\pm0.42E-16	0.18 \pm 1.23E-17	6.16 \pm 2.94E-17	2.34\pm0.03E-10	5.53 \pm 7.89E-18
2nd Quarter	8.61 \pm 4.32E-17	-2.43 \pm 3.46E-18	6.59\pm3.75E-17	2.00 \pm 0.03E-10	1.52 \pm 6.45E-18
3rd Quarter	4.97 \pm 2.26E-17	1.02 \pm 1.05E-17	5.08\pm2.64E-17	1.76 \pm 0.03E-10	4.05 \pm 6.06E-18
4th Quarter	4.38\pm2.27E-17	-0.14 \pm 1.10E-17	5.63 \pm 2.37E-17	1.54\pm0.02E-10	1.51 \pm 3.04E-18

	Pu-239/240	Am-241
1st Quarter	5.53 \pm 7.88E-18	1.49 \pm 6.41E-18
2nd Quarter	5.81 \pm 8.25E-18	4.56\pm2.42E-17
3rd Quarter	2.70 \pm 8.54E-18	1.06 \pm 1.24E-17
4th Quarter	0.43 \pm 3.75E-18	5.09 \pm 8.40E-18

Note: Bolding convention applied to these data. See page D-2.

Table D-14
2000 Airborne Radioactivity Concentrations ($\mu\text{Ci/mL}$)
at the SDA Trench 9 Air Sampler (ANSDAT9)

Month	Alpha	Beta	H-3
January	0.75 \pm 1.21E-15	2.52\pm0.37E-14	7.85 \pm 2.85E-13
February	0.90 \pm 1.08E-15	2.48 \pm 0.37E-14	1.15 \pm 0.20E-12
March	0.84 \pm 1.25E-15	1.50 \pm 0.32E-14	1.14 \pm 0.38E-12
April	0.00 \pm 1.09E-15	1.28 \pm 0.29E-14	1.25\pm0.37E-12
May	1.59 \pm 3.76E-15	1.64 \pm 0.67E-14	3.40 \pm 5.87E-13
June	2.37 \pm 9.47E-16	1.32 \pm 0.31E-14	-0.71 \pm 6.32E-13
July	1.19 \pm 8.70E-16	1.19\pm0.29E-14	1.07 \pm 1.04E-12
August	0.55 \pm 1.13E-15	1.66 \pm 0.32E-14	0.80 \pm 1.03E-12
September	0.41 \pm 1.17E-15	1.77 \pm 0.32E-14	0.16 \pm 1.01E-12
October	1.22 \pm 1.23E-15	2.52\pm0.37E-14	5.49 \pm 4.24E-13
November	0.75 \pm 1.16E-15	2.10 \pm 0.34E-14	4.73 \pm 3.48E-13
December	0.74 \pm 1.14E-15	1.73 \pm 0.32E-14	4.37 \pm 2.26E-13

Quarter	K-40	Co-60	I-129	Cs-137
1st Quarter	0.00 \pm 3.47E-15	-1.25 \pm 2.59E-16	1.74 \pm 2.19E-16	1.13 \pm 2.51E-16
2nd Quarter	2.86 \pm 5.03E-15	1.62 \pm 2.25E-16	-0.16 \pm 1.07E-16	0.90 \pm 1.92E-16
3rd Quarter	1.60 \pm 4.32E-15	0.10 \pm 2.41E-16	0.00 \pm 1.12E-16	1.88 \pm 2.27E-16
4th Quarter	1.02 \pm 4.71E-15	-2.59 \pm 2.42E-16	1.85 \pm 2.52E-16	-0.44 \pm 2.02E-16

Note: Bolding convention applied to these data. See page D-2.

Table D-15
2000 Airborne Radioactive Effluent Totals (curies)
from Outdoor Ventilation Enclosures/Portable Ventilation Units

Month	Alpha	Beta
January	NA	NA
February	NA	NA
March	3.01±9.46E-11	-1.30±1.93E-10
April	NA	NA
May	NA	NA
June	-0.54±1.07E-11	1.60±1.91E-11
July	-8.50±9.61E-12	0.86±1.90E-11
August	NA	NA
September	2.39±4.10E-10	4.24±0.86E-09
October	NA	NA
November	-0.40±3.39E-10	-0.84±5.12E-10
December	7.40±3.61E-10	1.40±0.10E-08
Annual Total	9.55±6.51E-10	1.81±0.14E-08

Quarter	Co-60	Sr-90	Cs-137	Eu-154	U-232
1st Quarter	-0.27±1.84E-11	0.02±2.00E-11	1.07±1.47E-11	0.88±4.42E-11	-0.63±1.34E-12
2nd Quarter	0.65±1.78E-11	4.64±1.93E-11	1.12±1.56E-11	5.70±4.95E-11	0.36±1.43E-12
3rd Quarter	-0.71±7.19E-10	6.38±5.51E-10	2.39±0.94E-09	-0.69±1.90E-09	1.12±4.66E-11
4th Quarter	-3.50±3.20E-10	-0.54±3.67E-10	0.00±4.57E-10	1.27±9.12E-10	0.29±1.56E-11
Annual Total	-4.18±7.87E-10	6.30±6.63E-10	2.42±1.04E-09	-0.50±2.11E-09	1.39±4.92E-11

	U-233/234	U-235/236	U-238	Total U (g)	Pu-238
1st Quarter	0.05±1.68E-12	-0.34±1.77E-12	2.02±2.04E-12	5.69±0.08E-06	4.35±8.74E-13
2nd Quarter	2.39±2.74E-12	0.00±2.97E-11	0.76±1.75E-12	3.32±0.08E-06	1.32±1.33E-12
3rd Quarter	3.12±0.61E-10	1.35±2.70E-11	1.76±0.88E-10	1.90±0.05E-04	0.51±2.26E-11
4th Quarter	2.52±2.09E-11	1.55±9.63E-12	2.99±2.13E-11	1.05±0.01E-04	1.35±1.25E-11
Annual Total	3.40±0.64E-10	1.47±4.14E-11	2.09±0.90E-10	3.05±0.05E-04	2.03±2.59E-11

	Pu-239/240	Am-241
1st Quarter	0.00±3.78E-11	1.83±1.65E-12
2nd Quarter	3.30±6.60E-13	1.81±1.31E-12
3rd Quarter	3.04±2.88E-11	0.86±2.11E-11
4th Quarter	-0.91±5.88E-12	1.67±1.68E-11
Annual Total	2.98±4.79E-11	2.90±2.71E-11

NA - Not applicable. Ventilation units not in use.

Note: Bolding convention applied to these data. See page D-2.

Table D-16
2000 Airborne Radioactivity Concentrations ($\mu\text{Ci/mL}$) at the
Rock Springs Road Air Sampler (AFRSPRD)

Month	Alpha	Beta	H-3			
January	0.47 \pm 1.18E-15	2.24 \pm 0.36E-14	-1.56 \pm 3.49E-13			
February	1.32\pm1.22E-15	2.42\pm0.37E-14	0.65 \pm 2.00E-13			
March	0.59 \pm 1.23E-15	1.74 \pm 0.34E-14	-1.31 \pm 3.59E-13			
April	0.89 \pm 1.34E-15	1.29\pm0.30E-14	2.51 \pm 4.78E-13			
May	0.90 \pm 1.38E-15	1.85 \pm 0.35E-14	-6.34 \pm 5.34E-13			
June	1.26 \pm 1.23E-15	1.33 \pm 0.31E-14	-3.80 \pm 4.60E-13			
July	4.44 \pm 9.52E-16	1.30 \pm 0.30E-14	0.65 \pm 6.07E-13			
August	0.25 \pm 1.03E-15	1.46 \pm 0.30E-14	0.72 \pm 1.14E-12			
September	0.50 \pm 1.17E-15	1.95 \pm 0.33E-14	1.81 \pm 8.19E-13			
October	0.70 \pm 1.09E-15	2.12 \pm 0.34E-14	-0.54 \pm 5.97E-13			
November	0.65 \pm 1.13E-15	1.95 \pm 0.33E-14	-1.88 \pm 4.41E-13			
December	0.58 \pm 1.08E-15	1.36 \pm 0.30E-14	-1.10 \pm 3.44E-13			

Quarter	K-40	Co-60	Sr-90	I-129	Cs-137
1st Quarter	3.43 \pm 5.21E-15	2.64\pm2.60E-16	-1.56 \pm 1.85E-16	1.09 \pm 3.39E-16	0.49 \pm 2.42E-16
2nd Quarter	8.73\pm4.14E-15	-0.40 \pm 2.06E-16	2.00\pm0.24E-15	0.88 \pm 2.47E-16	0.14 \pm 2.10E-16
3rd Quarter	0.88 \pm 6.30E-15	0.31 \pm 2.80E-16	0.70 \pm 1.26E-16	0.17 \pm 2.64E-16	-0.03 \pm 2.74E-16
4th Quarter	0.00 \pm 2.49E-15	0.86 \pm 1.93E-16	-0.05 \pm 2.73E-16	0.18 \pm 2.09E-16	0.00 \pm 2.77E-16

	U-232	U-233/234	U-235/236	U-238	Total U ($\mu\text{g/mL}$)
1st Quarter	2.19 \pm 2.13E-17	8.89\pm3.68E-17	0.90 \pm 1.29E-17	9.44 \pm 3.86E-17	3.51\pm0.04E-10
2nd Quarter	3.24\pm2.76E-17	1.10 \pm 0.39E-16	1.67\pm1.53E-17	9.37\pm3.51E-17	2.90 \pm 0.04E-10
3rd Quarter	0.22 \pm 1.76E-17	2.11\pm0.38E-16	8.54 \pm 9.89E-18	1.32\pm0.44E-16	2.52\pm0.04E-10
4th Quarter	1.99 \pm 1.68E-17	1.07 \pm 0.36E-16	0.91 \pm 1.26E-17	9.76 \pm 3.35E-17	2.85 \pm 0.04E-10

	Pu-238	Pu-239/240	Am-241
1st Quarter	0.72 \pm 1.27E-17	0.72 \pm 1.05E-17	0.39 \pm 1.18E-17
2nd Quarter	1.06\pm0.46E-16	0.46 \pm 1.38E-17	-0.01 \pm 1.56E-17
3rd Quarter	3.17 \pm 1.49E-17	3.17\pm1.63E-17	1.25\pm1.09E-17
4th Quarter	-0.18 \pm 2.15E-17	-0.92 \pm 5.99E-18	6.69 \pm 9.48E-18

Note: Bolding convention applied to these data. See page D-2.

Table D-17
2000 Radioactivity Concentrations ($\mu\text{Ci/mL}$) in Airborne Particulates
at the Dutch Hill Air Sampler (AFBOEHN)

Month	Alpha	Beta
January	0.28 \pm 1.11E-15	2.70\pm0.38E-14
February	0.99 \pm 1.11E-15	2.51 \pm 0.37E-14
March	0.73 \pm 1.23E-15	1.82 \pm 0.34E-14
April	0.26 \pm 1.17E-15	1.28 \pm 0.29E-14
May	1.29 \pm 1.55E-15	1.93 \pm 0.37E-14
June	1.25 \pm 1.25E-15	1.97 \pm 0.35E-14
July	0.39 \pm 1.03E-15	9.47\pm2.96E-15
August	0.72 \pm 1.13E-15	1.40 \pm 0.30E-14
September	0.17 \pm 1.09E-15	1.62 \pm 0.31E-14
October	0.81 \pm 1.07E-15	2.63 \pm 0.36E-14
November	0.84 \pm 1.11E-15	2.11 \pm 0.33E-14
December	0.99 \pm 1.13E-15	1.64 \pm 0.30E-14
Quarter	Sr-90	Cs-137
1st Quarter	-0.46 \pm 2.74E-16	-0.93 \pm 1.53E-16
2nd Quarter	-0.62 \pm 1.49E-16	0.76 \pm 1.99E-16
3rd Quarter	-1.04 \pm 1.76E-16	0.28 \pm 3.89E-16
4th Quarter	-1.46 \pm 2.38E-16	0.50 \pm 4.64E-16

Table D-18
2000 Radioactivity Concentrations ($\mu\text{Ci/mL}$) in Airborne Particulates
at the Fox Valley Air Sampler (AFFXVRD)

Month	Alpha	Beta
January	0.84 \pm 1.25E-15	2.64 \pm 0.38E-14
February	1.38\pm1.22E-15	2.79\pm0.39E-14
March	1.04 \pm 1.32E-15	1.75 \pm 0.34E-14
April	0.41 \pm 1.21E-15	1.26 \pm 0.30E-14
May	1.23 \pm 1.30E-15	1.76 \pm 0.32E-14
June	0.76 \pm 1.10E-15	1.38 \pm 0.31E-14
July	4.09 \pm 9.61E-16	1.17\pm0.29E-14
August	0.87 \pm 1.23E-15	1.67 \pm 0.33E-14
September	0.50 \pm 1.19E-15	2.06 \pm 0.34E-14
October	0.97 \pm 1.15E-15	2.45 \pm 0.36E-14
November	0.72 \pm 1.11E-15	2.28 \pm 0.34E-14
December	0.93 \pm 1.14E-15	1.72 \pm 0.31E-14
Quarter	Sr-90	Cs-137
1st Quarter	2.48\pm2.35E-16	1.31 \pm 1.59E-16
2nd Quarter	0.79 \pm 1.50E-16	1.05 \pm 2.15E-16
3rd Quarter	0.64 \pm 1.67E-16	0.78 \pm 2.64E-16
4th Quarter	0.18 \pm 2.53E-16	-0.55 \pm 2.60E-16

Note: Bolding convention applied to these data. See page D-2.

Table D-19
2000 Radioactivity Concentrations ($\mu\text{Ci/mL}$) in Airborne Particulates
at the Bulk Storage Warehouse Air Sampler (AFBLKST)

Month	Alpha	Beta
January	0.93 \pm 1.27E-15	2.50 \pm 0.37E-14
February	1.49\pm1.24E-15	2.69\pm0.38E-14
March	0.77 \pm 1.25E-15	1.69 \pm 0.33E-14
April	0.45 \pm 1.22E-15	1.24\pm0.29E-14
May	0.76 \pm 1.17E-15	1.95 \pm 0.33E-14
June	0.70 \pm 1.08E-15	1.37 \pm 0.31E-14
July	5.29 \pm 9.97E-16	1.41 \pm 0.31E-14
August	0.77 \pm 1.18E-15	1.55 \pm 0.31E-14
September	0.41 \pm 1.17E-15	1.78 \pm 0.32E-14
October	1.42 \pm 1.26E-15	2.35 \pm 0.35E-14
November	0.94 \pm 1.17E-15	1.98 \pm 0.33E-14
December	0.54 \pm 1.05E-15	1.69 \pm 0.31E-14
Quarter	Sr-90	Cs-137
1st Quarter	-1.64 \pm 1.98E-16	-0.26 \pm 1.58E-16
2nd Quarter	1.23 \pm 1.89E-16	1.78 \pm 2.25E-16
3rd Quarter	0.46 \pm 2.18E-16	1.37 \pm 2.66E-16
4th Quarter	-8.45 \pm 3.24E-16	1.29 \pm 2.14E-16

Table D-20
2000 Radioactivity Concentrations ($\mu\text{Ci/mL}$) in Airborne Particulates
at the Route 240 Air Sampler (AFRT240)

Month	Alpha	Beta
January	1.22 \pm 1.37E-15	2.57 \pm 0.38E-14
February	1.31\pm1.23E-15	2.60\pm0.39E-14
March	0.79 \pm 1.29E-15	1.68 \pm 0.34E-14
April	0.45 \pm 1.24E-15	1.23 \pm 0.30E-14
May	1.02 \pm 1.23E-15	1.83 \pm 0.32E-14
June	0.59 \pm 1.04E-15	1.35 \pm 0.31E-14
July	0.93 \pm 1.10E-15	1.17\pm0.29E-14
August	0.22 \pm 1.04E-15	1.74 \pm 0.32E-14
September	0.20 \pm 1.11E-15	1.91 \pm 0.33E-14
October	1.20 \pm 1.19E-15	2.39 \pm 0.35E-14
November	0.70 \pm 1.12E-15	1.95 \pm 0.33E-14
December	0.67 \pm 1.09E-15	1.64 \pm 0.31E-14
Quarter	Sr-90	Cs-137
1st Quarter	-1.10 \pm 2.13E-16	0.00 \pm 1.76E-16
2nd Quarter	0.30 \pm 2.55E-16	0.59 \pm 2.00E-16
3rd Quarter	-0.88 \pm 1.42E-16	1.46 \pm 2.37E-16
4th Quarter	-0.17 \pm 2.85E-16	0.01 \pm 1.99E-16

Note: Bolding convention applied to these data. See page D-2.

D - 19

Table D-21
2000 Radioactivity Concentrations ($\mu\text{Ci/mL}$) in Airborne Particulates
at the Thomas Corners Road Air Sampler (AFTCORD)

Month	Alpha	Beta
January	0.92 \pm 1.28E-15	2.79\pm0.39E-14
February	1.36\pm1.23E-15	2.64 \pm 0.39E-14
March	0.53 \pm 1.21E-15	1.71 \pm 0.34E-14
April	0.30 \pm 1.19E-15	1.34 \pm 0.30E-14
May	1.02 \pm 1.23E-15	1.67 \pm 0.32E-14
June	0.78 \pm 1.10E-15	1.47 \pm 0.31E-14
July	1.02 \pm 1.13E-15	1.26\pm0.30E-14
August	0.51 \pm 1.21E-15	1.49 \pm 0.33E-14
September	0.44 \pm 1.56E-15	1.91 \pm 0.38E-14
October	0.73 \pm 1.10E-15	2.48 \pm 0.36E-14
November	0.68 \pm 1.09E-15	2.06 \pm 0.33E-14
December	0.69 \pm 1.08E-15	1.72 \pm 0.31E-14
Quarter	Sr-90	Cs-137
1st Quarter	-0.87 \pm 2.04E-16	0.69 \pm 2.77E-16
2nd Quarter	-0.48 \pm 2.33E-16	0.68 \pm 2.16E-16
3rd Quarter	1.76\pm1.67E-16	1.19 \pm 3.52E-16
4th Quarter	-0.31 \pm 2.10E-16	1.33 \pm 2.07E-16

Table D-22
2000 Radioactivity Concentrations ($\mu\text{Ci/mL}$) in Airborne Particulates
at the West Valley Air Sampler (AFWEVAL)

Month	Alpha	Beta
January	0.90 \pm 1.27E-15	2.37 \pm 0.36E-14
February	1.50\pm1.25E-15	2.51\pm0.38E-14
March	0.74 \pm 1.25E-15	1.61 \pm 0.33E-14
April	0.64 \pm 1.27E-15	1.22\pm0.29E-14
May	1.18 \pm 1.27E-15	1.70 \pm 0.32E-14
June	0.76 \pm 1.23E-15	1.28 \pm 0.34E-14
July	0.70 \pm 1.04E-15	1.29 \pm 0.30E-14
August	0.22 \pm 1.05E-15	1.45 \pm 0.31E-14
September	0.55 \pm 1.20E-15	1.70 \pm 0.32E-14
October	1.26 \pm 1.22E-15	2.38 \pm 0.35E-14
November	0.79 \pm 1.12E-15	2.03 \pm 0.33E-14
December	0.91 \pm 1.14E-15	1.65 \pm 0.31E-14
Quarter	Sr-90	Cs-137
1st Quarter	0.17 \pm 1.73E-16	-0.63 \pm 1.94E-16
2nd Quarter	2.84\pm2.05E-16	0.55 \pm 1.82E-16
3rd Quarter	1.00 \pm 1.65E-16	-0.11 \pm 2.67E-16
4th Quarter	-2.77 \pm 2.14E-16	-0.46 \pm 1.99E-16

Note: Bolding convention applied to these data. See page D-2.

Table D-23
2000 Radioactivity Concentrations ($\mu\text{Ci/mL}$) in Airborne Particulates
at the Springville Air Sampler (AFSPRVL)

Month	Alpha	Beta
<i>January</i>	1.45\pm1.38E-15	2.43 \pm 0.36E-14
<i>February</i>	1.33 \pm 1.20E-15	2.62\pm0.38E-14
<i>March</i>	0.46 \pm 1.17E-15	1.80 \pm 0.34E-14
<i>April</i>	0.60 \pm 1.25E-15	1.29\pm0.30E-14
<i>May</i>	0.90 \pm 1.20E-15	1.73 \pm 0.32E-14
<i>June</i>	0.85 \pm 1.12E-15	1.39 \pm 0.31E-14
<i>July</i>	0.65 \pm 1.03E-15	1.29\pm0.30E-14
<i>August</i>	0.38 \pm 1.13E-15	1.40 \pm 0.32E-14
<i>September</i>	0.35 \pm 1.15E-15	1.91 \pm 0.33E-14
<i>October</i>	0.84 \pm 1.20E-15	2.45 \pm 0.38E-14
<i>November</i>	0.68 \pm 1.13E-15	2.14 \pm 0.34E-14
<i>December</i>	0.94 \pm 1.18E-15	1.74 \pm 0.32E-14

Quarter	Sr-90	Cs-137
<i>1st Quarter</i>	-0.53 \pm 2.08E-16	0.68 \pm 2.33E-16
<i>2nd Quarter</i>	1.32 \pm 2.42E-16	2.21 \pm 5.17E-16
<i>3rd Quarter</i>	0.87 \pm 1.90E-16	0.16 \pm 2.20E-16
<i>4th Quarter</i>	-2.49 \pm 3.18E-16	2.34 \pm 5.62E-16

Note: Bolding convention applied to these data. See page D-2.

Table D-24
2000 Airborne Radioactivity Concentrations ($\mu\text{Ci/mL}$)
at the Great Valley Background Air Sampler (AFGRVAL)

Month	Alpha	Beta	H-3			
January	0.81 \pm 1.22E-15	2.31 \pm 0.35E-14	1.33 \pm 2.67E-13			
February	1.12 \pm 1.13E-15	2.45\pm0.37E-14	0.75 \pm 2.13E-13			
March	0.87 \pm 1.25E-15	1.61 \pm 0.33E-14	0.06 \pm 3.62E-13			
April	0.22 \pm 1.13E-15	1.16 \pm 0.28E-14	-0.56 \pm 4.42E-13			
May	0.57 \pm 1.06E-15	1.58 \pm 0.30E-14	-9.00 \pm 6.90E-13			
June	6.13\pm1.00E-15	1.24 \pm 0.29E-14	-7.53 \pm 9.93E-13			
July	4.29 \pm 9.15E-16	1.05\pm0.27E-14	-1.13 \pm 9.08E-13			
August	0.62 \pm 1.10E-15	1.31 \pm 0.29E-14	3.44 \pm 9.31E-13			
September	0.41 \pm 1.10E-15	1.55 \pm 0.30E-14	-1.71 \pm 9.81E-13			
October	1.33 \pm 1.22E-15	2.34 \pm 0.35E-14	3.08 \pm 5.36E-13			
November	0.92 \pm 1.22E-15	2.07 \pm 0.35E-14	1.46 \pm 5.70E-13			
December	0.99 \pm 1.22E-15	1.65 \pm 0.32E-14	2.01 \pm 2.37E-13			

Quarter	K-40	Co-60	Sr-90	I-129	Cs-137
1st Quarter	1.52 \pm 6.66E-15	1.17 \pm 2.97E-16	1.37\pm0.45E-15	1.08 \pm 3.24E-16	2.41 \pm 2.91E-16
2nd Quarter	0.41 \pm 5.26E-15	0.30 \pm 2.08E-16	3.80 \pm 2.71E-16	0.25 \pm 2.22E-16	0.62 \pm 1.92E-16
3rd Quarter	1.50 \pm 4.68E-15	-1.70 \pm 2.74E-16	1.22 \pm 2.76E-16	7.69 \pm 9.15E-17	3.28 \pm 4.46E-16
4th Quarter	5.49\pm3.10E-15	0.66 \pm 2.28E-16	-0.80 \pm 2.78E-16	0.01 \pm 2.95E-16	0.59 \pm 2.17E-16

	U-232	U-233/234	U-235/236	U-238	Total U ($\mu\text{g/mL}$)
1st Quarter	0.52 \pm 1.86E-17	1.37\pm0.44E-16	1.59\pm1.45E-17	1.32 \pm 0.42E-16	2.78\pm0.04E-10
2nd Quarter	0.55 \pm 1.43E-17	9.35 \pm 3.85E-17	3.34 \pm 6.71E-18	8.19 \pm 3.56E-17	2.71 \pm 0.04E-10
3rd Quarter	-1.59 \pm 1.55E-17	9.27 \pm 1.81E-17	5.31 \pm 7.53E-18	1.47\pm0.47E-16	2.62 \pm 0.04E-10
4th Quarter	-0.24 \pm 2.28E-17	7.36\pm2.95E-17	0.64 \pm 1.16E-17	7.42\pm2.70E-17	2.61\pm0.03E-10

	Pu-238	Pu-239/240	Am-241
1st Quarter	2.97\pm2.14E-17	1.81 \pm 7.72E-18	2.74 \pm 3.00E-17
2nd Quarter	4.86 \pm 9.74E-18	0.74 \pm 1.46E-17	0.88 \pm 1.02E-17
3rd Quarter	1.29 \pm 0.98E-17	0.00 \pm 1.76E-17	1.19 \pm 0.85E-17
4th Quarter	1.68 \pm 2.13E-17	-5.89 \pm 5.93E-18	2.72\pm2.25E-17

Note: Bolding convention applied to these data. See page D-2.

Table D-25
2000 Radioactivity Concentrations ($\mu\text{Ci/mL}$) in Airborne Particulates
at the Nashville Background Air Sampler (AFNASHV)

Month	Alpha	Beta
January	0.90 \pm 1.29E-15	2.64 \pm 0.38E-14
February	1.76\pm1.33E-15	2.72 \pm 0.39E-14
March	1.08 \pm 1.35E-15	1.67 \pm 0.34E-14
April	0.27 \pm 1.20E-15	1.50 \pm 0.31E-14
May	1.09 \pm 1.27E-15	1.83 \pm 0.33E-14
June	0.69 \pm 1.08E-15	1.38 \pm 0.31E-14
July	0.95 \pm 1.11E-15	1.23\pm0.30E-14
August	0.36 \pm 1.09E-15	1.47 \pm 0.31E-14
September	-0.14 \pm 1.10E-15	1.68 \pm 0.33E-14
October	0.68 \pm 1.11E-15	2.73\pm0.38E-14
November	0.36 \pm 1.07E-15	2.09 \pm 0.34E-14
December	0.49 \pm 1.10E-15	1.93 \pm 0.34E-14

Quarter	Sr-90	Cs-137
1st Quarter	0.95 \pm 2.07E-16	0.10 \pm 1.67E-16
2nd Quarter	1.22 \pm 1.88E-16	-1.05 \pm 2.10E-16
3rd Quarter	1.51 \pm 1.58E-16	2.46 \pm 2.56E-16
4th Quarter	0.33 \pm 2.54E-16	1.89 \pm 3.23E-16

Note: Bolding convention applied to these data. See page D-2.

Table D-26
2000 Radioactivity (nCi/m²/month) and pH in Fallout
Dutch Hill (AFDHFOP)

Month	Alpha	Beta	H-3 (μCi/mL)	K-40	Cs-137	pH (standard units)
January	3.61±4.00E-03	2.56±0.23E-01	1.05±8.21E-08	-0.35±3.41E+00	-1.04±2.99E-01	5.08
February	2.99±0.52E-02	4.31±0.19E-01	7.22±8.34E-08	0.55±1.52E+00	0.44±1.21E-01	3.91
March	2.28±2.23E-03	3.57±0.69E-02	1.38±0.85E-07	-3.03±8.75E-01	0.24±5.34E-02	5.41
April	4.86±1.52E-02	7.49±0.57E-01	7.85±8.39E-08	0.66±8.54E+00	-0.67±5.29E-01	4.18
May	2.86±0.78E-02	6.15±0.36E-01	3.92±8.16E-08	-4.32±3.92E+00	-0.44±3.70E-01	5.05
June	3.66±0.91E-02	6.19±0.37E-01	-8.22±8.27E-08	0.35±4.08E+00	-2.78±3.43E-01	4.19
July	1.16±0.46E-02	2.34±0.15E-01	-0.97±5.77E-08	-0.91±2.12E+00	1.06±1.41E-01	7.12
August	6.34±1.99E-02	9.06±0.69E-01	-2.37±5.76E-08	-0.22±1.06E+01	-3.06±8.24E-01	4.03
September	6.70±1.61E-02	8.75±0.58E-01	-2.62±8.52E-08	0.85±1.08E+01	3.18±8.74E-01	6.25
October	5.64±1.01E-02	5.07±0.31E-01	1.17±8.26E-08	2.10±3.42E+00	0.51±2.94E-01	4.27
November	1.70±0.40E-02	2.00±0.13E-01	-9.24±5.67E-08	-0.45±2.16E+00	0.32±1.88E-01	4.38
December	2.07±0.57E-02	2.91±0.21E-01	-1.54±0.81E-07	-1.22±3.08E+00	0.68±1.98E-01	4.42

Table D-27
2000 Radioactivity (nCi/m²/month) and pH in Fallout
Rain Gauge (ANRGFOP)

Month	Alpha	Beta	H-3 (μCi/mL)	K-40	Cs-137	pH (standard units)
January	4.92±6.39E-03	3.20±0.34E-01	-3.96±8.27E-08	5.95±8.93E+00	1.85±6.13E-01	5.29
February	4.94±1.02E-02	6.05±0.38E-01	-1.27±5.80E-08	5.07±6.62E+00	2.69±5.31E-01	4.72
March	2.97±1.22E-02	4.05±0.34E-01	9.98±8.27E-08	-4.54±3.96E+00	-0.36±3.28E-01	6.50
April	2.73±1.69E-02	3.73±0.53E-01	1.56±8.25E-08	0.90±1.59E+01	-0.31±1.14E+00	7.13
May	7.61±1.53E-02	7.67±0.50E-01	-0.87±8.14E-08	-0.43±1.09E+01	-4.51±5.99E-01	6.72
June	6.34±1.51E-02	8.65±0.57E-01	-1.05±0.82E-07	-6.89±6.01E+00	-1.65±5.23E-01	5.28
July	4.08±0.87E-02	4.55±0.28E-01	-5.27±8.04E-08	2.86±4.27E+00	1.24±2.82E-01	4.63
August	5.14±2.00E-02	9.15±0.76E-01	-7.08±8.02E-08	-1.74±1.83E+01	0.54±1.45E+00	4.05
September	6.01±1.80E-02	1.06±0.08E+00	1.35±5.87E-08	-0.62±1.52E+01	-0.07±1.45E+00	5.87
October	2.56±0.98E-02	4.18±0.38E-01	4.72±5.64E-08	3.04±8.16E+00	2.42±6.42E-01	4.11
November	3.36±1.07E-02	3.94±0.34E-01	-1.03±0.79E-07	-1.44±4.23E+00	1.48±3.84E-01	4.40
December	6.85±1.48E-02	6.79±0.48E-01	-2.16±8.26E-08	5.67±8.71E+00	-2.66±7.13E-01	4.83

Note: Bolding convention applied to these data. See page D-2.

Table D-28
2000 Radioactivity (nCi/nr²/month) and pH in Fallout
Route 240 (AF24FOP)

Month	Alpha	Beta	H-3 (μCi/mL)	K-40	Cs-137	pH (standard units)
January	2.90±0.81E-02	2.27±0.07E+00	7.60±8.36E-08	1.44±6.43E+00	1.06±4.26E-01	4.78
February	4.41±0.86E-02	4.47±0.25E-01	3.12±8.33E-08	2.28±5.15E+00	-0.18±2.98E-01	4.13
March	2.80±0.60E-02	3.85±0.20E-01	1.40±0.59E-07	-0.42±3.52E+00	0.07±1.88E-01	4.31
April	5.74±1.67E-02	8.07±0.62E-01	0.60±5.83E-08	0.54±8.72E+00	-2.32±6.58E-01	4.52
May	5.18±1.11E-02	8.19±0.45E-01	-2.49±8.10E-08	-0.22±4.50E+00	0.09±3.40E-01	5.53
June	2.71±0.98E-02	6.75±0.45E-01	-1.06±0.83E-07	-6.29±4.56E+00	-0.05±4.06E-01	4.45
July	1.29±0.38E-02	3.00±0.15E-01	7.96±8.14E-08	0.31±1.22E+00	0.88±1.88E-01	3.80
August	4.39±1.85E-02	9.60±0.74E-01	-0.29±8.15E-08	-0.89±1.07E+01	3.92±6.96E-01	4.04
September	5.87±1.69E-02	1.15±0.08E+00	2.90±8.30E-08	-0.71±9.89E+00	-1.84±8.04E-01	5.40
October	2.65±0.82E-02	3.31±0.29E-01	1.14±0.81E-07	0.10±4.89E+00	4.38±3.43E-01	3.96
November	2.53±0.83E-02	3.04±0.26E-01	-4.76±8.02E-08	1.95±4.38E+00	-0.80±3.03E-01	4.35
December	4.26±0.93E-02	4.78±0.31E-01	-8.98±8.20E-08	-1.55±2.70E+00	-2.42±2.09E-01	4.45

Table D-29
2000 Radioactivity (nCi/nr²/month) and pH in Fallout
Thomas Corners Road (AFTCFOP)

Month	Alpha	Beta	H-3 (μCi/mL)	K-40	Cs-137	pH (standard units)
January	1.04±6.14E-03	9.13±2.34E-02	4.28±5.86E-08	0.09±4.08E+00	1.27±2.92E-01	5.58
February	3.52±1.00E-02	3.96±0.31E-01	7.88±8.44E-08	-3.14±5.09E+00	-0.85±3.06E-01	6.76
March	9.98±8.83E-03	2.15±0.29E-01	1.81±8.13E-08	0.89±4.86E+00	2.99±3.55E-01	6.39
April	6.72±1.90E-02	9.29±0.70E-01	3.65±8.28E-08	-2.55±7.20E+00	5.27±5.38E-01	5.48
May	8.10±1.43E-02	1.10±0.05E+00	0.92±8.14E-08	1.87±5.97E+00	5.18±3.66E-01	6.05
June	4.18±1.41E-02	6.79±0.56E-01	-1.51±0.82E-07	-1.87±7.44E+00	-1.92±3.91E-01	5.43
July	2.07±0.94E-02	4.72±0.40E-01	1.32±0.82E-07	8.13±8.78E+00	-2.30±6.20E-01	5.40
August	2.24±1.58E-02	1.00±0.07E+00	5.88±8.27E-08	0.61±1.35E+01	2.56±7.86E-01	4.40
September	6.61±2.12E-02	8.96±0.82E-01	-2.17±8.08E-08	0.58±1.59E+01	-0.08±1.41E+00	5.87
October	4.03±1.04E-02	4.03±0.35E-01	0.85±8.01E-08	3.71±7.48E+00	2.55±6.44E-01	4.05
November	3.36±1.23E-02	4.53±0.40E-01	-1.35±0.81E-07	-0.08±1.04E+01	0.50±8.26E-01	4.58
December	3.98±1.36E-02	6.73±0.51E-01	-3.73±8.27E-08	0.18±1.05E+01	3.87±8.57E-01	4.83

Note: Bolding convention applied to these data. See page D-2.

Table D-30
2000 Radioactivity (nCi/m²/month) and pH in Fallout
Fox Valley Road (AFFXFOP)

Month	Alpha	Beta	H-3 (μCi/mL)	K-40	Cs-137	pH (standard units)
January	1.09±0.76E-02	9.39±2.44E-02	1.77±0.84E-07	-6.52±5.95E+00	5.97±4.55E-01	5.63
February	3.16±0.89E-02	4.06±0.27E-01	7.60±8.36E-08	0.31±5.96E+00	1.96±3.86E-01	6.73
March	3.04±0.92E-02	3.16±0.25E-01	6.27±8.32E-08	-0.79±3.04E+00	-0.07±2.74E-01	6.43
April	3.81±1.59E-02	8.27±0.66E-01	3.37±8.28E-08	-0.43±1.01E+01	-1.55±6.81E-01	4.63
May	8.53±1.73E-02	8.64±0.56E-01	2.17±8.25E-08	3.15±8.82E+00	2.76±5.17E-01	7.15
June	6.34±1.52E-02	6.70±0.52E-01	-1.30±0.82E-07	-0.40±6.35E+00	0.45±6.31E-01	4.67
July	3.62±0.72E-02	2.82±0.19E-01	-6.23±8.15E-08	2.60±2.29E+00	1.36±1.56E-01	6.55
August	5.39±2.28E-02	7.68±0.78E-01	-0.78±8.20E-08	-0.56±1.59E+01	-0.54±1.01E+00	4.19
September	8.45±1.96E-02	1.32±0.08E+00	4.84±8.31E-08	-0.22±1.06E+01	0.71±7.23E-01	5.48
October	2.40±0.89E-02	2.29±0.26E-01	4.79±8.43E-08	1.18±5.67E+00	-1.08±3.33E-01	6.54
November	2.57±0.92E-02	3.35±0.30E-01	5.23±8.18E-08	1.90±5.38E+00	3.98±5.22E-01	4.94
December	6.79±1.49E-02	5.54±0.44E-01	2.65±8.39E-08	-2.74±5.59E+00	-2.71±5.02E-01	6.12

Note: Bolding convention applied to these data. See page D-2.

Appendix E

Summary of Groundwater Monitoring Data

The tables on pages E-7 through E-19 contain a bolding convention devised to help the reader, when viewing the data, to quickly see the range of detectable measurements within a data series. A data series is a set of chemical or radionuclide measurements (e.g., gross alpha, gross beta, tritium) from a single location or from similar locations. Note that some tables contain data that should not be technically evaluated under this convention.

Key to bolding convention:

Results for each constituent constitute a single data series. If a radiological result is larger than the uncertainty term, the measurement is considered positive. Otherwise, a result is considered nondetectable. Chemical results preceded by "less than" (<) are considered nondetectable.

If all results in a data series are positive, the lowest and highest values are bolded.

If a data series contains some positive results, the highest value is bolded.

If all values in a data series are nondetectable, no values are bolded.

Table E-1
Groundwater Monitoring Network: Super Solid Waste Management Units

SSWMUS and Constituent SWMUs	Well ID Number ¹	Additional Analytes Measured in 2000 ²	Well ID Number ¹	Additional Analytes Measured in 2000 ²
SSWMU #1 - Low-Level Waste Treatment Facilities:				
	103*	(S:D) V	110*	(T:D) V
• Former Lagoon 1	104	(S:C) SV,V	111*	(S:D) M33, S, SV, V
• LLWTF Lagoons	105	(S:C) V	114	(T:D) <i>p</i>
• LLWTF Building	106	(S:D) V	115	(T:U) <i>p</i>
• Interceptors	107	(T:D) V	116*	(S:U) S,V
• Neutralization Pit	108	(T:D) V	8604	(S:C) V
	109	(T:D) <i>p</i>	8605*	(S:D) M33, S, SV, V
SSWMU #2 - Miscellaneous Small Units:				
	201	(S:U) V	206	(TS:D)
• Sludge Ponds	202	(TS:U) <i>p</i>	207	(S:D) <i>p</i>
• Solvent Dike	203	(S:D) <i>p</i>	208	(TS:D) V
• Equalization Mixing Basin	204*	(TS:D)	8606	(S:D) <i>p</i>
• Paper Incinerator	205	(S:D)		
SSWMU #3 - Liquid Waste Treatment System:				
• Liquid Waste Treatment System	301*	(S:B)	307	(S:D) <i>p</i>
• Cement Solidification System	302	(TS:U)		
• Main Process Building (specific areas)	305	(S:D) <i>p</i>		

¹ Hydrogeologic unit monitored and well position in SSWMU follow the well ID in parentheses. Hydrogeologic units monitored are: WT (weathered Lavery till); T (unweathered Lavery till); S (sand and gravel); K (Kent recessional sequence); TS (till-sand). Well position in SSWMU: U (upgradient); D (downgradient); B (background); C (crossgradient). Example: 401* (S:B) monitors background conditions in the sand and gravel unit.

² See Table 3-1 (p. 3-6) for a description of codes and analytes. The parameters listed in this table, Table E-1, are in addition to the contamination indicator parameters (I) and radiological indicator parameters (RI) routinely scheduled at all monitoring locations for 2000. Wells measured for potentiometric (water-level) data only are designated by *p*.

* Monitoring for certain parameters is required by the RCRA §3008(h) Order on Consent.

Table E-1 (continued)
Groundwater Monitoring Network: Super Solid Waste Management Units

SSWMUS and Constituent SWMUs	Well ID Number ¹	Additional Analytes Measured in 2000 ²	Well ID Number ¹	Additional Analytes Measured in 2000 ²
SSWMU #4 - HLW Storage and Processing Area:				
• Vitrification Facility	401*	(S:B) R	405	(T:C)
• Vitrification Test Tanks	402	(TS:U)	406*	(S:D) R, V
• HLW Tanks	403	(S:U) V	408*	(S:D) R, V
• Supernatant Treatment System	404	(TS:U) <i>p</i>	409	(T:D)
SSWMU #5 - Maintenance Shop Leach Field:				
• Maintenance Shop Leach Field	501*	(S:U) S, V	502*	(S:D) S, SM, V
SSWMU #6 - Low-level Waste Storage Area:				
• Hardstands (old and new)	601	(S:D) <i>p</i>	605	(S:D) S
• Lag Storage	602A	(S:D) S	8607*	(S:U) V
• Lag Storage Additions	603	(S:U) <i>p</i>	8608	(S:U) <i>p</i>
(LSAs 1,2,3,4)	604	(S:D)	8609*	(S:U) S, V
SSWMU #7- Chemical Process Cell (CPC)Waste Storage Area:				
	701	(TS:U) <i>p</i>	705	(T:C) <i>p</i>
	702	(T:C) <i>p</i>	706*	(S:B)
	703	(T:D) <i>p</i>	707	(T:D)
	704	(T:D) V		
• CPC Waste Storage Area				

¹ Hydrogeologic unit monitored and well position in SSWMU follow the well ID in parentheses. Hydrogeologic units monitored are: WT (weathered Lavery till); T (unweathered Lavery till); S (sand and gravel); K (Kent recessional sequence); TS (till-sand). Well position in SSWMU: U (upgradient); D (downgradient); B (background); C (crossgradient). Example: 401* (S:B) monitors background conditions in the sand and gravel unit.

² See Table 3-1 (p. 3-6) for a description of codes and analytes. The parameters listed in this table, Table E-1, are in addition to the contamination indicator parameters (I) and radiological indicator parameters (RI) routinely scheduled at all monitoring locations for 2000. Wells measured for potentiometric (water-level) data only are designated by *p*.

* Monitoring for certain parameters is required by the RCRA §3008(h) Order on Consent.

Table E-1 (continued)
Groundwater Monitoring Network: Super Solid Waste Management Units

SSWMUS and Constituent SWMUs	Well ID Number ¹	Additional Analytes Measured in 2000 ²	Well ID Number ¹	Additional Analytes Measured in 2000 ²
SSWMU #8 - Construction and Demolition Debris Landfill:				
• Former Construction and Demolition Debris Landfill	801*	(S:U) S, V	804*	(S:D) V
	802	(S:D) V	8603	(S:U) S
	803*	(S:D) SV, V	8612*	(S:D) SV, V
SSWMU #9 - NRC-licensed Disposal Area:				
• NRC-licensed Disposal Area • Container Storage Area • Trench Interceptor Project	901*	(K:U)	908*	(WT:U)
	902*	(K:U)	909*	(WT:D) M33, R, SV, V
	903*	(K:D)	910*	(T:D)
	904	(T:D) <i>p</i>	8610*	(K:D)
	905	(S:D) <i>p</i>	8611*	(K:D)
	906*	(WT:D)	NDATR	(Interceptor Trench Manhole Sump: D) M33, R, SV, V
	907	(WT:D) <i>p</i>		
SSWMU #10 - IRTS Drum Cell:				
• IRTS Drum Cell • Background (south plateau)	1001	(K:U) <i>p</i>	1006*	(WT:D)
	1002	(K:D) <i>p</i>	1007	(WT:D)
	1003	(K:D) <i>p</i>	1008B	(K:B)
	1004	(K:D) <i>p</i>	1008C*	(WT:B)
	1005*	(WT:U)		

¹ Hydrogeologic unit monitored and well position in SSWMU follow the well ID in parentheses. Hydrogeologic units monitored are: WT (weathered Lavery till); T (unweathered Lavery till); S (sand and gravel); K (Kent recessional sequence); TS (till-sand). Well position in SSWMU: U (upgradient); D (downgradient); B (background); C (crossgradient). Example: 401* (S:B) monitors background conditions in the sand and gravel unit.

² See Table 3-1 (p. 3-6) for a description of codes and analytes. The parameters listed in this table, Table E-1, are in addition to the contamination indicator parameters (I) and radiological indicator parameters (RI) routinely scheduled at all monitoring locations for 2000. Wells measured for potentiometric (water-level) data only are designated by *p*.

* Monitoring for certain parameters is required by the RCRA §3008(h) Order on Consent.

Table E-1 (concluded)
Groundwater Monitoring Network: Super Solid Waste Management Units

SSWMUS and Constituent SWMUs	Well ID Number ¹	Additional Analytes Measured in 2000 ²	Well ID Number ¹	Additional Analytes Measured in 2000 ²
Main Plant Area Well Points:				
<i>(Monitor groundwater at various locations north and east of the main plant. Not in a SSWMU.)</i>	WP-A	(S)		
	WP-C	(S)		
	WP-H	(S)		
Former Sand and Gravel Background:	NB1S	(S:B)		
<i>(Well originally used for background; replaced by a combination of wells 301, 401, and 706. Not in a SSWMU.)</i>				
North Plateau Groundwater Seeps:				
<i>(Monitor groundwater emanating from seeps along the north pleateau edge. Not in a SSWMU.)</i>	SP04	(S)	RI	SP12*
	SP06	(S)	RI	GSEEP*
	SP11	(S)	RI	
				I, RI,V
				I, RI, V

Note: The SDA is sampled by NYSERDA under an independent monitoring program.

SSWMU #11 - State-licensed Disposal Area (SDA) • State-licensed Disposal Area [NYSERDA]	1101A	(WT:U)	See Appendix L	1104C	(K:D)	See Appendix L
	1101B	(T:U)		1105A	(WT:D)	
	1101C	(K:U)		1105B	(T:D)	
	1102A	(WT:D)		1106A	(WT:U)	
	1102B	(T:D)		1106B	(T:U)	
	1103A	(WT:D)		1107A	(WT:D)	
	1103B	(T:D)		1108A	(WT:U)	
	1103C	(K:D)		1109A	(WT:U)	
	1104A	(WT:D)		1109B	(WT:U)	
	1104B	(T:D)		1110A	(WT:D)	
				1111A	(WT:D)	

¹ Hydrogeologic unit monitored and well position in SSWMU follow the well ID in parentheses. Hydrogeologic units monitored are: WT (weathered Lavery till); T (unweathered Lavery till); S (sand and gravel); K (Kent recessional sequence); TS (till-sand). Well position in SSWMU: U (upgradient); D (downgradient); B (background); C (crossgradient). Example: 401* (S:B) monitors background conditions in the sand and gravel unit.

² See Table 3-1 (p. 3-6) for a description of codes and analytes. The parameters listed in this table, Table E-1, are in addition to the contamination indicator parameters (I) and radiological indicator parameters (RI) routinely scheduled at all monitoring locations for 2000. Wells measured for potentiometric (water-level) data only are designated by p.

* Monitoring for certain parameters is required by the RCRA §3008(h) Order on Consent.

Table E-2
2000 Contamination Indicator and Radiological Indicator Results
Sand and Gravel Unit

Location Code	Hydraulic Position	pH (standard units)	Conductivity (μmhos/cm@25°C)	Gross Alpha (μCi/mL)	Gross Beta (μCi/mL)	Tritium (μCi/mL)
301	UP(1)	7.29	1158	-0.41±1.69E-09	9.63±2.91E-09	-2.35±8.05E-08
301	UP(2)	6.55	1110	-0.84±1.84E-09	1.10±0.29E-08	-5.68±8.06E-08
301	UP(3)	6.92	1272	1.10±2.82E-09	9.82±3.10E-09	-1.15±0.59E-07
301	UP(4)	6.81	1139	-1.21±2.85E-09	1.44±0.50E-08	8.28±8.01E-08
401	UP(1)	6.73	1990	-4.77±6.06E-09	0.46±7.22E-09	1.01±0.58E-07
401	UP(2)	6.90	2870	-2.68±6.89E-09	8.34±8.03E-09	-1.05±0.80E-07
401	UP(3)	6.87	1984	0.48±5.91E-09	-4.59±6.94E-09	-6.93±7.88E-08
401	UP(4)	6.69	1300	0.90±2.25E-09	7.80±4.59E-09	1.72±0.81E-07
403	UP(1)	7.25	612	0.45±1.25E-09	2.37±3.46E-09	1.24±8.08E-08
403	UP(2)	6.89	1092	-1.48±2.65E-09	4.92±3.68E-09	-5.12±8.10E-08
403	UP(3)	7.10	1066	2.09±2.83E-09	9.94±4.09E-09	-8.73±8.35E-08
403	UP(4)	6.78	1191	-0.71±2.57E-09	1.02±0.38E-08	6.67±8.02E-08
706	UP(1)	7.03	557	-0.09±1.45E-09	9.55±2.29E-09	-4.27±8.00E-08
706	UP(2)	6.86	664	-0.62±1.36E-09	1.04±0.23E-08	-1.02±0.80E-07
706	UP(3)	6.90	753	0.66±1.75E-09	1.29±0.24E-08	-1.30±0.83E-07
706	UP(4)	6.60	630	1.44±1.42E-09	1.16±0.23E-08	2.85±5.73E-08
NB1S	UP(1)	6.54	551	-7.34±9.72E-10	0.62±1.76E-09	-1.43±8.02E-08
NB1S	UP(2)	6.21	676	-0.37±1.19E-09	1.79±1.82E-09	-9.26±8.14E-08
NB1S	UP(3)	7.03	668	0.00±1.99E-09	3.58±1.92E-09	-1.23±0.79E-07
NB1S	UP(4)	6.62	716	-0.52±1.03E-09	1.70±1.72E-09	-0.80±8.04E-08
201	DOWN-B(1)	6.47	1396	3.14±2.58E-09	2.55±0.43E-08	-0.97±1.75E-07
201	DOWN-B(2)	6.24	2615	-5.84±5.21E-09	6.25±0.81E-08	-8.49±8.50E-08
201	DOWN-B(3)	6.42	2690	2.73±3.40E-09	4.49±0.70E-08	-3.22±5.70E-08
201	DOWN-B(4)	6.29	1381	-2.15±2.59E-09	2.88±0.56E-08	-0.45±8.26E-08
103	DOWN-C(1)	8.69	1886	-1.30±4.14E-09	3.88±0.90E-08	-2.81±5.70E-08
103	DOWN-C(2)	9.10	5500	-1.55±6.05E-09	2.36±0.12E-07	1.64±0.83E-07
103	DOWN-C(3)	7.99	5995	-5.08±6.85E-09	2.54±0.12E-07	0.65±8.02E-08
103	DOWN-C(4)	8.65	3315	-2.78±5.89E-09	1.02±0.11E-07	4.65±8.24E-08
104	DOWN-C(1)	6.80	1516	-5.50±9.50E-09	3.20±0.02E-05	3.23±0.88E-07
104	DOWN-C(2)	6.96	666	0.00±8.39E-09	3.24±0.02E-05	5.94±0.91E-07
104	DOWN-C(3)	7.07	1503	2.08±3.20E-09	3.83±0.01E-05	4.99±0.75E-07
104	DOWN-C(4)	7.07	1604	2.68±9.07E-09	4.61±0.03E-05	4.47±0.85E-07
111	DOWN-C(1)	6.48	691	1.03±5.25E-09	4.95±0.06E-06	2.82±0.60E-07
111	DOWN-C(2)	6.42	509	3.28±6.42E-09	3.32±0.08E-06	1.30±0.59E-07
111	DOWN-C(3)	6.56	660	6.44±2.56E-09	5.51±0.05E-06	6.40±0.87E-07
111	DOWN-C(4)	6.53	807	8.50±8.81E-09	8.83±0.12E-06	4.98±0.85E-07

Sample collection quarter is noted in parentheses next to hydraulic position. Hydraulic position is relative to other wells within the same hydrogeologic unit.

Note: Bolding convention applied to these data. See page E-2.

Table E-2 (continued)
2000 Contamination Indicator and Radiological Indicator Results
Sand and Gravel Unit

Location Code	Hydraulic Position	pH (standard units)	Conductivity (μmhos/cm@25°C)	Gross Alpha (μCi/mL)	Gross Beta (μCi/mL)	Tritium (μCi/mL)
205	DOWN-C(1)	6.84	2875	2.03±4.87E-09	2.29±0.63E-08	-3.70±8.02E-08
205	DOWN-C(2)	6.85	1906	0.41±4.93E-09	1.80±0.77E-08	-7.32±8.06E-08
205	DOWN-C(3)	7.01	2540	2.49±5.59E-09	1.61±0.60E-08	1.00±8.13E-08
205	DOWN-C(4)	6.84	1844	-2.23±4.00E-09	1.68±0.69E-08	-2.49±7.91E-08
406	DOWN-C(1)	7.09	684	0.00±1.04E-09	6.93±1.82E-09	1.26±0.83E-07
406	DOWN-C(2)	6.80	760	-1.19±1.34E-09	1.03±0.28E-08	1.83±0.83E-07
406	DOWN-C(3)	7.04	998	-1.76±2.33E-09	1.08±0.29E-08	-9.48±9.34E-08
406	DOWN-C(4)	6.70	878	-0.98±1.69E-09	1.11±0.28E-08	-0.43±1.18E-07
408	DOWN-C(1)	6.92	1800	1.94±2.36E-09	4.29±0.01E-04	2.21±0.14E-06
408	DOWN-C(2)	7.16	1936	-1.07±1.68E-09	4.83±0.01E-04	1.85±1.01E-07
408	DOWN-C(3)	7.14	2180	0.53±1.39E-08	5.94±0.16E-04	0.63±1.03E-07
408	DOWN-C(4)	7.24	2170	-1.31±0.86E-08	5.82±0.01E-04	1.60±1.08E-07
501	DOWN-C(1)	7.12	1652	-0.67±1.16E-08	2.23±0.01E-04	1.53±0.86E-07
501	DOWN-C(2)	6.83	1742	-2.18±9.54E-09	2.25±0.01E-04	1.57±0.83E-07
501	DOWN-C(3)	7.09	1414	-0.34±3.22E-09	2.55±0.01E-04	9.80±5.71E-08
501	DOWN-C(4)	7.30	1975	0.32±1.08E-08	2.77±0.01E-04	1.70±0.81E-07
502	DOWN-C(1)	6.99	1548	0.18±1.18E-08	1.70±0.01E-04	6.38±8.50E-08
502	DOWN-C(2)	6.84	1612	0.77±1.20E-08	1.71±0.01E-04	1.38±0.58E-07
502	DOWN-C(3)	7.20	1640	1.36±3.06E-09	1.84±0.01E-04	9.27±8.12E-08
502	DOWN-C(4)	7.20	1830	0.59±1.16E-08	2.11±0.01E-04	2.63±0.83E-07
602A	DOWN-C(1)	7.03	608	1.19±1.81E-09	1.12±0.29E-08	2.66±0.85E-07
602A	DOWN-C(2)	6.69	656	-3.04±9.66E-10	1.55±0.21E-08	3.04±0.85E-07
602A	DOWN-C(3)	6.89	532	0.87±1.68E-09	1.39±0.29E-08	1.29±0.87E-07
602A	DOWN-C(4)	6.83	554	0.45±1.13E-09	1.82±0.22E-08	2.91±0.84E-07
604	DOWN-C(1)	6.52	988	0.41±2.14E-09	4.93±2.12E-09	2.63±8.11E-08
604	DOWN-C(2)	6.36	822	-0.74±1.57E-09	6.17±2.16E-09	-5.58±8.01E-08
604	DOWN-C(3)	6.71	842	0.15±1.83E-09	6.88±2.12E-09	-5.00±8.14E-08
604	DOWN-C(4)	6.31	1048	3.10±2.14E-09	4.33±2.43E-09	1.51±0.57E-07
8605	DOWN-C(1)	6.79	1022	8.29±6.13E-09	1.26±0.01E-05	9.73±0.95E-07
8605	DOWN-C(2)	6.73	932	7.01±9.11E-09	1.49±0.02E-05	9.42±0.94E-07
8605	DOWN-C(3)	6.84	1276	1.17±0.42E-08	1.33±0.01E-05	7.59±0.90E-07
8605	DOWN-C(4)	6.78	1469	1.59±1.34E-08	1.12±0.01E-05	3.36±0.85E-07
8607	DOWN-C(1)	6.33	976	1.32±2.20E-09	1.70±0.54E-08	2.92±8.48E-08
8607	DOWN-C(2)	6.24	1916	-5.32±4.74E-09	3.79±0.69E-08	-2.85±0.94E-07
8607	DOWN-C(3)	6.88	1592	0.49±3.95E-09	2.61±0.58E-08	-1.84±8.08E-08
8607	DOWN-C(4)	6.24	1124	-1.56±2.70E-09	2.76±0.57E-08	9.18±8.13E-08

Sample collection quarter is noted in parentheses next to hydraulic position. Hydraulic position is relative to other wells within the same hydrogeologic unit.

Note: Bolding convention applied to these data. See page E-2.

Table E-2 (continued)
2000 Contamination Indicator and Radiological Indicator Results
Sand and Gravel Unit

Location Code	Hydraulic Position	pH (standard units)	Conductivity (μmhos/cm @ 25°C)	Gross Alpha (μCi/mL)	Gross Beta (μCi/mL)	Tritium (μCi/mL)
8609	DOWN-C(1)	7.07	1199	0.86±2.76E-09	8.01±0.16E-07	7.60±0.93E-07
8609	DOWN-C(2)	7.13	918	-2.99±2.66E-09	6.72±0.18E-07	5.73±0.89E-07
8609	DOWN-C(3)	7.16	1228	0.25±3.12E-09	7.04±0.18E-07	6.49±0.63E-07
8609	DOWN-C(4)	7.03	1270	-0.85±3.07E-09	7.87±0.19E-07	7.20±0.89E-07
105	DOWN-D(1)	6.95	1446	-0.19±1.12E-08	1.58±0.05E-06	4.25±0.89E-07
105	DOWN-D(2)	6.89	1418	5.61±7.79E-09	2.18±0.04E-06	5.92±0.88E-07
105	DOWN-D(3)	7.06	1525	1.74±3.10E-09	2.28±0.03E-06	5.10±0.86E-07
105	DOWN-D(4)	7.10	1500	3.75±9.04E-09	2.65±0.07E-06	5.74±0.87E-07
106	DOWN-D(1)	6.99	1211	0.99±1.94E-09	5.04±2.65E-09	1.76±0.12E-06
106	DOWN-D(2)	6.63	1348	-0.45±2.54E-09	5.53±2.68E-09	1.36±0.10E-06
106	DOWN-D(3)	6.72	1325	-0.82±2.33E-09	6.00±2.86E-09	9.23±0.93E-07
106	DOWN-D(4)	6.84	1326	-1.20±2.36E-09	1.33±0.35E-08	1.62±0.11E-06
116	DOWN-D(1)	7.24	936	-0.42±1.78E-09	1.02±0.05E-07	1.16±0.82E-07
116	DOWN-D(2)	6.63	4175	-0.71±1.07E-09	1.44±0.06E-07	0.81±8.21E-08
116	DOWN-D(3)	7.15	1641	1.06±4.53E-09	1.58±0.13E-07	2.38±0.85E-07
116	DOWN-D(4)	7.13	1322	1.55±3.03E-09	2.16±0.12E-07	3.18±0.83E-07
605	DOWN-D(1)	6.75	609	-4.44±7.81E-10	7.48±0.31E-08	-5.23±5.90E-08
605	DOWN-D(2)	6.86	766	6.13±9.65E-10	8.05±0.32E-08	-3.24±8.07E-08
605	DOWN-D(3)	6.77	792	1.22±1.69E-09	6.03±0.41E-08	-2.87±8.01E-08
605	DOWN-D(4)	6.66	618	0.39±1.11E-09	6.68±0.41E-08	8.40±8.02E-08
801	DOWN-D(1)	6.62	1035	-5.86±7.03E-09	6.86±0.11E-06	5.64±8.48E-08
801	DOWN-D(2)	6.54	1448	0.00±8.54E-09	9.77±0.13E-06	5.47±8.11E-08
801	DOWN-D(3)	6.69	1680	2.71±3.76E-09	1.04±0.01E-05	1.47±0.81E-07
801	DOWN-D(4)	6.70	1465	5.34±7.38E-09	8.30±0.09E-06	2.72±0.84E-07
802	DOWN-D(1)	7.14	936	1.72±1.84E-09	4.72±2.59E-09	2.49±0.84E-07
802	DOWN-D(2)	6.85	236	-7.70±7.68E-10	3.79±2.34E-09	-1.00±0.57E-07
802	DOWN-D(3)	7.12	395	1.82±2.71E-09	2.48±2.54E-09	-1.51±8.45E-08
802	DOWN-D(4)	6.93	1129	0.20±2.68E-09	8.84±2.63E-09	3.08±0.60E-07
803	DOWN-D(1)	6.87	1500	-1.35±2.84E-09	1.74±0.45E-08	1.85±0.90E-07
803	DOWN-D(2)	6.81	1499	0.14±3.00E-09	1.45±0.43E-08	2.15±0.84E-07
803	DOWN-D(3)	6.84	1505	4.64±4.68E-09	1.55±0.46E-08	1.07±0.85E-07
803	DOWN-D(4)	6.70	1515	-1.52±3.50E-09	2.24±0.53E-08	2.60±0.83E-07
804	DOWN-D(1)	6.85	690	-0.10±1.54E-09	2.81±0.08E-07	0.00±5.71E-08
804	DOWN-D(2)	6.55	2002	3.00±4.11E-09	6.89±0.16E-07	2.02±0.84E-07
804	DOWN-D(3)	6.83	1297	2.05±1.88E-09	2.85±0.08E-07	1.83±0.84E-07
804	DOWN-D(4)	6.65	834	-0.62±1.22E-09	2.34±0.07E-07	1.08±0.82E-07

Sample collection quarter is noted in parentheses next to hydraulic position. Hydraulic position is relative to other wells within the same hydrogeologic unit.

Note: Bolding convention applied to these data. See page E-2.

Table E-2 (concluded)
2000 Contamination Indicator and Radiological Indicator Results
Sand and Gravel Unit

Location Code	Hydraulic Position	pH (standard units)	Conductivity (μ mhos/cm@25°C)	Gross Alpha (μ Ci/mL)	Gross Beta (μ Ci/mL)	Tritium (μ Ci/mL)
8603	DOWN-D(1)	7.08	1567	-0.63 \pm 1.09E-08	3.05\pm0.02E-05	3.94\pm0.86E-07
8603	DOWN-D(2)	7.12	1501	-1.90 \pm 8.32E-09	2.53 \pm 0.02E-05	4.71 \pm 0.87E-07
8603	DOWN-D(3)	7.18	1466	-0.71 \pm 3.27E-09	2.08\pm0.01E-05	4.93\pm0.86E-07
8603	DOWN-D(4)	7.32	1588	0.00 \pm 7.18E-09	2.12 \pm 0.02E-05	4.93\pm0.87E-07
8604	DOWN-D(1)	6.95	1398	0.54 \pm 1.26E-08	3.02\pm0.02E-05	3.53\pm0.63E-07
8604	DOWN-D(2)	7.06	1426	-1.80 \pm 7.90E-09	3.57\pm0.03E-05	4.36 \pm 0.86E-07
8604	DOWN-D(3)	7.16	1492	1.48 \pm 3.13E-09	3.32 \pm 0.01E-05	5.23\pm0.86E-07
8604	DOWN-D(4)	7.21	1608	0.53 \pm 1.04E-08	3.53 \pm 0.03E-05	4.85 \pm 0.87E-07
8612	DOWN-D(1)	7.30	1204	0.79 \pm 1.90E-09	5.53\pm2.76E-09	4.80\pm0.64E-07
8612	DOWN-D(2)	7.19	1221	-1.03 \pm 2.40E-09	0.77 \pm 2.42E-09	5.46 \pm 0.88E-07
8612	DOWN-D(3)	7.20	1228	4.26\pm3.17E-09	-1.08 \pm 2.43E-09	5.52\pm0.62E-07
8612	DOWN-D(4)	7.22	1218	-2.82 \pm 2.51E-09	3.30 \pm 3.21E-09	5.21 \pm 0.88E-07

Sample collection quarter is noted in parentheses next to hydraulic position. Hydraulic position is relative to other wells within the same hydrogeologic unit.

Note: Bolding convention applied to these data. See page E-2.

Table E-3
2000 Contamination Indicator and Radiological Indicator Results
Lavery Till-Sand Unit

Location Code	Hydraulic Position	pH (standard units)	Conductivity (μmhos/cm@25°C)	Gross Alpha (μCi/mL)	Gross Beta (μCi/mL)	Tritium (μCi/mL)
302	UP(1)	7.09	2285	-0.56±4.77E-09	6.63±7.36E-09	1.79±8.09E-08
302	UP(2)	6.98	2260	-0.91±6.02E-09	8.73±7.74E-09	-8.73±8.09E-08
302	UP(3)	7.14	2440	4.26±7.99E-09	-2.25±7.33E-09	-3.49±7.93E-08
302	UP(4)	7.03	2375	-3.74±5.08E-09	6.10±6.62E-09	1.04±0.80E-07
402	UP(1)	7.10	2160	-0.44±3.73E-09	4.24±5.05E-09	-6.50±8.01E-08
402	UP(2)	7.04	2215	-3.03±4.12E-09	1.82±5.02E-09	-5.54±5.67E-08
402	UP(3)	7.25	2180	0.86±3.61E-09	0.00±4.70E-09	-3.84±8.50E-08
402	UP(4)	7.10	2190	1.14±2.74E-09	5.88±3.25E-09	1.26±0.81E-07
204	DOWN-B(1)	7.49	1094	0.70±1.69E-09	2.75±2.48E-09	-1.19±8.06E-08
204	DOWN-B(2)	7.57	1102	-1.34±2.02E-09	3.34±2.50E-09	2.31±8.12E-08
204	DOWN-B(3)	7.63	1110	-0.20±2.33E-09	3.87±2.71E-09	-3.04±8.08E-08
204	DOWN-B(4)	7.62	1154	-0.61±2.66E-09	4.62±3.27E-09	6.56±8.09E-08
206	DOWN-C(1)	7.46	1132	0.75±1.81E-09	2.30±2.47E-09	-3.17±8.02E-08
206	DOWN-C(2)	7.39	1160	0.89±2.14E-09	3.13±2.58E-09	8.42±8.25E-08
206	DOWN-C(3)	7.39	1174	4.60±3.06E-09	2.89±2.65E-09	-4.18±7.96E-08
206	DOWN-C(4)	7.63	996	-1.67±2.26E-09	4.03±3.20E-09	6.19±8.09E-08
208	DOWN-C(1)	7.50	299	1.80±8.29E-10	1.94±1.28E-09	-7.40±7.94E-08
208	DOWN-C(2)	7.52	302	6.46±7.60E-10	2.77±1.29E-09	-1.35±0.79E-07
208	DOWN-C(3)	7.91	296	1.21±9.78E-10	2.01±1.21E-09	-7.54±5.89E-08
208	DOWN-C(4)	7.85	292	4.20±6.12E-10	2.71±0.82E-09	1.20±7.98E-08

Sample collection quarter is noted in parentheses next to hydraulic position. Hydraulic position is relative to other wells within the same hydrogeologic unit.

Note: Bolding convention applied to these data. See page E-2.

Table E-4
2000 Contamination Indicator and Radiological Indicator Results
Weathered Lavery Till Unit

Location Code	Hydraulic Position	pH (standard units)	Conductivity (µmhos/cm@25°C)	Gross Alpha (µCi/mL)	Gross Beta (µCi/mL)	Tritium (µCi/mL)
908	UP(1)	7.01	2380	9.22±4.57E-09	1.57±0.56E-08	-1.64±0.82E-07
908	UP(3)	6.92	2950	8.24±5.70E-09	1.68±0.59E-08	-3.81±8.43E-08
1005	UP(1)	7.27	819	0.90±1.50E-09	1.86±2.39E-09	-6.48±8.32E-08
1005	UP(3)	7.28	775	-0.48±2.50E-09	3.00±2.44E-09	0.49±8.40E-08
1008C	UP(1)	7.53	614	-0.40±1.26E-09	1.32±1.84E-09	-9.81±8.26E-08
1008C	UP(3)	7.57	614	0.80±1.54E-09	2.04±1.78E-09	1.96±8.07E-08
906	DOWN-B(1)	7.72	468	0.50±1.18E-09	2.09±1.86E-09	-1.39±0.85E-07
906	DOWN-B(3)	7.33	508	0.61±1.68E-09	7.23±2.06E-09	-6.08±8.49E-08
1006	DOWN-B(1)	6.97	2360	3.40±4.94E-09	4.92±7.18E-09	-1.58±0.82E-07
1006	DOWN-B(3)	6.95	1235	2.26±7.45E-09	1.42±6.80E-09	-4.60±8.43E-08
1007	DOWN-B(1)	NS	NS	0.58±2.15E-09	3.54±2.67E-09	-1.18±0.82E-07
1007	DOWN-B(3)	7.01	1339	2.49±4.14E-09	3.67±3.89E-09	8.92±8.54E-08
NDATR	DOWN-C(1)	7.54	940	-0.75±1.84E-09	9.92±0.59E-08	3.17±0.15E-06
NDATR	DOWN-C(2)	7.44	1243	1.58±2.57E-09	1.14±0.06E-07	6.02±0.23E-06
NDATR	DOWN-C(3)	7.29	1108	6.09±3.09E-09	8.80±0.58E-08	1.29±0.04E-05
NDATR	DOWN-C(4)	7.38	1076	1.29±2.43E-09	9.55±0.57E-08	1.04±0.04E-05
909	DOWN-C(1)	6.72	1215	-0.22±3.37E-09	3.19±0.14E-07	4.78±0.69E-07
909	DOWN-C(3)	6.75	1378	-1.94±4.16E-09	3.82±0.16E-07	9.35±0.91E-07

NS- Not sampled.

Sample collection quarter is noted in parentheses next to hydraulic position. Hydraulic position is relative to other wells within the same hydrogeologic unit.

Note: Bolding convention applied to these data. See page E-2.

Table E-5
2000 Contamination Indicator and Radiological Indicator Results
Unweathered Lavery Till Unit

Location Code	Hydraulic Position	pH (standard units)	Conductivity (μmhos/cm@25°C)	Gross Alpha (μCi/mL)	Gross Beta (μCi/mL)	Tritium (μCi/mL)
405	UP(1)	7.36	1244	0.21±1.85E-09	5.16±2.68E-09	-6.74±7.96E-08
405	UP(2)	7.01	1007	-1.04±1.57E-09	4.64±2.51E-09	1.39±8.08E-08
405	UP(3)	7.44	1064	1.64±2.44E-09	3.20±2.60E-09	-5.18±8.38E-08
405	UP(4)	7.06	1220	-0.35±2.54E-09	6.63±3.52E-09	6.76±5.70E-08
110	DOWN-B(1)	7.43	574	0.74±1.52E-09	0.80±1.82E-09	1.47±0.11E-06
110	DOWN-B(2)	7.38	412	1.50±1.40E-09	2.25±1.86E-09	1.48±0.11E-06
110	DOWN-B(3)	7.48	568	1.41±2.03E-09	2.22±1.80E-09	1.38±0.10E-06
110	DOWN-B(4)	7.42	562	1.03±1.05E-09	2.99±1.28E-09	1.48±0.10E-06
704	DOWN-B(1)	6.60	1006	0.00±1.36E-09	9.96±2.86E-09	3.06±8.17E-08
704	DOWN-B(2)	6.58	940	-1.23±1.90E-09	9.15±2.89E-09	-1.28±0.79E-07
704	DOWN-B(3)	6.80	892	1.65±1.91E-09	1.18±0.31E-08	-7.88±8.32E-08
704	DOWN-B(4)	6.66	868	0.00±2.38E-09	1.05±0.37E-08	1.38±0.81E-07
707	DOWN-B(1)	6.76	381	-0.79±1.05E-09	5.61±2.06E-09	-5.73±8.32E-08
707	DOWN-B(2)	6.85	478	-0.15±1.01E-09	3.65±1.92E-09	-1.24±0.80E-07
707	DOWN-B(3)	6.90	706	-1.35±1.78E-09	2.71±1.84E-09	-8.44±7.84E-08
707	DOWN-B(4)	6.82	628	1.04±1.41E-09	5.17±1.93E-09	6.05±8.14E-08
107	DOWN-C(1)	7.22	828	2.73±1.60E-09	3.03±1.43E-09	9.72±0.94E-07
107	DOWN-C(2)	7.27	755	1.39±1.14E-09	4.71±1.44E-09	7.58±0.90E-07
107	DOWN-C(3)	7.31	730	1.10±2.08E-09	3.72±1.91E-09	8.00±0.91E-07
107	DOWN-C(4)	7.18	762	-0.82±1.74E-09	4.61±1.83E-09	8.77±0.90E-07
108	DOWN-C(1)	7.68	590	0.18±1.43E-09	1.08±1.52E-09	1.76±8.06E-08
108	DOWN-C(2)	7.24	606	1.79±1.50E-09	3.02±1.55E-09	0.54±8.09E-08
108	DOWN-C(3)	7.60	600	0.11±1.76E-09	2.62±1.52E-09	6.23±8.15E-08
108	DOWN-C(4)	7.56	596	1.99±1.68E-09	3.40±1.71E-09	1.38±0.81E-07
409	DOWN-C(1)	8.02	350	5.17±9.47E-10	2.32±1.32E-09	-2.62±8.02E-08
409	DOWN-C(2)	8.04	347	9.89±8.74E-10	2.56±1.29E-09	-7.78±8.00E-08
409	DOWN-C(3)	8.15	316	6.94±9.61E-10	2.64±1.23E-09	-7.30±7.80E-08
409	DOWN-C(4)	7.82	386	1.58±0.92E-09	3.16±1.25E-09	-3.34±7.85E-08
910	DOWN-C(1)	7.12	1324	1.53±2.76E-09	2.58±0.49E-08	-7.18±8.06E-08
910	DOWN-C(3)	7.05	1338	1.72±2.55E-09	2.80±0.34E-08	-2.60±8.40E-08

Sample collection quarter is noted in parentheses next to hydraulic position. Hydraulic position is relative to other wells within the same hydrogeologic unit.

Note: Bolding convention applied to these data. See page E-2.

Table E-6
2000 Contamination Indicator and Radiological Indicator Results
Kent Recessional Sequence

Location Code	Hydraulic Position	pH (standard units)	Conductivity (μmhos/cm@25°C)	Gross Alpha (μCi/mL)	Gross Beta (μCi/mL)	Tritium (μCi/mL)
901	UP(1)	7.71	375	6.29±9.21E-10	2.70±1.33E-09	-1.17±0.83E-07
901	UP(3)	7.69	385	0.57±1.09E-09	3.31±1.29E-09	-1.03±0.79E-07
902	UP(1)	8.33	424	0.82±1.03E-09	1.96±1.71E-09	-1.12±0.83E-07
902	UP(3)	7.87	445	-0.10±1.52E-09	2.63±1.79E-09	-1.84±7.96E-08
1008B	UP(1)	7.88	328	2.09±9.56E-10	3.38±1.38E-09	-1.09±0.83E-07
1008B	UP(3)	7.73	382	2.04±8.75E-10	2.13±1.22E-09	2.90±8.10E-08
903	DOWN-B(1)	7.56	922	-1.42±1.88E-09	9.21±2.32E-09	-1.40±0.83E-07
903	DOWN-B(3)	7.55	910	1.04±1.41E-09	2.77±1.36E-09	-7.87±8.03E-08
8610	DOWN-B(1)	7.89	960	-0.13±1.93E-09	4.32±2.11E-09	-1.22±0.83E-07
8610	DOWN-B(3)	8.01	1016	-0.61±2.36E-09	4.50±2.53E-09	-6.18±8.38E-08
8611	DOWN-B(1)	7.58	916	0.56±1.34E-09	3.54±2.48E-09	-5.79±7.97E-08
8611	DOWN-B(3)	7.65	865	1.51±2.05E-09	1.71±2.43E-09	-1.41±0.83E-07

Table E-7
2000 Contamination Indicator and Radiological Indicator Results
North Plateau Seep Monitoring Locations

Location Code	Hydraulic Position	pH (standard units)	Conductivity (μmhos/cm@25°C)	Gross Alpha (μCi/mL)	Gross Beta (μCi/mL)	Tritium (μCi/mL)
GSEEP	DOWN-D(1)	6.79	838	-0.73±1.50E-09	4.40±2.59E-09	5.41±0.87E-07
GSEEP	DOWN-D(2)	7.52	799	-0.68±1.47E-09	7.02±2.62E-09	5.16±0.88E-07
GSEEP	DOWN-D(3)	6.75	917	-0.14±2.26E-09	4.75±2.51E-09	5.32±0.88E-07
GSEEP	DOWN-D(4)	6.57	909	-1.18±1.83E-09	8.69±2.55E-09	4.23±0.85E-07
SP04	DOWN-D(1)	NS	NS	0.66±1.29E-09	5.89±2.63E-09	3.31±0.63E-07
SP04	DOWN-D(3)	NS	NS	-1.03±2.21E-09	7.80±2.69E-09	2.54±0.60E-07
SP06	DOWN-D(1)	NS	NS	-0.30±1.49E-09	1.86±1.91E-09	2.98±0.84E-07
SP06	DOWN-D(3)	NS	NS	0.76±1.46E-09	4.47±1.91E-09	6.54±8.22E-08
SP11	DOWN-D(1)	NS	NS	0.15±1.37E-09	1.27±0.30E-08	2.74±0.84E-07
SP11	DOWN-D(3)	NS	NS	-1.38±2.96E-09	1.86±0.33E-08	9.26±7.83E-08
SP12	DOWN-D(1)	7.35	1083	1.14±1.25E-09	1.76±1.77E-09	6.46±0.89E-07
SP12	DOWN-D(3)	7.13	1050	2.76±2.75E-09	0.84±2.51E-09	5.29±0.88E-07

NS- Not sampled.

Sample collection quarter is noted in parentheses next to hydraulic position. Hydraulic position is relative to other wells within the same hydrogeologic unit.

Note: Bolding convention applied to these data. See page E-2.

Table E-8
2000 Contamination Indicator and Radiological Indicator Results
North Plateau Well Points

Location Code	Hydraulic Position	pH (standard units)	Conductivity (µmhos/cm@25°C)	Gross Alpha (µCi/mL)	Gross Beta (µCi/mL)	Tritium (µCi/mL)
WP-A	DOWN-C(4)	9.30	98	0.26±2.81E-10	4.98±0.24E-08	1.04±0.04E-05
WP-C	DOWN-C(4)	6.80	152	-0.64±1.85E-10	2.00±0.11E-08	5.67±0.12E-05
WP-H	DOWN-C(4)	7.74	694	6.08±5.46E-09	5.09±0.07E-06	3.30±0.15E-06

Table E-9
2000 Detections of Volatile Organic Compounds
at Selected Groundwater Monitoring Locations

Location Code	Sampling Quarter	1,1,1-TCA (µg/L)	1,1-DCA (µg/L)	DCDFMeth (µg/L)	1,2-DCE(total) (µg/L)	TCE (µg/L)
SP12	1	< 5.0	< 5.0	< 5.0	NS	< 5.0
	3	< 5.0	< 5.0	< 5.0	NS	< 5.0
803	1	< 5.0	< 5.0	< 5.0	NS	< 5.0
	2	< 5.0	< 5.0	< 5.0	NS	< 5.0
	3	< 5.0	< 5.0	< 5.0	NS	< 5.0
	4	< 5.0	< 5.0	< 5.0	< 5.0	< 5.0
8609	1	< 5.0	< 5.0	< 5.0	NS	< 5.0
8612	1	< 5.0	15.6	< 5.0	21.2	< 5.0
	2	< 5.0	15.5	< 5.0	21.2	< 5.0
	3	< 5.0	14.8	< 5.0	22.9	< 5.0
	4	< 5.0	17.7	< 5.0	24.6	< 5.0

NS- Not sampled.

Sample collection quarter is noted in parentheses next to hydraulic position. Hydraulic position is relative to other wells within the same hydrogeologic unit.

Note: Bolding convention applied to these data. See page E-2.

Table E-10
2000 Tributyl Phosphate Sampling Results
at Selected Groundwater Monitoring Locations

Location Code	Sampling Quarter	Tributyl Phosphate (TBP) (µg/L)
111	1	< 10.0
	3	< 10.0
8605	1	272
	3	257

Detection limit is 10 µg/L.

Table E-11
2000 Metals (µg/L) Sampling Results
Title 6 NYCRR Appendix 33 List

Location Code	Hydraulic Position	Antimony	Arsenic	Barium	Beryllium	Cadmium	Chromium	Cobalt	Copper
Sand and Gravel									
111	DOWN-C(1)	< 10	< 10	103	< 1	< 5	< 10	2	1
502	DOWN-C(1)	NS	8	447	NS	< 5	891	< 50	10
502	DOWN-C(3)	NS	5	370	NS	< 5	653	2	8
8605	DOWN-C(1)	< 10	< 8	115	< 1	< 5	< 10	1	13
Weathered Till									
NDATR	DOWN-C(1)	< 10	< 10	< 200	< 1	< 5	< 10	< 50	< 25
NDATR	DOWN-C(2)	< 10	< 10	< 200	< 1	< 5	< 10	< 50	< 25
NDATR	DOWN-C(3)	< 10	< 10	< 200	< 1	< 5	< 10	< 50	< 25
NDATR	DOWN-C(4)	< 10	< 10	< 200	< 1	< 5	< 10	< 50	< 25
909	DOWN-C(1)	< 10	< 10	< 200	< 1	< 5	< 10	< 50	< 25

NS- Not sampled.

Sample collection quarter is noted in parentheses next to hydraulic position. Hydraulic position is relative to other wells within the same hydrogeologic unit.

Note: Bolding convention not applicable to these data.

Table E-11 (concluded)
2000 Metals (µg/L) Sampling Results
Title 6 NYCRR Appendix 33 List

Location Code	Hydraulic Position	Lead	Mercury	Nickel	Selenium	Silver	Thallium	Tin	Vanadium	Zinc
Sand and Gravel										
111	DOWN-C(1)	< 3	< 0.2	7	< 5	< 10	7	< 3000	< 50	7
502	DOWN-C(1)	< 3	< 0.2	27	< 5	< 10	NS	NS	5	8
502	DOWN-C(3)	4	< 0.2	39	< 5	< 10	NS	NS	3	< 20
8605	DOWN-C(1)	< 3	< 0.2	2	< 5	< 10	8	< 3000	< 50	4
Weathered Till										
NDATR	DOWN-C(1)	< 3	< 0.2	< 40	6	< 10	<10	< 3000	< 50	< 20
NDATR	DOWN-C(2)	4	< 0.2	< 40	< 5	< 10	<10	< 3000	< 50	< 20
NDATR	DOWN-C(3)	< 3	0.2	< 40	< 5	< 10	<10	< 3000	< 50	< 20
NDATR	DOWN-C(4)	< 3	< 0.2	< 40	< 5	< 10	<10	< 3000	< 50	< 20
909	DOWN-C(1)	4	< 0.2	< 40	6	< 10	<10	< 3000	< 50	24

Sample collection quarter is noted in parentheses next to hydraulic position. Hydraulic position is relative to other wells within the same hydrogeologic unit.

NS - Not sampled.

Table E-12
2000 Sampling Parameters at Early Warning Monitoring Wells (µg/L)

Location Code	Sample Quarter	Aluminum Total	Iron Total	Manganese Total
502	(1)	42.5	14,900	9.7
	(3)	< 200	8,250	7.8

Note: Bolding convention applied to these data. See page E-2.

Table E-13
2000 Alpha-, Beta-, and Gamma-emitting Radioisotopic Results ($\mu\text{Ci/mL}$)
for Selected Groundwater Monitoring Locations

Location Code	Hydraulic Position	C-14	Sr-90	Tc-99
Sand and Gravel				
401	UP(1)	2.47 \pm 4.04E-09	0.46 \pm 1.29E-09	0.80 \pm 1.77E-09
111	DOWN-C(1)	NS	2.56 \pm 0.03E-06	NS
406	DOWN-C(1)	-1.18 \pm 3.91E-09	3.25 \pm 1.80E-09	4.89 \pm 2.14E-09
408	DOWN-C(1)	2.10 \pm 4.02E-09	1.93 \pm 0.01E-04	2.36 \pm 0.57E-08
501	DOWN-C(1)	NS	1.15 \pm 0.01E-04	NS
502	DOWN-C(1)	NS	9.19 \pm 0.02E-05	NS
602A	DOWN-C(1)	NS	6.08 \pm 2.08E-09	NS
602A	DOWN-C(3)	NS	6.63 \pm 1.95E-09	NS
8605	DOWN-C(1)	NS	6.13 \pm 0.06E-06	NS
8609	DOWN-C(1)	NS	4.05 \pm 0.09E-07	NS
8609	DOWN-C(3)	NS	3.76 \pm 0.12E-07	NS
116	DOWN-D(1)	NS	4.67 \pm 0.50E-08	NS
116	DOWN-D(3)	NS	7.74 \pm 0.55E-08	NS
605	DOWN-D(1)	NS	3.42 \pm 0.45E-08	NS
605	DOWN-D(3)	NS	3.44 \pm 0.38E-08	NS
801	DOWN-D(1)	NS	3.79\pm0.05E-06	NS
801	DOWN-D(2)	NS	5.36\pm0.05E-06	NS
801	DOWN-D(3)	NS	5.26 \pm 0.04E-06	NS
801	DOWN-D(4)	NS	4.46 \pm 0.05E-06	NS
8603	DOWN-D(1)	NS	1.60 \pm 0.01E-05	NS
8603	DOWN-D(3)	NS	1.11 \pm 0.01E-05	NS
Weathered Till				
NDATR	DOWN-C(1)	1.76 \pm 4.00E-09	4.79 \pm 0.45E-08	1.91 \pm 1.95E-09
NDATR	DOWN-C(3)	1.10 \pm 0.51E-08	3.97 \pm 0.40E-08	1.08 \pm 1.94E-09
909	DOWN-C(1)	6.92 \pm 4.21E-09	1.59 \pm 0.08E-07	-0.39 \pm 1.80E-09

NS- Not sampled.

Sample collection quarter is noted in parentheses next to hydraulic position. Hydraulic position is relative to other wells within the same hydrogeologic unit.

Note: Bolding convention applied to these data. See page E-2.

Table E-13 (concluded)
2000 Alpha-, Beta-, and Gamma-emitting Radioisotopic Results (μCi/mL)

Location Code	Hydraulic Position	I-129	Cs-137	Ra-226	Ra-228	U-232
401	UP(1)	-4.67±4.54E-10	-0.79±7.65E-09	4.40±5.71E-10	2.75±4.45E-10	6.48±6.29E-11
406	DOWN-C(1)	1.24±1.10E-09	-3.12±6.12E-09	-1.71±3.35E-10	2.00±4.61E-10	0.70±5.18E-11
408	DOWN-C(1)	5.32±5.46E-10	-1.66±4.20E-09	5.61±5.66E-10	2.88±0.62E-09	4.12±6.03E-11
Weathered Till						
NDATR	DOWN-C(1)	6.86±7.85E-10	-1.31±7.10E-09	0.85±4.40E-10	4.94±4.17E-10	5.46±5.71E-11
NDATR	DOWN-C(3)	2.93±6.19E-10	0.42±7.46E-09	4.95±3.53E-10	5.37±7.36E-10	-1.75±7.12E-11
909	DOWN-C(1)	2.73±1.17E-09	-0.13±7.08E-09	5.07±4.69E-10	1.50±0.52E-09	-3.19±5.53E-11
		U-233/234	U-235/236	U-238	Total U (µg/mL)	
Sand and Gravel						
401	UP(1)	3.48±0.90E-10	-0.43±1.98E-11	2.81±0.81E-10	1.57±0.05E-04	
406	DOWN-C(1)	4.33±5.84E-11	0.42±2.16E-11	9.57±4.50E-11	6.86±0.13E-04	
408	DOWN-C(1)	2.61±0.75E-10	0.50±2.18E-11	2.43±0.73E-10	7.73±0.10E-04	
Weathered Till						
NDATR	DOWN-C(1)	1.52±0.24E-09	5.79±3.68E-11	1.13±0.19E-09	3.55±0.04E-03	
NDATR	DOWN-C(3)	1.89±0.32E-09	3.17±3.19E-11	1.35±0.25E-09	4.87±0.07E-03	
909	DOWN-C(1)	5.34±1.14E-10	2.41±2.35E-11	4.26±0.99E-10	1.26±0.03E-03	

Sample collection quarter is noted in parentheses next to hydraulic position. Hydraulic position is relative to other wells within the same hydrogeologic unit.

Note: Bolding convention not applicable to these data. See page E-2.

Table E-14
Practical Quantitation Limits (PQLs)

COMPOUND	PQL (µg/L)	COMPOUND	PQL (µg/L)
<i>Appendix 33 Volatiles</i>		<i>Appendix 33 Volatiles</i>	
Acetone	10	Methacrylonitrile	5
Acetonitrile	100	Methyl ethyl ketone	10
Acrolein	5	Methyl iodide	5
Acrylonitrile	5	Methyl methacrylate	5
Allyl chloride	5	4-Methyl-2-pentanone	10
Benzene	5	Methylene bromide	10
Bromodichloromethane	5	Methylene chloride	5
Bromoform	5	Pentachloroethane	5
Bromomethane	10	Propionitrile	50
Carbon disulfide	10	Styrene	5
Carbon tetrachloride	5	1,1,1,2-Tetrachloroethane	5
Chlorobenzene	5	1,1,2,2-Tetrachloroethane	5
Chloroethane	10	Tetrachloroethylene	5
Chloroform	5	Toluene	5
Chloromethane	10	1,1,1-Trichloroethane	5
Chloroprene	5	1,1,2-Trichloroethane	5
1,2-Dibromo-3-chloropropane	5	1,2,3-Trichloropropane	5
Dibromochloromethane	5	Vinyl acetate	10
1,2-Dibromoethane	5	Vinyl chloride	10
Dichlorodifluoromethane	5	Xylene (total)	5
1,1-Dichloroethane	5	cis-1,3-Dichloropropene	5
1,2-Dichloroethane	5	trans-1,2-Dichloroethylene	5
1,1-Dichloroethylene	5	trans-1,3-Dichloropropene	5
1,2-Dichloropropane	5	trans-1,4-Dichloro-2-butene	5
Ethyl benzene	5	Trichloroethylene	5
Ethyl methacrylate	5	Trichlorofluoromethane	5
2-Hexanone	10		
Isobutyl alcohol	100		
<i>Appendix 33 Metals</i>		<i>Appendix 33 Metals</i>	
*Aluminum	200	Lead	5
Antimony	10	*Manganese	15
Arsenic	10	Mercury	0.2
Barium	200	Nickel	40
Beryllium	1	Selenium	5
Cadmium	5	Silver	10
Chromium	10	Thallium	10
Cobalt	50	Tin	3000
Copper	25	Vanadium	50
*Iron	100	Zinc	20

Note: Specific quantitation limits are highly matrix-dependent and may not always be achievable.

** Not an Appendix 33 parameter; sampled for the north plateau early warning program.*

Table E-14 (continued)
Practical Quantitation Limits (PQLs)

COMPOUND	PQL (µg/L)	COMPOUND	PQL (µg/L)
<i>Appendix 33 Semivolatiles</i>		<i>Appendix 33 Semivolatiles</i>	
Acenaphthene	10	2,4-Dinitrotoluene	10
Acenaphthylene	10	2,6-Dinitrotoluene	10
Acetophenone	10	Diphenylamine	10
2-Acetylaminofluorene	10	Ethyl methanesulfonate	10
4-Aminobiphenyl	10	Famphur	10
Aniline	10	Fluoranthene	10
Anthracene	10	Fluorene	10
Aramite	10	Hexachlorobenzene	10
Benzo[a]anthracene	10	Hexachlorobutadiene	10
Benzo[a]pyrene	10	Hexachlorocyclopentadiene	10
Benzo[b]fluoranthene	10	Hexachloroethane	10
Benzo[ghi]perylene	10	Hexachlorophene	500
Benzo[k]fluoranthene	10	Hexachloropropene	10
Benzyl alcohol	10	Indeno(1,2,3,-cd)pyrene	10
Bis(2-chlorethyl)ether	10	Isodrin	10
Bis(2-chloroethoxy)methane	10	Isophorone	10
Bis(2-chloroisopropyl)ether	10	Isosafrole	10
Bis(2-ethylhexyl)phthalate	10	Kepone	70
4-Bromophenyl phenyl ether	10	Methapyrilene	10
Butyl benzyl phthalate	10	Methyl methanesulfonate	10
Chlorobenzilate	10	3-Methylcholanthrene	10
2-Chloronaphthalene	10	2-Methylnaphthalene	10
2-Chlorophenol	10	1,4-Naphthoquinone	10
4-Chlorophenyl phenyl ether	10	1-Naphthylamine	10
Chrysene	10	2-Naphthylamine	10
Di-n-butyl phthalate	10	Nitrobenzene	10
Di-n-octyl phthalate	10	5-Nitro-o-toluidine	10
Diallate	10	4-Nitroquinoline 1-oxide	40
Dibenz[a,h]anthracene	10	N-Nitrosodi-n-butylamine	10
Dibenzofuran	10	N-Nitrosodiethylamine	10
3,3-Dichlorobenzidine	10	N-Nitrosodimethylamine	10
2,4-Dichlorophenol	10	N-Nitrosodipropylamine	10
2,6-Dichlorophenol	10	N-Nitrosodiphenylamine	10
Diethyl phthalate	10	N-Nitrosomethylethylamine	10
Dimethoate	10	N-Nitrosomorpholine	10
7, 12-Dimethylbenz[a]anthracene	10	N-Nitrosopiperidine	10
3,3-Dimethylbenzidine	20	N-Nitrosopyrrolidine	10
2,4-Dimethylphenol	10	Naphthalene	10
Dimethyl phthalate	10	0,0,0-Triethyl phosphorothioate	10
4,6-Dinitro-o-cresol	25	0,0-Diethyl 0-2-pyrazinyl- phosphorothioate	10
2,4-Dinitrophenol	25		

Note: Specific quantitation limits are highly matrix-dependent and may not always be achievable.

Table E-14 (concluded)
Practical Quantitation Limits (PQLs)

COMPOUND	PQL (µg/L)	COMPOUND	PQL (µg/L)
<i>Appendix 33 Semivolatiles</i>		<i>Appendix 33 Semivolatiles</i>	
p-(Dimethylamino)azobenzene	10	2,3,4,6-Tetrachlorophenol	10
p-Chloroaniline	10	Tetraethyl dithiopyrophosphate	10
p-Chloro-m-cresol	10	1,2,4-Trichlorobenzene	10
p-Cresol	10	2,4,5-Trichlorophenol	25
p-Dichlorobenzene	10	2,4,6-Trichlorophenol	10
p-Nitroaniline	25	alpha,alpha-Dimethylphenethylamine	50
p-Nitrophenol	25	m-Cresol	10
p-Phenylenediamine	20	m-Dichlorobenzene	10
Parathion	10	m-Dinitrobenzene	10
Pentachlorobenzene	10	m-Nitroaniline	25
Pentachloronitrobenzene	10	o-Cresol	10
Pentachlorophenol	25	o-Dichlorobenzene	10
Phenacetin	10	o-Nitroaniline	25
Phenanthrene	10	o-Nitrophenol	10
Phenol	10	o-Toluidine	10
Pronamide	10	sym-Trinitrobenzene	10
Pyrene	10	2-Picoline	10
Safrole	10	Pyridine	10
1,2,4,5-Tetrachlorobenzene	10	1,4-Dioxane	10

Note: Specific quantitation limits are highly matrix-dependent and may not always be achievable.

Groundwater Data Graphs

Groundwater data for CY 2000 are presented in graphic format on the following pages.

The data point on the nonradiological graphs represents the average for the year and the bracket represents the high and low values for the year.

The graphed data points for the radiological analytes represent the averages for the year and the bracket represents the pooled (i.e., averaged) uncertainty.




Figure E-1. pH in Groundwater Samples from the Sand and Gravel Unit




Figure E-2. Conductivity (µmhos/cm@25°C) of Groundwater Samples from the Sand and Gravel Unit




Figure E-3. Gross Alpha ($\mu\text{Ci/mL}$) in Groundwater Samples from the Sand and Gravel Unit




Figure E-4. Gross Beta ($\mu\text{Ci/mL}$) in Groundwater Samples from the Sand and Gravel Unit




Figure E-4a. Gross Beta (μCi/mL) in Groundwater Samples from the Sand and Gravel Unit (Magnified Scale of Figure E-4)




Figure E-4b. Gross Beta (μCi/mL) in Groundwater Samples from the Sand and Gravel Unit (Magnified Scale of Figure E-4a)




Figure E-5. Tritium ($\mu\text{Ci/mL}$) in Groundwater Samples from the Sand and Gravel Unit




Figure E-6. pH of Groundwater Samples from the Till-Sand Unit




Figure E-7. Conductivity ($\mu\text{mhos/cm@25}^\circ\text{C}$) of Groundwater Samples from the Till-Sand Unit




Figure E-8. Gross Alpha ($\mu\text{Ci/mL}$) in Groundwater Samples from the Till-Sand Unit




Figure E-9. Gross Beta ($\mu\text{Ci/mL}$) in Groundwater Samples from the Till-Sand Unit




Figure E-10. Tritium ($\mu\text{Ci/mL}$) in Groundwater Samples from the Till-Sand Unit




Figure E-11. pH of Groundwater Samples from the Weathered Lavery Till Unit




Figure E-12. Conductivity ($\mu\text{mhos}/\text{cm}@25^\circ\text{C}$) of Groundwater Samples from the Weathered Lavery Till Unit




Figure E-13. Gross Alpha ($\mu\text{Ci}/\text{mL}$) in Groundwater Samples from the Weathered Lavery Till Unit




Figure E-14. Gross Beta ($\mu\text{Ci}/\text{mL}$) in Groundwater Samples from the Weathered Lavery Till Unit




Figure E-14a. Gross Beta ($\mu\text{Ci}/\text{mL}$) in Groundwater Samples from the Weathered Lavery Till Unit (Magnified scale of Figure E-14)




Figure E-15. Tritium ($\mu\text{Ci/mL}$) in Groundwater Samples from the Weathered Lavery Till Unit




Figure E-15a. Tritium ($\mu\text{Ci/mL}$) in Groundwater Samples from the Weathered Lavery Till Unit (Magnified scale of Figure E-15)




Figure E-16. pH of Groundwater Samples from the Unweathered Lavery Till Unit




Figure E-17. Conductivity ($\mu\text{mhos/cm@25}^\circ\text{C}$) of Groundwater Samples from the Unweathered Lavery Till Unit




Figure E-18. Gross Alpha ($\mu\text{Ci/mL}$) in Groundwater Samples from the Unweathered Lavery Till Unit




Figure E-19. Gross Beta ($\mu\text{Ci/mL}$) in Groundwater Samples from the Unweathered Lavery Till Unit




Figure E-20. Tritium ($\mu\text{Ci/mL}$) in Groundwater Samples from the Unweathered Lavery Till Unit




Figure E-21. pH of Groundwater Samples from the Kent Recessional Sequence




Figure E-22. Conductivity ($\mu\text{mhos/cm@25}^\circ\text{C}$) of Groundwater Samples from the Kent Recessional Sequence




Figure E-23. Gross Alpha ($\mu\text{Ci/mL}$) in Groundwater Samples from the Kent Recessional Sequence




Figure E-24. Gross Beta ($\mu\text{Ci/mL}$) in Groundwater Samples from the Kent Recessional Sequence




Figure E-25. Tritium ($\mu\text{Ci/mL}$) in Groundwater Samples from the Kent Recessional Sequence

Appendix F

Summary of Biological Data



Milk and Meat Samples are Collected from Local Bovine Herds

The following tables contain a bolding convention devised to help the reader, when viewing the data, to quickly see the range of detectable measurements within a data series. A data series is a set of chemical or radionuclide measurements (e.g., gross alpha, gross beta, tritium) from a single location or from similar locations. Note that some tables contain data that should not be technically evaluated under this convention.

Key to bolding convention:

Results for each constituent constitute a single data series. If a radiological result is larger than the uncertainty term, the measurement is considered positive. Otherwise, a result is considered non-detectable.

If all results in a data series are positive, the lowest and highest values are bolded.

If a data series contains some positive results, the highest value is bolded.

If all values in a data series are nondetectable, no values are bolded.

Table F-1
2000 Radioactivity Concentrations ($\mu\text{Ci/mL}$) in Milk

Location	H-3	K-40	Sr-90	I-129	Cs-137
BFMCOBO (WNW Farm)					
<i>1st Quarter</i>	-5.78 \pm 9.98E-08	1.21\pm0.14E-06	1.52\pm0.40E-09	-0.61 \pm 3.19E-10	1.32 \pm 1.45E-09
<i>2nd Quarter</i>	-2.95 \pm 6.97E-08	1.21\pm0.16E-06	2.99\pm0.95E-09	1.39 \pm 3.49E-10	1.11 \pm 2.14E-09
<i>3rd Quarter</i>	9.23\pm8.16E-08	1.34\pm0.07E-06	2.33 \pm 0.43E-09	-0.04 \pm 3.35E-10	0.00 \pm 2.65E-09
<i>4th Quarter</i>	2.83 \pm 8.64E-08	1.29 \pm 0.06E-06	1.80 \pm 0.35E-09	0.74 \pm 2.52E-10	0.56 \pm 1.23E-09
BFMCTLN (Background)					
<i>1st Quarter</i>	5.41\pm1.36E-07	1.51 \pm 0.18E-06	8.96\pm3.25E-10	-2.94 \pm 4.66E-10	0.39 \pm 1.61E-09
<i>2nd Quarter</i>	5.90 \pm 7.32E-08	1.40 \pm 0.18E-06	1.61\pm0.76E-09	-2.23 \pm 3.95E-10	-0.90 \pm 2.11E-09
<i>3rd Quarter</i>	1.51 \pm 0.82E-07	1.53\pm0.08E-06	1.34 \pm 0.30E-09	1.48 \pm 3.50E-10	0.00 \pm 2.69E-09
<i>4th Quarter</i>	1.12 \pm 0.90E-07	1.37\pm0.06E-06	1.11 \pm 0.34E-09	0.78 \pm 3.63E-10	-0.38 \pm 1.14E-09
BFMCTLS (Background)					
<i>1st Quarter</i>	0.00 \pm 1.03E-07	1.44 \pm 0.15E-06	1.48 \pm 0.34E-09	0.00 \pm 2.15E-10	1.86 \pm 1.98E-09
<i>2nd Quarter</i>	-8.88 \pm 6.74E-08	1.28\pm0.17E-06	1.09 \pm 0.85E-09	0.48 \pm 3.72E-10	-1.75 \pm 2.25E-09
<i>3rd Quarter</i>	5.88 \pm 7.69E-08	1.45\pm0.08E-06	2.81\pm0.33E-09	-0.89 \pm 3.59E-10	0.93 \pm 1.58E-09
<i>4th Quarter</i>	2.86 \pm 8.71E-08	1.37 \pm 0.07E-06	7.33\pm3.07E-10	-1.83 \pm 2.20E-10	-0.09 \pm 1.24E-09
BFMREED (NNW Farm)					
<i>1st Quarter</i>	0.00 \pm 1.03E-07	1.48\pm0.09E-06	1.86 \pm 3.30E-10	-0.72 \pm 3.84E-10	0.61 \pm 2.22E-09
<i>2nd Quarter</i>	0.00 \pm 7.14E-08	1.27\pm0.15E-06	2.92\pm0.84E-09	0.79 \pm 3.83E-10	1.62 \pm 2.83E-09
<i>3rd Quarter</i>	6.16 \pm 8.06E-08	1.44 \pm 0.07E-06	2.80 \pm 0.39E-09	1.51 \pm 5.15E-10	2.61\pm1.69E-09
<i>4th Quarter</i>	2.75 \pm 8.39E-08	1.28 \pm 0.06E-06	1.18 \pm 0.41E-09	1.56 \pm 2.18E-10	1.05 \pm 1.40E-09
BFMSCHT (S Farm)					
<i>Annual</i>	2.01 \pm 1.08E-07	1.25 \pm 0.08E-06	7.38 \pm 2.88E-10	3.08 \pm 2.30E-10	-0.26 \pm 1.08E-09
BFMWIDR (SE Farm)					
<i>Annual</i>	5.73 \pm 9.91E-08	1.43 \pm 0.06E-06	1.91 \pm 0.37E-09	2.08 \pm 3.78E-10	1.15 \pm 1.51E-09

Note: Bolding convention applied to these data. See page F-2.

Table F-2
2000 Radioactivity Concentrations ($\mu\text{Ci/g}$ - dry) in Meat

2000 Radioactivity Concentrations in Beef

Location	% Moisture	H-3 ($\mu\text{Ci/mL}$)	K-40	Sr-90	Cs-137
Beef Flesh Background (BFBCTRL 06/00)	72.4	5.84 \pm 6.53E-08	9.03 \pm 1.08E-06	2.82 \pm 3.27E-08	-0.56 \pm 1.50E-08
Beef Flesh Background (BFBCTRL 12/00)	75.3	1.45 \pm 1.09E-07	1.23 \pm 0.09E-05	1.70 \pm 3.10E-09	1.14 \pm 1.90E-08
Beef Flesh Near-Site (BFBNEAR 06/00)	69.8	5.92 \pm 6.62E-08	5.62 \pm 0.78E-06	0.23 \pm 3.54E-08	2.04 \pm 2.44E-08
Beef Flesh Near-Site (BFBNEAR 11/00)	75.5	0.85 \pm 1.03E-07	1.36 \pm 0.14E-05	0.20 \pm 1.20E-09	0.68 \pm 1.51E-08

2000 Radioactivity Concentrations in Venison

Location	% Moisture	H-3 ($\mu\text{Ci/mL}$)	K-40	Sr-90	Cs-137
Deer Flesh Background (BFDCTRL 10/00)	74.7	0.85 \pm 1.03E-07	1.18\pm0.08E-05	-0.20 \pm 1.40E-09	6.15 \pm 2.57E-08
Deer Flesh Background (BFDCTRL 11/00)	75.2	0.57 \pm 1.01E-07	9.79\pm0.81E-06	1.60\pm1.20E-09	1.84\pm0.36E-07
Deer Flesh Background (BFDCTRL 11/00)	75.7	2.82 \pm 9.92E-08	1.07 \pm 0.09E-05	0.20 \pm 1.10E-09	-0.73 \pm 2.63E-08
Deer Flesh Near-Site (BFDNEAR 10/00)	73.0	1.99\pm1.02E-07	1.07\pm0.09E-05	0.80 \pm 1.50E-09	1.33\pm0.40E-07
Deer Flesh Near-Site (BFDNEAR 11/00)	74.3	2.83 \pm 9.95E-08	1.10\pm0.09E-05	0.00 \pm 8.00E-10	3.04\pm2.13E-08
Deer Flesh Near-Site (BFDNEAR 11/00)	74.3	2.80 \pm 9.86E-08	1.10\pm0.09E-05	1.50 \pm 1.20E-09	4.32 \pm 3.30E-08

Note: Bolding convention applied to these data. See page F-2.

Table F-3
2000 Radioactivity Concentrations ($\mu\text{Ci/g}$ - dry) in Food Crops

Location	% Moisture	H-3 ($\mu\text{Ci/mL}$)	K-40	Co-60	Sr-90	Cs-137
CORN						
Background (BFVCTRC)	63.3	8.13 \pm 1.31E-07	1.37 \pm 0.18E-05	2.28 \pm 3.69E-08	8.20 \pm 9.60E-09	3.04 \pm 3.29E-08
Near-Site (BFVNEAC)	67.9	2.27 \pm 1.05E-07	1.34 \pm 0.18E-05	0.16 \pm 4.30E-08	1.40 \pm 0.69E-08	0.93 \pm 3.47E-08
BEANS						
Background (BFVCTRB)	76.7	3.14 \pm 9.24E-08	3.63 \pm 0.48E-05	3.81 \pm 7.01E-08	4.73 \pm 1.98E-08	0.08 \pm 6.11E-08
Near-Site (BFVNEAB)	78.2	6.42 \pm 9.61E-08	3.39 \pm 0.40E-05	0.32 \pm 6.94E-08	7.81 \pm 1.87E-08	3.22 \pm 5.65E-08
APPLES						
Background (BFVCTRA)	90.4	1.31 \pm 1.01E-07	1.03 \pm 0.15E-05	-0.92 \pm 4.96E-08	1.83 \pm 1.20E-08	1.58 \pm 0.81E-07
Near-Site (BFVNEAAF)	82.9	6.44 \pm 9.64E-08	1.36 \pm 0.16E-05	1.27 \pm 3.93E-08	6.80 \pm 1.70E-09	8.29 \pm 6.69E-08
HAY						
Background (BFHCTLN)	NA	NA	2.56 \pm 0.40E-05	1.29 \pm 1.10E-07	5.01 \pm 0.77E-08	2.82 \pm 9.43E-08
Near-Site (BFHNEAR)	NA	NA	1.78 \pm 0.41E-05	0.21 \pm 1.42E-07	2.05 \pm 0.86E-08	0.15 \pm 1.44E-07

NA - Not applicable.

Note: Bolding convention not applicable to these data.

Table F-4
2000 Radioactivity Concentrations ($\mu\text{Ci/g}$ - dry) in Fish Flesh
from Cattaraugus Creek

Cattaraugus Creek above the Springville Dam (BFFCATC)

1st Half 2000

Species	% Moisture	Sr-90	Cs-137
White Sucker	74.0	4.05 \pm 0.45E-08	2.46 \pm 2.49E-08
Hog-nosed Sucker	73.3	8.35 \pm 0.72E-08	0.29 \pm 2.68E-08
Hog-nosed Sucker	74.6	8.67\pm0.73E-08	0.40 \pm 3.38E-08
Hog-nosed Sucker	74.8	1.85 \pm 0.28E-08	1.95 \pm 1.68E-08
White Sucker	77.2	2.46 \pm 0.44E-08	4.60\pm2.61E-08
White Sucker	75.5	4.64 \pm 0.54E-08	1.20 \pm 4.40E-08
Rainbow Trout	76.7	2.10 \pm 0.66E-08	2.96 \pm 3.24E-08
Hog-nosed Sucker	73.0	3.89 \pm 0.58E-08	3.17 \pm 3.88E-08
Greater Red Horse	68.6	1.95 \pm 0.16E-08	1.28 \pm 0.95E-08
Greater Red Horse	73.0	1.18\pm0.38E-08	1.09 \pm 0.82E-08
Average % Moisture	74.1		
Median		3.18E-08	<2.96E-08
Maximum		8.67E-08	4.60E-08
Minimum		1.18E-08	1.09E-08

2nd Half 2000

Species	% Moisture	Sr-90	Cs-137
Hog-nosed Sucker	77.2	2.69 \pm 1.28E-08	3.62 \pm 5.22E-08
Hog-nosed Sucker	78.5	1.68 \pm 2.56E-08	3.40 \pm 7.98E-08
Hog-nosed Sucker	78.7	1.10\pm0.18E-07	1.59\pm1.23E-07
Hog-nosed Sucker	79.2	NR	6.30 \pm 5.80E-08
Hog-nosed Sucker	77.3	2.20 \pm 0.95E-08	7.95 \pm 6.96E-08
Hog-nosed Sucker	77.4	8.33 \pm 3.02E-08	5.19 \pm 5.83E-08
Hog-nosed Sucker	79.0	6.11 \pm 1.69E-08	2.60 \pm 8.11E-08
Hog-nosed Sucker	77.5	2.36 \pm 1.25E-08	0.00 \pm 9.85E-08
Hog-nosed Sucker	77.2	0.60 \pm 1.89E-08	-0.36 \pm 8.07E-08
Hog-nosed Sucker	78.7	-0.79 \pm 1.72E-08	0.83 \pm 1.07E-07
Average % Moisture	78.1		
Median		2.56E-08	<8.02E-08
Maximum		1.10E-07	1.59E-07
Minimum		<1.72E-08	<5.22E-08

NR - Not reported. The data validation process indicated that the data were not reliable.

Note: Bolding convention applied to these data. See page F-2.

Table F-4 (continued)
2000 Radioactivity Concentrations ($\mu\text{Ci/g}$ - dry) in Fish Flesh
from Cattaraugus Creek

Cattaraugus Creek below the Springville Dam (BFFCATD)

Annual 2000			
Species	% Moisture	Sr-90	Cs-137
Steelhead Trout	72.7	NR	1.58 \pm 2.16E-08
Steelhead Trout	69.5	NR	2.03 \pm 2.26E-08
Steelhead Trout	65.8	NR	6.57\pm2.40E-08
Steelhead Trout	60.4	1.50\pm0.90E-09	3.40 \pm 2.52E-08
Steelhead Trout	67.4	NR	1.04 \pm 3.99E-08
Steelhead Trout	73.5	NR	0.96 \pm 3.37E-08
Steelhead Trout	62.9	NR	4.73 \pm 4.48E-08
Steelhead Trout	74.2	NR	3.56 \pm 3.33E-08
Steelhead Trout	72.0	6.10\pm2.20E-09	6.28 \pm 4.39E-08
Steelhead Trout	71.5	NR	3.50 \pm 3.28E-08
Average % Moisture	69.0		
Median		3.80E-09	3.53E-08
Maximum		6.10E-09	6.57E-08
Minimum		1.50E-09	<2.16E-08

NR - Not reported. The data validation process indicated that the data were not reliable.

Note: Bolding convention applied to these data. See page F-2.

Table F-4 (concluded)
2000 Radioactivity Concentrations ($\mu\text{Ci/g}$ - dry) in Fish Flesh
from Cattaraugus Creek

Cattaraugus Creek Background (BFFCTRL)

1st Half 2000

Species	% Moisture	Sr-90	Cs-137
Hog-nosed Sucker	73.6	2.00 \pm 3.10E-09	-4.65 \pm 7.15E-09
Hog-nosed Sucker	72.4	1.31 \pm 0.16E-08	0.68 \pm 1.24E-08
White Sucker	75.0	NR	0.00 \pm 1.10E-08
White Sucker	75.5	NR	3.01\pm1.79E-08
White Sucker	76.4	3.10 \pm 4.80E-09	3.24 \pm 7.98E-09
Brown Trout	70.0	8.40 \pm 2.40E-09	1.19 \pm 4.72E-08
Brown Trout	71.9	1.37\pm0.15E-08	-0.09 \pm 1.61E-08
Brown Trout	72.4	7.60 \pm 1.20E-09	-0.93 \pm 1.07E-08
Brown Trout	74.3	0.40 \pm 1.04E-08	3.54 \pm 5.58E-08
White Sucker	74.5	1.17 \pm 0.18E-08	-0.03 \pm 1.19E-08
Average % Moisture	73.6		
Median		9.40E-09	<1.22E-08
Maximum		1.37E-08	3.01E-08
Minimum		<3.10E-09	<7.15E-09

2nd Half 2000

Species	% Moisture	Sr-90	Cs-137
Hog-nosed Sucker	77.8	NR	-2.29 \pm 4.50E-08
Brown Trout	79.1	NR	0.17 \pm 1.69E-07
Brown Trout	77.7	1.63\pm0.87E-08	1.82 \pm 4.95E-08
Brown Trout	79.3	NR	3.74 \pm 8.17E-08
White Sucker	78.4	-0.04 \pm 1.72E-08	-5.38 \pm 6.09E-08
Hog-nosed Sucker	76.9	8.50 \pm 9.80E-09	-3.15 \pm 5.06E-08
White Sucker	78.9	0.82 \pm 1.97E-08	8.45 \pm 8.70E-08
White Sucker	78.9	-0.43 \pm 1.57E-08	0.21 \pm 2.12E-07
Brown Trout	76.2	-1.11 \pm 1.89E-08	8.74 \pm 9.42E-08
White Sucker	79.2	NR	-8.32 \pm 6.89E-08
Average % Moisture	78.2		
Median		<1.68E-08	<7.53E-08
Maximum		1.63E-08	<2.12E-07
Minimum		<9.80E-09	<4.50E-08

NR - Not reported. The data validation process indicated that the data were not reliable.

Note: Bolding convention applied to these data. See page F-2.

Appendix G

Summary of Nonradiological Monitoring Data



Packaging Samples for Shipment to Off-site Laboratories

Table G -1
West Valley Demonstration Project State Pollutant Discharge Elimination System
(SPDES) Sampling Program

Outfall	Parameter	Daily Maximum Limit*	Sample Frequency
001 (Process and Storm Wastewater)	Flow	Monitor	2 per discharge
	Aluminum, total	14.0 mg/L	2 per discharge
	Ammonia (NH ₃)	Monitor	2 per discharge
	Arsenic, dissolved	0.15 mg/L	2 per discharge
	BOD ₅	10.0 mg/L	2 per discharge
	Iron, total	Monitor	2 per discharge
	Zinc, total recoverable	0.48 mg/L	2 per discharge
	Suspended solids	45.0 mg/L	2 per discharge
	Cyanide, amenable to chlorination	0.022 mg/L	2 per discharge
	Settleable solids	0.30 mL/L	2 per discharge
	pH (range)	6.5 — 8.5	2 per discharge
	Oil and grease	15.0 mg/L	2 per discharge
	Sulfate (as S)	Monitor	2 per discharge
	Sulfide, dissolved	0.4 mg/L	2 per discharge
	Manganese, total	2.0 mg/L	2 per discharge
	Nitrate (as N)	Monitor	2 per discharge
	Nitrite (as N)	0.1 mg/L	2 per discharge
	Chromium, total recoverable	0.3 mg/L	2 per discharge
	Chromium, hexavalent, total recoverable	0.011 mg/L	2 per discharge
	Cadmium, total recoverable	0.002 mg/L	2 per discharge
	Copper, total recoverable	0.030 mg/L	2 per discharge
	Copper, dissolved	Monitor	2 per discharge
	Lead, total recoverable	0.006 mg/L	2 per discharge
	Nickel, total recoverable	0.14 mg/L	2 per discharge
	Dichlorodifluoromethane	0.01 mg/L	2 per discharge
	Trichlorofluoromethane	0.01 mg/L	2 per discharge
	3,3-dichlorobenzidine	0.01 mg/L	2 per discharge
	Tributyl phosphate	32 mg/L	2 per discharge
	Vanadium, total recoverable	0.014 mg/L	2 per discharge
	Cobalt, total recoverable	0.005 mg/L	2 per discharge
	Selenium, total recoverable	0.004 mg/L	2 per discharge
	Hexachlorobenzene	0.02 mg/L	2 per discharge
	Alpha - BHC	0.00001 mg/L	2 per discharge
	Heptachlor	0.00001 mg/L	2 per discharge
	Surfactants (as LAS)	0.4 mg/L	2 per discharge
	Xylene	0.05 mg/L	2 per discharge
	2-butanone	0.5 mg/L	2 per discharge
	Total Dissolved Solids	Monitor	2 per discharge

* Daily average limitations are also identified in the permit but require only monitoring for all parameters except total aluminum (daily average limit - 7.0 mg/L); suspended solids (daily average limit - 30.0 mg/L); BOD₅ for the sum of outfalls 001, 007, and 008 (daily average limit - 5.0 mg/L); and ammonia for the sum of outfalls 001 and 007 (daily average limit - 1.49 mg/L).

Table G-1 (concluded)
West Valley Demonstration Project State Pollutant Discharge Elimination System
(SPDES) Sampling Program

Outfall	Parameter	Daily Maximum Limit*	Sample Frequency
001 (continued)	Barium	0.5 mg/L	annual
	Antimony	1.0 mg/L	annual
	Chloroform	0.3 mg/L	annual
	Bis(2-ethylhexyl)phthalate	1.6 mg/L	semiannual
	4-Dodecene	0.6 mg/L	semiannual
	Titanium	0.65 mg/L	semiannual
007 (Sanitary and Utility Wastewater)	Flow	Monitor	3 per month
	Ammonia (as NH ₃)	Monitor	3 per month
	BOD ₅	10 mg/L	3 per month
	Iron, total	Monitor	3 per month
	Solids, suspended	45.0 mg/L	3 per month
	Solids, settleable	0.3 mL/L	weekly
	pH (range)	6.5 — 8.5	weekly
	Nitrite (as N)	0.1 mg/L	3 per month
	Oil and grease	15 mg/L	3 per month
	Chlorine, total residual	0.1 mg/L	weekly
	Chloroform	0.20 mg/L	annual
008 (French Drain Wastewater)	Flow	Monitor	3 per month
	BOD ₅	5.0 mg/L	3 per month
	Iron, total	Monitor	3 per month
	pH (range)	6.5 — 8.5	3 per month
	Cadmium, total recoverable	0.002 mg/L	3 per month
	Lead, total recoverable	0.006 mg/L	3 per month
	Silver, total	0.008 mg/L	annual
	Zinc, total	0.100 mg/L	annual
	Arsenic	0.17 mg/L	annual
	Chromium	0.13 mg/L	annual
Sum of Outfalls 001, 007, and 008	Iron, total	0.30 mg/L	3 per month
	BOD ₅	Monitor	3 per month
Sum of Outfalls 001 and 007	Ammonia (as NH ₃)	2.1 mg/L	3 per month
Pseudo-monitoring point (116)	Solids, total dissolved	500 mg/L	2 per discharge

* Daily average limitations are also identified in the permit but require only monitoring for all parameters except total aluminum (daily average limit - 7.0 mg/L); suspended solids (daily average limit - 30.0 mg/L); BOD₅ for the sum of outfalls 001, 007, and 008 (daily average limit - 5.0 mg/L); and ammonia for the sum of outfalls 001 and 007 (daily average limit - 1.49 mg/L).

Table G-2
2000 SPDES Results for Outfall 001 (WNSP001)
Water Quality

<i>Analyte:</i>	Ammonia (mg/L)		BOD₅ (mg/L)		Cyanide (mg/L) (amenable to chlorination)		Discharge Rate (MGD)	
<i>Permit limit:</i>	<i>Monitor</i>		<i>10.0 mg/L daily maximum</i>		<i>0.022 mg/L daily maximum</i>		<i>Monitor</i>	
Month	Avg	Max	Avg	Max	Avg	Max	Avg	Max
<i>Jan</i>	0.150	0.177	3.3	3.4	< 0.010	< 0.010	0.417	0.544
<i>Feb*</i>								
<i>Mar</i>	0.156	0.171	< 2.0	< 2.0	< 0.010	< 0.010	0.353	0.510
<i>Apr*</i>								
<i>May</i>	0.166	0.171	< 2.0	< 2.0	< 0.010	< 0.010	0.375	0.674
<i>Jun*</i>								
<i>Jul</i>	< 0.056	< 0.062	< 2.0	< 2.0	< 0.010	< 0.010	0.294	0.490
<i>Aug*</i>								
<i>Sep</i>	< 0.053	0.055	< 2.3	2.6	< 0.010	< 0.010	0.371	0.465
<i>Oct*</i>								
<i>Nov</i>	< 0.010	< 0.010	2.9	3.4	< 0.010	< 0.010	0.392	0.690
<i>Dec*</i>								

<i>Analyte:</i>	Nitrate (as N) (mg/L)		Nitrite (as N) (mg/L)		Oil & Grease (mg/L)	
<i>Permit limit:</i>	<i>Monitor</i>		<i>0.1 mg/L daily maximum</i>		<i>15.0 mg/L daily maximum</i>	
Month	Avg	Max	Avg	Max	Avg	Max
<i>Jan</i>	1.35	1.40	< 0.05	< 0.05	8.0	9.8
<i>Feb*</i>						
<i>Mar</i>	2.50	2.80	0.1	0.1	< 5.0	< 5.0
<i>Apr*</i>						
<i>May</i>	0.91	1.00	< 0.05	< 0.05	< 5.0	< 5.0
<i>Jun*</i>						
<i>Jul</i>	0.86	1.00	< 0.05	< 0.05	< 5.0	< 5.0
<i>Aug*</i>						
<i>Sep</i>	1.60	1.70	< 0.05	< 0.05	< 5.0	< 5.0
<i>Oct*</i>						
<i>Nov</i>	0.82	0.83	< 0.05	< 0.05	< 5.0	< 5.0
<i>Dec*</i>						

** No discharge this month.*

Note: No results exceeded the permit limits.

Table G-2 (concluded)
2000 SPDES Results for Outfall 001 (WNSP001)
Water Quality

<i>Analyte:</i>	pH (standard units)		Solids, Settleable (mL/L)		Solids, Total Dissolved (mg/L)		Solids, Total Suspended (mg/L)	
Permit limit:	<i>6.5 to 8.5</i>		<i>0.30 mL/L daily maximum</i>		<i>Monitor</i>		<i>45.0 mg/L daily maximum 30.0 mg/L daily average</i>	

Month	Min	Max	Avg	Max	Avg	Max	Avg	Max
<i>Jan</i>	7.3	7.6	< 0.1	< 0.1	536	536	< 4.0	6.0
<i>Feb*</i>								
<i>Mar</i>	7.5	7.8	< 0.1	< 0.1	598	605	16.0	23.0
<i>Apr*</i>								
<i>May</i>	7.6	8.0	< 0.1	< 0.1	610	618	6.2	8.0
<i>Jun*</i>								
<i>Jul</i>	7.9	8.0	< 0.1	< 0.1	517	537	< 2.0	< 2.0
<i>Aug*</i>								
<i>Sep</i>	7.8	8.1	< 0.1	< 0.1	628	635	10.0	12.0
<i>Oct*</i>								
<i>Nov</i>	7.3	7.9	< 0.1	< 0.1	580	584	< 3.2	4.5
<i>Dec*</i>								

<i>Analyte:</i>	Sulfate (as S) (mg/L)		Sulfide, Dissolved (as S) (mg/L)		Surfactants as LAS (mg/L)	
Permit limit:	<i>Monitor</i>		<i>0.4 mg/L daily maximum</i>		<i>0.4 mg/L daily maximum</i>	

Month	Avg	Max	Avg	Max	Avg	Max
<i>Jan</i>	28	29	< 0.2	< 0.2	< 0.1	< 0.1
<i>Feb*</i>						
<i>Mar</i>	40	43	< 0.2	< 0.2	< 0.1	< 0.1
<i>Apr*</i>						
<i>May</i>	17	26	< 0.2	< 0.2	< 0.1	< 0.1
<i>Jun*</i>						
<i>Jul</i>	45	47	< 0.2	< 0.2	< 0.1	< 0.1
<i>Aug*</i>						
<i>Sep</i>	43	50	< 0.2	< 0.2	< 0.1	< 0.1
<i>Oct*</i>						
<i>Nov</i>	18	29	< 0.2	< 0.2	< 0.1	< 0.1
<i>Dec*</i>						

** No discharge this month.*

Note: No results exceeded the permit limits.

Table G-3
2000 SPDES Results for Outfall 001 (WNSP001)
Metals

<i>Analyte:</i>	Aluminum, Total (mg/L)		Arsenic, Dissolved (mg/L)		Cadmium Total Recoverable (mg/L)		Cobalt Total Recoverable (mg/L)	
Permit limit:	<i>14 mg/L daily maximum</i> <i>7.0 mg/L daily average</i>		<i>0.15 mg/L daily maximum</i>		<i>0.002 mg/L daily maximum</i>		<i>0.005 mg/L daily maximum</i>	
Month	Avg	Max	Avg	Max	Avg	Max	Avg	Max
<i>Jan</i>	< 0.236	0.271	< 0.003	< 0.003	< 0.001	< 0.001	< 0.004	< 0.004
<i>Feb*</i>								
<i>Mar</i>	0.450	0.489	< 0.003	< 0.003	< 0.001	< 0.001	< 0.004	< 0.004
<i>Apr*</i>								
<i>May</i>	< 0.200	< 0.200	< 0.003	< 0.003	< 0.001	< 0.001	< 0.004	< 0.004
<i>Jun*</i>								
<i>Jul</i>	< 0.200	< 0.200	< 0.003	< 0.003	< 0.001	< 0.001	< 0.004	< 0.004
<i>Aug*</i>								
<i>Sep</i>	0.330	0.455	< 0.003	< 0.003	< 0.001	< 0.001	< 0.004	< 0.004
<i>Oct*</i>								
<i>Nov</i>	< 0.200	< 0.200	< 0.001	< 0.001	< 0.001	< 0.001	< 0.004	< 0.004
<i>Dec*</i>								

<i>Analyte:</i>	Chromium, Total Recoverable (mg/L)		Chromium VI, Total Recoverable (mg/L)		Copper, Dissolved (mg/L)	
Permit limit:	<i>0.3 mg/L daily maximum</i>		<i>0.011 mg/L daily maximum</i>		<i>Monitor</i>	
Month	Avg	Max	Avg	Max	Avg	Max
<i>Jan</i>	< 0.010	< 0.010	< 0.010	< 0.010	< 0.010	< 0.010
<i>Feb*</i>						
<i>Mar</i>	< 0.010	< 0.010	< 0.010	< 0.010	< 0.010	< 0.010
<i>Apr*</i>						
<i>May</i>	< 0.010	< 0.010	< 0.010	< 0.010	< 0.010	< 0.010
<i>Jun*</i>						
<i>Jul</i>	< 0.010	< 0.010	< 0.010	< 0.010	< 0.010	< 0.010
<i>Aug*</i>						
<i>Sep</i>	< 0.010	< 0.010	< 0.010	< 0.010	< 0.010	< 0.010
<i>Oct*</i>						
<i>Nov</i>	< 0.002	0.002	< 0.010	< 0.010	< 0.005	0.0054
<i>Dec*</i>						

** No discharge this month.*

Note: No results exceeded the permit limits.

Table G-3 (concluded)
2000 SPDES Results for Outfall 001 (WNSP001)
Metals

<i>Analyte:</i>	Copper Total Recoverable (mg/L)		Iron Total (mg/L)		Lead Total Recoverable (mg/L)		Manganese Total (mg/L)	
Permit limit:	<i>0.030 mg/L daily maximum</i>		<i>Monitor</i>		<i>0.006 mg/L daily maximum</i>		<i>2.0 mg/L daily maximum</i>	

Month	Avg	Max	Avg	Max	Avg	Max	Avg	Max
<i>Jan</i>	< 0.010	< 0.010	0.166	0.221	< 0.002	< 0.002	0.015	0.016
<i>Feb*</i>								
<i>March</i>	< 0.010	< 0.010	0.274	0.316	0.002	0.003	0.020	0.022
<i>Apr*</i>								
<i>May</i>	< 0.010	< 0.010	0.136	0.180	< 0.002	< 0.002	0.015	0.016
<i>Jun*</i>								
<i>Jul</i>	< 0.010	< 0.010	0.0897	0.0999	< 0.002	< 0.002	0.010	0.011
<i>Aug*</i>								
<i>Sep</i>	< 0.010	< 0.010	0.244	0.320	< 0.002	< 0.002	0.012	0.012
<i>Oct*</i>								
<i>Nov</i>	< 0.006	0.006	0.106	0.114	< 0.002	< 0.003	0.0167	0.0175
<i>Dec*</i>								

<i>Analyte:</i>	Nickel Total Recoverable (mg/L)		Selenium Total Recoverable (mg/L)		Vanadium Total Recoverable (mg/L)		Zinc Total Recoverable (mg/L)	
Permit limit:	<i>0.14 mg/L daily maximum</i>		<i>0.004 mg/L daily maximum</i>		<i>0.014 mg/L daily maximum</i>		<i>0.48 mg/L daily maximum</i>	

Month	Avg	Max	Avg	Max	Avg	Max	Avg	Max
<i>Jan</i>	< 0.040	< 0.040	< 0.002	< 0.002	< 0.010	< 0.010	< 0.011	0.012
<i>Feb*</i>								
<i>Mar</i>	< 0.040	< 0.040	< 0.003	< 0.003	< 0.010	< 0.010	< 0.010	< 0.010
<i>Apr*</i>								
<i>May</i>	< 0.040	< 0.040	< 0.003	< 0.003	< 0.010	< 0.010	< 0.010	< 0.010
<i>Jun*</i>								
<i>Jul</i>	< 0.040	< 0.040	< 0.003	< 0.003	< 0.010	< 0.010	0.019	0.028
<i>Aug*</i>								
<i>Sep</i>	< 0.040	< 0.040	< 0.003	< 0.003	< 0.010	< 0.010	0.013	0.015
<i>Oct*</i>								
<i>Nov</i>	< 0.010	< 0.010	< 0.001	< 0.001	< 0.010	< 0.010	< 0.014	< 0.018
<i>Dec*</i>								

** No discharge this month.*

Note: No results exceeded the permit limits.

Table G-4
2000 SPDES Results for Outfall 001 (WNSP001)
Organics

VOLATILES

<i>Analyte:</i>	2-Butanone (mg/L)		Dichlorodifluoromethane (mg/L)		Trichlorofluoromethane (mg/L)		Xylene (mg/L)	
<i>Permit limit:</i>	<i>0.5 mg/L daily maximum</i>		<i>0.01 mg/L daily maximum</i>		<i>0.01 mg/L daily maximum</i>		<i>0.05 mg/L daily maximum</i>	
Month	Avg	Max	Avg	Max	Avg	Max	Avg	Max
<i>Jan</i>	< 0.01	< 0.01	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005
<i>Feb*</i>								
<i>Mar</i>	< 0.01	< 0.01	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005
<i>Apr*</i>								
<i>May</i>	< 0.01	< 0.01	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005
<i>Jun*</i>								
<i>Jul</i>	< 0.01	< 0.01	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005
<i>Aug*</i>								
<i>Sep</i>	< 0.01	< 0.01	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005
<i>Oct*</i>								
<i>Nov</i>	< 0.01	< 0.01	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005
<i>Dec*</i>								

SEMIVOLATILES

<i>Analyte:</i>	Alpha-BHC (mg/L)		3,3-Dichlorobenzidene (mg/L)		Hexachlorobenzene (mg/L)	
<i>Permit limit:</i>	<i>0.00001 mg/L daily maximum</i>		<i>0.01 mg/L daily maximum</i>		<i>0.02 mg/L daily maximum</i>	
Month	Avg	Max	Avg	Max	Avg	Max
<i>Jan</i>	< 0.000009	< 0.000009	< 0.0099	< 0.0099	< 0.01	< 0.01
<i>Feb*</i>						
<i>Mar</i>	< 0.000009	< 0.000009	< 0.0099	< 0.0099	< 0.01	< 0.01
<i>Apr*</i>						
<i>May</i>	< 0.000009	< 0.000009	< 0.0099	< 0.0099	< 0.01	< 0.01
<i>Jun*</i>						
<i>Jul</i>	< 0.000009	< 0.000009	< 0.0099	< 0.0099	< 0.01	< 0.01
<i>Aug*</i>						
<i>Sep</i>	< 0.000009	< 0.000009	< 0.0099	< 0.0099	< 0.01	< 0.01
<i>Oct*</i>						
<i>Nov</i>	< 0.000009	< 0.000009	< 0.009	< 0.009	< 0.01	< 0.01
<i>Dec*</i>						

** No discharge this month.*

Note: No results exceeded the permit limits.

Table G-4 (concluded)
2000 SPDES Results for Outfall 001 (WNSP001)
Organics

SEMIVOLATILES (concluded)

<i>Analyte:</i>	Heptachlor (mg/L)		Tributyl Phosphate (mg/L)	
<i>Permit limit:</i>	<i>0.00001 mg/L daily maximum</i>		<i>32 mg/L daily maximum</i>	
Month	Avg	Max	Avg	Max
<i>Jan</i>	< 0.000009	< 0.000009	< 0.010	< 0.010
<i>Feb*</i>				
<i>Mar</i>	< 0.000009	< 0.000009	< 0.010	< 0.010
<i>Apr*</i>				
<i>May</i>	< 0.000009	< 0.000009	< 0.010	< 0.010
<i>Jun*</i>				
<i>Jul</i>	< 0.000009	< 0.000009	< 0.010	< 0.010
<i>Aug*</i>				
<i>Sep</i>	< 0.000009	< 0.000009	< 0.010	< 0.010
<i>Oct*</i>				
<i>Nov</i>	< 0.000009	< 0.000009	< 0.010	< 0.010
<i>Dec*</i>				

** No discharge this month.*

Note: No results exceeded the permit limits.

Table G-5
2000 SPDES Results for Outfall 007 (WNSP007)
Water Quality and Iron

<i>Analyte:</i>	Ammonia (as NH₃) (mg/L)		BOD₅ (mg/L)		Chlorine Total Residual (mg/L)		Discharge Rate (MGD)		Iron Total (mg/L)	
<i>Permit limit:</i>	<i>Monitor</i>		<i>10.0 mg/L</i> <i>daily maximum</i>		<i>0.1 mg/L</i> <i>daily maximum</i>		<i>Monitor</i>		<i>Monitor</i>	
Month	Avg	Max	Avg	Max	Avg	Max	Avg	Max	Avg	Max
<i>Jan</i>	< 0.050	< 0.050	< 2.0	< 2.0	0.02	0.03	0.016	0.028	< 0.147	0.289
<i>Feb</i>	< 0.064	0.092	< 2.0	2.0	0.02	0.03	0.015	0.026	< 0.055	0.082
<i>Mar</i>	< 0.065	0.083	< 2.2	2.6	0.03	0.05	0.019	0.014	< 0.039	0.044
<i>Apr</i>	< 0.064	0.092	< 2.0	< 2.0	0.02	0.02	0.017	0.027	0.102	0.134
<i>May</i>	< 0.085	0.127	< 2.0	< 2.0	0.01	0.02	0.013	0.022	0.103	0.201
<i>Jun</i>	0.051	0.051	< 2.0	< 2.0	0.01	0.01	0.011	0.019	0.067	0.067
<i>Jul</i>	< 0.112	0.195	< 2.0	< 2.0	0.02	0.03	0.007	0.016	< 0.031	0.033
<i>Aug</i>	< 0.091	0.172	< 3.1	5.0	0.01	0.02	0.012	0.025	< 0.046	0.064
<i>Sep</i>	< 0.061	0.075	< 2.5	3.0	0.02	0.02	0.012	0.016	0.053	0.071
<i>Oct</i>	0.168	0.340	4.8	6.3	0.02	0.04	0.018	0.027	< 0.065	0.045
<i>Nov</i>	< 0.010	< 0.010	< 2.2	2.5	0.02	0.02	0.019	0.038	0.080	0.109
<i>Dec</i>	< 0.011	0.014	< 2.3	2.8	0.03	0.05	0.024	0.040	0.074	0.121

<i>Analyte:</i>	Nitrite (mg/L)		Oil & Grease (mg/L)		pH (standard units)		Solids Settleable (mL/L)		Solids Total Suspended (mg/L)	
<i>Permit limit:</i>	<i>0.1 mg/L</i> <i>daily maximum</i>		<i>15 mg/L</i> <i>daily maximum</i>		<i>6.5 to 8.5</i>		<i>0.30 mL/L</i> <i>daily maximum</i>		<i>45.0 mg/L daily maximum</i> <i>30.0 mg/L daily average</i>	
Month	Avg	Max	Avg	Max	Min	Max	Avg	Max	Avg	Max
<i>Jan</i>	< 0.05	< 0.05	< 5.0	< 5.0	7.7	7.9	< 0.1	< 0.1	< 5.3	11.0
<i>Feb</i>	< 0.05	< 0.05	< 7.4	10.2	7.5	7.9	< 0.1	< 0.1	< 2.7	4.0
<i>Mar</i>	< 0.05	< 0.05	< 5.0	< 5.0	7.5	7.9	< 0.1	< 0.1	< 2.2	2.6
<i>Apr</i>	< 0.05	< 0.05	< 5.0	< 5.0	7.6	7.7	< 0.1	< 0.1	4.7	6.0
<i>May</i>	< 0.05	< 0.05	< 5.0	< 5.0	7.5	7.7	< 0.1	< 0.1	8.3	21.0
<i>Jun</i>	< 0.05	< 0.05	< 5.0	< 5.0	7.6	7.6	< 0.1	< 0.1	< 2.0	< 2.0
<i>Jul</i>	< 0.05	< 0.05	< 5.7	7.1	7.4	7.7	< 0.1	< 0.1	< 3.7	7.0
<i>Aug</i>	< 0.05	0.06	< 5.0	< 5.0	7.3	8.0	< 0.1	< 0.1	< 6.3	15.0
<i>Sep</i>	< 0.05	< 0.05	< 5.0	< 5.0	7.3	7.9	< 0.1	< 0.1	< 5.0	10.0
<i>Oct</i>	< 0.05	< 0.05	< 5.0	< 5.0	7.5	8.4	< 0.1	< 0.1	< 3.7	6.0
<i>Nov</i>	< 0.05	< 0.05	< 5.0	< 5.0	7.7	8.1	< 0.1	< 0.1	< 2.0	< 2.0
<i>Dec</i>	< 0.05	< 0.05	< 5.0	< 5.0	7.2	7.9	< 0.1	< 0.1	< 2.0	2.0

Note: No results exceeded the permit limits.

Table G-6
2000 SPDES Results for Outfall 008 (WNSP008)
Water Quality

<i>Analyte:</i>	BOD₅ (mg/L)		Discharge Rate (GPD)		pH (standard units)	
Permit limit:	<i>5.0 mg/L</i> <i>daily maximum</i>		<i>Monitor</i>		<i>6.5 to 8.5</i>	
Month	Avg	Max	Avg	Max	Min	Max
<i>Jan</i>	< 2.0	< 2.0	2029	2659	6.8	7.7
<i>Feb</i>	< 2.0	< 2.0	1458	1771	6.6	6.8
<i>Mar</i>	< 2.0	< 2.0	2062	2185	6.8	7.0
<i>Apr</i>	< 2.0	< 2.0	2673	3202	6.6	6.8
<i>May</i>	< 2.0	< 2.0	1627	1873	6.8	7.1
<i>Jun</i>	< 2.0	< 2.0	1804	1979	6.7	7.1
<i>Jul</i>	< 2.0	< 2.0	1575	1911	6.8	7.1
<i>Aug</i>	< 2.7	4.1	2115	2280	6.8	6.9
<i>Sep</i>	< 2.0	< 2.0	1834	2478	7.0	7.1
<i>Oct</i>	< 3.1	5.0	1998	2461	6.7	7.5
<i>Nov</i>	< 2.0	< 2.0	1093	1179	6.8	7.0
<i>Dec</i>	< 2.0	< 2.0	2171	2395	6.6	7.2

<i>Analyte:</i>	Cadmium Total Recoverable (mg/L)		Iron Total (mg/L)		Lead Total Recoverable (mg/L)	
Permit limit:	<i>0.002 mg/L</i> <i>daily maximum</i>		<i>Monitor</i>		<i>0.006 mg/L daily</i> <i>maximum</i>	
Month	Avg	Max	Avg	Max	Avg	Max
<i>Jan</i>	< 0.001	< 0.001	< 0.030	< 0.030	< 0.002	< 0.002
<i>Feb</i>	< 0.001	< 0.001	< 0.034	0.0388	< 0.003	0.004
<i>Mar</i>	< 0.001	< 0.001	< 0.089	0.208	< 0.002	0.002
<i>Apr</i>	< 0.001	0.001	< 0.043	0.054	< 0.002	< 0.002
<i>May</i>	< 0.001	0.002	< 0.030	< 0.030	< 0.002	0.003
<i>Jun</i>	< 0.001	< 0.001	< 0.053	0.091	< 0.002	< 0.002
<i>Jul</i>	< 0.001	< 0.001	0.040	0.046	< 0.002	0.003
<i>Aug</i>	< 0.001	< 0.001	< 0.099	0.219	< 0.002	< 0.002
<i>Sep</i>	< 0.001	< 0.001	0.086	0.134	< 0.002	0.002
<i>Oct</i>	< 0.001	< 0.001	0.063	0.065	< 0.002	< 0.002
<i>Nov</i>	< 0.001	< 0.001	0.088	0.102	< 0.001	0.003
<i>Dec</i>	< 0.001	< 0.001	0.116	0.174	< 0.002	0.003

Note: No results exceeded the permit limits.

Table G-7
2000 SPDES Results for Sums of Outfalls 001, 007, and 008
Water Quality

<i>Analyte:</i>	Ammonia, as NH₃** Flow-weighted (mg/L)		BOD₅ Flow-weighted (mg/L)		Iron, Total Flow-weighted Net Average (mg/L)	
Permit limit:	<i>2.1 mg/L daily maximum</i> <i>1.49 mg/L daily average</i>		<i>5.0 mg/L daily maximum</i>		<i>0.30 mg/L daily average</i>	
Month	Avg	Max	Avg	Max	Avg	Max
<i>Jan</i>	< 0.114	< 0.172	< 2.8	< 3.3	0.01	—
<i>Feb</i>	< 0.064	0.092	< 2.0	< 2.0	0.00	—
<i>Mar</i>	< 0.118	0.170	< 2.0	< 2.0	0.06	—
<i>Apr</i>	< 0.064	0.092	< 2.0	< 2.0	0.00	—
<i>May</i>	< 0.151	< 0.170	< 2.0	< 2.0	0.00	—
<i>Jun</i>	0.051	0.051	< 2.0	< 2.0	0.00	—
<i>Jul</i>	< 0.103	0.195	< 2.0	< 2.0	0.00	—
<i>Aug</i>	< 0.091	0.172	< 3.0	4.9	0.00	—
<i>Sep</i>	< 0.052	0.056	< 2.5	< 2.9	0.00	—
<i>Oct</i>	0.168	0.340	< 4.6	6.2	0.00	—
<i>Nov</i>	< 0.010	< 0.010	< 2.6	< 3.3	0.00	—
<i>Dec</i>	< 0.011	0.014	< 2.3	< 2.8	0.00	—

2000 SPDES Results for Outfall 116
Water Quality

<i>Analyte:</i>	Total Dissolved Solids (mg/L)	
Permit limit:	<i>500 mg/L daily maximum</i>	
Month	Avg	Max
<i>Jan</i>	260	268
<i>Feb*</i>		
<i>Mar</i>	330	337
<i>Apr*</i>		
<i>May</i>	399	439
<i>Jun*</i>		
<i>Jul</i>	345	349
<i>Aug*</i>		
<i>Sep</i>	417	437
<i>Oct*</i>		
<i>Nov</i>	360	397
<i>Dec*</i>		

**** Sum of Outfalls 001 and 007 only. * No discharge this month.**

Note: No results exceeded the permit limits.

Table G-8
2000 Annual/Semiannual SPDES Results for Outfall 001
Water Quality, Metals, and Organics

Chloroform (mg/L)	Action Level 0.3 mg/L daily maximum	Monitoring Frequency Annual	Collection Date March 2000	Maximum Measured < 0.005
Antimony, Total (mg/L)	Action Level 1.0 mg/L daily maximum	Monitoring Frequency Annual	Collection Date March 2000	Maximum Measured < 0.060
Barium, Total (mg/L)	Action Level 0.5 mg/L daily maximum	Monitoring Frequency Annual	Collection Date March 2000	Maximum Measured < 0.050
<hr/>				
Titanium, Total (mg/L)	Action Level 0.65 mg/L daily maximum	Monitoring Frequency Semiannual	Collection Date March 2000 September 2000	Maximum Measured < 0.050 < 0.050
bis(2-ethylhexyl) phthalate (mg/L)	Action Level 1.6 mg/L daily maximum	Monitoring Frequency Semiannual	Collection Date March 2000 September 2000	Maximum Measured < 0.010 < 0.010
4-dodecene (mg/L)	Action Level 0.6 mg/L daily maximum	Monitoring Frequency Semiannual	Collection Date March 2000 September 2000	Maximum Measured < 0.060 < 0.060

Table G-9
2000 Annual SPDES Results for Outfall 007
Water Quality

Chloroform (mg/L)	Action Level	Monitoring Frequency	Collection Date	Maximum Measured
	0.20 mg/L daily maximum	Annual	January 2001	< 0.023

Table G-10
2000 Annual SPDES Results for Outfall 008
Water Quality

Arsenic, Total (mg/L)	Action Level	Monitoring Frequency	Collection Date	Maximum Measured
	0.17 mg/L daily maximum	Annual	January 2001	< 0.003
Chromium, Total (mg/L)	Action Level	Monitoring Frequency	Collection Date	Maximum Measured
	0.13 mg/L daily maximum	Annual	January 2001	< 0.010
Silver, Total (mg/L)	Action Level	Monitoring Frequency	Collection Date	Maximum Measured
	0.008 mg/L daily maximum	Annual	January 2001	< 0.003
Zinc, Total (mg/L)	Action Level	Monitoring Frequency	Collection Date	Maximum Measured
	0.100 mg/L daily maximum	Annual	January 2001	0.595

Appendix H

Summary of Direct Radiation Monitoring Data



An Environmental TLD Package

The following tables contain a bolding convention devised to help the reader, when viewing the data, to quickly see the range of detectable measurements within a data series. A data series is a set of chemical or radionuclide measurements (e.g., gross alpha, gross beta, tritium) from a single location or from similar locations. Note that some tables contain data that should not be technically evaluated under this convention.

Key to bolding convention:

Results for each constituent constitute a single data series. If a radiological result is larger than the uncertainty term, the measurement is considered positive. Otherwise, a result is considered non-detectable.

If all results in a data series are positive, the lowest and highest values are bolded.

If a data series contains some positive results, the highest value is bolded.

If all values in a data series are nondetectable, no values are bolded.

Table H-1
Summary of 2000 Quarterly Averages of Off-site TLD Measurements
(mR±2SD/quarter)

Location Number*	1st Quarter	2nd Quarter	3rd Quarter	4th Quarter	Location Average
DFTLD01	24±4.7	21±4.3	24±4.7	25±4.9	24±4.7
DFTLD02	23±4.7	21±4.3	23±4.6	24±4.9	23±4.6
DFTLD03	20±4.2	18±3.7	18±3.7	22±4.3	20±4.0
DFTLD04	21±4.3	21±4.3	22±4.4	24±4.7	22±4.4
DFTLD05	21±4.2	20±4.1	22±4.5	23±4.6	22±4.4
DFTLD06	20±4.1	20±4.1	21±4.2	24±4.7	21±4.3
DFTLD07	18±3.7	19±3.8	20±4.0	21±4.2	20±3.9
DFTLD08	21±4.3	20±4.0	22±4.4	23±4.6	22±4.3
DFTLD09	22±4.4	20±4.0	21±4.3	24±4.8	22±4.4
DFTLD10	21±4.3	21±4.3	20±4.1	23±4.6	21±4.3
DFTLD11	18±3.8	18±3.7	19±3.8	22±4.4	19±3.9
DFTLD12	23±4.6	20±4.2	21±4.3	24±4.7	22±4.5
DFTLD13	22±4.4	22±4.4	25±5.0	26±5.1	24±4.7
DFTLD14	22±4.4	22±4.6	22±4.5	24±4.9	23±4.6
DFTLD15	19±3.9	21±4.2	21±4.3	23±4.6	21±4.3
DFTLD16	21±4.2	19±4.0	23±4.5	24±4.8	22±4.4
DFTLD17**	21±4.3	22±4.4	24±4.8	25±4.9	23±4.6
DFTLD20	19±3.9	18±3.8	20±4.1	22±4.3	20±4.0
DFTLD21	21±4.3	22±4.5	24±4.7	25±4.9	23±4.6
DFTLD22	23±4.7	23±4.6	24±4.8	25±4.9	24±4.8
DFTLD23**	21±4.2	21±4.3	23±4.6	24±4.7	22±4.5
DFTLD37**	24±4.7	21±4.3	20±4.1	25±5.0	23±4.5
DFTLD41**	20±4.0	18±3.8	18±3.6	22±4.4	20±4.0

* Off-site locations are shown on Figure A-11 (p. A-13) and A-12 (p. A-14).

** Background measurements are provided by off-site TLDs 17, 23, 37, and 41.

Note: Bolding convention applied to these data. See page H-2.

Table H-2
Summary of 2000 Quarterly Averages of On-site TLD Measurements
(mR±2SD/quarter)

Location Number*	1st Quarter	2nd Quarter	3rd Quarter	4th Quarter	Location Average
DNTLD18	35±6.9	36±7.1	35±7.0	34±6.8	35±7.0
DNTLD19	24±4.9	26±5.2	26±5.2	27±5.3	26±5.2
DNTLD24	654±128.2	641±125.7	643±126.1	568±111.4	627±123.0
DNTLD25	25±5.0	25±5.0	28±5.6	29±5.7	27±5.3
DNTLD26	26±5.3	26±5.3	28±5.6	29±5.7	27±5.5
DNTLD27	23±4.6	22±4.5	24±4.8	25±5.0	24±4.7
DNTLD28	23±4.6	26±5.2	22±4.5	27±5.3	25±4.9
DNTLD29	21±4.3	25±5.1	23±4.6	26±5.2	24±4.8
DNTLD30	26±5.2	25±5.0	24±4.9	32±6.4	27±5.4
DNTLD31	24±4.7	22±4.4	21±4.3	28±5.5	24±4.7
DNTLD32	33±6.6	33±6.5	30±6.0	40±7.9	34±6.8
DNTLD33	36±7.1	41±8.1	32±6.4	36±7.2	36±7.2
DNTLD34	59±11.6	57±11.3	52±10.3	55±10.8	56±11.0
DNTLD35	79±15.6	80±15.8	72±14.1	75±14.8	77±15.1
DNTLD36	41±8.2	41±8.1	35±7.0	40±7.8	39±7.8
DNTLD38	38±7.5	40±7.8	33±6.5	37±7.4	37±7.3
DNTLD39	54±10.6	56±10.9	49±9.7	52±10.3	53±10.4
DNTLD40	125±24.6	128±25.2	114±22.4	123±24.1	123±24.1
DNTLD42	89±17.6	87±17.0	81±16.0	85±16.6	86±16.8
DNTLD43	33±6.5	32±6.4	29±5.8	33±6.6	32±6.3

* On-site locations are shown on Figure A-10 (p. A-12).

Note: Bolding convention applied to these data. See page H-2.

Table H-3
3rd Quarter 2000 Results and Instantaneous Dose Readings ($\mu\text{R/hr}$) with a
High-pressure Ion Chamber (HPIC) at Each Monitoring Location

Off-site Location Number	3rd Quarter TLD Result	August 2000 HPIC Result	On-site Location Number	3rd Quarter TLD Result	August 2000 HPIC Result
DFTLD01	10.86	9.00	DNTLD18	15.85	15.00
DFTLD02	10.41	9.00	DNTLD19	11.78	10.00
DFTLD03	8.15	8.00	DNTLD24	290.77	341.00
DFTLD04	9.96	8.00	DNTLD25	12.67	12.00
DFTLD05	9.96	9.00	DNTLD26	12.68	11.00
DFTLD06	9.51	9.00	DNTLD27	10.87	9.00
DFTLD07	9.05	8.00	DNTLD28	9.96	7.00
DFTLD08	9.96	9.00	DNTLD29	10.40	10.00
DFTLD09	9.51	9.00	DNTLD30	10.86	12.00
DFTLD10	9.06	9.00	DNTLD31	9.50	9.00
DFTLD11	8.60	9.00	DNTLD32	13.57	12.00
DFTLD12	9.50	8.00	DNTLD33	14.49	15.00
DFTLD13	11.31	8.00	DNTLD34	23.55	24.00
DFTLD14	9.96	9.00	DNTLD35	32.61	36.00
DFTLD15	9.50	9.00	DNTLD36	15.85	17.00
DFTLD16	10.41	9.00	DNTLD38	14.94	16.00
DFTLD17	10.87	9.00	DNTLD39	22.18	24.00
DFTLD20	9.05	9.00	DNTLD40	51.60	52.00
DFTLD21	10.87	9.00	DNTLD42	36.63	26.00
DFTLD22	10.86	10.00	DNTLD43	13.12	13.00
DFTLD23	10.41	9.00			
DFTLD37	9.05	10.00			
DFTLD41	8.15	8.00			

Note: Bolding convention not applicable to these data.




Figure H-1. 2000 Average Yearly Gamma Exposure Rates around the West Valley Demonstration Project Site




Figure H-2. 2000 Average Yearly Gamma Exposure Rates on the West Valley Demonstration Project Site

Appendix I

Summary of Meteorological Data



Checking the On-site Rain Gauge






Figure I-1
10.0-Meter Wind Frequency Rose
Regional Monitoring Station




WIND SPEED RANGE



CALM <0.5

NUMBERS INDICATE SECTOR MEAN WIND SPEED
SECTORS ARE DIRECTIONS FROM WHICH THE WIND IS BLOWING

Figure I-2
10.0-Meter Wind Frequency Rose
Primary Monitoring Station



NUMBERS INDICATE SECTOR MEAN WIND SPEED
SECTORS ARE DIRECTIONS FROM WHICH THE WIND IS BLOWING

Figure I-3
60.0-Meter Wind Frequency Rose

Primary Monitoring Station




Figure I-4. Calendar Year 2000 Weekly Precipitation




Figure I-5. Calendar Year 2000 Cumulative Precipitation

Table I-1
2000 Site Precipitation Collection Data

Week Ending:	Weekly		Cumulative		Week Ending:	Weekly		Cumulative	
	(cm)	(inches)	(cm)	(inches)		(cm)	(inches)	(cm)	(inches)
Jan 01	0.00	0.00	0.00	0.00	Jul 01	3.33	1.31	46.05	18.13
Jan 08	2.64	1.04	2.64	1.04	Jul 08	1.22	0.48	47.27	18.61
Jan 15	2.26	0.89	4.90	1.93	Jul 15	4.60	1.81	51.87	20.42
Jan 22	0.51	0.20	5.41	2.13	Jul 22	1.35	0.53	53.21	20.95
Jan 29	0.05	0.02	5.46	2.15	Jul 29	0.00	0.00	53.21	20.95
Feb 05	0.89	0.35	6.35	2.50	Aug 05	4.22	1.66	57.43	22.61
Feb 12	0.76	0.30	7.11	2.80	Aug 12	8.53	3.36	65.96	25.97
Feb 19	1.98	0.78	9.09	3.58	Aug 19	0.05	0.02	66.01	25.99
Feb 26	0.89	0.35	9.98	3.93	Aug 26	1.42	0.56	67.44	26.55
Mar 04	1.63	0.64	11.61	4.57	Sep 02	1.07	0.42	68.50	26.97
Mar 11	1.17	0.46	12.78	5.03	Sep 09	2.72	1.07	71.22	28.04
Mar 18	2.21	0.87	14.99	5.90	Sep 16	3.43	1.35	74.65	29.39
Mar 25	0.23	0.09	15.21	5.99	Sep 23	3.91	1.54	78.56	30.93
Apr 01	1.24	0.49	16.46	6.48	Sep 30	0.66	0.26	79.22	31.19
Apr 08	7.52	2.96	23.98	9.44	Oct 07	4.93	1.94	84.15	33.13
Apr 15	0.61	0.24	24.59	9.68	Oct 14	0.00	0.00	84.15	33.13
Apr 22	3.78	1.49	28.37	11.17	Oct 21	0.10	0.04	84.25	33.17
Apr 29	0.10	0.04	28.47	11.21	Oct 28	0.15	0.06	84.40	33.23
May 06	1.35	0.53	29.82	11.74	Nov 04	0.61	0.24	85.01	33.47
May 13	2.03	0.80	31.85	12.54	Nov 11	1.07	0.42	86.08	33.89
May 20	2.90	1.14	34.75	13.68	Nov 18	1.88	0.74	87.96	34.63
May 27	1.63	0.64	36.37	14.32	Nov 25	3.00	1.18	90.96	35.81
Jun 03	0.41	0.16	36.78	14.48	Dec 02	0.46	0.18	91.41	35.99
Jun 10	0.20	0.08	36.98	14.56	Dec 09	0.66	0.26	92.08	36.25
Jun 17	4.17	1.64	41.15	16.20	Dec 16	1.98	0.78	94.06	37.03
Jun 24	1.57	0.62	42.72	16.82	Dec 23	1.32	0.52	95.38	37.55
					Dec 31	1.27	0.50	96.65	38.05

Table I-2
2000 Annual Temperature Summary at the 10-Meter
Primary Meteorological Tower

Month	Average Temperature		Maximum Temperature		Minimum Temperature	
	°C	°F	°C	°F	°C	°F
<i>January</i>	-5.3	22.5	14.7	58.5	-21.5	-6.7
<i>February</i>	-1.2	29.8	17.0	62.6	-20.7	-5.3
<i>March</i>	3.9	39.0	22.2	72.0	-14.1	6.6
<i>April</i>	6.1	43.0	22.3	72.1	-5.2	22.6
<i>May</i>	14.0	57.2	27.5	81.5	0.9	33.6
<i>June</i>	17.9	64.2	30.4	86.7	4.4	39.9
<i>July</i>	17.7	63.9	26.4	79.5	6.8	44.2
<i>August</i>	18.0	64.4	28.3	82.9	3.9	39.0
<i>September</i>	14.7	58.5	28.1	82.6	-1.3	29.7
<i>October</i>	9.9	49.8	23.0	73.4	-4.2	24.4
<i>November</i>	2.4	36.3	17.9	64.2	-15.4	4.3
<i>December</i>	-6.7	19.9	10.4	50.7	-15.9	3.4
Annual Average	7.6	45.7	22.4	72.3	-6.9	19.7

Table I-3
2000 Annual Barometric Pressure Summary
(station pressure - inches of mercury)

Month	Average Pressure	Maximum Pressure	Minimum Pressure
<i>January</i>	28.51	29.06	27.82
<i>February</i>	28.56	28.99	28.04
<i>March</i>	28.48	29.02	27.74
<i>April</i>	28.44	28.97	27.92
<i>May</i>	28.43	28.76	28.00
<i>June</i>	28.51	28.72	28.23
<i>July</i>	28.51	28.75	28.20
<i>August</i>	28.55	28.87	28.30
<i>September</i>	28.54	28.96	28.08
<i>October</i>	28.65	29.02	28.24
<i>November</i>	28.46	28.82	27.93
<i>December</i>	28.56	29.05	27.70
Annual Average	28.52	28.92	28.02

Appendix J

Summary of Quality Assurance Crosscheck Analyses



Analyzing Data

Table J-1
Comparison of Radiological Results with Known Results of Crosscheck Samples
from the DOE Environmental Measurements Laboratory (EML) Quality
Assessment Program (QAP) 52; EML-608 QAP 2003; June 2000

Analyte	Matrix	Units	Actual	Reported	Ratio	Accept?	Analyzed by:
Am-241	Air filter	Bq/filter	8.80E-02	8.90E-02	1.011	Yes	GEL
Co-57	Air filter	Bq/filter	5.31E+ 00	5.11E+ 00	0.962	Yes	GEL
Co-60	Air filter	Bq/filter	5.32E+ 00	5.50E+ 00	1.034	Yes	GEL
Cs-137	Air filter	Bq/filter	6.10E+ 00	6.36E+ 00	1.043	Yes	GEL
Gross Alpha	Air filter	Bq/filter	3.02E+ 00	2.66E+ 00	0.881	Yes	GEL
Gross Beta	Air filter	Bq/filter	2.42E+ 00	2.64E+ 00	1.091	Yes	GEL
Mn-54	Air filter	Bq/filter	2.72E+ 01	2.77E+ 01	1.018	Yes	GEL
Pu-238	Air filter	Bq/filter	8.00E-02	8.50E-02	1.063	Yes	GEL
Pu-239	Air filter	Bq/filter	8.90E-02	8.00E-02	0.899	Pass	GEL
Ru-106	Air filter	Bq/filter	2.01E+ 00	3.57E+ 00	1.776	No	GEL
Sr-90	Air filter	Bq/filter	2.42E-01	1.70E-01	0.702	Pass	GEL
U-234	Air filter	Bq/filter	6.20E-02	5.50E-02	0.887	Pass	GEL
U-238	Air filter	Bq/filter	6.20E-02	6.20E-02	1.000	Yes	GEL
U (total)	Air filter	µg/filter	4.98E+ 00	4.35E+ 00	0.873	Pass	GEL
Co-57	Air filter	Bq/filter	5.31E+ 00	5.31E+ 00	1.000	Yes	EL
Co-60	Air filter	Bq/filter	5.32E+ 00	5.57E+ 00	1.047	Yes	EL
Cs-137	Air filter	Bq/filter	6.10E+ 00	6.52E+ 00	1.069	Yes	EL
Gross Alpha	Air filter	Bq/filter	3.02E+ 00	2.58E+ 00	0.854	Yes	EL
Gross Beta	Air filter	Bq/filter	2.42E+ 00	2.88E+ 00	1.190	Yes	EL
Mn-54	Air filter	Bq/filter	2.72E+ 01	3.23E+ 01	1.187	Pass	EL
Ru-106	Air filter	Bq/filter	2.01E+ 00	2.16E+ 00	1.075	Yes	EL
Ac-228	Soil	Bq/kg	9.76E+ 01	1.08E+ 02	1.107	Yes	GEL
Am-241	Soil	Bq/kg	3.36E+ 00	3.53E+ 00	1.051	Yes	GEL
Bi-212	Soil	Bq/kg	1.06E+ 02	6.33E+ 01	0.597	Yes	GEL
Bi-214	Soil	Bq/kg	8.67E+ 01	9.48E+ 01	1.093	Yes	GEL
Cs-137	Soil	Bq/kg	3.39E+ 02	3.49E+ 02	1.029	Yes	GEL
K-40	Soil	Bq/kg	8.11E+ 02	8.50E+ 02	1.048	Yes	GEL
Pb-212	Soil	Bq/kg	9.73E+ 01	1.10E+ 02	1.131	Yes	GEL
Pb-214	Soil	Bq/kg	8.65E+ 01	1.06E+ 02	1.225	Yes	GEL
Pu-239	Soil	Bq/kg	7.00E+ 00	5.00E+ 00	0.714	Pass	GEL
Sr-90	Soil	Bq/kg	2.02E+ 01	1.43E+ 01	0.708	Pass	GEL
Th-234	Soil	Bq/kg	1.30E+ 02	1.14E+ 02	0.877	Yes	GEL
U-234	Soil	Bq/kg	1.11E+ 02	1.10E+ 02	0.991	Yes	GEL
U-238	Soil	Bq/kg	1.14E+ 02	1.13E+ 02	0.991	Yes	GEL
U (total)	Soil	µg/g	9.15E+ 00	8.16E+ 00	0.892	Yes	GEL

Acceptance is based on the reported-to-actual ratio, assigned statistically on a case-by-case basis. **Yes** indicates a ratio within warning limits. **Pass** indicates a ratio within control limits but outside warning limits. **No** indicates a ratio outside control limits. Samples were analyzed by either the WVDP Environmental Laboratory (EL) or General Engineering Laboratory (GEL).

Table J-1 (concluded)
Comparison of Radiological Results with Known Results of Crosscheck Samples
from the DOE Environmental Measurements Laboratory (EML) Quality
Assessment Program (QAP) 52; EML-608 QAP 2003; June 2000

Analyte	Matrix	Units	Actual	Reported	Ratio	Accept?	Analyzed by:
Am-241	Veg	Bq/kg	1.04E+ 01	1.11E+ 01	1.067	Yes	GEL
Cm-244	Veg	Bq/kg	5.00E+ 00	6.98E+ 00	1.396	Pass	GEL
Co-60	Veg	Bq/kg	5.28E+ 01	6.69E+ 01	1.267	Pass	GEL
Cs-137	Veg	Bq/kg	1.38E+ 03	1.74E+ 03	1.258	Pass	GEL
K-40	Veg	Bq/kg	5.21E+ 02	6.62E+ 02	1.271	Pass	GEL
Pu-239	Veg	Bq/kg	1.55E+ 01	1.55E+ 01	1.000	Yes	GEL
Sr-90	Veg	Bq/kg	1.78E+ 03	8.90E+ 01	0.050	No	GEL
Am-241	Water	Bq/L	1.95E+ 00	2.53E+ 00	1.297	Pass	GEL
Co-60	Water	Bq/L	4.89E+ 01	5.14E+ 01	1.051	Yes	GEL
Cs-137	Water	Bq/L	1.03E+ 02	1.04E+ 02	1.010	Yes	GEL
Fe-55	Water	Bq/L	3.31E+ 01	3.16E+ 01	0.955	Yes	GEL
Gross Alpha	Water	Bq/L	1.70E+ 03	1.75E+ 03	1.031	Yes	GEL
Gross Beta	Water	Bq/L	6.90E+ 02	9.32E+ 02	1.351	Pass	GEL
H-3	Water	Bq/L	7.94E+ 01	8.11E+ 01	1.021	Yes	GEL
Ni-63	Water	Bq/L	1.12E+ 02	1.34E+ 02	1.196	Yes	GEL
Pu-238	Water	Bq/L	9.44E-01	1.34E+ 00	1.419	No	GEL
Pu-239	Water	Bq/L	9.18E-01	1.26E+ 00	1.373	Pass	GEL
Sr-90	Water	Bq/L	3.39E+ 00	3.13E+ 00	0.923	Yes	GEL
U-234	Water	Bq/L	4.82E-01	4.70E-01	0.975	Yes	GEL
U-238	Water	Bq/L	4.92E-01	4.90E-01	0.996	Yes	GEL
U (total)	Water	µg/mL	4.00E-02	4.40E-02	1.100	Yes	GEL
Co-60	Water	Bq/L	4.89E+ 01	5.24E+ 01	1.072	Yes	EL
Cs-137	Water	Bq/L	1.03E+ 02	1.08E+ 02	1.047	Yes	EL
Gross Alpha	Water	Bq/L	1.70E+ 03	1.69E+ 03	0.993	Yes	EL
Gross Beta	Water	Bq/L	6.90E+ 02	1.03E+ 03	1.487	Pass	EL
H-3	Water	Bq/L	7.94E+ 01	8.60E+ 01	1.083	Yes	EL
Sr-90	Water	Bq/L	3.39E+ 00	3.33E+ 00	0.982	Yes	EL

Note: EML did not list acceptance limits for µg of uranium; acceptance criteria for Bq of uranium were applied to these ratios.

*Acceptance is based on the reported-to-actual ratio, assigned statistically on a case-by-case basis. **Yes** indicates a ratio within warning limits. **Pass** indicates a ratio within control limits but outside warning limits. **No** indicates a ratio outside control limits. Samples were analyzed by either the WVDP Environmental Laboratory (EL) or General Engineering Laboratory (GEL).*

Table J-2
Comparison of Radiological Results with Known Results of Crosscheck Samples
from the DOE Environmental Measurements Laboratory (EML) Quality
Assessment Program (QAP) 53; EML-611 QAP 2009; December 2000

Analyte	Matrix	Units	Actual	Reported	Ratio	Accept?	Analyzed by:
Am-241	Air filter	Bq/filter	3.20E-02	3.00E-02	0.937	Yes	GEL
Co-57	Air filter	Bq/filter	1.46E+ 01	1.45E+ 01	0.997	Yes	GEL
Co-60	Air filter	Bq/filter	8.43E+ 00	8.92E+ 00	1.058	Yes	GEL
Cs-137	Air filter	Bq/filter	7.41E+ 00	7.98E+ 00	1.077	Yes	GEL
Gross Alpha	Air filter	Bq/filter	2.35E+ 00	2.75E+ 00	1.170	Yes	GEL
Gross Beta	Air filter	Bq/filter	1.52E+ 00	1.55E+ 00	1.020	Yes	GEL
Mn-54	Air filter	Bq/filter	4.32E+ 01	4.51E+ 01	1.044	Yes	GEL
Pu-238	Air filter	Bq/filter	4.50E-02	4.00E-02	0.889	Yes	GEL
Pu-239	Air filter	Bq/filter	7.40E-02	7.00E-02	0.946	Yes	GEL
Sr-90	Air filter	Bq/filter	1.64E+ 00	1.40E+ 00	0.854	Yes	GEL
U (total)	Air filter	µg/filter	3.33E+ 00	3.02E+ 00	0.907	Yes	GEL
U-234	Air filter	Bq/filter	4.10E-02	4.00E-02	0.976	Yes	GEL
U-238	Air filter	Bq/filter	4.10E-02	3.00E-02	0.732	No	GEL
Co-57	Air filter	Bq/filter	1.46E+ 01	1.40E+ 01	0.963	Yes	EL
Co-60	Air filter	Bq/filter	8.43E+ 00	8.43E+ 00	1.000	Yes	EL
Cs-137	Air filter	Bq/filter	7.41E+ 00	7.42E+ 00	1.001	Yes	EL
Gross Alpha	Air filter	Bq/filter	2.35E+ 00	1.95E+ 00	0.830	Yes	EL
Gross Beta	Air filter	Bq/filter	1.52E+ 00	1.78E+ 00	1.171	Yes	EL
Mn-54	Air filter	Bq/filter	4.32E+ 01	4.90E+ 01	1.135	Yes	EL
Ac-228	Soil	Bq/kg	8.02E+ 01	8.03E+ 01	1.001	Yes	GEL
Am-241	Soil	Bq/kg	8.27E+ 00	9.55E+ 00	1.155	Yes	GEL
Bi-212	Soil	Bq/kg	8.05E+ 01	5.29E+ 01	0.657	Yes	GEL
Bi-214	Soil	Bq/kg	8.33E+ 01	7.42E+ 01	0.891	Yes	GEL
Cs-137	Soil	Bq/kg	1.02E+ 03	1.12E+ 03	1.098	Yes	GEL
K-40	Soil	Bq/kg	7.13E+ 02	8.58E+ 02	1.203	Yes	GEL
Pb-212	Soil	Bq/kg	7.93E+ 01	8.81E+ 01	1.111	Yes	GEL
Pb-214	Soil	Bq/kg	8.63E+ 01	8.79E+ 01	1.019	Yes	GEL
Pu-239	Soil	Bq/kg	1.68E+ 01	1.74E+ 01	1.036	Yes	GEL
Sr-90	Soil	Bq/kg	5.04E+ 01	4.11E+ 01	0.815	Yes	GEL
Th-234	Soil	Bq/kg	1.48E+ 02	1.13E+ 02	0.764	Pass	GEL
U (total)	Soil	µg/g	1.32E+ 01	8.93E+ 00	0.677	Yes	GEL
U-234	Soil	Bq/kg	1.57E+ 02	1.32E+ 02	0.841	Pass	GEL
U-238	Soil	Bq/kg	1.63E+ 02	1.34E+ 02	0.822	Pass	GEL

Acceptance is based on the reported-to-actual ratio, assigned statistically on a case-by-case basis. **Yes** indicates a ratio within warning limits. **Pass** indicates a ratio within control limits but outside warning limits. **No** indicates a ratio outside control limits. Samples were analyzed by either the WVDP Environmental Laboratory (EL) or General Engineering Laboratory (GEL).

Table J-2 (concluded)
Comparison of Radiological Results with Known Results of Crosscheck Samples
from the DOE Environmental Measurements Laboratory (EML) Quality
Assessment Program (QAP) 53; EML-611 QAP 2009; December 2000

Analyte	Matrix	Units	Actual	Reported	Ratio	Accept?	Analyzed by:
Am-241	Veg	Bq/kg	5.60E+ 00	6.69E+ 00	1.195	Yes	GEL
Cm-244	Veg	Bq/kg	3.60E+ 00	4.11E+ 00	1.142	Yes	GEL
Co-60	Veg	Bq/kg	3.28E+ 01	3.43E+ 01	1.046	Yes	GEL
Cs-137	Veg	Bq/kg	8.67E+ 02	9.12E+ 02	1.052	Yes	GEL
K-40	Veg	Bq/kg	6.39E+ 02	7.57E+ 02	1.185	Yes	GEL
Pu-239	Veg	Bq/kg	9.60E+ 00	9.21E+ 00	0.959	Yes	GEL
Sr-90	Veg	Bq/kg	1.15E+ 03	1.33E+ 03	1.157	Pass	GEL
Am-241	Water	Bq/L	1.19E+ 00	1.33E+ 00	1.118	Yes	GEL
Co-60	Water	Bq/L	7.37E+ 01	7.62E+ 01	1.034	Yes	GEL
Cs-137	Water	Bq/L	6.70E+ 01	6.81E+ 01	1.016	Yes	GEL
Gross Alpha	Water	Bq/L	1.07E+ 03	9.64E+ 02	0.901	Yes	GEL
Gross Beta	Water	Bq/L	9.50E+ 02	1.02E+ 03	1.074	Yes	GEL
H-3	Water	Bq/L	9.13E+ 01	1.05E+ 02	1.150	Yes	GEL
Pu-238	Water	Bq/L	7.86E-01	7.60E-01	0.967	Yes	GEL
Pu-239	Water	Bq/L	5.91E-01	5.90E-01	0.998	Yes	GEL
Sr-90	Water	Bq/L	4.53E+ 00	3.60E+ 00	0.795	Pass	GEL
U (total)	Water	µg/mL	3.00E-02	2.00E-02	0.658	No	GEL
U-234	Water	Bq/L	4.81E-01	3.90E-01	0.811	Pass	GEL
U-238	Water	Bq/L	3.68E-01	3.20E-01	0.870	Pass	GEL
Co-60	Water	Bq/L	7.37E+ 01	7.40E+ 01	1.004	Yes	EL
Cs-137	Water	Bq/L	6.70E+ 01	6.44E+ 01	0.961	Yes	EL
Gross Alpha	Water	Bq/L	1.07E+ 03	1.26E+ 03	1.179	Pass	EL
Gross Beta	Water	Bq/L	9.50E+ 02	1.14E+ 03	1.198	Yes	EL
H-3	Water	Bq/L	9.13E+ 01	1.06E+ 02	1.160	Yes	EL
Sr-90	Water	Bq/L	4.53E+ 00	4.54E+ 00	1.002	Yes	EL

Acceptance is based on the reported-to-actual ratio, assigned statistically on a case-by-case basis. **Yes** indicates a ratio within warning limits. **Pass** indicates a ratio within control limits but outside warning limits. **No** indicates a ratio outside control limits. Samples were analyzed by either the WVDP Environmental Laboratory (EL) or General Engineering Laboratory (GEL).

Table J-3
Comparison of Results from Crosscheck Samples Analyzed for Water Quality
Parameters as Part of the EPA's 2000 Discharge Monitoring Report - Quality
Assurance (DMR-QA) Study 20 for the National Pollutant Discharge
Elimination System (NPDES)

Analyte	Units	Actual	Reported	Accept?	Analyzed by:
Aluminum, total	µg/L	500	330	No	E&E
Arsenic, total	µg/L	333	327	Yes	E&E
Cadmium, total	µg/L	250	240	Yes	E&E
Chromium, total	µg/L	417	405	Yes	E&E
Cobalt, total	µg/L	125	118	Yes	E&E
Copper, total	µg/L	167	161	Yes	E&E
Iron, total	µg/L	833	806	Yes	E&E
Lead, total	µg/L	333	324	Yes	E&E
Manganese, total	µg/L	500	474	Yes	E&E
Mercury, total	µg/L	15	15.8	Yes	E&E
Nickel, total	µg/L	833	802	Yes	E&E
Selenium, total	µg/L	167	169	Yes	E&E
Vanadium, total	µg/L	750	720	Yes	E&E
Zinc, total	µg/L	375	428	No	E&E
pH	SU	9.50	9.55	Yes	WVNS
Total cyanide	mg/L	0.266	0.29	Yes	E&E
Solids, total suspended	mg/L	65	61	Yes	E&E
Oil and grease, total recoverable	mg/L	21.2	23.9	Yes	E&E
Phenols	mg/L	2.37	1.6	Yes	E&E
Total residual chlorine	mg/L	0.763	0.840	Yes	WVNS
Ammonia (as nitrogen)	mg/L	6.28	4.76	No	E&E
Nitrate (as nitrogen)	mg/L	26.3	25.4	Yes	E&E
Biochemical oxygen demand	mg/L	81.3	53.3	Yes	E&E

Total residual chlorine and pH samples were from Environmental Research Associates (ERA). The remainder of the samples were from the New York State Department of Health (NYSDOH).

Analyses were conducted by Ecology & Environment, Inc. (E&E) or WVNS, as indicated.

*Acceptance limits are determined by ERA or NYSDOH, as applicable. **Yes** indicates a ratio within warning limits. **Pass** indicates a ratio within control limits but outside warning limits. **No** indicates a ratio outside control limits.*

Appendix K

Environmental Regulations, Standards, and Orders

Table K-1
Department of Energy Radiation Protection Standards
and Derived Concentration Guides ¹

Effective Dose Equivalent Radiation Standard for Protection of the Public

*Continuous exposure of any member of the public from routine activities:
All exposure pathways = 100 mrem/year (1 mSv/yr) effective dose equivalent*

**Department of Energy Derived Concentration Guides (DCGs) for
Inhaled Air or Ingested Water (μCi/mL)**

<i>Radionuclide</i>	<i>Half-life ^{2, 3} (years)</i>	<i>In Air</i>	<i>In Water</i>	<i>Radionuclide</i>	<i>Half-life ^{2, 3} (years)</i>	<i>In Air</i>	<i>In Water</i>
H-3*	1.23E+ 01	1E-07	2E-03	Eu-152	1.36E+ 01	5E-11	2E-05
C-14*	5.73E+ 03	6E-09	7E-05	Eu-154*	8.80E+ 00	5E-11	2E-05
K-40	1.28E+ 09	9E-10	7E-06	Eu-155	4.96E+ 00	3E-10	1E-04
Fe-55	2.70E+ 00	5E-09	2E-04	Th-232	1.40E+ 10	7E-15	5E-08
Co-60*	5.27E+ 00	8E-11	5E-06	U-232*	7.20E+ 01	2E-14	1E-07
Ni-59	7.50E+ 04	4E-09	7E-04	U-233*	1.59E+ 05	9E-14	5E-07
Ni-63	1.00E+ 02	2E-09	3E-04	U-234*	2.44E+ 05	9E-14	5E-07
Sr-90*	2.86E+ 01	9E-12	1E-06	U-235*	7.04E+ 08	1E-13	6E-07
Y-90	7.31E-03	1E-09	1E-05	U-236*	2.34E+ 07	1E-13	5E-07
Zr-93	1.53E+ 06	4E-11	9E-05	U-238*	4.47E+ 09	1E-13	6E-07
Nb-93m	1.46E+ 01	4E-10	3E-04	Np-239	6.45E-03	5E-09	5E-05
Tc-99*	2.13E+ 05	2E-09	1E-04	Pu-238*	8.78E+ 01	3E-14	4E-08
Ru-106	1.01E+ 00	3E-11	6E-06	Pu-239*	2.41E+ 04	2E-14	3E-08
Cd-113m	1.37E+ 01	8E-12	9E-07	Pu-240*	6.57E+ 03	2E-14	3E-08
Sn-126	1.00E+ 05	1E-10	8E-06	Pu-241	1.44E+ 01	1E-12	2E-06
Sb-125	2.77E+ 00	1E-09	5E-05	Am-241*	4.32E+ 02	2E-14	3E-08
Te-125m	1.59E-01	2E-09	4E-05	Am-242m	1.52E+ 02	2E-14	3E-08
I-129*	1.57E+ 07	7E-11	5E-07	Am-243	7.38E+ 03	2E-14	3E-08
Cs-134*	2.06E+ 00	2E-10	2E-06	Cm-243	2.85E+ 01	3E-14	5E-08
Cs-135	2.30E+ 06	3E-09	2E-05	Cm-244	1.81E+ 01	4E-14	6E-08
Cs-137*	3.02E+ 01	4E-10	3E-06	Gross Alpha	NA	2E-14	3E-08
Pm-147	2.62E+ 00	3E-10	1E-04	(as Am-241)			
Sm-151	9.00E+ 01	4E-10	4E-04	Gross Beta	NA	9E-12	1E-06
				(as Sr-90)			

¹ DOE Order 5400.5 (February 8, 1990). Effective May 8, 1990. (See Derived Concentration Guides, p. 1-5, in Chapter 1, Environmental Program Information.)

² U.S. Department of Energy. 1981. Radioactive Decay Tables. Washington, D.C.: Technical Information Center, U.S. Department of Energy.

³ Shleien, B. et al. 1998. Handbook of Health Physics and Radiological Health Safety. 3rd ed. Baltimore, Maryland: Williams & Wilkins.

* Radionuclides measured in WVDP effluent.

NA - Not applicable.

Table K-2

Environmental Regulations, Orders, and Standards

The following environmental standards and laws are applicable, in whole or in part, to the West Valley Demonstration Project.

Atomic Energy Act of 1954, 42 USC §2011 et seq.

Clean Air Act (CAA). Pub. L. No. 84-159. 42 USC §7401 et seq., as amended, and implementing regulations.

Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA). Pub. L. No. 96-510. 42 USC §9601 et seq. (including Superfund Amendments and Reauthorization Act of 1986), and implementing regulations.

DOE Order 231.1. September 30, 1995. Environment, Safety, and Health Reporting, including Change 2 (November 7, 1996).

DOE Order 232.1A. August 1, 1997. Occurrence Reporting and Processing of Operations Information.

DOE Order 414.1A. September 29, 1999. Quality Assurance.

DOE Order 451.1B. October 26, 2000. National Environmental Policy Act Compliance Program.

DOE Order 5400.1. November 9, 1988. General Environmental Protection Program, including Change 1 (June 29, 1990).

DOE Order 5400.5. February 8, 1990. Radiation Protection of the Public and the Environment, including Change 2 (January 7, 1993).

DOE Order 5480.4. May 15, 1984. Environmental Protection, Safety, and Health Protection Standards, including Change 4 (January 7, 1993).

DOE Regulatory Guide DOE/EH-0173T, January 1991. Environmental Regulatory Guide for Radiological Effluent Monitoring and Environmental Surveillance.

Emergency Planning and Community Right-to-Know Act (EPCRA) of 1986. Pub. L. No. 99-499. 42 USC §11001 et seq., and implementing regulations.

Endangered Species Act. Pub. L. No. 93-205. 16 USC §1531-1544.

Table K-2 (concluded)
Environmental Regulations, Orders, and Standards

Environmental Conservation Law of New York State and implementing regulations (NYCRR).

Executive Orders 11988 and 11990. *Floodplains-Wetland Environmental Review Requirements*. 10 CFR 10222.

Executive Order 12856. Federal Compliance with Right-to-Know Laws and Pollution Prevention Requirements.

Executive Order 13101. Greening the Government Through Waste Prevention, Recycling, and Federal Acquisition.

Executive Order 13148. Greening the Government Through Leadership in Environmental Management.

Federal Water Pollution Control Act [Clean Water Act (CWA)]. Pub. L. No. 95-217. 33 USC §1251 *et seq.*, as amended, and implementing regulations.

Resource Conservation and Recovery Act (RCRA). Pub. L. No. 94-580. 42 USC §6901 *et seq.*, as amended, and implementing regulations.

National Environmental Policy Act (NEPA) of 1969. Pub. L. No. 91-190. 42 USC §4321 *et seq.*, as amended, and implementing regulations.

National Historic Preservation Act of 1966. Pub. L. No. 102-575. 16 USC §470.

Toxic Substances Control Act (TSCA). Pub. L. No. 94-469. 15 USC §2601 *et seq.*, as amended, and implementing regulations.

Safe Drinking Water Act (SDWA). Pub. L. No. 93-523. 42 USC §300f *et seq.*, as amended, and implementing regulations.

Water quality standards contained in the State Pollutant Discharge Elimination System (SPDES) permit issued for the facility are listed in Table G-1. Airborne emissions are regulated by the Environmental Protection Agency under the National Emission Standards for Hazardous Air Pollutants (NESHAP), 40 CFR §61 Subpart H (December 15, 1989).

The above list covers the major activities at the West Valley Demonstration Project but does not constitute a complete enumeration.

Appendix L

Summary of NYSERDA Groundwater Monitoring Data



An Aerial View of the New York State-licensed Disposal Area

Table L-1
2000 Contamination Indicator Results at SDA Monitoring Wells

Sample Location	Date	Conductivity (µmhos/cm@25°C)	pH (standard units)	Temperature (°C)	Turbidity (NTU)
WNW1101A	June	606	7.86	11.4	0.83
WNW1101A	December	621	7.49	8.2	0.94
WNW1101B	June	657	7.39	11.8	0.69
WNW1101B	December	624	7.60	7.3	7.04
WNW1101C	June	378	NA	12.0	86.00
WNW1101C	December	330	NA	6.7	770.00
WNW1102A	June	722	7.87	12.3	1.47
WNW1102A	December	693	7.50	9.2	20.30
WNW1102A	December	693	7.50	9.2	20.30
WNW1102B	June	608	7.74	11.3	1.47
WNW1102B	December	584	7.47	5.6	29.90
WNW1103A	June	928	7.74	11.2	1.20
WNW1103A	June	928	7.74	11.2	1.20
WNW1103A	December	829	7.10	8.6	66.60
WNW1103B	June	688	7.81	11.4	8.95
WNW1103B	December	699	7.82	6.3	4.30
WNW1104A	June	640	8.03	12.2	2.90
WNW1104A	December	618	6.87	10.2	1.99
WNW1104B	June	612	8.14	12.2	1.43
WNW1104B	December	581	7.01	6.2	0.94
WNW1105A	June	692	7.85	11.4	995.00
WNW1105A	December	631	6.94	9.2	> 1,000.00
WNW1105B	June	702	7.30	11.0	> 1,000.00
WNW1105B	December	689	6.65	8.5	> 1,000.00
WNW1106A	June	766	7.58	13.1	72.10
WNW1106A	December	735	7.66	11.2	4.57
WNW1106B	June	809	7.43	12.2	254.00
WNW1106B	December	758	7.64	9.4	523.00
WNW1107A	June	1848	7.68	12.9	1.29
WNW1107A	December	1688	NA	8.8	2.19
WNW1108A	June	1021	7.50	10.0	184.00
WNW1108A	December	908	7.03	11.6	25.60
WNW1109A	June	560	7.54	12.3	12.20
WNW1109A	December	557	7.17	10.7	2.64
WNW1109B	June	431	6.95	11.4	39.00
WNW1109B	December	438	NA	10.3	31.20
WNW1111A	June	990	7.92	12.9	1.30
WNW1111A	December	995	7.51	8.4	3.01

All data in Tables L-1 through L-3 have been provided by NYSERDA.

NA - Not available. Some scheduled analyses could not be performed due to insufficient sample.

Table L-2
2000 Radiological Indicator Results at SDA Monitoring Wells (μCi/mL)

Sample Location	Date	Gross Alpha	Gross Beta	H-3
WNW1101A	June	2.70±1.30E-09	2.51±1.10E-09	5.55±7.50E-08
WNW1101A	December	2.53±1.40E-09	4.30±1.20E-09	4.18±7.30E-08
WNW1101B	June	3.47±1.60E-09	3.06±1.10E-09	-5.14±7.10E-08
WNW1101B	December	2.79±1.50E-09	3.17±1.00E-09	-4.80±6.90E-08
WNW1101C	June	2.03±1.10E-09	2.54±0.96E-09	-6.14±7.00E-08
WNW1101C	December	1.21±0.90E-09	2.57±0.73E-09	-3.58±7.00E-08
WNW1102A	June	2.03±0.96E-09	3.10±1.30E-09	2.98±0.82E-07
WNW1102A	December	2.58±1.20E-09	3.83±1.20E-09	3.01±0.85E-07
WNW1102A	December	7.67±7.80E-10	4.83±1.30E-09	2.44±0.82E-07
WNW1102B	June	3.13±1.50E-09	2.65±1.10E-09	2.86±7.10E-08
WNW1102B	December	9.69±9.70E-10	2.30±0.89E-09	-0.14±7.20E-08
WNW1103A	June	4.84±1.90E-09	4.11±1.40E-09	5.27±0.92E-07
WNW1103A	June	4.18±1.70E-09	4.54±1.50E-09	4.32±0.88E-07
WNW1103A	December	4.09±2.00E-09	6.47±1.70E-09	4.26±0.89E-07
WNW1103B	June	2.51±1.10E-09	3.83±1.40E-09	1.08±7.10E-08
WNW1103B	December	2.65±1.50E-09	3.31±1.10E-09	-2.66±7.00E-08
WNW1103C	June	1.98±5.20E-10	1.35±0.69E-08	-6.70±7.00E-08
WNW1103C	December	7.80±9.40E-10	1.16±0.52E-08	-0.32±7.10E-08
WNW1104A	June	1.96±1.00E-09	2.91±1.30E-09	2.33±0.80E-07
WNW1104A	December	1.70±1.30E-09	2.55±0.96E-09	9.97±7.50E-08
WNW1104B	June	2.64±1.10E-09	1.80±1.20E-09	4.08±7.20E-08
WNW1104B	December	1.13±0.97E-09	3.09±0.92E-09	-2.10±7.00E-08
WNW1104C	June	2.07±4.00E-09	1.10±0.41E-08	-0.10±7.00E-08
WNW1104C	December	1.14±0.66E-08	8.32±3.90E-09	-1.43±7.10E-08
WNW1105A	June	2.83±1.30E-09	2.59±0.98E-09	1.08±0.77E-07
WNW1105A	December	4.58±2.00E-09	3.15±0.99E-09	1.21±0.77E-07
WNW1105B	June	4.07±1.60E-09	2.29±0.95E-09	-1.04±0.68E-07
WNW1105B	December	2.00±1.50E-09	3.13±1.00E-09	-3.77±7.00E-08
WNW1106A	June	2.06±1.00E-09	3.09±1.20E-09	5.72±0.96E-07
WNW1106A	December	3.76±1.80E-09	2.66±1.10E-09	5.65±0.95E-07
WNW1106B	June	1.52±0.94E-09	2.91±1.20E-09	-9.65±6.90E-08
WNW1106B	December	1.31±1.30E-09	3.83±1.20E-09	-8.46±6.80E-08
WNW1107A	June	9.03±4.10E-09	2.43±0.51E-08	1.21±0.06E-05
WNW1107A	December	7.61±3.70E-09	1.55±0.39E-08	1.28±0.06E-05
WNW1108A	June	4.93±2.10E-09	4.30±1.40E-09	8.86±7.40E-08
WNW1108A	December	5.42±2.50E-09	6.88±1.60E-09	3.97±7.40E-08

All data in Tables L-1 through L-3 have been provided by NYSERDA.

NA - Not available. Some scheduled analyses could not be performed due to insufficient sample.

Table L-2 (concluded)
2000 Radiological Indicator Results at SDA Monitoring Wells ($\mu\text{Ci/mL}$)

Sample Location	Date	Gross Alpha	Gross Beta	H-3
WNW1109A	June	3.29 \pm 1.20E-09	3.57 \pm 1.00E-09	3.36 \pm 0.87E-07
WNW1109A	December	4.69 \pm 1.90E-09	3.73 \pm 0.97E-09	2.59 \pm 0.82E-07
WNW1109B	June	1.55 \pm 1.00E-09	9.83 \pm 6.70E-10	4.94 \pm 0.92E-07
WNW1109B	December	4.30 \pm 6.00E-10	1.73 \pm 0.67E-09	4.25 \pm 0.89E-07
WNW1110A	June	NA	NA	1.66 \pm 0.77E-07
WNW1110A	December	8.78 \pm 3.20E-09	7.81 \pm 2.30E-09	1.26 \pm 0.77E-07
WNW1111A	June	5.23 \pm 1.90E-09	4.34 \pm 1.70E-09	2.26 \pm 0.79E-07
WNW1111A	December	2.28 \pm 1.30E-09	5.37 \pm 1.50E-09	2.34 \pm 0.83E-07

All data in Tables L-1 through L-3 have been provided by NYSERDA.

NA - Not available. Some scheduled analyses could not be performed due to insufficient sample.

Table L-3
2000 Radioisotopic Results at SDA Monitoring Wells (μCi/mL)

Sample Location	Date	Actinium-228	Bismuth-214	Carbon-14	Cesium-134
WNW1101A	June	1.14±1.60E-08	2.54±6.10E-09	-4.03±5.30E-09	0.14±3.10E-09
WNW1101A	December	NA	NA	NA	NA
WNW1101B	June	2.33±1.80E-08	4.93±7.60E-09	-3.68±5.30E-09	-0.75±4.20E-09
WNW1101B	December	NA	NA	NA	NA
WNW1101C	June	0.29±1.40E-08	6.66±9.10E-09	-6.56±7.20E-09	-3.07±3.90E-09
WNW1101C	December	NA	NA	NA	NA
WNW1102A	June	0.71±1.20E-08	-0.05±6.60E-09	1.03±5.50E-09	2.19±3.00E-09
WNW1102A	December	NA	NA	NA	NA
WNW1102B	June	0.07±2.10E-08	-0.74±1.10E-08	-4.96±5.30E-09	-4.24±4.10E-09
WNW1102B	December	NA	NA	NA	NA
WNW1103A	June	0.51±2.10E-08	-0.60±1.10E-08	-2.82±5.40E-09	-1.74±4.50E-09
WNW1103A	June	1.52±2.00E-08	1.08±1.10E-08	1.78±5.50E-09	-3.57±5.20E-09
WNW1103A	December	NA	NA	NA	NA
WNW1103B	June	0.77±1.70E-08	3.00±9.20E-09	-6.14±5.30E-09	-3.50±4.80E-09
WNW1103B	December	NA	NA	NA	NA
WNW1104A	June	-0.06±1.80E-08	1.20±0.81E-08	-4.01±5.30E-09	-3.61±3.90E-09
WNW1104A	December	NA	NA	NA	NA
WNW1104B	June	1.95±2.10E-08	-0.23±1.00E-08	-7.41±5.20E-09	-3.14±4.20E-09
WNW1104B	December	NA	NA	NA	NA
WNW1104C	June	NA	NA	-0.75±1.20E-08	NA
WNW1104C	December	NA	NA	NA	NA
WNW1105A	June	1.67±1.50E-08	0.48±9.00E-09	-1.25±5.60E-09	-4.69±4.40E-09
WNW1105A	December	NA	NA	NA	NA
WNW1105B	June	0.23±1.80E-08	8.04±8.70E-09	-5.79±5.30E-09	-1.16±3.30E-09
WNW1105B	December	NA	NA	NA	NA
WNW1106A	June	1.80±1.70E-08	2.16±9.30E-09	2.20±5.50E-09	1.85±4.40E-09
WNW1106A	December	NA	NA	NA	NA
WNW1106B	June	-4.67±9.40E-09	-2.63±6.50E-09	-6.47±5.20E-09	2.82±3.10E-09
WNW1106B	December	NA	NA	NA	NA
WNW1107A	June	-1.28±1.90E-08	-1.05±1.20E-08	2.65±6.40E-09	-1.69±5.20E-09
WNW1107A	December	NA	NA	NA	NA
WNW1108A	June	0.68±1.80E-08	2.02±9.10E-09	-5.13±5.30E-09	-2.68±4.40E-09
WNW1108A	December	NA	NA	NA	NA
WNW1109A	June	0.82±2.30E-08	-0.05±1.10E-08	-6.57±5.20E-09	-3.47±4.60E-09
WNW1109A	December	NA	NA	NA	NA
WNW1109B	June	1.81±1.90E-08	9.32±9.70E-09	-0.67±5.40E-09	1.20±4.60E-09
WNW1109B	December	NA	NA	NA	NA
WNW1110A	June	NA	NA	NA	NA
WNW1110A	December	1.43±2.90E-08	0.95±1.70E-08	NA	-9.07±7.40E-09
WNW1111A	June	0.40±1.80E-08	8.45±9.60E-09	-1.05±7.10E-09	-1.00±4.70E-09
WNW1111A	December	NA	NA	NA	NA

All data in Tables L-1 through L-3 have been provided by NYSERDA.

NA - Not available. Some scheduled analyses could not be performed due to insufficient sample.

Table L-3 (continued)
2000 Radioisotopic Results at SDA Monitoring Wells (μCi/mL)

Sample Location	Date	Cesium-137	Cobalt-57	Cobalt-60	Iodine-129
WNW1101A	June	0.82±3.40E-09	0.73±1.50E-08	2.97±3.90E-09	-0.89±1.80E-10
WNW1101A	December	NA	NA	NA	NA
WNW1101B	June	0.28±4.00E-09	0.06±1.90E-08	2.10±4.10E-09	-2.12±1.40E-10
WNW1101B	December	NA	NA	NA	NA
WNW1101C	June	-1.96±3.50E-09	1.07±1.70E-08	5.63±4.70E-09	-0.04±1.00E-10
WNW1101C	December	NA	NA	NA	NA
WNW1102A	June	2.87±3.20E-09	-0.49±1.70E-08	-0.12±3.30E-09	-0.51±1.20E-10
WNW1102A	December	NA	NA	NA	NA
WNW1102B	June	0.82±4.50E-09	0.27±1.90E-08	1.03±4.80E-09	-0.94±1.10E-10
WNW1102B	December	NA	NA	NA	NA
WNW1103A	June	-1.94±4.80E-09	1.46±2.20E-08	3.83±4.10E-09	2.15±1.50E-10
WNW1103A	June	1.51±4.20E-09	0.31±2.20E-08	-4.03±4.60E-09	0.46±1.10E-10
WNW1103A	December	NA	NA	NA	NA
WNW1103B	June	-1.99±4.60E-09	0.84±1.70E-08	0.54±3.70E-09	-0.64±1.60E-10
WNW1103B	December	NA	NA	NA	NA
WNW1104A	June	-0.14±4.30E-09	1.03±1.70E-08	1.78±4.30E-09	-0.13±1.10E-10
WNW1104A	December	NA	NA	NA	NA
WNW1104B	June	-0.18±4.90E-09	-0.51±2.00E-08	1.03±4.30E-09	-0.20±1.60E-10
WNW1104B	December	NA	NA	NA	NA
WNW1105A	June	1.94±4.40E-09	-0.54±1.70E-08	-2.32±4.70E-09	0.13±1.40E-10
WNW1105A	December	NA	NA	NA	NA
WNW1105B	June	-0.08±4.10E-09	-0.77±1.70E-08	0.64±3.30E-09	0.31±1.10E-10
WNW1105B	December	NA	NA	NA	NA
WNW1106A	June	-2.17±3.80E-09	-1.00±1.70E-08	3.20±4.40E-09	0.04±1.60E-10
WNW1106A	December	NA	NA	NA	NA
WNW1106B	June	-0.55±3.40E-09	0.06±1.60E-08	-0.08±3.30E-09	0.21±1.10E-10
WNW1106B	December	NA	NA	NA	NA
WNW1107A	June	0.00±4.20E-09	1.07±2.30E-08	-2.03±5.70E-09	1.16±1.60E-10
WNW1107A	December	NA	NA	NA	NA
WNW1108A	June	-3.80±4.80E-09	-2.28±2.20E-08	0.29±4.60E-09	0.04±1.20E-10
WNW1108A	December	NA	NA	NA	NA
WNW1109A	June	-4.06±4.60E-09	0.25±2.10E-08	1.50±4.60E-09	-0.47±1.60E-10
WNW1109A	December	NA	NA	NA	NA
WNW1109B	June	1.55±4.30E-09	-0.32±2.00E-08	-3.37±3.90E-09	-1.13±1.10E-10
WNW1109B	December	NA	NA	NA	NA
WNW1110A	June	NA	NA	NA	NA
WNW1110A	December	-0.93±7.40E-09	-2.56±3.60E-08	3.40±7.60E-09	NA
WNW1111A	June	-3.78±4.60E-09	-1.34±2.20E-08	-1.15±4.50E-09	0.15±1.30E-10
WNW1111A	December	NA	NA	NA	NA

All data in Tables L-1 through L-3 have been provided by NYSERDA.

NA - Not available. Some scheduled analyses could not be performed due to insufficient sample.

Table L-3 (continued)
2000 Radioisotopic Results at SDA Monitoring Wells ($\mu\text{Ci/mL}$)

Sample Location	Date	Lead-212	Lead-214	Potassium-40	Radium-224
WNW1101A	June	1.21 \pm 5.70E-09	1.06 \pm 0.72E-08	-1.22 \pm 4.70E-08	1.23 \pm 5.80E-09
WNW1101A	December	NA	NA	NA	NA
WNW1101B	June	3.34 \pm 6.30E-09	5.65 \pm 7.40E-09	2.28 \pm 9.10E-08	3.39 \pm 6.40E-09
WNW1101B	December	NA	NA	NA	NA
WNW1101C	June	-7.15 \pm 6.60E-09	0.88 \pm 7.80E-09	-8.16 \pm 6.20E-08	-7.25 \pm 6.70E-09
WNW1101C	December	NA	NA	NA	NA
WNW1102A	June	3.55 \pm 5.80E-09	2.96 \pm 7.10E-09	-3.46 \pm 4.60E-08	3.60 \pm 5.90E-09
WNW1102A	December	NA	NA	NA	NA
WNW1102B	June	0.64 \pm 6.90E-09	-1.54 \pm 0.99E-08	-1.31 \pm 1.20E-07	0.65 \pm 7.00E-09
WNW1102B	December	NA	NA	NA	NA
WNW1103A	June	-4.17 \pm 7.90E-09	-0.14 \pm 1.10E-08	-0.14 \pm 1.20E-07	-4.23 \pm 8.10E-09
WNW1103A	June	-0.06 \pm 7.10E-09	-0.59 \pm 8.10E-09	2.25 \pm 9.40E-08	-0.06 \pm 7.20E-09
WNW1103A	December	NA	NA	NA	NA
WNW1103B	June	4.27 \pm 6.80E-09	7.90 \pm 7.60E-09	4.82 \pm 8.80E-08	4.34 \pm 6.90E-09
WNW1103B	December	NA	NA	NA	NA
WNW1104A	June	-0.92 \pm 6.70E-09	4.73 \pm 8.20E-09	-2.30 \pm 8.40E-08	-0.93 \pm 6.80E-09
WNW1104A	December	NA	NA	NA	NA
WNW1104B	June	0.62 \pm 7.10E-09	-2.03 \pm 9.70E-09	-1.47 \pm 1.20E-07	0.63 \pm 7.20E-09
WNW1104B	December	NA	NA	NA	NA
WNW1105A	June	-1.07 \pm 6.70E-09	2.71 \pm 7.90E-09	0.60 \pm 8.50E-08	-1.08 \pm 6.80E-09
WNW1105A	December	NA	NA	NA	NA
WNW1105B	June	0.11 \pm 6.20E-09	-6.60 \pm 7.30E-09	-3.09 \pm 8.30E-08	0.12 \pm 6.30E-09
WNW1105B	December	NA	NA	NA	NA
WNW1106A	June	3.24 \pm 7.10E-09	-0.01 \pm 8.10E-09	-0.90 \pm 8.30E-08	3.29 \pm 7.20E-09
WNW1106A	December	NA	NA	NA	NA
WNW1106B	June	2.75 \pm 6.10E-09	5.68 \pm 6.50E-09	3.30 \pm 6.10E-08	2.79 \pm 6.20E-09
WNW1106B	December	NA	NA	NA	NA
WNW1107A	June	4.98 \pm 8.10E-09	0.68 \pm 1.10E-08	0.12 \pm 1.20E-07	5.05 \pm 8.30E-09
WNW1107A	December	NA	NA	NA	NA
WNW1108A	June	1.75 \pm 7.10E-09	0.04 \pm 8.60E-09	0.82 \pm 9.00E-08	1.78 \pm 7.20E-09
WNW1108A	December	NA	NA	NA	NA
WNW1109A	June	-0.12 \pm 7.40E-09	-9.18 \pm 9.80E-09	-1.11 \pm 1.20E-07	-0.12 \pm 7.50E-09
WNW1109A	December	NA	NA	NA	NA
WNW1109B	June	2.02 \pm 6.90E-09	-5.22 \pm 9.20E-09	1.12 \pm 9.30E-08	2.05 \pm 7.00E-09
WNW1109B	December	NA	NA	NA	NA
WNW1110A	June	NA	NA	NA	NA
WNW1110A	December	0.33 \pm 1.00E-08	-0.59 \pm 1.50E-08	0.69 \pm 1.60E-07	0.34 \pm 1.10E-08
WNW1111A	June	1.88 \pm 7.00E-09	1.11 \pm 0.87E-08	0.07 \pm 1.00E-07	1.91 \pm 7.10E-09
WNW1111A	December	NA	NA	NA	NA

All data in Tables L-1 through L-3 have been provided by NYSERDA.

NA - Not available. Some scheduled analyses could not be performed due to insufficient sample.

Table L-3 (continued)
2000 Radioisotopic Results at SDA Monitoring Wells (μCi/mL)

Sample Location	Date	Radium-226	Strontium-90	Technetium-99	Thallium-208
WNW1101A	June	2.58±6.20E-09	NA	0.51±1.40E-09	2.31±3.30E-09
WNW1101A	December	NA	4.25±3.00E-10	NA	NA
WNW1101B	June	4.84±7.60E-09	NA	0.24±1.80E-09	-0.01±4.50E-09
WNW1101B	December	NA	2.37±2.90E-10	NA	NA
WNW1101C	June	6.71±9.10E-09	0.44±2.10E-10	0.00±1.00E-09	-1.44±4.50E-09
WNW1101C	December	NA	NA	NA	NA
WNW1102A	June	-0.05±6.60E-09	3.11±7.80E-10	0.48±1.10E-09	-0.81±3.70E-09
WNW1102A	December	NA	NA	NA	NA
WNW1102B	June	-0.74±1.10E-08	0.19±2.30E-10	0.49±1.00E-09	2.12±5.50E-09
WNW1102B	December	NA	NA	NA	NA
WNW1103A	June	-0.60±1.10E-08	0.54±2.40E-10	0.40±1.00E-09	7.35±5.60E-09
WNW1103A	June	1.08±1.10E-08	1.81±2.40E-10	3.97±9.90E-10	2.70±4.70E-09
WNW1103A	December	NA	NA	NA	NA
WNW1103B	June	3.00±9.20E-09	2.10±2.20E-10	0.24±1.00E-09	-1.80±4.70E-09
WNW1103B	December	NA	NA	NA	NA
WNW1104A	June	1.20±0.81E-08	0.43±2.20E-10	0.42±1.00E-09	-2.93±4.40E-09
WNW1104A	December	NA	NA	NA	NA
WNW1104B	June	-0.24±1.00E-08	1.03±2.10E-10	0.94±1.50E-09	4.68±5.10E-09
WNW1104B	December	NA	NA	NA	NA
WNW1105A	June	0.50±9.00E-09	2.76±2.40E-10	-5.28±9.70E-10	0.30±4.10E-09
WNW1105A	December	NA	NA	NA	NA
WNW1105B	June	8.09±8.70E-09	0.58±2.40E-10	-5.44±9.40E-10	1.51±4.60E-09
WNW1105B	December	NA	NA	NA	NA
WNW1106A	June	2.20±9.30E-09	1.79±2.70E-10	0.57±1.10E-09	0.74±5.30E-09
WNW1106A	December	NA	NA	NA	NA
WNW1106B	June	-2.65±6.50E-09	0.69±2.50E-10	0.55±1.00E-09	0.59±3.20E-09
WNW1106B	December	NA	NA	NA	NA
WNW1107A	June	-1.04±1.20E-08	9.52±2.40E-09	0.44±1.10E-09	1.32±5.30E-09
WNW1107A	December	NA	NA	NA	NA
WNW1108A	June	2.00±9.10E-09	2.72±4.70E-10	0.12±1.00E-09	1.64±5.00E-09
WNW1108A	December	NA	NA	NA	NA
WNW1109A	June	-0.05±1.10E-08	2.06±2.40E-10	0.16±1.00E-09	2.38±5.70E-09
WNW1109A	December	NA	NA	NA	NA
WNW1109B	June	9.27±9.60E-09	0.75±2.10E-10	3.04±9.90E-10	6.25±4.60E-09
WNW1109B	December	NA	NA	NA	NA
WNW1110A	June	NA	NA	NA	NA
WNW1110A	December	0.94±1.70E-08	NA	NA	9.60±7.50E-09
WNW1111A	June	8.36±9.60E-09	1.11±2.50E-10	0.28±1.00E-09	-0.42±5.10E-09
WNW1111A	December	NA	NA	NA	NA

All data in Tables L-1 through L-3 have been provided by NYSERDA.

NA - Not available. Some scheduled analyses could not be performed due to insufficient sample.

Table L-3 (concluded)
2000 Radioisotopic Results at SDA Monitoring Wells ($\mu\text{Ci/mL}$)

Sample Location	Date	Thorium-234	Uranium-235
WNW1101A	June	$-3.48 \pm 5.80\text{E-}07$	$-0.44 \pm 1.60\text{E-}08$
WNW1101A	December	NA	NA
WNW1101B	June	$1.85 \pm 7.90\text{E-}07$	$0.56 \pm 1.70\text{E-}08$
WNW1101B	December	NA	NA
WNW1101C	June	$0.60 \pm 5.50\text{E-}07$	$-0.03 \pm 1.70\text{E-}08$
WNW1101C	December	NA	NA
WNW1102A	June	$3.83 \pm 5.80\text{E-}07$	$-0.82 \pm 1.60\text{E-}08$
WNW1102A	December	NA	NA
WNW1102B	June	$1.88 \pm 6.40\text{E-}07$	$0.79 \pm 2.10\text{E-}08$
WNW1102B	December	NA	NA
WNW1103A	June	$3.66 \pm 7.60\text{E-}07$	$1.59 \pm 2.40\text{E-}08$
WNW1103A	June	$2.36 \pm 5.90\text{E-}07$	$0.00 \pm 2.10\text{E-}08$
WNW1103A	December	NA	NA
WNW1103B	June	$3.97 \pm 6.70\text{E-}07$	$0.33 \pm 1.90\text{E-}08$
WNW1103B	December	NA	NA
WNW1104A	June	$-0.75 \pm 5.50\text{E-}07$	$0.00 \pm 1.50\text{E-}08$
WNW1104A	December	NA	NA
WNW1104B	June	$-0.41 \pm 6.70\text{E-}07$	$1.87 \pm 2.10\text{E-}08$
WNW1104B	December	NA	NA
WNW1105A	June	$-3.18 \pm 6.50\text{E-}07$	$-1.91 \pm 1.90\text{E-}08$
WNW1105A	December	NA	NA
WNW1105B	June	$6.61 \pm 6.30\text{E-}07$	$0.46 \pm 1.80\text{E-}08$
WNW1105B	December	NA	NA
WNW1106A	June	$0.85 \pm 7.50\text{E-}07$	$0.66 \pm 1.60\text{E-}08$
WNW1106A	December	NA	NA
WNW1106B	June	$0.06 \pm 5.20\text{E-}07$	$2.48 \pm 1.60\text{E-}08$
WNW1106B	December	NA	NA
WNW1107A	June	$0.79 \pm 7.10\text{E-}07$	$-1.62 \pm 2.10\text{E-}08$
WNW1107A	December	NA	NA
WNW1108A	June	$-4.35 \pm 6.70\text{E-}07$	$0.04 \pm 2.10\text{E-}08$
WNW1108A	December	NA	NA
WNW1109A	June	$3.41 \pm 6.20\text{E-}07$	$1.63 \pm 2.20\text{E-}08$
WNW1109A	December	NA	NA
WNW1109B	June	$-3.53 \pm 7.50\text{E-}07$	$0.72 \pm 2.30\text{E-}08$
WNW1109B	December	NA	NA
WNW1110A	June	NA	NA
WNW1110A	December	$0.44 \pm 1.00\text{E-}06$	$0.65 \pm 3.20\text{E-}08$
WNW1111A	June	$1.09 \pm 0.82\text{E-}06$	$1.21 \pm 2.20\text{E-}08$
WNW1111A	December	NA	NA

All data in Tables L-1 through L-3 have been provided by NYSERDA.

NA - Not available. Some scheduled analyses could not be performed due to insufficient sample.

REFERENCES AND BIBLIOGRAPHY

Albanese, J.R., et al. 1984. *Geological and Hydrogeologic Research at the Western New York Nuclear Service Center, West Valley, New York. Final Report, August 1982-December 1983.* U.S. Nuclear Regulatory Commission Report. NUREG/CR-3782.

American National Standards Institute/American Society for Quality Control. 1994. *Specifications and Guidelines for Quality Systems for Environmental Data Collections and Environmental Technology Programs.* ANSI/ASQC E4-1994.

American Society of Mechanical Engineers. 1989. *Quality Assurance Program Requirements for Nuclear Facilities.* ASME-NQA-1. New York: The American Society of Mechanical Engineers.

Bergeron, M.P., et al. 1987. *Geohydrologic Conditions at the Nuclear Fuels Reprocessing Plant and Waste Management Facilities at the Western New York Nuclear Services Center, Cattaraugus County, New York.* U.S. Geological Survey Water Resources Investigations Report 85-4145.

Citizen Task Force. July 29, 1998. *West Valley Citizen Task Force Final Report.*

Dames & Moore. 1995. *Early Warning System for Evaluation of Groundwater Monitoring Results from the Vicinity of the Proposed Groundwater Extraction System.* Letter: CDF1004:CDF-0.01. AR # 95-692.

_____. July 1995. *Analysis of Hydraulic Conductivity Tests Conducted on Selected Wells at the WVDP: July 1995.* AR # 95-661.

_____. July 1996. *Analysis of Hydraulic Conductivity Tests Conducted on Selected Wells at the WVDP: July 1996.* AR # 96-1287.

_____. December 22, 1998. *1998 Wetlands Investigation and Delineation of the West Valley Assessment Area*. AR #99-117.

_____. December 1999. *Wetlands Investigation and Delineation of the West Valley Railroad Spur*.

Dunning, Donald E. nd. *Estimates of Internal Dose Equivalent from Inhalation and Ingestion of Selected Radionuclides*. Revised. WIPP-DOE-176.

Executive Order 11990. May 25, 1977. *Protection of Wetlands*. 42 FR 26961.

Executive Order 11988. May 25, 1977. *Floodplain Management*. 42 FR 26951.

Executive Order 12856. August 6, 1993. *Federal Compliance with Right-to-Know Laws and Pollution Prevention Requirements*. 58 FR 419981.

Executive Order 13101. September 16, 1998. *Greening of the Government through Waste Prevention, Recycling, and Federal Acquisition*. 63 FR 49643.

Executive Order 13148. April 26, 2000. *Greening the Government through Leadership in Environmental Management*. 65 FR 24595.

International Commission on Radiological Protection. 1959. *Recommendations of the International Commission on Radiological Protection – Permissible Dose for Internal Radiation*. ICRP Publication 2. Oxford: Pergamon Press.

_____. 1975. *Report of the Task Group on Reference Man*. ICRP Publication 23. Oxford: Pergamon Press.

_____. 1977. *Recommendations of the International Commission on Radiological Protection*. ICRP Publication 26. Oxford: Pergamon Press.

_____. 1979. *Recommendations of the International Commission on Radiological Protection – Limits for Intakes of Radionuclides by Workers*. ICRP Publication 30. Oxford: Pergamon Press.

_____. 1991. *1990 Recommendations of the International Commission on Radiological Protection*. ICRP Publication 60. Oxford: Pergamon Press.

International Organization for Standardization. 1996. *Environmental Management Systems*. ISO 14001:1996.

- LaFleur, R.G.** 1979. *Glacial Geology and Stratigraphy of Western New York Nuclear Service Center and Vicinity, Cattaraugus and Erie Counties, New York*. U.S. Geological Survey Open File Report 79-989.
- Moore, R.E., et al.** June 1979. *AIRDOS-EPA: A Computerized Methodology for Estimating Environmental Concentrations and Dose to Man from Airborne Releases of Radionuclides*. ORNL-5532.
- National Council on Radiation Protection and Measurements.** December 1979. *Environmental Radiation Measurements*. NCRP-50. Washington, D.C.
- _____. July 1985. *Recommendations on Radiation Exposure Limits*. Draft. Washington, D.C.
- _____. 1987a. *Recommendations on Limits for Exposure to Ionizing Radiation*. NCRP-91. Bethesda, Maryland.
- _____. 1987b. *Ionizing Radiation Exposure of the Population of the United States*. NCRP-93. Bethesda, Maryland.
- National Research Council.** 1990. *Health Effects of Exposure to Low Levels of Ionizing Radiation*. BEIR V. Washington: National Academy Press.
- New York State Department of Environmental Conservation.** 1991. *Draft Cleanup Policy and Guidelines, Appendix B - Water Cleanup Criteria*.
- _____. *Environmental Conservation Law of New York State*. 6 NYCRR.
- New York State Department of Health.** nd. *Environmental Laboratory Approval Program (ELAP) Certification Manual*.
- Nuclear Regulatory Commission.** 1998. *Decommissioning Criteria for West Valley*. SECY-98-251.
- _____. 1999. *Supplement to SECY-98-251, Decommissioning Criteria for West Valley*. SECY-99-057.
- Oak Ridge National Laboratory.** May 1980. *User's Manual for LADTAP II - A Computer Program for Calculating Radiation Exposure to Man from Routine Release of Nuclear Reactor Liquid Effluents*. NUREG/CR-1276.
- Rickard, L.V.** 1975. *Correlation of the Silurian and Devonian Rocks in New York State*. New York State Museum and Science Service Map and Chart Series No. 24.

- Sheppard, M.I., and D. H.Thibault.** 1990. *Default Soil Solid/Liquid Partition Coefficients, K_d s, for Four Major Soil Types: A Compendium.* Health Physics. 59 (no. 4): 471-482.
- Shleien, B. et al.** 1998. *Handbook of Health Physics and Radiological Health Safety.* 3rd ed. Baltimore, Maryland: Williams & Wilkens.
- Simpson, D.B., and B.L. McGill.** 1980. *LADTAP II: A Computer Program for Calculating Radiation Exposure to Man from Routine Release of Nuclear Reactor Liquid Effluents.* Technical Data Management Center. ORNL/NUREG/TDMC-1.
- Spector, H.** 2000. *WVDP Manual for Radiological Assessment of Environmental Releases at the WVDP.* Rev. 3. WVDP-065.
- Standish, P.N.** 1985. *Closure of the Construction Landfill Site.* Letter (WD:85:0434) to W.H. Hannum, Department of Energy, West Valley Project Office.
- Tesmer, I.H.** 1975. *Geology of Cattaraugus County, New York.* Buffalo Society of Natural Sciences Bulletin, Vol. 27.
- Tseng, J.C.** November 4, 1975. *Clarification of Applicable Radiation Protection Standards for the Public and the Environment.* Memorandum from EH-231, Office of Environmental Guidance and Compliance. Washington, D.C.
- U.S. Congress.** 1954. *Atomic Energy Act of 1954.* 42 USC § 2011 et seq.
- _____. 1955. *Clean Air Act.* 42 USC § 7401 et seq.
- _____. 1966. *National Historic Preservation Act of 1966.* 16 USC § 470 et seq.
- _____. 1969. *National Environmental Policy Act of 1969.* 42 USC § 4321 et seq.
- _____. 1973. *Endangered Species Act.* 16 USC § 1531-1544.
- _____. 1974. *Safe Drinking Water Act.* 42 USC § 300f et seq.
- _____. October 23, 1976. *Resource Conservation and Recovery Act of 1976.* Public Law 94-580, 90 Stat. 2795, Title 42.
- _____. 1977. *Federal Water Pollution Control Act.* 33 USC § 1251 et seq.
- _____. October 1, 1980. *An Act to Authorize the Department of Energy to Carry Out a High-Level Liquid Nuclear Waste Management Demonstration Project at the Western New York Service Center in West Valley, New York.* Public Law 96-368 [S.2443]. Congressional Record, Vol. 126.

- _____. December 11, 1980. *Comprehensive Environmental Response, Compensation, and Liability Act of 1980*. Public Law 96-150, 94 Stat. 2767, Title 26.
- _____. 1986. *Toxic Substances Control Act*. 15 USC § 2601 et seq.
- _____. 1986. *Emergency Planning and Community Right-to-Know Act of 1986*. 42 USC § 11001 et seq.
- _____. October 17, 1986. *Superfund Amendments and Reauthorization Act of 1986*. Public Law 99-499, 100 Stat. 1613, Title 10.
- U.S. Department of Energy.** July 1981. *A Guide for Environmental Radiological Surveillance at U.S. Department of Energy Installations*. DOE/EP-0023. Washington, D.C.
- _____. 1981. *Radioactive Decay Tables*. Washington, D.C.: Technical Information Center, U.S. Department of Energy.
- _____. June 1982. *Final Environmental Impact Statement: Long-Term Management of Liquid High-Level Radioactive Wastes Stored at the Western New York Nuclear Services Center, West Valley*. DOE/EIS-0081.
- _____. July 1983. *A Guide for Effluent Radiological Measurements at DOE Installations*. DOE/EP-0096. Washington, D.C.
- _____. May 15, 1984. *Environmental Protection, Safety, and Health Protection Standards*, including Change 4 (January 7, 1993). DOE Order 5480.4.
- _____. July 1988. *Internal Dose Conversion Factors for Calculation of Dose to the Public*. DOE/EH-0071.
- _____. November 9, 1988. *General Environmental Protection Program*. DOE Order 5400.1, including Change 1 (June 29, 1990). Washington, D.C.
- _____. February 1990. *Radiation Protection of the Public and Environment*. DOE Order 5400.5, including Change 2 (January 7, 1993). Washington, D.C.
- _____. January 1991. *Environmental Regulatory Guide for Radiological Effluent Monitoring and Environmental Surveillance*. DOE/EH-0173T. Washington, D.C.
- _____. 1994. *Quality Assurance*. 10 CFR 830.120.
- _____. September 30, 1995. *Environment, Safety, and Health Reporting*. DOE Order 231.1, including Change 2 (November 7, 1996). Washington, D.C.

- _____. January 1996. *Draft Environmental Impact Statement for Completion of the West Valley Demonstration Project and Closure or Long-term Management of Facilities at the Western New York Nuclear Services Center*. DOE/EIS-0226-D.
- _____. May 1997. *Final Waste Management Programmatic Impact Statement for Managing Treatment, Storage, and Disposal of Radioactive and Hazardous Waste*. DOE/EIS-0200-F.
- _____. August 1, 1997. *Occurrence Reporting and Processing of Operations Information*. DOE Order 232.1A.
- _____. January 23, 1998. *Record of Decision for the Department of Energy's Waste Isolation Pilot Plant Disposal Phase*.
- _____. June 23, 1998. *Supplemental Analysis II of Environmental Impacts Resulting from Modifications in the West Valley Demonstration Project*. WVDP-321.
- _____. August 5, 1998. *Record of Decision for the Department of Energy's Waste Management Program: Treatment of Non-Wastewater Hazardous Waste*.
- _____. August 26, 1999. *Record of Decision for the Department of Energy's Waste Management Program: Storage of High-level Radioactive Waste*.
- _____. September 29, 1999. *Quality Assurance*. DOE Order 414.1A. Washington, D.C.
- _____. December 10, 1999. *Identification of Preferred Alternatives for the Department of Energy's Waste Management Program: Low-level Waste and Mixed Low-level Waste Disposal Sites*.
- _____. October 26, 2000. *National Environmental Policy Act Compliance Program*. DOE Order 451.1B.
- U. S. Environmental Protection Agency.** 1976. *National Interim Primary Drinking Water Regulations*. EPA-570/9-76-003. Washington, D.C.: Office of Water Supply.
- _____. 1984a. *Drinking Water Guidelines*. 40 CFR 141, National Secondary Drinking Water Regulations, Subpart B, Maximum Contaminant Levels.
- _____. 1984b. *Drinking Water Guidelines*. 40 CFR 143, National Secondary Drinking Water Regulations, Section 143.3, Secondary Maximum Contaminant Levels.
- _____. September 1986. *Groundwater Monitoring Technical Enforcement Guidance Document*. OWSER-9950.1. Washington, D.C.

- _____. November 1986. *Test Methods for Evaluating Solid Waste*. Vol. IA: Laboratory Manual, Physical Chemical Methods. EPA Manual, SW-846, 3rd ed. Update II, September 1994. Washington, D.C.: Office of Solid Waste and Emergency Response.
- _____. December 15, 1989. *National Emission Standards for Hazardous Air Pollutants: Standards for Radionuclides*. 40 CFR 61. Washington, D.C.: U.S. Government Printing Office.
- _____. 1992. *Region II Administrative Order on Consent. Docket No. II RCRA 3008(h) -92-0202. In the Matter of: Western New York Nuclear Service Center*.
- _____. March 1992. *User's Guide for CAP88-PC*. Version 1.0. Las Vegas, NV: U.S. Environmental Protection Agency Office of Radiation Programs. 402-B-92-001.
- _____. 1995. *Appendix 33 Ground-water Monitoring List*. Title 6 NYCRR Subpart 373-2.
- _____. October 16, 1996. *Code of Environmental Management Principles*. Federal Register, Vol. 61, No. 201.
- U.S. Nuclear Regulatory Commission.** July 1977. *Regulatory Guide 1.111: Methods for Estimating Atmospheric Transport and Dispersion of Gaseous Effluents in Routine Releases from Light-Water-Cooled Reactors*.
- _____. October 1977. *Regulatory Guide 1.109: Calculation of Annual Doses to Man from Routine Releases of Reactor Effluents for the Purpose of Evaluating Compliance with 10 CFR Part 50, Appendix I*.
- West Valley Demonstration Project.** 1986. *WVDP Radioactive Air Emissions Permit Application General Information. Submitted to EPA Region II*.
- West Valley Nuclear Services Co., Inc.** 1992. *Groundwater Seep Investigation Report: 1,1,1-trichloroethane Detection*. Draft A, Rev. 0. WVDP-138.
- _____. January 1992. *Environmental Media Management Plan at the West Valley Demonstration Project*.
- _____. December 1993. *RCRA Facility Investigation (RFI) Work Plan*. West Valley Demonstration Project. WVDP-RFI-014. Rev. 0.
- _____. 1995. *Subsurface Probing Investigation of the North Plateau at the West Valley Demonstration Project*. WVDP-220.

- _____. March 1996. *Environmental Information Document, Volume III: Hydrology, Part 4.* WVDP-EIS-009.
- _____. July 1997. *RCRA Facility Investigation Report: Introduction and General Site Overview. Volume 1.* WVDP-RFI-017.
- _____. October 27, 1997. *WVDP Deer Management Program Plan.* WVDP-289.
- _____. July 16, 1998. *Supplement Analysis II of Environmental Impacts Resulting from Modifications in the West Valley Demonstration Project.* WVDP-321.
- _____. August 19, 1998. *Documentation and Reporting of Environmental Monitoring Data.* EMP-11.
- _____. December 28, 1998. *PCB and PCB-contaminated Material Management Plan.* Rev.5. WVDP-080.
- _____. 1999. *Waste Minimization/Pollution Prevention Awareness Plan.* WVDP-087.
- _____. October 26, 1999. *Asbestos Management Plan.* Rev. 5. WVDP-07.
- _____. June 1999. *1998 Geoprobe® Investigation in the Core Area of the North Plateau Groundwater Plume.* Rev. 0. WVDP-346.
- _____. February 15, 2000. *WVNS Environmental Management System.* Rev. 11. WV-980.
- _____. March 6, 2000. *Environmental Monitoring Program Plan.* WVDP-098.
- _____. May 2, 2000. *Groundwater Protection Management Program Plan.* Rev. 4. WVDP-091.
- _____. October 25, 2000. *Site Treatment Plan: Fiscal Year 2000 Update.* WVDP-299.
- _____. January 2001. *Groundwater Monitoring Plan.* WVDP-239.
- _____. February 2001. *New York State Department of Environmental Conservation Hazardous Waste Report for 2000.*
- West Valley Nuclear Services Co., Inc. and Dames & Moore.** July 1997. *Resource Conservation and Recovery Act Facility Investigation Report, Vol.1: Introduction and General Site Overview.* WVDP-RFI-017.
- West Valley Nuclear Services Co. and URS/Dames & Moore.** June 2000. *West Valley Demonstration Project Site Environmental Report Calendar Year 1999.*

_____. June 1998. *Final Report: Evaluation of the Pilot Program to Investigate Chromium and Nickel Concentrations in Groundwater in the Sand and Gravel Unit.*

_____. January 2001. *Results of Corrosion Evaluation in Selected Stainless Steel Monitoring Wells on the North Plateau and Recommendations for Long-term Management.*

Yager, R.M. 1987. *Simulation of Groundwater Flow near the Nuclear Fuel Reprocessing Facility at the Western New York Nuclear Service Center, Cattaraugus County, New York.* 85-4308. Ithaca, New York: U.S. Geological Survey.

GLOSSARY

Accuracy. The degree of agreement between a measurement and its true value. The accuracy of a data set is assessed by evaluating results from standards or spikes containing known quantities of an analyte.

Action plan. An action plan addresses assessment findings and root causes that have been identified in an audit or an assessment report. It is intended to set forth specific actions that the site will undertake to remedy deficiencies. The plan includes a timetable and funding requirements for implementation of the planned activities.

Alluvial fan. A cone-shaped deposit of alluvium made by a stream where it runs out onto a level plain.

Alluvium. Sedimentary material deposited by flowing water such as a river.

Aquifer. A water-bearing unit of permeable rock or soil that will yield water in usable quantities to wells. *Confined aquifers* are bounded above and below by less permeable layers. Groundwater in a confined aquifer is under a pressure greater than the atmospheric pressure. *Unconfined aquifers* are bounded below by less permeable material but are not bounded above. The pressure on the groundwater at the surface of an unconfined aquifer is equal to that of the atmosphere.

As low as reasonably achievable (ALARA). An approach to radiation protection that advocates controlling or managing exposures (both individual and collective) to the work force and the general public and releases of radioactive material to the environment as low as social, technical, economic, practical, and public policy considerations permit. As used in DOE Order 5400.5, ALARA is not a dose limit but, rather, a process that has as its objective the attainment of dose levels as far below the applicable limits of the Order as practicable.

Background radiation. Natural and manmade radiation such as cosmic radiation and radiation from naturally radioactive elements and from commercial sources and medical procedures.

Becquerel (Bq). A unit of radioactivity equal to one nuclear transformation per second.

Categorical exclusion. A proposed action that normally does not require an environmental assessment or an environmental impact statement and that the Department of Energy has determined does not individually or cumulatively have a significant effect on the human environment. See 10 CFR 1021.410.

Class A, B, and C low-level waste. Waste classifications from the Nuclear Regulatory Commission's 10 CFR Part 61 rule. Maximum concentration limits are set for specific isotopes. Class A waste disposal is minimally restricted with respect to the form of the waste. Class B waste must meet more rigorous requirements to ensure physical stability after disposal. Greater concentration limits are set for the same isotopes in Class C waste, which also must meet physical stability requirements. Moreover, special measures must be taken at the disposal facility to protect against inadvertent intrusion.

Compliance findings. Conditions that may not satisfy applicable environmental or safety and health regulations, DOE Orders and memoranda, enforcement actions, agreements with regulatory agencies, or permit conditions.

Confidence coefficient or factor. The chance or probability, usually expressed as a percentage, that a confidence interval includes some defined parameter of a population. The confidence coefficients usually associated with confidence intervals are 90%, 95%, and 99%.

Consistency. The condition of showing steady conformity to practices. In the environmental monitoring program, approved procedures are in place in order to ensure that data collection activities are carried out in a consistent manner so that variability is minimized.

Cosmic radiation. High-energy subatomic particles from outer space that bombard the earth's atmosphere. Cosmic radiation is part of natural background radiation.

Counting error. The variability caused by the inherent random nature of radioactive disintegration and by the detection process.

Curie (Ci). A unit of radioactivity equal to 37 billion (3.7×10^{10}) nuclear transformations per second.

Data set. A group of data (e.g., factual information such as measurements or statistics) used as a basis for reasoning, discussion, or calculation.

Decay (radioactive). Disintegration of the nucleus of an unstable nuclide by spontaneous emission of charged particles and/or photons or by spontaneous fission.

Derived concentration guide (DCG). The concentration of a radionuclide in air and water that, under conditions of continuous exposure for one year by one exposure mode (i.e., ingestion of water, submersion in air, or inhalation), would result in an effective dose equivalent of 100 mrem (1 mSv). See Table K-1 in Appendix K.

Detection limit or level. The smallest amount of a substance that can be distinguished in a sample by a given measurement procedure at a given confidence level. (See **lower limit of detection**.)

Dispersion (groundwater). The process whereby solutes are spread or mixed as they are transported by groundwater as it moves through sediments.

Dosimeter. A portable device for measuring the total accumulated exposure to ionizing radiation.

Downgradient. The direction of water flow from a reference point to a selected point of interest. (See **gradient**.)

Effective dose. See **effective dose equivalent** under **radiation dose**.

Effluent. Any treated or untreated air emission or liquid discharge, including storm water runoff, at a DOE site or facility.

Effluent monitoring. Sampling or measuring specific liquid or gaseous effluent streams for the presence of pollutants.

Enhanced work planning. A process that evaluates and improves the program by which work is identified, planned, approved, controlled, and executed. The key elements are line management ownership, a graded approach to work management based on risk and complexity, worker involvement beginning at the earliest phases of work management, organizationally diverse teams, and organized, institution-wide communication.

Environmental assessment. An evaluation that provides sufficient evidence and analysis for determining whether to prepare an environmental impact statement or a finding of no significant impact. See 40 CFR 1508.9.

Environmental impact statement. A detailed statement that includes the environmental impact of the proposed action, any adverse environmental effects that cannot be avoided should the proposal be implemented, and alternatives to the proposed action. See Section 102 (2) (C) of the National Environmental Policy Act.

Environmental management system. The systematic application of business management practices to environmental issues, including defining the organizational structure, planning for activities, identifying responsibilities, and defining practices, procedures, processes, and resources.

Environmental monitoring. The collection and analysis of samples or the direct measurement of environmental media. Environmental monitoring consists of two major activities: effluent monitoring and environmental surveillance.

Environmental surveillance. The collection and analysis of samples or the direct measurement of air, water, soil, foodstuff, and biota in order to determine compliance with applicable standards and permit requirements.

Erg. One-billionth (1E-09) of the energy released by a 100-watt bulb in 1 second.

Evapotranspiration. The combined total precipitation returned to the air through direct evaporation and by transpiration of vegetation.

Exposure. The subjection of a target (usually living tissue) to radiation.

Fallout. Radioactive materials mixed into the earth's atmosphere. Fallout constantly precipitates onto the earth.

Finding. A Department of Energy compliance term. A finding is a statement of fact concerning a condition in the Environmental, Safety, and Health program that was investigated during an appraisal. Findings include best management practice findings, compliance findings, and noteworthy practices. A finding may be a simple statement of proficiency or a description of deficiency (i.e., a variance from procedures or criteria). See also **self-assessment**.

Fission. The act or process of splitting into parts. A nuclear reaction in which an atomic nucleus splits into fragments, i.e., fission products, usually fragments of comparable mass, with the evolution of approximately 100 million to several hundred million electron volts of energy.

Gamma isotopic (also gamma scan). An analytical method by which the quantity of several gamma ray-emitting radioactive isotopes may be determined simultaneously. Typical nuclear fuel cycle isotopes determined by this method include but are not limited to Co-60, Zr-95, Ru-106, Ag-110m, Sb-125, Cs-134, Cs-137, and Eu-154. Naturally occurring isotopes for which samples also often are analyzed are Be-7, K-40, Ra-224, and Ra-226.

Gradient. Change in value of one variable with respect to another variable, especially vertical or horizontal distance.

Groundwater. Subsurface water in the pore spaces of soil and geologic units.

Half-life. The time in which half the atoms of a radionuclide disintegrate into another nuclear form. The half-life may vary from a fraction of a second to thousands of years.

Hazardous waste. A waste or combination of wastes that because of quantity, concentration, or physical, chemical, or infectious characteristics may: a) cause or significantly contribute to an increase in mortality or an increase in serious irreversible or incapacitating reversible illness; or (b) pose a substantial present or potential hazard to human health or the environment when improperly treated, stored, transported, disposed of, or otherwise managed.

High-level waste (HLW). The highly radioactive waste material that results from the reprocessing of spent nuclear fuel, including liquid waste produced directly in reprocessing and any solid waste derived from the liquid, that contains a combination of transuranic waste and fission products in concentrations sufficient to require permanent isolation. (See also **transuranic waste**.)

Hydraulic conductivity. The ratio of flow velocity to driving force for viscous flow under saturated conditions of a specified liquid in a porous medium; the ratio describing the rate at which water can move through a permeable medium.

Integrated safety management system (ISMS). The integrated safety management system (ISMS) describes the programs, policies, and procedures used by WVNS and the DOE to ensure that WVNS establishes a safe workplace for the employees, the public, and the environment. The guiding principles of ISMS are line management responsibility for safety; clear roles and responsibilities; competence commensurate with responsibilities; balanced priorities; identification of safety standards and requirements; hazard controls; and operations authorization.

Interim status. The status of any currently existing facility that becomes subject to the requirement to have a RCRA permit because of a new statutory or regulatory amendment to RCRA.

Interstitial. The (annular) space between the inner and outer tank walls in a double-walled storage tank.

Ion. An atom or group of atoms with an electric charge.

Ion exchange. The reversible exchange of ions contained in solution with other ions that are part of the ion-exchange material.

Isotope. Different forms of the same chemical element that are distinguished by having the same number of protons but a different number of neutrons in the nucleus. An element can have many isotopes. For example, the three isotopes of hydrogen are protium, deuterium, and tritium, with one, two, and three neutrons in the nucleus, respectively.

Kame delta. A conical hill or short irregular ridge of gravel or sand deposited in contact with glacier ice.

Lacustrine sediments. A sedimentary deposit consisting of material pertaining to, produced by, or formed in a lake or lakes.

Land disposal restrictions (LDR). Regulations promulgated by the U.S. EPA (and by NYSDEC in New York State) governing the land disposal of hazardous wastes. The wastes must be treated using the best demonstrated available technology or must meet certain treatment standards before being disposed.

Lower limit of detection (LLD). The lowest limit of a given parameter an instrument is capable of detecting. A measurement of analytical sensitivity.

Low-level waste (LLW). Radioactive waste not classified as high-level waste, transuranic waste, spent fuel, or uranium mill tailings. (See **Class A, B, and C low-level waste.**)

Maximally exposed individual. A hypothetical person who remains in an uncontrolled area who would, when all potential routes of exposure from a facility's operations are considered, receive the greatest possible dose equivalent.

Mean. The average value of a series of measurements.

Metric ton. A unit of mass equal to 1,000 kilograms.

Millirem (mrem). A unit of radiation dose equivalent that is equal to one one-thousandth of a rem. An individual member of the public can receive up to 500 millirems per year according to DOE standards. This limit does not include radiation received for medical treatment or the 100 to 360 mrem that people receive annually from background radiation.

Minimum detectable concentration (MDC). Depending on the sample medium, the smallest amount or concentration of a radioactive or nonradioactive analyte that can be reliably detected using a specific analytical method. Calculations of the minimum detectable concentrations are based on the lower limit of detection.

Mixed waste. A waste that is both radioactive and hazardous. Also referred to as radioactive mixed waste (RMW).

n-Dodecane/tributyl phosphate. An organic solution composed of 30% tributyl phosphate (TBP) dissolved in n-dodecane used to first separate the uranium and plutonium from the fission products in the dissolved fuel and then to separate the uranium from the plutonium.

Neutron. An electrically neutral subatomic particle in the baryon family with a mass 1,839 times that of an electron, stable when bound in an atomic nucleus, and having a mean lifetime of approximately 16.6 minutes as a free particle.

Notice of violation. A letter of notice from a regional water engineer in response to an instance of significant noncompliance with a SPDES permit. Generally, an official notification from a regulatory agency of noncompliance with permit requirements.

Nucleus. The positively charged central region of an atom, made up of protons and neutrons and containing almost all of the mass of the atom.

Outfall. The end of a drain or pipe that carries wastewater or other effluents into a ditch, pond, or river.

Parameter. Any of a set of physical properties whose values determine the characteristics or behavior of something (e.g., temperature, pressure, density of air). In relation to environmental monitoring, a monitoring parameter is a constituent of interest. Statistically, the term “parameter” is a calculated quantity, such as a mean or variance, that describes a statistical population.

Particulates. Solid particles and liquid droplets small enough to become airborne.

Person-rem. The sum of the individual radiation dose equivalents received by members of a certain group or population. It may be calculated by multiplying the average dose per person by the number of persons exposed. For example, a thousand people each exposed to one millirem would have a collective dose of one person-rem.

Plume. The distribution of a pollutant in air or water after being released from a source.

Precision. The degree of reproducibility of a measurement under a given set of conditions. Precision in a data set is assessed by evaluating results from duplicate field or analytical samples.

Proglacial lake. A lake occupying a basin in front of a glacier; generally in direct contact with the ice.

Proton. A stable, positively charged subatomic particle in the baryon family with a mass 1,836 times that of an electron.

Pseudo-monitoring point. A theoretical monitoring location rather than an actual physical location; a calculation based on analytical test results of samples obtained from other associated, tributary, monitored locations. (Point 116 at the WVDP is classified as a “pseudo” monitoring point because samples are not actually physically collected at that location. Rather, using analytical results from samples collected from “real” upstream outfall locations, compliance with the total dissolved solids limit in the WVDP’s SPDES permit is calculated for this theoretical point.)

Quality factor. The extent of tissue damage caused by different types of radiation of the same energy. The greater the damage, the higher the quality factor. More specifically, the factor by which absorbed doses are multiplied to obtain a quantity that indicates the degree of biological damage produced by ionizing radiation. (See **radiation dose**.) The factor is dependent upon radiation type (alpha, beta, gamma, or x-ray) and exposure (internal or external).

Rad. Radiation absorbed dose. One hundred ergs of energy absorbed per gram.

Radiation. The process of emitting energy in the form of rays or particles that are thrown off by disintegrating atoms. The rays or particles emitted may consist of alpha, beta, or gamma radiation.

Alpha radiation. The least penetrating type of radiation. Alpha radiation can be stopped by a sheet of paper or the outer dead layer of skin.

Beta radiation. Electrons emitted from a nucleus during fission and nuclear decay. Beta radiation can be stopped by an inch of wood or a thin sheet of aluminum.

Gamma radiation. A form of electromagnetic, high-energy radiation emitted from a nucleus. Gamma rays are essentially the same as x-rays and require heavy shielding such as lead, concrete, or steel to be stopped.

Internal radiation. Radiation originating from a source within the body as a result of the inhalation, ingestion, or implantation of natural or manmade radionuclides in body tissues.

Radiation dose:

Absorbed dose. The amount of energy absorbed per unit mass in any kind of matter from any kind of ionizing radiation. Absorbed dose is measured in rads or grays.

Collective dose equivalent. The sum of the dose equivalents for all the individuals comprising a defined population. The per capita dose equivalent is the quotient of the collective dose equivalent divided by the population. The unit of collective dose equivalent is person-rem or person-sievert.

Collective effective dose equivalent. The sum of the effective dose equivalents for the individuals comprising a defined population. Units of measurement are person-rem or person-sieverts. The per capita effective dose equivalent is obtained by dividing the collective dose equivalent by the population. Units of measurement are rem or sieverts.

Committed dose equivalent. A measure of internal radiation. The predicted total dose equivalent to a tissue or organ over a fifty-year period after a known intake of a radionuclide into the body. It does not include contributions from sources of external penetrating radiation. Committed dose equivalent is measured in rem or sieverts.

Committed effective dose equivalent. The sum of the committed dose equivalents to various tissues in the body, each multiplied by the appropriate weighting factor. Committed effective dose equivalent is measured in rem or sieverts.

Radioactivity. A property possessed by some elements (such as uranium) whereby alpha, beta, or gamma rays are spontaneously emitted.

Radioisotope. A radioactive isotope of a specified element. Carbon-14 is a radioisotope of carbon. Tritium is a radioisotope of hydrogen. (See **isotope**.)

Radionuclide. A radioactive nuclide. Radionuclides are variations (isotopes) of elements. They have the same number of protons and electrons but different numbers of neutrons, resulting in different atomic masses. There are several hundred known nuclides, both manmade and naturally occurring.

Rem. An acronym for Roentgen Equivalent Man. A unit of radiation exposure that indicates the potential effect of radiation on human cells.

Remote-handled waste. At the WVDP, waste that has an external surface dose rate that exceeds 100 millirem per hour or a high level of alpha and/or beta surface contamination.

Self-assessment. Appraisals of work at the WVDP by individuals, groups, or organizations responsible for overseeing and/or performing the work. Self-assessments are intended to provide an internal review of performance to determine that specific functional areas are in programmatic and site-specific compliance with applicable DOE directives, WVDP procedures, and regulations.

Finding. A direct and significant violation of applicable Department of Energy, regulatory, or other procedural or programmatic requirements. A finding requires documented corrective action.

Observation. A condition that, while not a direct and significant violation of applicable Department of Energy, regulatory, or other procedural or programmatic requirements, could result in a finding if not corrected. An observation requires documented corrective action.

Good practice. A statement of proficiency or confirmed excellence worthy of documenting.

Sievert. A unit of dose equivalent from the International System of Units (Système Internationale). Equal to one joule per kilogram.

Solid waste management unit (SWMU). Any discernible unit at which solid wastes have been placed at any time, irrespective of whether the unit was intended for the management of solid or hazardous waste. Such units include any area at a facility at which solid wastes have been routinely and systematically released.

Spent fuel. Nuclear fuel that has been used in a nuclear reactor; this fuel contains uranium, activation products, fission products, and plutonium.

Spill. A spill or release is defined as “any spilling, leaking, pumping, pouring, emitting, emptying, discharging, injecting, escaping, leaching, dumping, or otherwise disposing of substances from the ordinary containers employed in the normal course of storage, transfer, processing, or use.”

Stakeholder. A person or group that has an investment, share, or interest in something. At the WVDP stakeholders include Project management, scientists, other employees, politicians, regulatory agencies, local and national interest groups, and members of the general public.

Standard deviation. An indication of the dispersion of a set of results around their average.

Super solid waste management unit (SSWMU). Individual solid waste management units that have been grouped and ranked into larger units — super solid waste management units — because some individual units are contiguous or so close together as to make monitoring of separate units impractical.

Surface water. Water that is exposed to the atmospheric conditions of temperature, pressure, and chemical composition at the surface of the earth.

Surveillance. The act of monitoring or observing a process or activity to verify conformance with specified requirements.

Thermoluminescent dosimeter (TLD). A device that luminesces upon heating after being exposed to radiation. The amount of light emitted is proportional to the amount of radiation to which the luminescent material has been exposed.

Ton, metric (also tonne). A unit of mass equal to 1,000 kilograms.

Ton (short ton). A unit of weight equal to 2,000 lbs or 907.1847 kilograms.

Transuranic waste. Waste containing transuranic elements, i.e., those elements with an atomic number greater than 92, including neptunium, plutonium, americium, and curium.

Universal wastes. Wastes subject to special management provisions that are intended to ease the management burden and facilitate recycling of such materials. Four types of waste are currently covered under the universal waste regulations: hazardous waste batteries, hazardous waste pesticides that are either recalled or collected in waste pesticide collection programs, hazardous waste thermostats, and hazardous waste lamps.

Upgradient. Referring to the flow of water or air, “upgradient” is analogous to upstream. Upgradient is a point that is “before” an area of study that is used as a baseline for comparison with downstream data. See **gradient** and **downgradient**.

Watershed. The area contained within a drainage divide above a specified point on a stream.

Water table. The upper surface in a body of groundwater; the surface in an unconfined aquifer or confining bed at which the pore water pressure is equal to atmospheric pressure.

X-ray. Penetrating electromagnetic radiations having wave lengths shorter than those of visible light. They are usually produced by bombarding a metallic target with fast electrons in a high vacuum. In nuclear reactions it is customary to refer to photons originating in the nucleus as gamma rays and those originating in the extranuclear part of the atom as x-rays. These rays are sometimes called roentgen rays after their discoverer, W.C. Roentgen.

ACRONYMS AND ABBREVIATIONS

ACM	Asbestos-containing material
ALARA	As Low As Reasonably Achievable
ANSI	American National Standards Institute
ASME	American Society of Mechanical Engineers
ASQ	American Society for Quality
BEIR	Committee on Biological Effects of Ionizing Radiation
BOD₅	Biochemical Oxygen Demand (5-day)
CAA	Clean Air Act
CDDL	Construction and Demolition Debris Landfill
CEDE	Committed Effective Dose Equivalent
CEMP	Code of Environmental Management Principles for Federal Agencies
CEQ	(President's) Council on Environmental Quality
CERCLA	Comprehensive Environmental Response, Compensation, and Liability Act
CFR	Code of Federal Regulations
CO	Certificate-to-Operate
CPC	Chemical Process Cell
CPC-WSA	Chemical Process Cell Waste Storage Area
CSPF	Container Sorting and Packaging Facility
CSRF	Contact Size-reduction Facility
CSS	Cement Solidification System
CWA	Clean Water Act
CWAP	Clean Water Action Plan
CX	Categorical Exclusion
CY	Calendar Year
DCG	Derived Concentration Guide
DMR	Discharge Monitoring Report
DOE	(U.S.) Department of Energy
DOE-EM	Department of Energy, Office of Environmental Restoration and Waste Management
DOE-HQ	Department of Energy, Headquarters Office
DOE-OH	Department of Energy, Ohio Field Office
DOT	(U.S.) Department of Transportation

EA	Environmental Assessment
EDE	Effective Dose Equivalent
EHS	Extremely Hazardous Substance
EIS	Environmental Impact Statement
EML	Environmental Measurements Laboratory
EMS	Environmental Management System
EPA	(U.S.) Environmental Protection Agency
EPCRA	Emergency Planning and Community Right-to-Know Act
ES&H	Environmental Safety and Health
ESR	(WVDP) Effluent Summary Report
EWP	Enhanced Work Planning
FFC Act	Federal Facility Compliance Act
FONSI	Finding of No Significant Impact
FR	Federal Register
FRS	Fuel Receiving and Storage
FSFCA	Federal and State Facility Compliance Agreement
FY	Fiscal Year
GEL	General Engineering Laboratory
HEPA	High-efficiency Particulate Air (filter)
HLW	High-level (radioactive) Waste
HPIC	High-pressure Ion Chamber
HTO	Hydrogen Tritium Oxide
HVAC	Heating, Ventilation, and Air Conditioning
ICRP	International Commission on Radiological Protection
IRTS	Integrated Radwaste Treatment System
ISMS	Integrated Safety Management System
ISO	International Organization for Standardization
LAS	Linear Alkylate Sulfonate
LDR	Land Disposal Restriction
LIMS	Laboratory Information Management System
LLD	Lower Limit of Detection
LLW	Low-level (radioactive) Waste
LLW2	Low-level (liquid) Waste Treatment Facility (new)
LLWTF	Low-level (liquid) Waste Treatment Facility (old)
LPS	Liquid Pretreatment System
LSA	Lag Storage Area
LTR	License Termination Rule
LWTS	Liquid Waste Treatment System
MDC	Minimum Detectable Concentration
MDL	Method Detection Limit
MSDS	Material Safety Data Sheet
MTAR	Monthly Trend Analysis Report
MW	(Radioactive) Mixed Waste

NCRP	National Council on Radiation Protection and Measurements
NDA	Nuclear Regulatory Commission-licensed Disposal Area
NEPA	National Environmental Policy Act
NESHAP	National Emission Standards for Hazardous Air Pollutants
NFS	Nuclear Fuel Services, Inc.
NGVD	National Geodetic Vertical Datum
NIST	National Institute of Standards and Technology
NOI	Notice of Intent
NO_x	Nitrogen Oxides
NPOC	Nonpurgeable Organic Carbon
NPGRS	North Plateau Groundwater Recovery System
NPDES	National Pollutant Discharge Elimination System
NRC	(U.S.) Nuclear Regulatory Commission
NTU	Nephelometric Turbidity Unit
NYCRR	New York Official Compilation of Codes, Rules, and Regulations
NYSDEC	New York State Department of Environmental Conservation
NYSDOH	New York State Department of Health
NYSDEL	New York State Department of Labor
NYSERDA	New York State Energy Research and Development Authority
NYSGS	New York State Geological Survey
OH/WVDP	Department of Energy, West Valley Demonstration Project
OSHA	Occupational Safety and Health Act
OSR	Operational Safety Requirement
OVE	Outdoor Ventilated Enclosure
PC	Permit-to-Construct
PCB	Polychlorinated Biphenyl
PQL	Practical Quantitation Limit
PTW	Permeable Treatment Wall
PVS	Permanent Ventilation System
PVU	Portable Ventilation Unit
QA	Quality Assurance
QAP	Quality Assessment Program (also Quality Assurance Program)
QC	Quality Control
RCRA	Resource Conservation and Recovery Act
RFI	RCRA Facility Investigation
RHWF	Remote-handled Waste Facility
SAR	Safety Analysis Report
SARA	Superfund Amendments and Reauthorization Act
SD	Standard Deviation
SDA	(New York) State-licensed Disposal Area
SDWA	Safe Drinking Water Act
SER	Site Environmental Report
SI	Système Internationale (International System of Units)

SO₂	Sulfur Dioxide
SPDES	State Pollutant Discharge Elimination System
STS	Supernatant Treatment System
SVOC	Semivolatile Organic Compound
SWMU	Solid Waste Management Unit
SSWMU	Super Solid Waste Management Unit
TBP	Tributyl Phosphate
TDS	Total Dissolved Solids
TLD	Thermoluminescent Dosimetry
TOC	Total Organic Carbon
TOX	Total Organic Halogens
TRI	Toxic Release Inventory
TRU	Transuranic
TSCA	Toxic Substances Control Act
TSDF	Treatment, Storage, and Disposal Facility
USGS	United States Geological Survey
VOC	Volatile Organic Compound
WNYNSC	Western New York Nuclear Service Center
WRG	Work Review Group
WVDP	West Valley Demonstration Project
WVNS	West Valley Nuclear Services Company
WWTF	Wastewater Treatment Facility

Units of Measure

Radioactivity	Symbol	Name	Volume	Symbol	Name
	Ci	curie		cm ³	cubic centimeter
	mCi	millicurie (1E-03 Ci)		L	liter
	μCi	microcurie (1E-06 Ci)		mL	milliliter
	nCi	nanocurie (1E-09 Ci)		m ³	cubic meter
	pCi	picocurie (1E-12 Ci)		gal	gallon
	Bq	becquerel (27 pCi)		ft ³	cubic feet
				ppm	parts per million
				ppb	parts per billion
Dose	Symbol	Name	Area	Symbol	Name
	Sv	sievert (100 rems)		ha	hectare (10,000 m ²)
	mSv	millisievert (1E-03 Sv)			
	Gy	gray (100 rads)			
	mrem	millirem			
Concentration	Symbol	Name	Length	Symbol	Name
	μCi/mL	microcuries per milliliter		m	meter
	mL/L	milliliters per liter		km	kilometer (1E+ 03 m)
	μCi/g	microcuries per gram		cm	centimeter (1E-02 m)
	mg/L	milligrams per liter		mm	millimeter (1E-03 m)
	μg/mL	micrograms per milliliter		μm	micrometer (1E-06 m)
	pCi/L	picocuries per liter			
Mass	Symbol	Name	Flow Rate	Symbol	Name
	g	gram		mgd	million gallons per day
	kg	kilogram (1E+ 03 g)		cfm	cubic feet per minute
	mg	milligram (1E-03 g)		Lpm	liters per minute
	μg	microgram (1E-06 g)		gpd	gallons per day
	ng	nanogram (1E-09 g)			
	t	metric ton (1E+ 06 g)			

Unit Prefixes

centi	$1/100 = 1 \times 10^{-2} = 0.01 = \text{E-02}$
milli	$1/1,000 = 1 \times 10^{-3} = 0.001 = \text{E-03}$
micro	$1/1,000,000 = 1 \times 10^{-6} = 0.000001 = \text{E-06}$
nano	$1/1,000,000,000 = 1 \times 10^{-9} = 0.000000001 = \text{E-09}$
pico	$1/1,000,000,000,000 = 1 \times 10^{-12} = 0.000000000001 = \text{E-12}$

Scientific Notation

Scientific notation may be used to express very large or very small numbers. A number smaller than 1 is expressed with a negative exponent, e.g., 1.3×10^{-6} . To convert this number to decimal form, the decimal point is moved left by the number of places equal to the exponent. Thus, 1.3×10^{-6} becomes 0.0000013.

A number larger than 10 is expressed with a positive exponent, e.g., 1.3×10^6 . To convert this number to decimal form, the decimal point is moved right by the number of places equal to the exponent. Thus, 1.3×10^6 becomes 1,300,000.

The power of 10 also is expressed as E. For example, 1.3×10^{-6} also can be written as 1.3E-06. The chart below shows equivalent exponential and decimal values.

1.0×10^2	=	1E+02	=	100	
1.0×10^1	=	1E+01	=	10	
1.0×10^0	=	1E+00	=	1	
1.0×10^{-1}	=	1E-01	=	0.1	
1.0×10^{-2}	=	1E-02	=	0.01	
1.0×10^{-3}	=	1E-03	=	0.001	
1.0×10^{-4}	=	1E-04	=	0.0001	
1.0×10^{-5}	=	1E-05	=	0.00001	
1.0×10^{-6}	=	1E-06	=	0.000001	One Millionth
1.0×10^{-7}	=	1E-07	=	0.0000001	
1.0×10^{-8}	=	1E-08	=	0.00000001	

Conversion Chart

Both traditional radiological units (curie, roentgen, rad, rem) and the Systeme Internationale (S.I.) units (becquerel, gray, sievert) are used in this report. Nonradiological measurements are presented in metric units with the English equivalent noted in parentheses.

1 centimeter (cm)	=	0.3937 inches (in)
1 meter (m)	=	39.37 inches (in) = 3.28 feet (ft)
1 kilometer (km)	=	0.62 miles (mi)
1 milliliter (mL)	=	0.0338 ounces (oz)
	=	0.061 cubic inches (in ³)
	=	1 cubic centimeter (cm ³)
1 liter (L)	=	1.057 quarts (qt)
	=	61.02 cubic inches (in ³)
1 gram (g)	=	0.0353 ounces (oz)
	=	0.0022 pounds (lbs)
1 kilogram (kg)	=	2.2 pounds (lbs)
1 curie (Ci)	=	3.7×10^{10} disintegrations per second (d/s)
1 becquerel (Bq)	=	1 disintegration per second (d/s)
	=	27 picocuries (pCi)
1 roentgen (R)	=	2.58×10^{-4} coulombs per kilogram of air (C/kg)
1 rad	=	0.01 gray (Gy)
1 rem	=	0.01 sievert (Sv)
1 millirem (mrem)	=	0.001 rem

Distribution

R. Natoli DOE-HQ
M. Rawlings DOE-HQ
D. Stadler DOE-HQ (EH-2)

F. Galpin USEPA- Washington, D.C.
J. Eng USEPA-Region II
S. Venezia USEPA-Region II
P. Giardina USEPA-Region II

J. Craig DOE-OH
B. Granfield DOE-OH
W. Best DOE-OH
J. Ebersole DOE-OH

W. Kappel USGS

L. Maybee SNIEPD
E. Wohlers CCHD

T. Jackson NRC-Region 1
A. Snyder NRC-HQ

DOE Office of Scientific and Technical Information

T. DiGiulio NYSDEC-Syracuse
P. Merges NYSDEC- Albany
R. Murphy NYSDEC-Albany
T. Rice NYSDEC-Albany
M. Wang NYSDEC-Albany
M. Jackson NYSDEC-Region 9
J. Krajewski NYSDEC-Region 9
J. Scasia NYSDEC-Region 9
J. Strickland NYSDEC-Region 9

A. Houghton U.S. Congressman, 31st Dist.
T. Reynolds U.S. Congressman, 27th Dist.
J. Quinn U.S. Congressman, 30th Dist.
C. Schumer U.S. Senator, New York
H. Clinton U.S. Senator, New York
P. McGee New York Senator, 56th Dist.
W. Stachowski New York Senator, 58th Dist.
D. Burling New York Assemblyman, 147th Dist.

P. Piciulo NYSERDA
R. Fakundiny NYSGS

J. Huang NYSDOH-Albany
K. Rimawi NYSDOH-Albany
G. Baker NYSDOH-Buffalo

*Buffalo News, Buffalo, New York **

Olean Public Library, Olean, New York

*Salamanca Republican Press, Salamanca, New York **

West Valley Central School Library, West Valley, New York

*Springville Journal, Springville, New York **

Town of Concord Hulbert Library, Springville, New York

Central Buffalo Public Library, Buffalo, New York

Ashford Office Complex Reading Room, Ashford, New York

Seneca Nation of Indians Library, Cattaraugus Reservation,
Irving, New York

Seneca Nation of Indians Library, Allegheny Reservation,
Salamanca, New York

** Notice of public availability*

<http://www.wvnsco.com> (Media Research)

Acknowledgments

This report was compiled and edited by E.D. Picazo and Valerie Marvin of the URS West Valley Demonstration Project staff. Technical preparers and reviewers are listed below. Photography by David Kasper.

Adams, T.G.
Banzer, C.B.
Biedermann, C.A.
Bird, A.M.
Bleech, J.P.
Boada-Clista, L.
Centrich, G.F.
Chilson, L.J.
Cohen, F.J.
Dubiel, B.
Durkin, C.P.
Eigenbrod, E.M.
Fox, J.R.
Gerber, J.R.
Griffith, C.A.
Hadden-Carter, P.J.
Heim, B.F.
Hoch, J.J.
Kasper, D.T.
Kean, W.N.
Keller, K.D.
Klenk, D.P.
Komasara, S.M.
Kutina, L.S.

Lenter, C.M.
Loop, M.C.
Lowes, E.A.
Maloney, M.N.
McNeil, N.A.
Moore, H.R.
Moorehead, L.M.
Moran, R.E.
Nagel, A.S.
Paskuly, S.J.
Pendl, M.P.
Pillittere, J.T.
Roesch, C.T.
Scalise, D.M.
Sheridan, M. J.
Skiba, K.S.
Spector, H.L.
Steiner, A.F.
Steiner, D.R.
Steiner, R.E.
Valenti, P.J.
Wilcox, J.M.
Wrotniak, C.M.
Zadins, Z.Z.



Spent Fuel Shipping

125 assemblies remaining at the WVDP will be shipped to INEEL in 2001.



Waste Management Services Projects

The WVDP is now shipping low-level waste off-site by rail.



Vitrification Facility Closure (VEMP)

Expendable materials from the vitrification facility are being inventoried and sorted for disposal.



High-level Waste Tanks Closure

Liquid high-level waste storage tanks will be closed following decisions on long-term site management.



Remote-handled Waste Projects

A new facility under construction will be used to prepare higher activity wastes for shipment for off-site disposal.



Environmental Projects

Site-wide environmental monitoring and management projects such as the pilot permeable treatment wall being used to evaluate groundwater decontamination methods will continue to ensure the safety of the public and the environment.



Facility Closure Projects

To complete the West Valley Demonstration Project Act, facilities used to carry out solidification of the high-level waste will be decontaminated and decommissioned in preparation for long-term management decisions.

